

Archimages **project manual**

architecture | interiors

new project for:

**Central County
Fire & Rescue
House #06**

1151 Jungs Station Road
St. Charles, Mo. 63303-6010

**procurement & contracting
requirements**

specifications

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 21 05 00
COMMON WORK REQUIREMENTS
FOR FIRE PROTECTION

PART 1 - GENERAL

1.1 GENERAL

- A. Where the word contractor is used in this specification or on the drawings, the term shall apply to a prime contractor or a subcontractor. Where the term "this contractor" is used in this specification, the term shall apply to the fire protection contractor as applicable. Words such as "he" and "she" used in this specification is not intended to designate gender.
- B. This Contractor shall refer to the "Instructions to Bidders", General Conditions, Supplementary General Conditions and Special Conditions and Applicable Provisions for bidding requirements and items that effect his work.
- C. Pertinent Federal, State and Local requirements and regulations of OSHA, National Electrical Codes, and NFPA, are hereby made a part of this contract. Use of the term "code" in sections of this specification refers to applicable requirements and regulations of above listed agencies.
- D. It shall be the responsibility of this Contractor to promptly inform the Architects of all deviations in the drawings and specifications from the City, County and State Laws, Ordinances, Regulations or Rulings. This Contractor shall install all work strictly in accordance with all such requirements at no additional cost to Owner.
- E. In the event the specifications or drawings conflict with such laws or ordinances, the conflicting portion of the work affected shall be installed in strict accordance with the laws or ordinances above mentioned and the remainder of the drawings and specifications shall remain in full force.
- F. If the requirements of these specifications or drawings are more stringent than the conflicting laws or ordinances, the requirements of the specifications and drawings shall govern unless amended by the Engineer.

1.2 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and the Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.3 SUMMARY

- A. This Section includes the following basic mechanical materials and methods to complement other Division 21 Sections.
 - 1. Piping materials and installation instructions common to most piping systems.
 - 2. Concrete equipment base construction requirements.
 - 3. Equipment nameplate data requirements.

4. Labeling and identifying mechanical systems and equipment is specified in Division 21 Section "Fire Protection Identification."
5. Nonshrink grout for equipment installations.
6. Field-fabricated metal and wood equipment supports.
7. Installation requirements common to equipment specification Sections.
8. Mechanical demolition.
9. Cutting and patching.
10. Touchup painting and finishing.
11. Firestopping

B. Pipe and pipe fitting materials are specified in piping system Sections.

1.4 DEFINITIONS

- A. Pipe, pipe fittings, and piping include tube, tube fittings, and tubing.
- B. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below the roof, spaces above ceilings, unexcavated spaces, crawl spaces, and tunnels.
- C. Exposed Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- D. Exposed Exterior Installations: Exposed to view outdoors, or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- E. Concealed Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in duct shafts.
- F. Concealed Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants, but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.

1.5 MATERIAL AND EQUIPMENT SELECTION

- A. Product Options: The specification of each item of major equipment required for the project may include a list of manufacturers, with one "basis of design" manufacturer, type, and model identified by virtue of their being the first listed manufacturer in the specifications. Where several manufacturers in addition to the "basis of design" manufacturer are listed in the specifications, it shall be understood that the words "or approved equal by" are implied to precede each of the other manufacturer's names.
- B. The manufacturers other than the "basis of design" may be furnished at the contractor's option in lieu of the "basis of design" product, provided that the selected manufacturer's product is equal in all material and functional respects. Additional work required for equipment that is other than the "basis of design", shall be at the expense of the contractor. In addition to submittal requirements that may be specified in this section, submit a line-by-line written verification of the applicable specification section(s) identifying compliance with or variations from the specified features, materials, performance, capacities, weight, size, durability, energy consumption and efficiency,

warranty, and visual impact (if exposed to view by other than maintenance persons). The burden of proof of manufacturer/product equality is on the contractor.

- C. Where a product is not scheduled on the drawings and, therefore, where no “basis of design” is indicated, the first listed manufacturer in the specifications shall be deemed as “basis of design”
- D. Products of manufacturers not listed in the Contract Documents are considered Substitutions and are not permitted, except as provided under the General and Supplementary Conditions and Division 1 Specifications. Full compliance with section “Product Substitutions” below is mandatory for acceptance of products or manufacturers not listed.
- E. Listing of a manufacturer does not imply approval of that manufacturer’s standard product or products. Rather, listing of a manufacturer indicates only a general acceptance of that manufacturer’s name and reputation. Final approval is subject to full compliance with these Contract Documents.
- F. Model numbers identified on the Drawings notwithstanding, all equipment must comply with the requirements of these Contract Documents. Do not assume that a manufacturer’s standard product is acceptable as is. For example, one or more custom modifications, custom colors or finishes, manufacturer’s options, and/or accessories may be required to meet the specified requirements.
- G. Where drawings indicate sizes, profiles, connections, and dimensional requirements of material and equipment, these are based on the “basis of design” manufacturer, type and model indicated. In the event that equipment of power, dimensions, capacities, layout, connections, and/or ratings differing from the “basis of design” are selected by the contractor and approved by the Owner’s representative, any necessary adjustments are the contractor’s responsibility. All connecting mechanical and electrical services, circuit breakers, conduit, motors, bases, pipe and duct sizes, pipe and duct layout, and the like shall be adjusted by the contractor to suit the equipment provided. No additional costs will be approved for these changes. Should revisions to the design because of contractor’s selection of manufacturer, type, or model other than the “basis of design” require additional review and/or redesign by an Architect or Engineer, the contractor shall reimburse the Owner for Owner’s added professional fee expenses.
- H. Where two or more materials are listed in the “Part 2 – Products” subsection of any Division 22 section, do not assume that the selection of materials is the contractor’s option. Refer to “Part 3 – Execution” subsection of that same Division 22 section for an explanation of which specific material(s) shall be used for which specific application(s). For example, Part 2 may list several types and grades of piping, and Part 3 will describe which type and grade of pipe to use for a given application.
- I. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems, and have been coordinated, as much as possible, based on available information and field observations. Deviations to layout that may require additional fittings, and are within 6’-0” of design document layout, shall be at the expense of the contractor. Deviations to layout shall be documented on the coordination drawings. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated, unless deviations to layout are approved on Coordination Drawings.

1.6 SUBSTITUTIONS

- A. Notwithstanding any reference in the specifications to any article, device, product, material, form or type of construction by name, or make, or catalog number, such references shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition; and the Contractor in such cases may, at his option, use any article, device, product, material, fixture, form or type of construction which in the judgment of the Engineer, expressed in writing, is equal to that specified.
- B. Any materials or products other than those specified shall be submitted in writing to the Engineer for approval at least 10 days prior to the submission of bids. Materials and products so approved will be so stated by addendum.
- C. No substitute equipment will be considered unless sufficient data is submitted with the request to allow adequate comparison with the specified equipment.
- D. The Engineer reserves the right to reject any or all substitute equipment, if, in his opinion, said equipment is not of equal quality, capacity or like design. In all cases, the decision of the Engineer shall be final.
- E. This Contractor, at his option, may submit any item of material or equipment in a separate letter listing volunteer alternatives. An add or deduct price shall be indicated for each volunteer alternate submitted. Sufficient data shall accompany each volunteer alternate submitted to allow adequate comparison with the specified equipment. The Contractor shall pay all costs associated with reviewing proposed substitute material or equipment.
- F. This Contractor shall pay all costs arising from the use of substitute equipment or material. Such costs shall include but shall not be limited to architectural design costs, mechanical, electrical, plumbing, fire protection, civil & structural engineering costs & cost to other trades to accommodate the substitute equipment.

1.7 SHOP DRAWINGS

- A. This Contractor shall submit for the Engineer's review a list of all equipment and subcontractors he proposes to use. This list shall be submitted within thirty (30) days after signing of contracts or receiving "Letter of Intent". The engineer will review and comment on this list prior to submission of shop drawings.
- B. After the Contractor has received the comments from the engineer concerning the list of equipment and subcontractors, this Contractor shall submit either 8 hard copies or electronic PDF of complete shop drawings or manufacturer data sheets, certification and descriptive literature for ALL material and equipment furnished on this project:
- C. Shop drawings, manufacturer data sheets and descriptive literature shall include parts lists, operating and maintenance manuals, etc.
- D. The Contractor shall review each shop drawing etc. before submitting to the engineer to determine that it is acceptable in terms of the means, methods, techniques, orientation, sequences, operations of construction, safety precautions and programs incidental there to, all of which are the contractor's responsibility.

- E. The engineer shall review each shop drawing, etc. for its conformity with design intent and compliance with information given in the construction documents.
- F. The Contractor shall bring to the engineer's attention any shop drawing, etc. that varies from the contract documents requirements.
- G. The engineers review time for all submittals will be 10 working days.
- H. The Contractor shall pay for the review of all shop drawings, etc. that varies from the requirements of the contract documents.
- I. Shop drawings, etc. submitted for equipment or material which was not specified, included in the specification or drawings by written addendum, or submitted by separate letter with the contractors bid will be returned without review and will not be considered for this project.
- J. At the completion of the project, this Contractor shall give the Owner three copies of all shop drawings, data sheets, operating manuals, parts lists, maintenance manuals, etc. which shall be bound in vinyl-covered three-ring binders with a complete index and index tabs. All manuals to be submitted to the Engineer's Office for review and acceptance prior to transmittal to the Owner.

1.8 OWNERS RECORD SET OF DRAWINGS

- A. This Contractor shall keep a careful record of all changes in location of all piping, valves, controls, etc. underground and on all floors from that actually shown on the working drawings. Upon completion of this project, this Contractor shall transmit these changes to an electronic medial in PDF format. The set of drawings shall include all drawings, even if no changes were made. Each "record drawing" shall be so labeled, dated and signed by this Contractor.
- B. This Contractor shall indicate all changes to the Architectural backgrounds and Fire Protection systems in the identical manner as the original drawings, i.e., without crossouts, etc. and shall also transcribe to these drawings all change orders.
- C. The cost of the reproductions shall be paid by this Contractor.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end-caps. Maintain end-caps through shipping, storage, and handling to prevent pipe-end damage and prevent entrance of dirt, debris, and moisture.
- B. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. When stored inside, do not exceed structural capacity of the floor.
- C. Protect flanges, fittings, and piping specialties from moisture and dirt.
- D. Protect stored plastic pipes from direct sunlight. Support to prevent sagging and bending.

1.10 SEQUENCING AND SCHEDULING

- A. Coordinate mechanical equipment installation with other building components.
- B. Arrange for chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.
- C. Coordinate the installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- D. Sequence, coordinate, and integrate installations of mechanical materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning prior to closing in the building.
- E. Coordinate connection of electrical services.
- F. Coordinate requirements for access panels and doors where mechanical items requiring access are concealed behind finished surfaces. Access panels and doors are specified in this section.
- G. Coordinate installation of identifying devices after completing covering and painting where devices are applied to surfaces. Install identifying devices prior to installing acoustical ceilings and similar concealment.

1.11 COORDINATION DRAWINGS

- A. Coordination drawings are not required on this project. Contractor shall coordinate their work with the work of other trades. In the event a Contractor fails to coordinate with other trades, he will be held responsible for all costs incurred for adjustments to the work of others made necessary to accommodate the uncooperative Contractor's installations.
- B. The Contractor shall oversee the preparation of coordination drawings as follows:
 - 1. Contractors responsible for the following items of work located in or above ceilings shall participate in preparation of Coordination Drawings.
 - a. Recessed light fixtures.
 - b. Pneumatic tube systems.
 - c. Ductwork and appurtenances.
 - d. Plumbing waste and roof drainage.
 - e. Fire Protection (Sprinkler System).
 - f. HVAC piping
 - g. Plumbing vent, supply and medical gas piping.
 - h. Plumbing domestic water piping.
 - i. Medical gas piping.
 - j. Electrical conduit.
 - 2. The above list, in descending order, is the precedence assigned the work items for space priority. Recessed light fixtures and space for their installation has first priority, pneumatic tube and other record or material conveying systems, second priority, etc. An exception to the precedence listing would be the gravity flow requirements for plumbing waste and roof drainage.

- C. After award of contracts and prior to start of construction, the General Contractor will schedule a meeting with the Contractors responsible for the work items listed above. The purpose of the meeting is to introduce the coordination program and to determine its implementation in relation to the progress schedule.
- D. At the initial coordination meeting, the General Contractor will provide to the HVAC Contractor electronic AutoCAD drawings showing column center lines, interior partition locations, and ceiling heights. The HVAC Contractor, with reference and consideration to the structural, mechanical, electrical, fire protection, plumbing and reflected ceiling plans, will draw, to scale, his proposed installation showing duct sizes, equipment layouts, and dimensions from column lines and from finished floors to bottom of ducts. Ductwork will be maintained as tight as possible to the underside of floor slabs and/or beams. In congested areas, the HVAC Contractor will, in addition, prepare drawings in section view. During this phase of the program, it will be the Electrical Contractor's responsibility to furnish the HVAC Contractor with recessed lighting installation and clearance requirements. This information will be outlined on the drawings by the HVAC Contractor.
- E. The ductwork layouts will be produced in sequence as mandated by the project schedule. The earliest area indicated in the schedule will receive the first effort, etc.
- F. When the ductwork drawings for the earliest scheduled area have been completed (time limitation as determined at the initial coordination meeting), the HVAC Contractor will provide the General Contractor electronic AutoCAD drawing files for each participant in the effort. The General Contractor will distribute the drawings to the participating Contractors for their use in drawing thereon the major components of their proposed installations using the general scheme shown on the Contract Drawings as a guide.
 - 1. The major components to be indicated include (but are not limited to):
 - a. Roof drain leaders
 - b. Large waste piping
 - c. Sprinkler mains
 - d. Heating hot water mains
 - e. Chilled water mains
 - f. Conveying systems
 - g. Significant conduit runs
 - h. Cable trays
 - i. Domestic water mains
 - j. Pneumatic Tube System
 - 2. Information delineated will be distance from column center lines, pipe/equipment size and distance from finished floor to bottom of pipe/equipment.
- G. Within a period of not to exceed two (2) weeks after distribution of the drawings, the General Contractor will schedule a meeting with the participating Contractors at which time, the drawings will be overlaid to identify areas of conflict. All parties including ceiling contractor will then cooperate in resolving the conflicts. Records of the agreements will be entered on the HVAC Contractor's AutoCAD drawings, acknowledged by all participants by signature in a space provided for this purpose, and two (2) blue-line copies distributed to all involved parties. All drawing reproduction costs will be borne by the General Contractor. The above drawing review and coordination process will be repeated until all areas on the Project have been coordinated.

- H. In the event a Contractor fails to cooperate in the Coordination Program, he will be held responsible for all costs incurred for adjustments to the work of others made necessary to accommodate the uncooperative Contractor's installations.
- I. When a Change Order request is issued, the affected Contractors shall review the Coordination Drawings and bring to the attention of the General Contractor any revisions necessary to the work of others not directly affected by the Change Order.

PART 2 - PRODUCTS

2.1 PIPE AND PIPE FITTINGS

- A. Refer to individual piping system specification Sections for pipe and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.2 JOINING MATERIALS

- A. Refer to individual piping system specification Sections in Division 21 for special joining materials not listed below.
- B. Pipe Flange Gasket Materials: Suitable for the chemical and thermal conditions of the piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch (3mm) maximum thickness, except where thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125 cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250 cast-iron and steel flanges.
 - 2. ASME B16.20 for grooved, ring-joint, steel flanges.
 - 3. AWWA C110, rubber, flat face, 1/8 inch (3 mm) thick, except where other thickness is indicated; and full-face or ring type, except where type is indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, stainless steel, except where other material is indicated.
- D. Brazing Filler Metals: AWS A5.8.
 - 1. BCuP Series: Stay Silv 15
 - 2. BAg1: Silver alloy.
- E. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- F. Solvent Cements: Manufacturer's standard solvents complying with the following:
 - 1. Chlorinated Poly(Vinyl Chloride) (CPVC): ASTM F 493.
- G. Flanged, Ductile-Iron Pipe Gasket, Bolts, and Nuts: AWWA C110, rubber gasket, carbon steel bolts and nuts.
- H. Couplings: Iron body sleeve assembly, fabricated to match outside diameters of plain-end pressure pipes.

1. Sleeve: ASTM A 126, Class B, gray iron.
2. Followers: ASTM A 47 (ASTM A 47M), Grade 32510 or ASTM A 536 ductile iron.
3. Gaskets: Rubber.
4. Bolts and Nuts: AWWA C111.
5. Finish: Enamel paint.

2.3 PIPING SPECIALTIES

- A. Escutcheons: Manufactured wall, ceiling, and floor plates; deep-pattern type where required to conceal protruding fittings and sleeves.
 1. Inside Diameter: Closely fit around pipe, tube, and insulation.
 2. Outside Diameter: Completely cover opening.
 3. Cast Brass: One-piece, with set-screw.
 - a. Finish: Polished chrome plate.
 4. Cast Brass: Split casting, with concealed hinge and set-screw.
 - a. Finish: Polished chrome plate.
- B. Dielectric Fittings: Assembly or fitting having insulating material isolating joined dissimilar metals to prevent galvanic action and stop corrosion.
 1. Description: Combination of copper alloy and ferrous; threaded, solder, plain, and weld neck end types and matching piping system materials.
 2. Insulating Material: Suitable for system fluid, pressure, and temperature.
 3. Dielectric Unions: Factory-fabricated, union assembly for 250-psig (1725kPa) minimum working pressure at a 180 deg F (82 deg C) temperature.
 4. Dielectric Flanges: Factory-fabricated, companion-flange assembly for 150- or 300-psig (1035kPa or 2070kPa) minimum pressure to suit system pressures.
 5. Dielectric-Flange Insulation Kits: Field-assembled, companion-flange assembly, full-face or ring type. Components include neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - a. Provide separate companion flanges and stainless steel bolts and nuts for 150- or 300-psig (1035kPa or 2070kPa) minimum working pressure to suit system pressures.
 6. Dielectric Couplings: Galvanized-steel coupling, having inert and noncorrosive, thermoplastic lining, with threaded ends and 300-psig (2070kPa) minimum working pressure at 225 deg F (107 deg C) temperature.
 7. Dielectric Nipples: Electroplated steel nipple, having inert and noncorrosive thermoplastic lining, with combination of plain, threaded, or grooved end types and 300-psig (2070kPa) working pressure at 225 deg F (107 deg C) temperature.
- C. Mechanical Sleeve Seals: Modular, watertight mechanical type. Components include interlocking synthetic rubber links shaped to continuously fill annular space between pipe and sleeve. Connecting bolts and pressure plates cause rubber sealing elements to expand when tightened.
- D. Sleeves: The following materials are for wall, floor, slab, and roof penetrations:
 1. Steel Sheet-Metal: 24-gage (0.70mm) or heavier galvanized sheet metal, round tube closed with welded longitudinal joint.
 2. Steel Pipe: ASTM A 53, Type E, Grade A, Schedule 40, galvanized, plain ends.
 3. Cast-Iron: Cast or fabricated wall pipe equivalent to ductile-iron pressure pipe, having plain ends and integral water stop, except where other features are specified.

4. Wall Penetration Systems: Wall sleeve assembly, consisting of housing, gaskets, and pipe sleeve, with 1 mechanical-joint end conforming to AWWA C110 and 1 plain pipe-sleeve end.
 - a. Penetrating Pipe Deflection: 5 percent without leakage.
 - b. Housing: Ductile-iron casting having waterstop and anchor ring, with ductile-iron gland, steel studs and nuts, and rubber gasket conforming to AWWA C111, of housing and gasket size as required to fit penetrating pipe.
 - c. Pipe Sleeve: AWWA C151, ductile-iron pipe.
 - d. Housing-to-Sleeve Gasket: Rubber or neoprene push-on type of manufacturer's design.
5. Cast-Iron Sleeve Fittings: Commercially made sleeve having an integral clamping flange, with clamping ring, bolts, and nuts for membrane flashing.
6. Underdeck Clamp: Clamping ring with set-screws.
7. PVC Plastic: Manufactured, permanent, with nailing flange for attaching to wooden forms.
8. PVC Plastic Pipe: ASTM D 1785, Schedule 40.
9. PE Plastic: Manufactured, reusable, tapered, cup-shaped, smooth outer surface, with nailing flange for attaching to wooden forms.

2.4 GROUT

- A. Nonshrink, Nonmetallic Grout: ASTM C 1107, Grade B.
 1. Characteristics: Post-hardening, volume-adjusting, dry, hydraulic-cement grout, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 2. Design Mix: 5000-psi (34.50MPa), 28-day compressive strength.
 3. Packaging: Premixed and factory-packaged.

PART 3 - EXECUTION

3.1 PIPING SYSTEMS--COMMON REQUIREMENTS

- A. General: Install piping as described below, except where system Sections specify otherwise. Individual piping system specification Sections in Division 21 specify piping installation requirements unique to the piping system.
- B. General Locations and Arrangements: Drawings (plans, schematics, and diagrams) indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated, except where deviations to layout are approved on coordination drawings.
- C. Install piping at indicated slope.
- D. Install components having pressure rating equal to or greater than system operating pressure.
- E. Install piping in concealed interior and exterior locations, except in equipment rooms and service areas.
- F. Install piping free of sags and bends.

- G. Install exposed interior and exterior piping at right angles or parallel to building walls. Diagonal runs are prohibited, except where indicated.
- H. Install piping tight to slabs, beams, joists, columns, walls, and other building elements. Allow sufficient space above removable ceiling panels to allow for ceiling panel removal.
- I. Install piping to allow application of insulation plus 1-inch (25mm) clearance around insulation.
- J. Locate groups of pipes parallel to each other, spaced to permit valve servicing.
- K. Install fittings for changes in direction and branch connections.
- L. Install couplings according to manufacturer's printed instructions.
- M. Install pipe escutcheons for pipe penetrations of concrete and masonry walls, wall board partitions, and suspended ceilings according to the following:
 - 1. Chrome-Plated Piping: Cast-brass, one-piece, with set-screw, and polished chrome-plated finish. Use split-casting escutcheons, where required, for existing piping.
 - 2. Uninsulated Piping Wall Escutcheons: Cast-brass or stamped-steel, with set-screw.
 - 3. Uninsulated Piping Floor Plates in Utility Areas: Cast-iron floor plates.
 - 4. Insulated Piping: Cast-brass or stamped-steel, with concealed hinge, spring clips, and chrome-plated finish.
 - 5. Piping in Utility Areas: Cast-brass or stamped-steel, with set-screw or spring clips.
- N. Sleeves are not required for core drilled holes.
- O. Above Grade, Exterior Wall, Pipe Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Size sleeve for 1-inch (25mm) annular clear space between pipe and sleeve for installation of mechanical seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches (150 mm).
 - 2. Install cast-iron wall pipes for sleeves 6 inches (150 mm) and larger.
 - 3. Assemble and install mechanical seals according to manufacturer's printed instructions.
- P. Fire Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestopping sealant material.
- Q. Verify final equipment locations for roughing in.
- R. Refer to equipment specifications in other Sections for roughing-in requirements.
- S. Piping Joint Construction: Join pipe and fittings as follows and as specifically required in individual piping system Sections.
 - 1. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
 - 2. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
 - 3. Soldered Joints: Construct joints according to AWS "Soldering Manual," Chapter 22 "The Soldering of Pipe and Tube."
 - 4. Brazed Joints: Construct joints according to AWS "Brazing Manual" in the "Pipe and Tube" chapter.

5. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full inside diameter. Join pipe fittings and valves as follows:
 - a. Note the internal length of threads in fittings or valve ends, and proximity of internal seat or wall, to determine how far pipe should be threaded into joint.
 - b. Apply appropriate tape or thread compound to external pipe threads (except where dry seal threading is specified).
 - c. Align threads at point of assembly.
 - d. Tighten joint with wrench. Apply wrench to valve end into which pipe is being threaded.
 - e. Damaged Threads: Do not use pipe or pipe fittings having threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
 6. Welded Joints: Construct joints according to AWS D10.12 "Recommended Practices and Procedures for Welding Low Carbon Steel Pipe" using qualified processes and welding operators according to the "Quality Assurance" Article.
 7. Flanged Joints: Align flange surfaces parallel. Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Assemble joints by sequencing bolt tightening to make initial contact of flanges and gaskets as flat and parallel as possible. Use suitable lubricants on bolt threads. Tighten bolts gradually and uniformly using torque wrench.
 8. Plastic Pipe and Fitting Solvent-Cement Joints: Clean and dry joining surfaces by wiping with clean cloth or paper towels. Join pipe and fittings according to the following standards:
 - a. Chlorinated Poly(Vinyl Chloride) (CPVC): ASTM D 2846 and ASTM F 493.
- T. Piping Connections: Except as otherwise indicated, make piping connections as specified below.
1. Install unions in piping 2 inches (50 mm) and smaller adjacent to each valve and at final connection to each piece of equipment having a 2-inch (50mm) or smaller threaded pipe connection.
 2. Install flanges in piping 2-1/2 inches (65 mm) and larger adjacent to flanged valves and at final connection to each piece of equipment having flanged pipe connection.
 3. Dry Piping Systems (Gas, Compressed Air, and Vacuum): Install dielectric unions and flanges to connect piping materials of dissimilar metals.
 4. Wet Piping Systems (Water): Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

3.2 EQUIPMENT INSTALLATION--COMMON REQUIREMENTS

- A. Install equipment to provide the maximum possible headroom where mounting heights are not indicated.
- B. Install equipment according to approved submittal data. Portions of the Work are shown only in diagrammatic form. Refer conflicts to the Architect.
- C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, except where otherwise indicated.
- D. Install mechanical equipment to facilitate servicing, maintenance, and repair or replacement of equipment components. Connect equipment for ease of disconnecting, with minimum of interference with other installations. Extend grease fittings to an accessible location.

- E. Install equipment giving right-of-way to piping systems installed at a required slope.

3.3 PAINTING AND FINISHING

- A. Damage and Touch Up: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.4 CONCRETE BASES

- A. All concrete equipment bases will be furnished and installed by the contractor for concrete work. It will, however, be the responsibility of this Contractor to provide the concrete contractor with the exact location and size of all bases required after the purchased equipment is known.
- B. All concrete equipment bases shall be furnished and installed by this Contractor. Bases shall be reinforced with 10/10 steel mesh. Edges shall have a 1"-45° champher. The top surface shall have a steel trowel finish. The exact exact size and location of all bases shall be determined after the purchased equipment is known and prior to pouring the bases.
- C. Bases of insufficient size for the equipment which it was designed to support shall be removed and a new base of adequate size installed.
- D. Construct concrete equipment bases less than 4 inches (100 mm) larger than supported unit in both directions. Follow supported equipment manufacturer's setting templates for anchor bolt and tie locations. Use 3000-psi (20.70MPa), 28-day compressive strength concrete and reinforcement as specified in Division 3 Section "Cast-in-Place Concrete."

3.5 ERECTION OF METAL SUPPORTS AND ANCHORAGE

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor mechanical materials and equipment.
- B. Field Welding: Comply with AWS D1.1 "Structural Welding Code--Steel."

3.6 DEMOLITION

- A. Disconnect, demolish, and remove work specified under Division 21 and as indicated.
- B. Where pipe, ductwork, insulation, or equipment to remain is damaged or disturbed, remove damaged portions and install new products of equal capacity and quality.
- C. Accessible Work: Remove indicated exposed pipe and ductwork in its entirety.
- D. Removal: Remove indicated equipment from the Project site.
- E. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.

3.7 CUTTING AND PATCHING

- A. This Contractor shall sleeve all holes in the new construction for the installation of his work.
- B. This Contractor shall cut all holes in floors, walls, ceiling, and roof necessary for the installation of the work in the existing building, except work shown on the Architectural Wrecking Drawings to be performed by the General Contractor.
- C. The holes for piping shall be cut with a diamond edge core drill. Under no circumstances shall a pneumatic or electric hammer be used to cut holes in walls or floors with the exception of the floor on ground. Saw cutting of concrete slab on grade will not be required; however, the floors shall be scored with a sharp instrument to outline the trench before breaking floor to obtain a fairly straight line trench. Provide watertight receptacle, wedged to bottom of structure, where core drilling occurs; preventing water from staining finishes of floors below.
- D. Before cutting holes in floors and ceilings; make careful field measurements at floor and ceiling to determine location of structural beams, and under no circumstances shall structural beams be cut or damaged during the cutting of these holes.
- E. This Contractor shall coordinate the cutting of existing construction with the (Construction Manager, Owner, General Contractor) and shall obtain approval prior to commencing any demolition work.
- F. The patching of all holes shall be by this Contractor. Where holes are left after removal of pipes or equipment, the openings shall be closed. All plaster ceiling, ceiling tile, floor tile, wall covering, etc. which must be removed in areas which will not receive new finishes under the General Contract Work must be replaced by this Contractor including all necessary painting to match existing colors. If the painted area does not blend into and match the adjacent area of a ceiling panel or wall panel, the entire ceiling or wall panel must be repainted. All such patching and painting shall restore areas to like conditions at time of starting work, subject to the direction and satisfaction of the Architect and Owner. This Contractor shall hire mechanics skilled in their trades to perform all patching work and painting where required. Refer to the Architectural Plans and to the Room Finish Schedules to determine the scope of other Contractors work.
- G. Where holes are left after removal of pipes or plumbing equipment or due to revisions, alteration, changes or errors, the openings shall be closed.
- H. This Contractor shall hire mechanics skilled in their trades to perform all patching such as concrete work, plastering, painting, etc. Such patching shall restore areas to like conditions at time of starting work, and shall be subject to the approval of the Architect.

3.8 CAULKING AND SEALANT

- A. Refer to Division 7 specifications for fire caulk requirements.

3.9 ACCESS TO EQUIPMENT

- A. All control devices, specialties, etc., shall be so located as to provide for easy access for operation, repair and maintenance; if concealed, access doors shall be provided by this Contractor.

- B. The doors shall be Acudor Products Inc (www.acudor.com) of the following types:
 - 1. Plaster ceilings-----Type "PS5030"
 - 2. Plaster walls-----Type "PS5030"
 - 3. Masonry walls-----Type "UF5000"
 - 4. Gypsum drywall walls-----Type "DW5040"
 - 5. Gypsum drywall ceilings-----Type "DW5040"
 - 6. Gypsum drywall above finished ceiling -----Type "UF5000"
- C. No access doors shall be smaller than 18" x 18".
- D. SPECIAL NOTE: Install "FW5050" "B" labeled access doors in all 1-hour and 2 -hour fire rated walls and ceilings.
- E. Furnish all ceiling panels with a factory applied baked-on off-white enamel finish, and all wall panels with a factory applied prime coat, baked-on enamel finish.
- F. Where valves, control devices, etc., are located above removable ceiling panels, this Contractor shall furnish and install color coded screws or tacks installed in the ceiling tile to identify the location.
- G. All access panels will be installed by the contractor for the installation of the walls or the ceilings in locations designated by this Contractor.
- H. Comparable access panels by Cesco or Milcor will be acceptable.

3.10 GROUTING

- A. Install nonmetallic nonshrink grout for mechanical equipment base bearing surfaces, pump and other equipment base plates, and anchors. Mix grout according to manufacturer's printed instructions.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms for placement of grout, as required.
- D. Avoid air entrapment when placing grout.
- E. Place grout to completely fill equipment bases.
- F. Place grout on concrete bases to provide a smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout according to manufacturer's printed instructions.

END OF SECTION 21 05 00

This page intentionally left blank.

SECTION 210549

FIRE PROTECTION SYSTEMS

SUPPORTS, BRACING AND SEISMIC RESTRAINTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. ASCE (American Society of Civil Engineers) 7 - Minimum Design Loads for Buildings and Other Structures Latest Edition.
- C. SMACNA Seismic Restraint Manual Guidelines for Mechanical Systems (latest edition).
- D. International Code Council (ICC) Evaluation Service Program-provided seismic restraint, anchorage, and only bracing guidelines and details (latest editions).
- E. Office of Statewide Health Planning and Development published seismic restraint manuals, guidelines and details (latest editions).

1.2 SUMMARY

- A. This Section includes designing, furnishing, and installing the following:
 - 1. Hangers and supports for mechanical (HVAC or process) and plumbing or fire protection equipment and systems.
 - 2. Seismic restraints for mechanical (HVAC or process) and plumbing or fire protection equipment and systems.
 - 3. Concrete bases for mechanical, plumbing or fire protection equipment.

1.3 DEFINITIONS

- A. ASTM: American Society for Testing and Materials
- B. AWS: American Welding Society
- C. CHECK THE FOLLOWING CODE (Coordinate with ASCE Code Reference Above)
- D. IBC: International Building Code (2015 IBC).
- E. ICC: International Code Council.
- F. MFMA: Metal Framing Manufacturer's Association.

- G. MSS: Manufacturer's Standardization Society.
- H. NBC: National Building Code (latest edition).
- I. NFPA: National Fire Protection Association.
- J. OSHPD: Office of Statewide Health Planning and Development.
- K. SBC: Standard Building Code (latest edition).
- L. Seismic Restraint: A structural support element (such as a metal framing member, a cable, an anchor bolt or stud, a fastening device, or an assembly of these items) used to transfer seismic forces from an item of equipment or system to a building structural element and/or to limit movement of such item during a seismic event.
- M. SMACNA: Sheet Metal and Air Conditioning Contractor's National Association.
- N. UBC: Uniform Building Code (latest edition).

1.4 SUBMITTALS

- A. Product Data submitted shall illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of electrical support or seismic-restraint component used:
 - 1. Tabulate types, sizes and points of application of all seismic restraints, anchorages, sway bracing and other support elements to be used complete with report on numbers and rated strength in tension and shear, as evaluated by an agency acceptable to authorities having jurisdiction.
 - 2. Annotate to indicate application point of each product submitted and to document compliance with requirements.
- B. Shop Drawings submitted shall indicate materials and dimensions as well as identify hardware, (including attachment and anchorage devices), identify seismic support locations, all signed and sealed by a qualified registered professional engineer. Professional engineer qualification requirements are specified in Division 1 of this Specification include the following, as a minimum:
 - 1. Fabricated Supports: Representations of field-fabricated supports for all required locations.
 - 2. Seismic Restraints: Detailing anchorage bracing, and location. Include the following:
 - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads. Include location of designed restraint.
 - b. Details: Fabrication and arrangement, as well as attachments of restraints to the restrained items and to the structure shall be detailed. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events.
 - c. Pre-approval and Evaluation Documentation from by an agency acceptable to authorities having jurisdiction shall be submitted, showing maximum ratings of restraint items and the basis for approval (tests or calculations).
 - d. Location: Identify by tables or drawings all required seismic restraint locations and associated restraints for this Project.

3. Contractor is hereby cautioned that the design of the anchorages, sway bracing, seismic restraints, and other support elements required to be completed under this Section of this Specification by a qualified, registered professional engineer may NOT be accomplished solely by means of general references to published design manuals, tables, standard details, or other such references from Accepted Engineering Practice documents. However, incorporating such information, tables, details, or other published reference material directly into the specific design of such anchorages, sway bracing, seismic restraints, and other support elements required to be completed under this Section of this Specification (that will ultimately be signed and sealed by the registered professional engineer prior to submittal) is permissible.
- C. Coordination Drawings shall show coordination of seismic bracing for mechanical, plumbing and fire protection components with other systems and equipment in the vicinity, including other supports and seismic restraints.
- D. Welding certificates shall be submitted, as appropriate.
- E. Qualification Data for registered professional design engineer and testing agency shall be submitted.
- F. Field quality-control test reports shall be submitted.

1.5 QUALITY ASSURANCE

- A. Comply with seismic-restraint requirements in the IBC, unless requirements in these Contract Documents are more stringent.
- B. Testing of Seismic Anchorage Devices: Comply with testing requirements in Part 3 of this Specification Section.
- C. Welding: Qualify welding procedures and welding personnel capabilities according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Seismic restraint devices shall have been subjected to both horizontal and vertical load testing and analysis acceptable to authorities having jurisdiction, showing maximum seismic restraint ratings.
- E. Ratings based on independent testing are preferred to ratings based on calculations. Testing and/or calculations must include both shear and tensile loads (including combined shear and tensile loads), and one test or analysis at 45 degrees to the weakest mode.

1.6 PROJECT CONDITIONS

- A. See Table(s) on Contract Drawings for specific project conditions.
- B. Site Class = D.
- C. Spectral Response Factors:
 1. See geotechnical report or structural drawings

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists of acceptable manufacturers, the following requirements apply to product selection:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified or Engineer-approved equal.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Rated Strength: Adequate tension, shear, and pullout force to resist maximum loads calculated or imposed on mechanical and plumbing system components for this Project, with a minimum structural safety factor of five (5) times the applied force.
- B. Steel Slotted Support Systems shall comply with MFMA-3, factory-fabricated components for field assembly.
 - 1. Acceptable Manufacturers:
 - a. Cooper B-Line; a division of Cooper Industries.
 - b. ERICO International Corporation.
 - c. Allied Support Systems; Power-Strut Unit.
 - d. GS Metals Corp.
 - e. Michigan Hanger Co., Inc.; O-Strut Div.
 - f. National Pipe Hanger Corp.
 - g. Thomas & Betts Corporation.
 - h. Unistrut; Tyco International, Ltd.
 - i. Wesanco, Inc.
 - j. Engineer-approved equal.
 - 2. Finishes:
 - a. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-3.
 - b. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-3.
 - 3. Channel Dimension shall be selected for structural loading condition and applicable seismic forces.
- C. Raceway and Cable Tray Support shall be as described in the IBC and ASCE 7 documents.
- D. Conduit and Cable Support Device shall be steel hangers, clamps, and associated fittings, specifically designed for the types and sizes of raceway or pipe to be supported.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Requirements for items for fastening mechanical or plumbing items or their supports to building surfaces shall include the following:
 - 1. Verify suitability of all fasteners for use with lightweight concrete or concrete slabs less than 4 inches thick.

2. Powder-Actuated Fasteners shall be threaded-steel stud, for use in hardened portland cement concrete, steel, or wood; with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - a. Acceptable Manufacturers:
 - 1) Hilti, Inc.
 - 2) ITW Construction Products.
 - 3) MKT Fastening, LLC.
 - 4) Simpson Strong-Tie Co. Inc.
 - 5) Engineer-approved equal.
3. Mechanical-Expansion Anchors shall be insert-wedge-type, stainless steel, for use in hardened portland cement concrete; with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
 - a. Acceptable Manufacturers:
 - 1) Cooper B-Line; a division of Cooper Industries.
 - 2) Empire Tool and Manufacturing Co., Inc
 - 3) Hilti, Inc.
 - 4) ITW Construction Products.
 - 5) MKT Fastening, LLC.
 - 6) Powers Fasteners.
 - 7) Engineer-approved equal.
4. Concrete Inserts shall be steel or malleable-iron slotted-support-system units similar to MSS Type 18; complying with MFMA-3 or MSS SP-58.
5. Clamps for Attachment to Steel Structural Elements shall conform to MSS SP-58, type suitable for attached structural element.
6. Through Bolts shall be structural type, hex head, high-strength. Comply with ASTM A 325.
7. Toggle Bolts shall be all-steel springhead type.
8. Hanger Rods shall be threaded steel.

2.3 SEISMIC RESTRAINT COMPONENTS

- A. Manufacturers:
 1. Amber/Booth Company, Inc.
 2. B-Line Systems, Inc.
 3. California Dynamics Corp.
 4. Kinetics Noise Control, Inc.
 5. Loos & Co., Inc.; Cableware Technology Division.
 6. Mason Industries, Inc.
 7. Unistrut Diversified Products Co.; Wayne Manufacturing Division.
 8. Vibration Eliminator Co., Inc.
 9. Vibration Isolation Co., Inc.
 10. Vibration Mountings & Controls/Korfund.
- B. Rated Strength, Features, and Application Requirements for Restraint Components shall be as defined by an agency acceptable to authorities having jurisdiction.
 1. Structural Safety Factor: Strength in tension, shear, and pullout force of components used shall be at least five (5) times the maximum seismic forces to which they will be subjected.

- C. Angle and Channel-Type Brace Assemblies: Steel angles or steel slotted-support-system components; with accessories for attachment to braced component at one end and to building structure at the other end.
- D. Cable Restraints: ASTM A 603, zinc-coated, steel wire rope attached to steel or stainless-steel thimbles, brackets, swivels, and bolts designed for restraining cable service.
- E. Seismic Mountings, Anchors, and Attachments: For this application, items shall be selected to resist seismic forces.
 - 1. Hanger Rod Stiffeners shall be steel tube or steel slotted-support-system sleeves with internally bolted connections or reinforcing steel angle clamped to hanger rod, of design recognized by an agency acceptable to authorities having jurisdiction.
 - 2. Bushings for Floor-Mounted Equipment Anchors shall be neoprene units designed for seismically rated rigid equipment mountings, and matched to type and size of anchor bolts and studs used.
 - 3. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves shall be designed for seismically-rated rigid equipment mountings, and matched to type and size of attachment devices used.
- F. Seismic Snubbers: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.
 - 1. Anchor bolts for attaching to concrete shall be seismic-rated, drill-in, and stud-wedge or female-wedge type.
 - 2. Resilient Isolation Washers and Bushings: 1-piece, molded, bridge-bearing neoprene complying with AASHTO M 251 and having a durometer of 50, plus or minus 5.

2.4 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

PART 3 - EXECUTION

3.1 GENERAL REQUIREMENTS

- A. Comply with IBC for specific application requirements for hangers and supports for mechanical and plumbing equipment and systems, except if requirements in these Contract Documents are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway or Pipes: Space supports as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- C. Multiple Raceways or Pipes: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits; and:
 - 1. Secure raceways and pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
 - 2. Secure raceways and pipes to these supports with two-bolt pipe clamps.

- D. Spring-steel clamps designed for supporting single pipes without bolts may be used for 1-1/2-inch and smaller raceways, and for fastening raceways to trapeze supports.
- E. Install all supports, restraints, attachments, and other elements specified in this Section of this Specification in strict conformance with the written installation requirements of the manufacturers of each support, restraint, attachment, or other element.

3.2 SUPPORT AND SEISMIC RESTRAINT INSTALLATION

- A. Comply with SMACNA and MSS for installation requirements, except as otherwise specified in this Article of this Section of this Specification.
- B. Install seismic restraint components using methods approved by the evaluation service providing required submittals for component.
- C. Strength of Support and Seismic Restraint Assemblies: Where not otherwise indicated, select sizes of components so that strength will be adequate to carry present and future static and seismic loads within specified loading limits. Minimum static design load used for strength determination shall be the weight of the supported components plus 200 lb.
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten mechanical and plumbing items and their supports to building structural elements by the following methods, unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To New Concrete: Bolt to concrete inserts.
 - 3. To Masonry: Use approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4. To Existing Concrete: Fasten with expansion anchors.
 - 5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches thick.
 - 6. To Steel: Use welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts or beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69 or Spring-tension clamps.
 - 7. To Light Steel: Use sheet metal screws.
 - 8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount such devices on slotted-channel racks attached to substrate by means that meet seismic restraint strength and anchorage requirements.
- E. Drill holes for expansion anchors in reinforced concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- B. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

- A. Concrete Bases: Anchor equipment to concrete base according to equipment manufacturer's written instructions and seismic requirements for Project.
- B. Construct concrete bases of dimensions indicated but not less than 4 inches larger in both directions than supported unit, and such that expansion anchors will be a minimum of 10 bolt diameters from edge of the base; and:
 - 1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around full perimeter of the base.
 - 2. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base, and anchor into structural concrete floor.
 - 3. Place and secure anchorage devices using the equipment to be supported manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - 5. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
 - 6. Use 3000-psi, 28-day compressive-strength concrete, minimum.

3.5 INSTALLATION OF SEISMIC RESTRAINT COMPONENTS

- A. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- B. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- C. Restraint Cables shall be installed with slack within maximum tolerance recommended by cable manufacturer.
- D. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, upper truss chords of bar joists, or at concrete members.

3.6 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Make flexible connections in runs of raceways and piping where they cross expansion and seismic control joints, where adjacent sections or branches are supported by different structural elements, and where they terminate with connection to mechanical and plumbing equipment that is anchored to a different structural element from the one supporting them as they approach equipment.

3.7 FIELD QUALITY CONTROL TESTS

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Record test results and submit to Engineer.
- C. Test pullout resistance of seismic anchorage devices, and:

1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
2. Schedule test with Owner and Engineer present before connecting anchorage devices to components to be restrained (unless post-connection testing has been approved by Engineer in advance). Provide at least 7 days advance notice of scheduled test.
3. Obtain Engineer's concurrence before transferring test loads to structure. Provide temporary load-spreading members.
4. Test at least four of each type and size of installed anchorages and fasteners.
5. Test anchorages and fasteners to 90 percent of rated proof load of item.
6. If any item fails test, modify all installations of same type for project, then retest item until satisfactory test result is achieved.

3.8 PAINTING AND FINISHING

- A. Refer to Section 09900 – Protective Coatings of this Specification for field painting requirements.
- B. Damage and Touch-Up: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.9 CUTTING AND PATCHING

- A. Cut, channel, chase, and drill floors, walls, partitions, ceilings, and other surfaces necessary for mechanical installations. Perform cutting by skilled mechanics of the trades involved.
- B. Repair cut surfaces to match adjacent surfaces.

3.10 GROUTING

- A. Install non-metallic, non-shrink grout for mechanical equipment base bearing surfaces, pump and other equipment base plates and anchors. Mix grout according to manufacturer's printed instructions.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms for placement of grout, as required.
- D. Avoid air entrapment when placing grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases to provide a smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout according to manufacturer's printed instructions.

3.11 ERECTION OF WOOD SUPPORTS AND ANCHORAGE

- A. Cut, fit, and place wood grounds, nailers, blocking, and anchorage to support and anchor mechanical materials and equipment.
- B. Select fastener sizes that will not penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood members.
- C. Attach to substrates as required to support applied loads.

END OF SECTION 210549

SECTION 21 06 00

HANGERS AND SUPPORTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes hangers and supports for mechanical system piping and equipment.
- B. Related Sections include the following:
 - 1. Division 5 Section "Metal Fabrications" for materials for attaching hangers and supports to building structure.
 - 2. Division 21 Sections on fire-suppression piping for fire-suppression pipe hangers.
 - 3. Section 21 05 48 "Mechanical Systems Vibration Control" for vibration isolation.
 - 4. Section 21 05 49 "Fire Protection Systems; Supports, Bracing and Seismic Requirements".
 - 5. Section 21 05 00 "Common Work Requirements for Fire Protection".

1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for the Valve and Fittings Industry.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.4 PERFORMANCE REQUIREMENTS

- A. Design channel support systems for piping to support multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
- B. Design heavy-duty steel trapezes for piping to support multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
- C. Design seismic restraint hangers and supports for piping and equipment.
- D. Design and obtain approval from authorities having jurisdiction for seismic restraint hangers and supports for piping and equipment.

1.5 SUBMITTALS

- A. Product Data: For each type of pipe hanger, channel support system component, and thermal-hanger shield insert indicated.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer for multiple piping supports and trapeze hangers. Include design calculations and indicate size and characteristics of components and fabrication details.
- C. Welding Certificates: Copies of certificates for welding procedures and operators.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
- B. Engineering Responsibility: Design and preparation of Shop Drawings and calculations for each multiple pipe support and trapeze by a qualified professional engineer.
- C. Engineering Responsibility: Design and preparation of Shop Drawings and calculations for each multiple pipe support, trapeze, and seismic restraint by a qualified professional engineer.
 - 1. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of hangers and supports that are similar to those indicated for this Project in material, design, and extent.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Pipe Hangers:
 - a. B-Line Systems, Inc.
 - b. Globe Pipe Hanger Products, Inc.
 - c. Grinnell Corp.
 - d. Michigan Hanger Co., Inc.
 - e. National Pipe Hanger Corp.

2.2 MANUFACTURED UNITS

- A. Pipe Hangers, Supports, and Components: MSS SP-58, factory-fabricated components. Refer to "Hanger and Support Applications" Article in Part 3 for where to use specific hanger and support types.

1. Galvanized, Metallic Coatings: For piping and equipment that will not have field-applied finish.
2. Nonmetallic Coatings: On attachments for electrolytic protection where attachments are in direct contact with copper tubing.

2.3 MISCELLANEOUS MATERIALS

- A. Mechanical-Anchor Fasteners: Insert-type attachments with pull-out and shear capacities appropriate for supported loads and building materials where used.
- B. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars, black and galvanized.
- C. Grout: ASTM C 1107, Grade B, factory-mixed and -packaged, nonshrink and nonmetallic, dry, hydraulic-cement grout.
 1. Characteristics: Post hardening and volume adjusting; recommended for both interior and exterior applications.
 2. Properties: Nonstaining, noncorrosive, and nongaseous.
 3. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger requirements are specified in Sections specifying equipment and systems.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Specification Sections.
- C. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
 1. Adjustable Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 2-1/2 to NPS 30. Provide Plastic coated hangers for hot piping.
 2. Adjustable Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 2. provide plastic coated hangers for hot piping.
 3. Adjustable Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 2.
- D. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
 1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.
- E. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:

1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 2. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 3. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
- F. Building Attachments: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 13. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 14. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where head room is limited.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Pipe Hanger and Support Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Install building attachments within concrete slabs or attach to structural steel. Space attachments within maximum piping span length indicated in MSS SP-69. Install additional attachments at concentrated loads, including valves, flanges, guides, strainers, and expansion joints, and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- C. Install mechanical-anchor fasteners in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- D. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.

- E. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- F. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- G. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and so maximum pipe deflections allowed by ASME B31.9, "Building Services Piping," is not exceeded.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure above or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.

3.4 METAL FABRICATION

- A. Cut, drill, and fit miscellaneous metal fabrications for heavy-duty steel trapezes and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field-weld connections that cannot be shop-welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1 procedures for shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work, and with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections so no roughness shows after finishing and contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustment: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

3.6 PAINTING

- A. Touching Up: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Touching Up: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 9 Section "Painting."

- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 21 06 00

SECTION 21 07 50

FIRE PROTECTION IDENTIFICATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following mechanical identification materials and their installation:
 - 1. Equipment nameplates.
 - 2. Pipe markers.
 - 3. Valve tags.
 - 4. Valve schedules.
 - 5. Warning tags.
- B. Related Sections include the following:
 - 1. Section 21 05 00 "Common Work Requirements for Fire Protection".

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system. Furnish extra copies (in addition to mounted copies) to include in maintenance manuals.

1.4 QUALITY ASSURANCE

- A. ASME Compliance: Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.

1.5 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

- B. Coordinate installation of identifying devices with location of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 EQUIPMENT IDENTIFICATION DEVICES

- A. Equipment Nameplates: Metal, with data engraved or stamped, for permanent attachment on equipment.
 - 1. Data:
 - a. Manufacturer, product name, model number, and serial number.
 - b. Capacity, operating and power characteristics, and essential data.
 - c. Labels of tested compliances.
 - 2. Location: Accessible and visible.
 - 3. Fasteners: As required to mount on equipment.
- B. Equipment Markers: Engraved, color-coded laminated plastic. Include contact-type, permanent adhesive.
 - 1. Terminology: Match schedules as closely as possible.
 - 2. Data:
 - a. Name and plan number.
 - b. Equipment service.
 - c. Design capacity.
 - d. Other design parameters such as pressure drop, entering and leaving conditions, and speed.
 - 3. Size: 2-1/2 by 4 inches for control devices, dampers, and valves; 4-1/2 by 6 inches for equipment.

2.2 PIPING IDENTIFICATION DEVICES

- A. Manufactured Pipe Markers, General: Preprinted, color-coded, with lettering indicating service, and showing direction of flow.
 - 1. Colors: Comply with ASME A13.1, unless otherwise indicated.
 - 2. Lettering: Use piping system terms indicated and abbreviate only as necessary for each application length.
 - 3. Pipes with OD, Including Insulation, Less Than 6 Inches: Full-band pipe markers extending 360 degrees around pipe at each location.
 - 4. Pipes with OD, Including Insulation, 6 Inches and Larger: Either full-band or strip-type pipe markers at least three times letter height and of length required for label.
 - 5. Arrows: Integral with piping system service lettering to accommodate both directions; or as separate unit on each pipe marker to indicate direction of flow.
- B. Pretensioned Pipe Markers: Precoiled semirigid plastic formed to cover full circumference of pipe and to attach to pipe without adhesive.

- C. Shaped Pipe Markers: Preformed semirigid plastic formed to partially cover circumference of pipe and to attach to pipe with mechanical fasteners that do not penetrate insulation vapor barrier.
- D. Self-Adhesive Pipe Markers: Plastic with pressure-sensitive, permanent-type, self-adhesive back.
- E. Plastic Tape: Continuously printed, vinyl tape at least 3 mils thick with pressure-sensitive, permanent-type, self-adhesive back.
 - 1. Width for Markers on Pipes with OD, Including Insulation, Less Than 6 Inches: 3/4 inch minimum.
 - 2. Width for Markers on Pipes with OD, Including Insulation, 6 Inches or Larger: 1-1/2 inches minimum.

2.3 WARNING TAGS

- A. Warning Tags: Preprinted or partially preprinted, accident-prevention tags; of plasticized card stock with matte finish suitable for writing.
 - 1. Size: 3 by 5-1/4 inches minimum.
 - 2. Fasteners: Brass grommet and wire.
 - 3. Nomenclature: Large-size primary caption such as DANGER, CAUTION, or DO NOT OPERATE.
 - 4. Color: Yellow background with black lettering.

PART 3 - EXECUTION

3.1 APPLICATIONS, GENERAL

- A. Products specified are for applications referenced in other Division 15 Sections. If more than single-type material, device, or label is specified for listed applications, selection is Installer's option.

3.2 EQUIPMENT IDENTIFICATION

- A. Install and permanently fasten equipment nameplates on each major item of mechanical equipment that does not have nameplate or has nameplate that is damaged or located where not easily visible. Locate nameplates where accessible and visible. Include nameplates for the following general categories of equipment:
 - 1. Pumps and similar motor-driven units.
- B. Install equipment markers with permanent adhesive on or near each major item of mechanical equipment. Data required for markers may be included on signs, and markers may be omitted if both are indicated.
 - 1. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.

2. Data: Distinguish among multiple units, indicate operational requirements, indicate safety and emergency precautions, warn of hazards and improper operations, and identify units.
3. Locate markers where accessible and visible. Include markers for the following general categories of equipment:
 - a. Main control and operating valves, including safety devices and hazardous units such as gas outlets.
 - b. Fire department hose valves and hose stations.
 - c. Meters, gages, thermometers, and similar units.
 - d. Pumps and similar motor-driven units.

3.3 PIPING IDENTIFICATION

- A. Install manufactured pipe markers indicating service on each piping system. Install with flow indication arrows showing direction of flow.
 1. Pipes with OD Less Than 6 Inches: Pretensioned pipe markers. Use size to ensure a tight fit.
 2. Pipes with OD Less Than 6 Inches: Self-adhesive pipe markers. Use color-coded, self-adhesive plastic tape, at least 3/4 inch wide, lapped at least 1-1/2 inches at both ends of pipe marker, and covering full circumference of pipe.
 3. Pipes with OD 6 Inches and Larger: Shaped pipe markers. Use size to match pipe and secure with fasteners.
 4. Pipes with OD 6 Inches and Larger: Self-adhesive pipe markers. Use color-coded, self-adhesive plastic tape, at least 1-1/2 inches wide, lapped at least 3 inches at both ends of pipe marker, and covering full circumference of pipe.
- B. Locate pipe markers and color bands where piping is exposed in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior nonconcealed locations as follows:
 1. Near each valve and control device.
 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 3. Near penetrations through walls, floors, ceilings, and nonaccessible enclosures.
 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 5. Near major equipment items and other points of origination and termination.
 6. Spaced at maximum intervals of 50 feet along each run.
 7. On piping above removable acoustical ceilings. Omit intermediately spaced markers.

3.4 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

3.5 ADJUSTING

- A. Relocate mechanical identification materials and devices that have become visually blocked by other work.

END OF SECTION 21 07 50

This page intentionally left blank.

SECTION 21 14 00

FIRE PROTECTION METERS AND GAGES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including the General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes meters and gages used in plumbing and fire protection systems.
- B. Related Sections: Division 21 piping Sections contain requirements that relate to this Section.
 - 1. Meters and gages furnished as part of factory-fabricated equipment are specified as part of the equipment assembly in other Division 21 Sections.
 - 2. Section 21 05 00 "Common Work Requirements for Fire Protection".

1.3 SUBMITTALS

- A. General: Submit the following according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product data for each type of meter, gage, and fitting specified. Include scale range, ratings, and calibrated performance curves, certified where indicated. Submit a meter and gage schedule showing manufacturer's figure number, scale range, location, and accessories for each meter and gage.
- C. Product certificates signed by manufacturers of meters and gages certifying accuracies under specified operating conditions and compliance with specified requirements.
- D. Maintenance data to include in the "Operating and Maintenance Manuals" specified in Division 1 Section "Project Closeout." Include data for the following:
 - 1. Pressure gages.

1.4 QUALITY ASSURANCE

- A. Comply with applicable portions of American Society of Mechanical Engineers (ASME) and Instrument Society of America (ISA) standards pertaining to construction and installation of meters and gages.
- B. Design Criteria: Meters and gages having equal performance characteristics by other manufacturers may be considered, provided that deviations do not change the design concept or intended

performance as judged by the Engineer. The burden of proof for equality of meters and gages is on the proposer.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Pressure Gages:
 - a. Ashcroft by Dresser Industries, Instrument Div.
 - b. H.O. Trerice Co.
 - c. Weiss Instruments, Inc.

2.2 PRESSURE GAGES

- A. Description: ASME B40.1, Grade A phosphor-bronze Bourdon-tube pressure gage, with bottom connection.
- B. Case: Drawn steel, brass, or aluminum with 4-1/2-inch (115mm) -diameter glass lens.
- C. Connector: Brass, 1/4-inch (8mm) NPS.
- D. Scale: White-coated aluminum, with permanently etched markings.
- E. Accuracy: Plus or minus 1 percent of range span.
- F. Range: Conform to the following:
 - 1. Fluids Under Pressure: 2 times operating pressure.

2.3 PRESSURE-GAGE ACCESSORIES

- A. Syphons: 1/4-inch (8mm) straight coil of brass tubing with threads on each end.
- B. Snubbers: 1/4-inch (8mm) brass bushing with corrosion-resistant porous-metal disc of material suitable for system fluid and working pressure.

PART 3 - EXECUTION

3.1 METER AND GAGE APPLICATIONS

- A. General: Where indicated, install meters and gages of types, sizes, capacities, and with features indicated.

3.2 METER AND GAGE INSTALLATION, GENERAL

- A. Install meters, gages, and accessories according to manufacturers' written instructions for applications where used.

3.3 PRESSURE GAGE INSTALLATION

- A. Install pressure gages in piping tee with pressure gage valve located on pipe at most readable position.
- B. Install in the following locations and elsewhere as indicated:
 - 1. At suction and discharge of each pump.
 - 2. At building water service entrance.
- C. Pressure Gage Needle Valves: Install in piping tee with snubber. Install syphon instead of snubber for steam pressure gages.

3.4 CONNECTIONS

- A. Piping installation requirements are specified in other Division 15 Sections. The Drawings indicate the general arrangement of piping, fittings, and specialties.
- B. Install meters and gages adjacent to machines and equipment to allow servicing and maintenance.

3.5 ADJUSTING AND CLEANING

- A. Calibrate meters according to manufacturer's written instructions, after installation.
- B. Adjusting: Adjust faces of meters and gages to proper angle for best visibility.
- C. Cleaning: Clean windows of meters and gages and factory-finished surfaces. Replace cracked and broken windows and repair scratched and marred surfaces with manufacturer's touchup paint.

END OF SECTION 21 14 00

This page intentionally left blank.

SECTION 21 32 60

STANDPIPE AND SPRINKLER SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section specifies standpipe and sprinkler systems for buildings and structures.
- B. Products specified in this Section with installation not in Contract include sprinkler cabinets with spare sprinklers and sprinkler wrenches. Deliver to the Owner.
- C. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 28 Section "Fire Alarm Systems" for alarm devices not specified in this Section.
 - 2. Section 21 05 48 "Mechanical Systems Vibration Control" for vibration isolation.
 - 3. Section 21 05 49 "Fire Protection Systems; Supports, Bracing and Seismic Requirements".
 - 4. Section 21 05 00 "Common Work Requirements for Fire Protection".

1.2 DEFINITIONS

- A. Pipe sizes used in this Section are nominal pipe size (NPS) specified in inches. Tube sizes are standard tube sizes specified in inches.
- B. Working plans as used in this Section refer to documents (including drawings and calculations) prepared pursuant to requirements in NFPA 13, Engineer and owners insurance underwriter for obtaining approval of authority having jurisdiction.
- C. Other definitions for fire protection systems are included in referenced NFPA standards.

1.3 SYSTEM DESCRIPTION

- A. Wet-Pipe Sprinkler System: System with automatic sprinklers attached to piping system containing water and connected to water supply so that water discharges immediately from sprinklers when they are opened by fire.
- B. Dry-Pipe Sprinkler System: System with automatic sprinklers attached to piping system containing water with a pre-action or pressure operated discharge valve operated by use of smoke detectors or sprinkler heads so that water discharges from sprinklers when they are opened by fire.
- C. Sprinkler System Protection Limits: All spaces within areas indicated. Include closets, toilet and locker room areas, each landing of each stair, and special applications areas.
- D. Sprinkler System Protection Limits: All spaces within areas indicated. Include closets, toilet areas, each landing of each stair, and special applications areas.

1.4 SYSTEM PERFORMANCE REQUIREMENTS

- A. Design and obtain approval from authority having jurisdiction and Owner for fire protection systems specified.
- B. Minimum Pipe Sizes: Not smaller than sizes indicated for connection to water supply piping, standpipes, and branches from standpipes to sprinklers.
- C. Hydraulically design sprinkler systems according to:
 - 1. Sprinkler System Occupancy Hazard Classifications: As follows:
 - a. Offices & Corridors: Light hazard.
 - b. Storage Areas: Ordinary hazard.
 - c. Equipment Rooms: Ordinary hazard.
 - 2. Minimum Density Requirements for Automatic Sprinkler System Hydraulic Design: As follows:
 - a. Light Hazard Occupancy: 0.10 GPM over 1500 sq. ft.
 - b. Light Hazard Occupancy: 0.15 GPM over 1500 sq. ft.
 - c. Ordinary Hazard, Group 1 Occupancy: 0.15 GPM over 2000 sq. ft.
 - d. Ordinary Hazard, Group 2 Occupancy: 0.20 GPM over 2500 sq. ft.
 - 3. Maximum Sprinkler Spacing: As follows:
 - a. Light Hazard: 200 sq. ft./sprinkler
 - b. Ordinary Hazard: 130 sq. ft./sprinkler
 - c. Mechanical Equipment Rooms: 130 sq. ft./sprinkler (12 sq. m/sprinkler).
 - d. Electrical Equipment Rooms: 130 sq. ft./sprinkler (12 sq. m/sprinkler).
 - e. Other Areas: According to NFPA 13.
- D. Components and Installation: Capable of producing piping systems with the following minimum working pressure ratings except where indicated otherwise.
 - 1. Sprinkler Systems: 175 psig.
 - 2. Standpipe and Hose Systems: 175 psig.

1.5 SUBMITTALS

- A. Product data for fire protection system components. Include the following:
 - 1. Valves.
 - 2. Specialty valves, accessories, and devices.
 - 3. Alarm devices. Include electrical data.
 - 4. Sprinklers, escutcheons, and guards. Include sprinkler flow characteristics, mounting, finish, and other data.
- B. Sprinkler system drawings identified as "working plans," prepared according to NFPA 13. Submit required number of sets to authority having jurisdiction and Owner for review, comment, and approval. Include system hydraulic calculations where applicable.
- A. Licensed engineer's sprinkler system drawings specified in "Quality Assurance" Article to authority having jurisdiction. Include system hydraulic calculations.
- B. Test reports and certificates as described in NFPA 13. Include "Contractor's Material & Test Certificate for Aboveground Piping" and "Contractor's Material & Test Certificate for Underground Piping."

- C. Maintenance data for each type of fire protection specialty specified, for inclusion in Operating and Maintenance Manual specified in Division 1 Section "Project Closeout."

1.6 QUALITY ASSURANCE

- A. Manufacturers: Except for products required to comply with a recognized product listing, provide system products of types and sizes required, whose products have been in satisfactory use in similar service for not less than 5 years.
- B. Local Fire Department/Marshall Regulations: Comply with local regulations for sizes, threading and arrangement of connections for Fire Department equipment to standpipe and sprinkler systems.
- C. NFPA Code: Comply with National Fire Code No. 13 "Standard for the Installation of Sprinkler Systems" and National Fire Code No. 14 "Standpipes and Hose Systems".
- D. FM Approval: Provide fire and sprinkler piping products which have been approved and labeled by Factory Mutual system.
- E. Comply with requirements of authority having jurisdiction and Owner for submittals, approvals, materials, hose threads, installation, inspections, and testing.
- F. Licensed Engineer: Submit design drawings, design calculations, and installation inspection reports. Include seal and signature of registered engineer licensed in jurisdiction where Project is located, certifying compliance with specifications.
- G. Installer's Qualifications: Firms qualified to install and alter fire protection piping, equipment, specialties, and accessories, and repair and service equipment. A qualified firm is one that is experienced (minimum of 5 previous projects similar in size and scope to this Project) in such work, familiar with precautions required, and in compliance with the requirements of the authority having jurisdiction. Submit evidence of qualifications to the Engineer upon request.
- H. NFPA Standards: Equipment, specialties, accessories, installation, and testing complying with the following:
 - 1. NFPA 13 "Standard for the Installation of Sprinkler Systems."
 - 2. NFPA 26 "Recommended Practice for the Supervision of Valves Controlling Water Supplies for Fire Protection."
 - 3. NFPA 70 "National Electrical Code."

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Waterflow Indicators and Supervisory Switches:
 - a. Potter Electric Signal Co.
 - b. Reliable Automatic Sprinkler Co., Inc.
 - 2. Sprinklers:
 - a. Viking Corp.

- b. Central Sprinkler Corp.
 - c. Reliable.
- 3. Fire Protection Service Gate and Check Valves:
 - a. Kennedy Valve Div., McWane, Inc.
 - b. Nibco, Inc.
 - c. Victaulic Company of America.
- 4. Grooved Couplings for Steel Piping:
 - a. Grinnell Supply Sales Co., Grinnell Corp.
 - b. Victaulic Company of America.

2.2 PIPES AND TUBES

- A. Refer to Part 3 Articles "Sprinkler System Piping Applications" for identification of systems where pipe and fitting materials specified below are used.
- B. Steel Pipe: ASTM A 53, Schedule 10 in sizes 3 inches (150 mm) and larger, black and rolled groove joints.
- C. Steel Pipe: ASTM A 53, Schedule 40 in sizes 1-1/2 inches to 2-1/2 inches, black and rolled groove joints.
- D. Steel Pipe: ASTM A53, Schedule 40 in sizes 1-1/4" and smaller, threaded ends for threaded joints.
- E. Malleable-Iron Threaded Fittings: ASME B16.3, Class 125, standard pattern, with threads according to ASME B1.20.1.
- F. Gray-Iron Threaded Fittings: ASME B16.4, Class 125, standard pattern, with threads according to ASME B1.20.1.
- G. Grooved-End Fittings for Steel Pipe: UL-listed and FM-approved, ASTM A 536, Grade 65-45-12 ductile iron or ASTM A 47 Grade 32510 malleable iron, with grooves or shoulders designed to accept grooved couplings.

2.3 JOINING MATERIALS

- A. Refer to Division 15 Section "Basic Mechanical Materials and Methods" for joining materials not included in this Section.
- B. Couplings for Grooved-End Steel Pipe and Grooved-End Ferrous Fittings: UL 213, AWWA C606, ASTM A 536 ductile-iron or ASTM A 47 malleable-iron housing, with enamel finish. Include synthetic-rubber gasket with central-cavity, pressure-responsive design; ASTM A 183 carbon-steel bolts and nuts; and locking pin, toggle, or lugs to secure grooved pipe and fittings. Similar to Victaulic Style 75.

2.4 FIRE PROTECTION SERVICE VALVES

- A. General: UL-listed and FM-approved, with 175-psig non-shock minimum working pressure rating.
 - 1. Option: Valves for use with grooved piping may be grooved type.

- B. Gate Valves, 2 Inches and Smaller: UL 262, cast-bronze, threaded ends, solid wedge, outside screw and yoke, rising stem
- C. Gate Valves, 2-1/2 Inches and Larger: UL 262, iron body, bronze mounted, taper wedge, outside screw and yoke, rising stem. Include replaceable, bronze, wedge facing rings and flanged ends.

2.5 SPRINKLERS

- A. Automatic Sprinklers: With heat-responsive element conforming to:
 - 1. UL 199, for applications except residential, quick response.
- B. Sprinkler types and categories are as indicated and as required by application. Furnish automatic sprinklers with nominal 1/2-inch (12.7 mm) orifice for "Quick Response" "Standard" temperature classification rating except where otherwise indicated and required by application.
- C. Sprinkler types, features, and options include:
 - 1. Concealed ceiling sprinklers, including cover plate.
 - 2. Semi-Recessed sprinklers, including escutcheon plate.
 - 3. Fully Recessed sprinklers, including escutcheon plate.
 - 4. Pendent sprinklers.
 - 5. Upright sprinklers.
- D. Sprinkler Finishes: Chrome-plated, bronze, and painted.
- E. Sprinkler Escutcheons: Materials, types, and finishes for following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.
 - 1. Ceiling Mounting: Chrome-plated steel, 1-piece, flat.
- F. Sprinkler Cabinets: Finished steel cabinet and hinged cover, with space for minimum of 6 spare sprinklers plus sprinkler wrench, suitable for wall mounting. Include number of sprinklers required by NFPA 13 and 1 wrench for sprinklers. Include separate cabinet with sprinklers and wrench for each style sprinkler on Project.

2.6 ALARM DEVICES

- A. Alarm Devices: Types and sizes that will match piping and equipment connections.
- B. Waterflow Indicators: UL 346, electrical-supervision type, vane-type waterflow detector, rated to 250 psig (1725 kPa), and designed for horizontal or vertical installation. Include 2 SPDT (single-pole, double-throw) circuit switches to provide isolated alarm and auxiliary contacts, 7 ampere, 125 volts a.c. (7 A, 125 V a.c.) and 0.25 ampere, 24 volts d.c. (0.25 A, 24 V d.c.); complete with factory-set, field-adjustable retard element to prevent false signals and tamper-proof cover that sends a signal when cover is removed.
- C. Supervisory Switches: UL 753, for valves, electrical-supervision type, SPDT (single-pole, double-throw), normally closed contacts, designed to signal controlled valve in other than full open position.

2.7 FIRE DEPARTMENT INLET CONNECTION

- A. The Fire Protection Contractor shall furnish and install where indicated on the drawings a flush type fire department inlet connection equal to Potter-Roemer No. 5025-D 6" x 2-1/2" x 2-1/2" two-way with clappers, cast brass two-way inlet body, cast brass identification plate, cast brass plugs and chains on each pin lug swivel. Finish shall be polished chrome plated.
- B. Identification plate to read "STANDPIPE-AUTO. SPKR."
- C. Similar unit by Elkhart, Allen or Seco will be acceptable.

2.8 BACKFLOW PREVENTERS

- A. Backflow Preventers-Double Check Valve Type, U.L./F.M. Approved
 - 1. Furnish and install in the Fire Protection water supply line where indicated on the Contract Drawings a Watts NO. 709-O.S.&Y double check valve assembly with U.L. & F.M. approved OS&Y gate valve shut-off, epoxy coated (FDA approved) cast iron check valve bodies with bronze seats (removable), stainless steel internal parts and bronze seats (removable), stainless steel internal parts and bronze body ball valve test cocks. Similar units, manufactured by Cla-Val or FEBCO will also be acceptable.
 - 2. Refer to schedule of double check valve backflow preventers on the Contract Drawings for Number, Size, Capacity, etc.

2.9 DRY PIPE SYSTEM ACCESSORIES

- A. Sprinkler Alarm Valves
 - 1. Sprinkler alarm valves shall be dry pipe type equal to Viking Model G, complete with the following equipment:
 - a. Model E-1 accelerator
 - b. Water Pressure Switch
 - c. Air pressure supervisory switch
 - d. Main gate valve
 - e. Control piping, drain valves, and all other standard trim.
 - 2. All electrical alarms and all electrical wiring shall be by the Electrical Subcontractor.
- B. AIR COMPRESSOR AND AIR PIPING
 - 1. Furnish and install at each valve location, where indicated on the plans, a EMGLO Model K1A-30S or approved equal, tank mounted air compressor to fill and maintain air pressure in the dry-pipe automatic sprinkler systems.
 - 2. Compressors shall be powered by an electric air cooled, U.L. listed 2 hp motor. Motor shall be wired for 825 rpm, 480v, 3 phase, 60 cycle current.
 - 3. Accessories to be furnished with the compressor shall be as follows:
 - a. pressure switch control
 - b. starter
 - c. air intake filter
 - d. silencer
 - e. pressure regulators and gauges
 - f. pressure relief valves
 - g. ASME air receiver

4. Piping between air compressor and dry pipe valves shall be Schedule 40 black steel fittings of like material and shall be not less than 3/4" in size. System shall include all control valves, check valves, small air cocks and relief valves.
5. All electrical wiring shall be by Electrical Subcontractor. Compressor shall be connected to the emergency power system.

C. CPOTTER INTELLIGENT™ NITROGEN GENERATOR (INS SERIES)

1. Furnish and install a nitrogen generator system in each fire sprinkler riser room to service all dry/pre-action zones as required by the system size and pressure requirement stipulated in the engineering drawings. Install per manufacturer's instructions.
2. The nitrogen generator shall have an air compressor system that is sized appropriately for the application and capable of achieving system supervisory pressure within 30 minutes in accordance with requirements of NFPA 13. The air compressor system may include an external compressor.
3. The nitrogen generator shall provide a minimum of 98% purity nitrogen to the fire sprinkler system.
4. The nitrogen generator shall be equipped with a filtration system to remove residual water and all hydrocarbons from the air stream.
5. The nitrogen generator shall have a nitrogen control panel capable of monitoring compressor runtimes, nitrogen generator pressure, as well as its operational mode locally and via the internet.
6. The nitrogen generator shall have a leak detection system capable of determining sprinkler system leak rates, giving alerts if leaks develop within the sprinkler piping, nitrogen generator system or air compressor.
7. The nitrogen generator shall be able to indicate trouble alerts: locally via nitrogen control panel, via BMS trouble alert relay, via internet, and via email.
8. The nitrogen generator system shall automatically switch between air bypass mode and nitrogen generating mode based on the demands of the sprinkler system.
9. The nitrogen generator system shall automatically switch between air bypass mode and nitrogen generating mode based on the demands of the sprinkler system.
10. The nitrogen generator shall have a nitrogen storage tank that conforms to the ASME standard for pressure vessels.

D. POTTER INTELLIPURGE™ NITROGEN PURGE VALVE (INS-PV)

1. Furnish and install a nitrogen purge valve at the furthest point from the fire sprinkler riser for each fire sprinkler system.
2. The nitrogen purge valve shall be supplied with a restricted orifice with size determined by the total system pressure requirements.
3. The nitrogen purge valve shall have a nitrogen sensor that can shut off the purge valve after 98% nitrogen has been achieved throughout the fire sprinkler system.
4. The nitrogen purge valve shall monitor the nitrogen level in the fire protection system periodically.
5. The nitrogen purge valve shall have a BMS trouble alert relay to indicate trouble if nitrogen purity drops below desired levels.
6. The nitrogen purge valve shall be able to connect to a nitrogen generator for remote monitoring.
7. The nitrogen purge valve shall be able to network with other purge valves.
8. The nitrogen purge valve shall be closed during hydrostatic and air pressure testing of the fire sprinkler system, then placed in the open position for the commissioning, treatment and operation of the system.

E. AIR MAINTENANCE DEVICE

1. Furnish and install an Air Maintenance Device for each dry or preaction fire sprinkler system.
2. The Air Maintenance Device shall be equipped with an adjustable pressure regulator that is capable of setting the required pressure for the fire sprinkler system.
3. The Air Maintenance Device shall be listed or approved for fire sprinkler application.
4. The Air Maintenance Device shall be installed per manufacturer's specifications.

F. NETWORKING AND INTERCONNECTIONS

1. Furnish and install networking wiring per manufacturer instructions from INS Series nitrogen generator to the nearest INS-PV nitrogen purge valve. Connect remaining INS-PV nitrogen purge valves in a daisy chain manner.
2. Connect CAT 5 internet wiring to INS nitrogen control panel and register INS Series nitrogen generator per manufacturer instructions.
3. Optionally connect BMS trouble alert relay in INS Series nitrogen generator to building management system or trouble zone of fire panel.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine walls and partitions for suitable thickness, fire- and smoke-rated construction, framing for cabinets, and other conditions where cabinets are to be installed.
- B. Do not proceed until unsatisfactory conditions have been corrected.

3.2 SPRINKLER SYSTEM PIPING APPLICATIONS

- A. Refer to Part 2 of this Section for detailed specifications on pipe and fittings type and size applications.

3.3 DRY PIPE SYSTEM PIPING APPLICATIONS

- A. Refer to Part 2 of this Section for detailed specifications on pipe and fittings type and size applications.

3.4 VALVE APPLICATIONS

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
 1. Shutoff Duty: Use gate valves.

3.5 JOINT CONSTRUCTION

- A. Refer to Division 21 05 00 Section "Common Work Requirements for Fire Protection" for basic piping joint construction.

- B. Grooved-End Pipe and Grooved-End Fitting Joints: Use grooved-end fittings and grooved couplings that are made by the same manufacturer and that are listed for use together. Groove pipe and assemble joints with grooved coupling, gasket, lubricant, and bolts according to coupling and fitting manufacturer's written instructions.
 - 1. Groove Type: Rolled.
- C. Brazed Joints: Use AWS A5.8, BCuP-3, or BCuP-4 filler metals.
- D. Dissimilar Materials Piping Joints: Make joints using adapters compatible with both piping materials.

3.6 PIPING INSTALLATIONS

- A. Refer to Division 21 Section "Common Work Requirements for Fire Protection" for basic piping installation.
- B. Locations and Arrangements: Drawings (plans, schematics, and diagrams) indicate general location and arrangement of piping. Install piping as indicated, as far as practical.
 - 1. Deviations from approved "working plans" for sprinkler piping require written approval from authority with jurisdiction. File written approval with the Architect prior to deviating from approved "working plans."
- C. Use approved fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.
- D. Install unions adjacent to each valve in pipes 2 inches (50 mm) and smaller. Unions are not required on flanged devices or in piping installations using grooved couplings.
- E. Install flanges or flange adapters on valves, apparatus, and equipment having 2-1/2-inch (65 mm) and larger connections.
- F. Install "Inspector's Test Connections" in sprinkler piping, complete with shutoff valve, sized and located according to NFPA 13 or as located on the drawings. Terminate inspectors test over nearest janitors closet or as shown on the drawings within the sprinkler zone.
- G. Install sprinkler piping with drains for complete system drainage.
- H. Install sprinkler zone control valves, test assemblies, and drain headers adjacent to standpipes when sprinkler piping is connected to standpipe.
- I. Install drain valves on standpipe systems, of sizes and in locations indicated.
- J. Install ball drip valves to drain piping between fire department connections and check valves, and where indicated. Drain to floor drain or outside building.
- K. Install alarm devices in piping systems.
- L. Hangers and Supports: Comply with NFPA 13. Install according to NFPA 13 and NFPA 14.
 - 1. Install hanger and support spacing and locations for steel piping joined with grooved mechanical couplings according to manufacturer's written instructions for rigid systems.

2. Earthquake Protection: Install piping according to NFPA 13 to protect from earthquake damage.
- M. Install pressure gages on riser or feed main, at each sprinkler test connection, and at top of each standpipe. Include pressure gages with connection not less than 1/4 inch (7 mm) and with soft metal seated globe valve, arranged for draining pipe between gage and valve. Install gages to permit removal and install where they will not be subject to freezing.
- N. The use of Hooker Tees or U-Bolt tees is not allowed.
- O. The use of weld-O-Lets for branch pipe or sprinkler head connections to mains or branch piping is acceptable.

3.7 VALVE INSTALLATIONS

- A. Refer to Division 22 Section "Valves" for installation of general-duty valves. Install fire-protection specialty valves, trim, fittings, controls, and specialties according to NFPA 13 and NFPA 14, manufacturer's written instructions, and the authority having jurisdiction.
- B. Gate Valves: Install fire-protection service valves supervised-open, located to control sources of water supply except from fire department connections. Where there is more than 1 control valve, provide permanently marked identification signs indicating portion of system controlled by each valve.

3.8 SPRINKLER APPLICATIONS

- A. Rooms without Ceilings: Upright and pendent sprinklers, as indicated.
- B. Rooms with Suspended Ceilings: Concealed sprinklers, Recessed sprinklers, Fully recessed sprinklers.
- C. Sprinkler Finishes: Use sprinklers with following finishes:
 1. Upright and Pendent Sprinklers: Chrome-plated in finished spaces exposed to view; rough bronze in unfinished spaces not exposed to view; wax-coated where exposed to acids, chemicals, or other corrosive fumes.
 2. Concealed Sprinklers: Rough brass with white or chrome cover plate.
 3. Recessed Sprinklers: Chrome plated brass with chrome cover plate.
 4. Fully Recessed Sprinklers: Chrome plated brass with chrome cover plate.
- D. Unheated Ceiling spaces: Pendent, Upright, Concealed dry pendant sprinkler heads.
- E. Sprinkler Cabinet and Wrench: Furnish steel baked red enameled, sprinkler box with capacity to store 12 additional sprinklers of each type installed and wrench sized to fit the sprinklers.

3.9 SPRINKLER INSTALLATIONS

- A. Install sprinklers in accordance with NFPA 13.

3.10 CONNECTIONS

- A. Electrical Connections: Power wiring is specified in Division 26.
- B. Connect alarm devices to fire alarm system.

3.11 FIELD QUALITY CONTROL

- A. Perform field acceptance tests of each fire protection system.
 - 1. Flush, test, and inspect sprinkler piping systems according to NFPA 13 Chapter "System Acceptance."
 - 2. Flush, test, and inspect standpipe systems according to NFPA 14 Chapter "Tests and Inspection."
- B. Replace piping system components that do not pass test procedures specified, then retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
 - 1. Report test results promptly and in writing to Architect.
 - 2. Report test results promptly and in writing to authority having jurisdiction when required.

3.12 CLEANING

- A. Clean dirt and debris from sprinklers. Replace sprinklers having paint other than factory finish with new sprinklers. Cleaning and reuse of painted sprinklers is prohibited.

3.13 COMMISSIONING

- A. Starting Procedures: Follow manufacturer's written procedures. If no procedures are prescribed by manufacturer, proceed as follows:
 - 1. Verify that specialty valves, trim, fittings, controls, and accessories have been installed correctly and operate correctly.
 - 2. Verify that specified tests of piping are complete.
 - 3. Check that damaged sprinklers and sprinklers with paint or coating not specified have been replaced with new, correct type of sprinklers.
 - 4. Check that sprinklers are correct type, have correct finish and temperature ratings, and have guards where required for applications.
 - 5. Check that hose valves and fire department connections have threads compatible with local fire department equipment and have correct pressure rating.
 - 6. Fill wet-pipe sprinkler systems with water.
 - 7. Fill wet standpipe systems with water.
 - 8. Check for correct type and size hose valves.
 - 9. Energize circuits to electrical equipment and devices.
 - 10. Adjust operating controls and pressure settings.
- B. Coordinate with fire alarm system tests. Operate systems as required.

3.14 DEMONSTRATION

- A. Demonstrate equipment, specialties, and accessories. Review operating and maintenance information.
- B. Schedule demonstration with at least 7 days' advance notice.

END OF SECTION 21 32 60

SECTION 22 05 00

BASIC PLUMBING MATERIALS AND METHODS

PART 1 - GENERAL

1.1 GENERAL

- A. Where the word contractor is used in this specification or on the drawings, the term shall apply to a prime contractor or a subcontractor. Where the term "this contractor" is used in this specification, the term shall apply to the plumbing contractor as applicable. Words such as "he" and "she" used in this specification is not intended to designate gender.
- B. This Contractor shall refer to the "Instructions to Bidders", General Conditions, Supplementary General Conditions and Special Conditions and Applicable Provisions for bidding requirements and items that effect his work.
- C. Pertinent Federal, State and Local requirements and regulations of OSHA, National Electrical Codes, and NFPA, are hereby made a part of this contract. Use of the term "code" in sections of this specification refers to applicable requirements and regulations of above listed agencies.
- D. It shall be the responsibility of this Contractor to promptly inform the Architects of all deviations in the drawings and specifications from the City, County and State Laws, Ordinances, Regulations or Rulings. This Contractor shall install all work strictly in accordance with all such requirements at no additional cost to Owner.
- E. In the event the specifications or drawings conflict with such laws or ordinances, the conflicting portion of the work affected shall be installed in strict accordance with the laws or ordinances above mentioned and the remainder of the drawings and specifications shall remain in full force.
- F. If the requirements of these specifications or drawings are more stringent than the conflicting laws or ordinances, the requirements of the specifications and drawings shall govern unless amended by the Engineer.

1.2 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and the Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.3 SUMMARY

- A. This Section includes the following basic mechanical materials and methods to complement other Division 22 Sections.
 - 1. Piping materials and installation instructions common to most piping systems.
 - 2. Concrete equipment base construction requirements.
 - 3. Equipment nameplate data requirements.

4. Labeling and identifying mechanical systems and equipment is specified in Division 22 Section "Plumbing Identification."
5. Nonshrink grout for equipment installations.
6. Field-fabricated metal and wood equipment supports.
7. Installation requirements common to equipment specification Sections.
8. Cutting and patching.
9. Touchup painting and finishing.
10. Firestopping

B. Pipe and pipe fitting materials are specified in piping system Sections.

1.4 DEFINITIONS

- A. Pipe, pipe fittings, and piping include tube, tube fittings, and tubing.
- B. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below the roof, spaces above ceilings, unexcavated spaces, crawl spaces, and tunnels.
- C. Exposed Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- D. Exposed Exterior Installations: Exposed to view outdoors, or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- E. Concealed Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in duct shafts.
- F. Concealed Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants, but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.

1.5 MATERIAL AND EQUIPMENT SELECTION

- A. Product Options: The specification of each item of major equipment required for the project may include a list of manufacturers, with one "basis of design" manufacturer, type, and model identified by virtue of their being the first listed manufacturer in the specifications. Where several manufacturers in addition to the "basis of design" manufacturer are listed in the specifications, it shall be understood that the words "or approved equal by" are implied to precede each of the other manufacturer's names.
- B. The manufacturers other than the "basis of design" may be furnished at the contractor's option in lieu of the "basis of design" product, provided that the selected manufacturer's product is equal in all material and functional respects. Additional work required for equipment that is other than the "basis of design", shall be at the expense of the contractor. In addition to submittal requirements that may be specified in this section, submit a line-by-line written verification of the applicable specification section(s) identifying compliance with or variations from the specified features, materials, performance, capacities, weight, size, durability, energy consumption and efficiency,

warranty, and visual impact (if exposed to view by other than maintenance persons). The burden of proof of manufacturer/product equality is on the contractor.

- C. Where a product is not scheduled on the drawings and, therefore, where no “basis of design” is indicated, the first listed manufacturer in the specifications shall be deemed as “basis of design”
- D. Products of manufacturers not listed in the Contract Documents are considered Substitutions and are not permitted, except as provided under the General and Supplementary Conditions and Division 1 Specifications. Full compliance with section “Product Substitutions” below is mandatory for acceptance of products or manufacturers not listed.
- E. Listing of a manufacturer does not imply approval of that manufacturer’s standard product or products. Rather, listing of a manufacturer indicates only a general acceptance of that manufacturer’s name and reputation. Final approval is subject to full compliance with these Contract Documents.
- F. Model numbers identified on the Drawings notwithstanding; all equipment must comply with the requirements of these Contract Documents. Do not assume that a manufacturer’s standard product is acceptable as is. For example, one or more custom modifications, custom colors or finishes, manufacturer’s options, and/or accessories may be required to meet the specified requirements.
- G. Where drawings indicate sizes, profiles, connections, and dimensional requirements of material and equipment, these are based on the “basis of design” manufacturer, type and model indicated. In the event that equipment of power, dimensions, capacities, layout, connections, and/or ratings differing from the “basis of design” are selected by the contractor and approved by the Owner’s representative, any necessary adjustments are the contractor’s responsibility. All connecting mechanical and electrical services, circuit breakers, conduit, motors, bases, pipe and duct sizes, pipe and duct layout, and the like shall be adjusted by the contractor to suit the equipment provided. No additional costs will be approved for these changes. Should revisions to the design because of contractor’s selection of manufacturer, type, or model other than the “basis of design” require additional review and/or redesign by an Architect or Engineer, the contractor shall reimburse the Owner for Owner’s added professional fee expenses.
- H. Where two or more materials are listed in the “Part 2 – Products” subsection of any Division 22 section, do not assume that the selection of materials is the contractor’s option. Refer to “Part 3 – Execution” subsection of that same Division 22 section for an explanation of which specific material(s) shall be used for which specific application(s). For example, Part 2 may list several types and grades of piping, and Part 3 will describe which type and grade of pipe to use for a given application.
- I. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems, and have been coordinated, as much as possible, based on available information and field observations. Deviations to layout that may require additional fittings and are within 6’-0” of design document layout, shall be at the expense of the contractor. Deviations to layout shall be documented on the coordination drawings. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated, unless deviations to layout are approved on Coordination Drawings.

1.6 SUBSTITUTIONS

- A. Notwithstanding any reference in the specifications to any article, device, product, material, form or type of construction by name, or make, or catalog number, such references shall be interpreted as

establishing a standard of quality and shall not be construed as limiting competition; and the Contractor in such cases may, at his option, use any article, device, product, material, fixture, form or type of construction which in the judgment of the Engineer, expressed in writing, is equal to that specified.

- B. Any materials or products other than those specified shall be submitted in writing to the Engineer for approval at least 10 days prior to the submission of bids. Materials and products so approved will be so stated by addendum.
- C. No substitute equipment will be considered unless sufficient data is submitted with the request to allow adequate comparison with the specified equipment.
- D. The Engineer reserves the right to reject any or all substitute equipment, if, in his opinion, said equipment is not of equal quality, capacity or like design. In all cases, the decision of the Engineer shall be final.
- E. This Contractor, at his option, may submit any item of material or equipment in a separate letter listing volunteer alternatives. An add or deduct price shall be indicated for each volunteer alternate submitted. Sufficient data shall accompany each volunteer alternate submitted to allow adequate comparison with the specified equipment. The Contractor shall pay all costs associated with reviewing proposed substitute material or equipment.
- F. This Contractor shall pay all costs arising from the use of substitute equipment or material. Such costs shall include but shall not be limited to architectural design costs, mechanical, electrical, plumbing, fire protection, civil & structural engineering costs & cost to other trades to accommodate the substitute equipment.

1.7 SHOP DRAWINGS

- A. This Contractor shall submit for the Engineer's review a list of all equipment and subcontractors he proposes to use. This list shall be submitted within thirty (30) days after signing of contracts or receiving "Letter of Intent". The engineer will review and comment on this list prior to submission of shop drawings.
- B. After the Contractor has received the comments from the engineer concerning the list of equipment and subcontractors, this Contractor shall submit either 8 hard copies or electronic PDF of complete shop drawings or manufacturer data sheets, certification and descriptive literature for ALL material and equipment furnished on this project:
- C. Shop drawings, manufacturer data sheets and descriptive literature shall include parts lists, operating and maintenance manuals, etc.
- D. The Contractor shall review each shop drawing etc. before submitting to the engineer to determine that it is acceptable in terms of the means, methods, techniques, orientation, sequences, operations of construction, safety precautions and programs incidental there to, all of which are the contractor's responsibility.
- E. The engineer shall review each shop drawing, etc. for its conformity with design intent and compliance with information given in the construction documents.

- F. The Contractor shall bring to the engineer's attention any shop drawing, etc. that varies from the contract documents requirements.
- G. The engineers review time for all submittals will be 10 working days.
- H. The Contractor shall pay for the review of all shop drawings, etc. that varies from the requirements of the contract documents.
- I. Shop drawings, etc. submitted for equipment or material which was not specified, included in the specification or drawings by written addendum, or submitted by separate letter with the contractors bid will be returned without review and will not be considered for this project.
- J. At the completion of the project, this Contractor shall give the Owner three copies of all shop drawings, data sheets, operating manuals, parts lists, maintenance manuals, etc. which shall be bound in vinyl-covered three-ring binders with a complete index and index tabs. All manuals to be submitted to the Engineer's Office for review and acceptance prior to transmittal to the Owner.

1.8 OWNERS RECORD SET OF DRAWINGS

- A. This Contractor shall keep a careful record of all changes in location of all piping, valves, controls, etc. underground and on all floors from that actually shown on the working drawings. Upon completion of this project, this Contractor shall transmit these changes on electronic medial in PDF format. The set of drawings shall include all drawings, even if no changes were made. Each "record drawing" shall be so labeled, dated and signed by this Contractor.
- B. This Contractor shall indicate all changes to the Architectural backgrounds and Plumbing and Sewering systems in the identical manner as the original drawings, i.e., without crossouts, etc. and shall also transcribe to these drawings all change orders.
- C. The cost of the reproductions shall be paid by this Contractor.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end-caps. Maintain end-caps through shipping, storage, and handling to prevent pipe-end damage and prevent entrance of dirt, debris, and moisture.
- B. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. When stored inside, do not exceed structural capacity of the floor.
- C. Protect flanges, fittings, and piping specialties from moisture and dirt.
- D. Protect stored plastic pipes from direct sunlight. Support to prevent sagging and bending.

1.10 SEQUENCING AND SCHEDULING

- A. Coordinate mechanical equipment installation with other building components.

- B. Arrange for chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.
- C. Coordinate the installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- D. Sequence, coordinate, and integrate installations of mechanical materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning prior to closing in the building.
- E. Coordinate connection of electrical services.
- F. Coordinate requirements for access panels and doors where mechanical items requiring access are concealed behind finished surfaces. Access panels and doors are specified in this section.
- G. Coordinate installation of identifying devices after completing covering and painting where devices are applied to surfaces. Install identifying devices prior to installing acoustical ceilings and similar concealment.

1.11 COORDINATION DRAWINGS

- A. Coordination drawings are not required on this project. Contractor shall coordinate their work with the work of other trades. In the event a Contractor fails to coordinate with other trades, he will be held responsible for all costs incurred for adjustments to the work of others made necessary to accommodate the uncooperative Contractor's installations.
 - 1. The Contractor shall oversee the preparation of coordination drawings as follows:
 - a. Contractors responsible for the following items of work located in or above ceilings shall participate in preparation of Coordination Drawings.
 - 1) Recessed light fixtures.
 - 2) Pneumatic tube systems.
 - 3) Ductwork and appurtenances.
 - 4) Plumbing waste and roof drainage.
 - 5) Fire Protection (Sprinkler System).
 - 6) HVAC piping
 - 7) Plumbing vent, supply and medical gas piping.
 - 8) Plumbing domestic water piping.
 - 9) Medical gas piping.
 - 10) Electrical conduit.
 - b. The above list, in descending order, is the precedence assigned the work items for space priority. Recessed light fixtures and space for their installation has first priority, pneumatic tube and other record or material conveying systems, second priority, etc. An exception to the precedence listing would be the gravity flow requirements for plumbing waste and roof drainage.
 - 2. After award of contracts and prior to start of construction, the General Contractor will schedule a meeting with the Contractors responsible for the work items listed above. The purpose of the meeting is to introduce the coordination program and to determine its implementation in relation to the progress schedule.

3. At the initial coordination meeting, the General Contractor will provide to the HVAC Contractor electronic AutoCAD drawings showing column center lines, interior partition locations, and ceiling heights. The HVAC Contractor, with reference and consideration to the structural, mechanical, electrical, fire protection, plumbing and reflected ceiling plans, will draw, to scale, his proposed installation showing duct sizes, equipment layouts, and dimensions from column lines and from finished floors to bottom of ducts. Ductwork will be maintained as tight as possible to the underside of floor slabs and/or beams. In congested areas, the HVAC Contractor will, in addition, prepare drawings in section view. During this phase of the program, it will be the Electrical Contractor's responsibility to furnish the HVAC Contractor with recessed lighting installation and clearance requirements. This information will be outlined on the drawings by the HVAC Contractor.
4. The ductwork layouts will be produced in sequence as mandated by the project schedule. The earliest area indicated in the schedule will receive the first effort, etc.
5. When the ductwork drawings for the earliest scheduled area have been completed (time limitation as determined at the initial coordination meeting), the HVAC Contractor will provide the General Contractor electronic AutoCAD drawing files for each participant in the effort. The General Contractor will distribute the drawings to the participating Contractors for their use in drawing thereon the major components of their proposed installations using the general scheme shown on the Contract Drawings as a guide.
 - a. The major components to be indicated include (but are not limited to):
 - 1) Roof drain leaders
 - 2) Large waste piping
 - 3) Sprinkler mains
 - 4) Heating hot water mains
 - 5) Chilled water mains
 - 6) Conveying systems
 - 7) Significant conduit runs
 - 8) Cable trays
 - 9) Domestic water mains
 - 10) Pneumatic Tube System
 - b. Information delineated will be distance from column center lines, pipe/equipment size and distance from finished floor to bottom of pipe/equipment.
6. Within a period of not to exceed two (2) weeks after distribution of the drawings, the General Contractor will schedule a meeting with the participating Contractors at which time, the drawings will be over layed to identify areas of conflict. All parties including ceiling contractor will then cooperate in resolving the conflicts. Records of the agreements will be entered on the HVAC Contractor's AutoCAD drawings, acknowledged by all participants by signature in a space provided for this purpose, and two (2) blue-line copies distributed to all involved parties. All drawing reproduction costs will be borne by the General Contractor. The above drawing review and coordination process will be repeated until all areas on the Project have been coordinated.
7. In the event a Contractor fails to cooperate in the Coordination Program, he will be held responsible for all costs incurred for adjustments to the work of others made necessary to accommodate the uncooperative Contractor's installations.
8. When a Change Order request is issued, the affected Contractors shall review the Coordination Drawings and bring to the attention of the General Contractor any revisions necessary to the work of others not directly affected by the Change Order.

PART 2 - PRODUCTS

2.1 PIPE AND PIPE FITTINGS

- A. Refer to individual piping system specifications for pipe and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.a) JOINING MATERIALS
- C. Refer to individual piping system specification Sections in Division 22 for special joining materials not listed below.
- D. Pipe Flange Gasket Materials: Suitable for the chemical and thermal conditions of the piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch (3mm) maximum thickness, except where thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125 cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250 cast-iron and steel flanges.
 - 2. ASME B16.20 for grooved, ring-joint, steel flanges.
 - 3. AWWA C110, rubber, flat face, 1/8 inch (3 mm) thick, except where other thickness is indicated; and full-face or ring type, except where type is indicated.
- E. Flange Bolts and Nuts: ASME B18.2.1, stainless steel, except where other material is indicated.
- F. Plastic Pipe Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer, except where other type or material is indicated.
- G. Solder Filler Metal: ASTM B 32.
 - 1. Alloy Sn95: Lead Free
 - 2. Alloy Sn50: Tin (50 percent) and lead (50 percent).
 - 3. Alloy E: Tin (approximately 95 percent) and copper (approximately 5 percent).
 - 4. Alloy HA: Tin-antimony-silver-copper-zinc.
 - 5. Alloy HB: Tin-antimony-silver-copper-nickel.
- H. Brazing Filler Metals: AWS A5.8.
 - 1. BCuP Series: Stay Silv 15
 - 2. BAg1: Silver alloy.
- I. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- J. Solvent Cements: Manufacturer's standard solvents complying with the following:
 - 1. Acrylonitrile-Butadiene-Styrene (ABS): ASTM D 2235.
 - 2. Chlorinated Poly(Vinyl Chloride) (CPVC): ASTM F 493.
 - 3. Poly(Vinyl Chloride) (PVC): ASTM D 2564.
 - 4. PVC to ABS Transition: Made to requirements of ASTM D 3138, color other than orange.
- K. Plastic Pipe Seals: ASTM F 477, elastomeric gasket.

- L. Flanged, Ductile-Iron Pipe Gasket, Bolts, and Nuts: AWWA C110, rubber gasket, carbon steel bolts and nuts.
- M. Couplings: Iron body sleeve assembly, fabricated to match outside diameters of plain-end pressure pipes.
 - 1. Sleeve: ASTM A 126, Class B, gray iron.
 - 2. Followers: ASTM A 47 (ASTM A 47M), Grade 32510 or ASTM A 536 ductile iron.
 - 3. Gaskets: Rubber.
 - 4. Bolts and Nuts: AWWA C111.
 - 5. Finish: Enamel paint.

2.2 PIPING SPECIALTIES

- A. Escutcheons: Manufactured wall, ceiling, and floor plates; deep-pattern type where required to conceal protruding fittings and sleeves.
 - 1. Inside Diameter: Closely fit around pipe, tube, and insulation.
 - 2. Outside Diameter: Completely cover opening.
 - 3. Cast Brass: One-piece, with set-screw.
 - a. Finish: Polished chrome plate.
 - 4. Cast Brass: Split casting, with concealed hinge and set-screw.
 - a. Finish: Polished chrome plate.
- B. Dielectric Fittings: Assembly or fitting having insulating material isolating joined dissimilar metals to prevent galvanic action and stop corrosion.
 - 1. Description: Combination of copper alloy and ferrous; threaded, solder, plain, and weld neck end types and matching piping system materials.
 - 2. Insulating Material: Suitable for system fluid, pressure, and temperature.
 - 3. Dielectric Unions: Factory-fabricated, union assembly for 250-psig (1725kPa) minimum working pressure at a 180 deg F (82 deg C) temperature.
 - 4. Dielectric Flanges: Factory-fabricated, companion-flange assembly for 150- or 300-psig (1035kPa or 2070kPa) minimum pressure to suit system pressures.
 - 5. Dielectric-Flange Insulation Kits: Field-assembled, companion-flange assembly, full-face or ring type. Components include neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - a. Provide separate companion flanges and stainless steel bolts and nuts for 150- or 300-psig (1035kPa or 2070kPa) minimum working pressure to suit system pressures.
 - 6. Dielectric Couplings: Galvanized-steel coupling, having inert and noncorrosive, thermoplastic lining, with threaded ends and 300-psig (2070kPa) minimum working pressure at 225 deg F (107 deg C) temperature.
 - 7. Dielectric Nipples: Electroplated steel nipple, having inert and noncorrosive thermoplastic lining, with combination of plain, threaded, or grooved end types and 300-psig (2070kPa) working pressure at 225 deg F (107 deg C) temperature.
- C. Mechanical Sleeve Seals: Modular, watertight mechanical type. Components include interlocking synthetic rubber links shaped to continuously fill annular space between pipe and sleeve. Connecting bolts and pressure plates cause rubber sealing elements to expand when tightened.
- D. Sleeves: The following materials are for wall, floor, slab, and roof penetrations:

1. Steel Sheet-Metal: 24-gage (0.70mm) or heavier galvanized sheet metal, round tube closed with welded longitudinal joint.
2. Steel Pipe: ASTM A 53, Type E, Grade A, Schedule 40, galvanized, plain ends.
3. Cast-Iron: Cast or fabricated wall pipe equivalent to ductile-iron pressure pipe, having plain ends and integral water stop, except where other features are specified.
4. Wall Penetration Systems: Wall sleeve assembly, consisting of housing, gaskets, and pipe sleeve, with 1 mechanical-joint end conforming to AWWA C110 and 1 plain pipe-sleeve end.
 - a. Penetrating Pipe Deflection: 5 percent without leakage.
 - b. Housing: Ductile-iron casting having waterstop and anchor ring, with ductile-iron gland, steel studs and nuts, and rubber gasket conforming to AWWA C111, of housing and gasket size as required to fit penetrating pipe.
 - c. Pipe Sleeve: AWWA C151, ductile-iron pipe.
 - d. Housing-to-Sleeve Gasket: Rubber or neoprene push-on type of manufacturer's design.
5. Cast-Iron Sleeve Fittings: Commercially made sleeve having an integral clamping flange, with clamping ring, bolts, and nuts for membrane flashing.
 - a. Underdeck Clamp: Clamping ring with set-screws.
6. PVC Plastic: Manufactured, permanent, with nailing flange for attaching to wooden forms.
7. PVC Plastic Pipe: ASTM D 1785, Schedule 40.
8. PE Plastic: Manufactured, reusable, tapered, cup-shaped, smooth outer surface, with nailing flange for attaching to wooden forms.

2.3 GROUT

- A. Nonshrink, Nonmetallic Grout: ASTM C 1107, Grade B.
 1. Characteristics: Post-hardening, volume-adjusting, dry, hydraulic-cement grout, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 2. Design Mix: 5000-psi (34.50MPa), 28-day compressive strength.
 3. Packaging: Premixed and factory-packaged.

PART 3 - EXECUTION

3.1 PIPING SYSTEMS--COMMON REQUIREMENTS

- A. General: Install piping as described below, except where system Sections specify otherwise. Individual piping system specification Sections in Division 15 specify piping installation requirements unique to the piping system.
- B. General Locations and Arrangements: Drawings (plans, schematics, and diagrams) indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated, except where deviations to layout are approved on coordination drawings.
- C. Install piping at indicated slope.

- D. Install components having pressure rating equal to or greater than system operating pressure.
- E. Install piping in concealed interior and exterior locations, except in equipment rooms and service areas.
- F. Install piping free of sags and bends.
- G. Install exposed interior and exterior piping at right angles or parallel to building walls. Diagonal runs are prohibited, except where indicated.
- H. Install piping tight to slabs, beams, joists, columns, walls, and other building elements. Allow sufficient space above removable ceiling panels to allow for ceiling panel removal.
- I. Install piping to allow application of insulation plus 1-inch (25mm) clearance around insulation.
- J. Locate groups of pipes parallel to each other, spaced to permit valve servicing.
- K. Install fittings for changes in direction and branch connections.
- L. Install couplings according to manufacturer's printed instructions.
- M. Install pipe escutcheons for pipe penetrations of concrete and masonry walls, wallboard partitions, and suspended ceilings according to the following:
 - 1. Chrome-Plated Piping: Cast-brass, one-piece, with set-screw, and polished chrome-plated finish. Use split-casting escutcheons, where required, for existing piping.
 - 2. Uninsulated Piping Wall Escutcheons: Cast-brass or stamped-steel, with set-screw.
 - 3. Uninsulated Piping Floor Plates in Utility Areas: Cast-iron floor plates.
 - 4. Insulated Piping: Cast-brass or stamped-steel, with concealed hinge, spring clips, and chrome-plated finish.
 - 5. Piping in Utility Areas: Cast-brass or stamped-steel, with set-screw or spring clips.
- N. Sleeves are not required for core drilled holes.
- O. Above Grade, Exterior Wall, Pipe Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Size sleeve for 1-inch (25mm) annular clear space between pipe and sleeve for installation of mechanical seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches (150 mm).
 - 2. Install cast-iron wall pipes for sleeves 6 inches (150 mm) and larger.
 - 3. Assemble and install mechanical seals according to manufacturer's printed instructions.
- P. Fire Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestopping sealant material.
- Q. Verify final equipment locations for roughing in.
- R. Refer to equipment specifications in other Sections for roughing-in requirements.
- S. Piping Joint Construction: Join pipe and fittings as follows and as specifically required in individual piping system Sections.
 - 1. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

2. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
 3. Soldered Joints: Construct joints according to AWS "Soldering Manual," Chapter 22 "The Soldering of Pipe and Tube."
 4. Brazed Joints: Construct joints according to AWS "Brazing Manual" in the "Pipe and Tube" chapter.
 5. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full inside diameter. Join pipe fittings and valves as follows:
 - a. Note the internal length of threads in fittings or valve ends, and proximity of internal seat or wall, to determine how far pipe should be threaded into joint.
 - b. Apply appropriate tape or thread compound to external pipe threads (except where dry seal threading is specified).
 - c. Align threads at point of assembly.
 - d. Tighten joint with wrench. Apply wrench to valve end into which pipe is being threaded.
 - e. Damaged Threads: Do not use pipe or pipe fittings having threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
 6. Welded Joints: Construct joints according to AWS D10.12 "Recommended Practices and Procedures for Welding Low Carbon Steel Pipe" using qualified processes and welding operators according to the "Quality Assurance" Article.
 7. Flanged Joints: Align flange surfaces parallel. Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Assemble joints by sequencing bolt tightening to make initial contact of flanges and gaskets as flat and parallel as possible. Use suitable lubricants on bolt threads. Tighten bolts gradually and uniformly using torque wrench.
 8. Plastic Pipe and Fitting Solvent-Cement Joints: Clean and dry joining surfaces by wiping with clean cloth or paper towels. Join pipe and fittings according to the following standards:
 - a. Comply with ASTM F 402 for safe handling of solvent-cement and primers.
 - b. Acrylonitrile-Butadiene-Styrene (ABS): ASTM D 2235 and ASTM D 2661.
 - c. Chlorinated Poly(Vinyl Chloride) (CPVC): ASTM D 2846 and ASTM F 493.
 - d. Poly(Vinyl Chloride) (PVC) Pressure Application: ASTM D 2672.
 - e. Poly(Vinyl Chloride) (PVC) Non-Pressure Application: ASTM D 2855.
 - f. PVC to ABS (Non-Pressure) Transition: Procedure and solvent cement described in ASTM D 3138.
 9. Plastic Pipe and Fitting Heat-Fusion Joints: Prepare pipe and fittings and join with heat-fusion equipment according to manufacturer's printed instructions.
 - a. Plain-End Pipe and Fittings: Butt joining.
 - b. Plain-End Pipe and Socket-Type Fittings: Socket joining.
- T. Piping Connections: Except as otherwise indicated, make piping connections as specified below.
1. Install unions in piping 2 inches (50 mm) and smaller adjacent to each valve and at final connection to each piece of equipment having a 2-inch (50mm) or smaller threaded pipe connection.
 2. Install flanges in piping 2-1/2 inches (65 mm) and larger adjacent to flanged valves and at final connection to each piece of equipment having flanged pipe connection.
 3. Dry Piping Systems (Gas, Compressed Air, and Vacuum): Install dielectric unions and flanges to connect piping materials of dissimilar metals.
 4. Wet Piping Systems (Water): Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

3.2 EQUIPMENT INSTALLATION--COMMON REQUIREMENTS

- A. Install equipment to provide the maximum possible headroom where mounting heights are not indicated.
- B. Install equipment according to approved submittal data. Portions of the Work are shown only in diagrammatic form. Refer conflicts to the Architect.
- C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, except where otherwise indicated.
- D. Install mechanical equipment to facilitate servicing, maintenance, and repair or replacement of equipment components. Connect equipment for ease of disconnecting, with minimum of interference with other installations. Extend grease fittings to an accessible location.
- E. Install equipment giving right-of-way to piping systems installed at a required slope.

3.3 PAINTING AND FINISHING

- A. Damage and Touch Up: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.4 CONCRETE BASES

- A. All concrete equipment bases will be furnished and installed by the contractor for concrete work. It will, however, be the responsibility of this Contractor to provide the concrete contractor with the exact location and size of all bases required after the purchased equipment is known.
- B. All concrete equipment bases shall be furnished and installed by this Contractor. Bases shall be reinforced with 10/10 steel mesh. Edges shall have a 1"-45° champher. The top surface shall have a steel trowel finish. The exact exact size and location of all bases shall be determined after the purchased equipment is known and prior to pouring the bases.
- C. Bases of insufficient size for the equipment which it was designed to support shall be removed and a new base of adequate size installed.
- D. Construct concrete equipment bases less than 4 inches (100 mm) larger than supported unit in both directions. Follow supported equipment manufacturer's setting templates for anchor bolt and tie locations. Use 3000-psi (20.70MPa), 28-day compressive strength concrete and reinforcement as specified in Division 3 Section "Cast-in-Place Concrete."

3.5 ERECTION OF METAL SUPPORTS AND ANCHORAGE

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor mechanical materials and equipment.
- B. Field Welding: Comply with AWS D1.1 "Structural Welding Code--Steel."

3.6 CUTTING AND PATCHING

- A. This Contractor shall sleeve all holes in the new construction for the installation of his work.
- B. This Contractor shall cut all holes in floors, walls, ceiling, and roof necessary for the installation of the work in the existing building, except work shown on the Architectural Wrecking Drawings to be performed by the General Contractor.
- C. The holes for piping shall be cut with a diamond edge core drill. Under no circumstances shall a pneumatic or electric hammer be used to cut holes in walls or floors with the exception of the floor on ground. Saw cutting of concrete slab on grade will not be required; however, the floors shall be scored with a sharp instrument to outline the trench before breaking floor to obtain a fairly straight line trench. Provide watertight receptacle, wedged to bottom of structure, where core drilling occurs; preventing water from staining finishes of floors below.
- D. Before cutting holes in floors and ceilings; make careful field measurements at floor and ceiling to determine location of structural beams, and under no circumstances shall structural beams be cut or damaged during the cutting of these holes.
- E. This Contractor shall coordinate the cutting of existing construction with the (Construction Manager, Owner, General Contractor) and shall obtain approval prior to commencing any demolition work.
- F. The patching of all holes shall be by this Contractor. Where holes are left after removal of pipes or equipment, the openings shall be closed. All plaster ceiling, ceiling tile, floor tile, wall covering, etc. which must be removed in areas which will not receive new finishes under the General Contract Work must be replaced by this Contractor including all necessary painting to match existing colors. If the painted area does not blend into and match the adjacent area of a ceiling panel or wall panel, the entire ceiling or wall panel must be repainted. All such patching and painting shall restore areas to like conditions at time of starting work, subject to the direction and satisfaction of the Architect and Owner. This Contractor shall hire mechanics skilled in their trades to perform all patching work and painting where required. Refer to the Architectural Plans and to the Room Finish Schedules to determine the scope of other Contractors work.
- G. Where holes are left after removal of pipes or plumbing equipment or due to revisions, alteration, changes or errors, the openings shall be closed.
- H. This Contractor shall hire mechanics skilled in their trades to perform all patching such as concrete work, plastering, painting, etc. Such patching shall restore areas to like conditions at time of starting work, and shall be subject to the approval of the Architect.

3.7 CAULKING AND SEALANT

- A. Refer to division 7 for fire caulking requirements.
- B. This Contractor shall furnish and install caulking and sealant for all piping passing through fire rated floor structural slab and partition walls. This shall apply to all piping whether concealed in chases, above dropped ceiling areas, or exposed.

- C. A Fire-Stop System equivalent to 3M brand fire protection products as required for the specific application shall be used to seal penetrations of pipes and conduits through fire-rated walls and floors per NEC 300-21, NEC 800-3 (C), and ASTM E-814.
- D. All piping shall be firmly secured prior to installation of putty or caulk. Inspect and clean opening of all loose foreign material prior to the installation of the putty or caulk.
- E. Install caulk or putty as recommended by the manufacturer.

3.8 ACCESS TO EQUIPMENT

- A. All control devices, specialties, etc., shall be so located as to provide easy access for operation, repair and maintenance; if concealed, access doors shall be provided by this Contractor.
- B. The doors shall be Acudor Products Inc (www.acudor.com) of the following types:
 - 1. Plaster ceilings-----Type "PS5030"
 - 2. Plaster walls-----Type "PS5030"
 - 3. Masonry walls-----Type "UF5000"
 - 4. Gypsum drywall walls-----Type "DW5040"
 - 5. Gypsum drywall ceilings-----Type "DW5040"
 - 6. Gypsum drywall above finished ceiling -----Type "UF5000"
- C. No access doors shall be smaller than 18" x 18".
- D. SPECIAL NOTE: Install "FW5050" "B" labeled access doors in all 1-hour and
- E. 2 -hour fire rated walls and ceilings.
- F. Furnish all ceiling panels with a factory applied baked-on off-white enamel finish, and all wall panels with a factory applied prime coat, baked-on enamel finish.
- G. Where valves, control devices, etc., are located above removable ceiling panels, this Contractor shall furnish and install color coded screws or tacks installed in the ceiling tile to identify the location.
- H. All access panels will be installed by the contractor for the installation of the walls or the ceilings in locations designated by this Contractor.
- I. Comparable access panels by CESCO or Milcor will be acceptable.

3.9 GROUTING

- A. Install nonmetallic nonshrink grout for mechanical equipment base bearing surfaces, pump and other equipment base plates, and anchors. Mix grout according to manufacturer's printed instructions.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms for placement of grout, as required.

- D. Avoid air entrapment when placing grout.
- E. Place grout to completely fill equipment bases.
- F. Place grout on concrete bases to provide a smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout according to manufacturer's printed instructions.

END OF SECTION 22 05 00

SECTION 22 05 49

PLUMBING SYSTEMS

SUPPORTS, BRACING AND SEISMIC RESTRAINTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. ASCE (American Society of Civil Engineers) 7 - Minimum Design Loads for Buildings and Other Structures Latest Edition SMACNA Seismic Restraint Manual Guidelines for Mechanical Systems (latest edition).
- C. International Code Council (ICC) Evaluation Service Program-provided seismic restraint, anchorage, and only bracing guidelines and details (latest editions).
- D. Office of Statewide Health Planning and Development published seismic restraint manuals, guidelines and details (latest editions).

1.2 SUMMARY

- A. This Section includes designing, furnishing, and installing the following:
 - 1. Hangers and supports for mechanical (HVAC or process) and plumbing or fire protection equipment and systems.
 - 2. Seismic restraints for mechanical (HVAC or process) and plumbing or fire protection equipment and systems.
 - 3. Concrete bases for mechanical, plumbing or fire protection equipment.

1.3 DEFINITIONS

- A. ASTM: American Society for Testing and Materials
- B. AWS: American Welding Society
- C. IBC: International Building Code (2015 IBC).
- D. ICC: International Code Council.
- E. MFMA: Metal Framing Manufacturer's Association.
- F. MSS: Manufacturer's Standardization Society.

- G. NBC: National Building Code (latest edition).
- H. NFPA: National Fire Protection Association.
- I. OSHPD: Office of Statewide Health Planning and Development.
- J. SBC: Standard Building Code (latest edition).
- K. Seismic Restraint: A structural support element (such as a metal framing member, a cable, an anchor bolt or stud, a fastening device, or an assembly of these items) used to transfer seismic forces from an item of equipment or system to a building structural element and/or to limit movement of such item during a seismic event.
- L. SMACNA: Sheet Metal and Air Conditioning Contractor's National Association.
- M. UBC: Uniform Building Code (latest edition).

1.4 SUBMITTALS

- A. Product Data submitted shall illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of electrical support or seismic-restraint component used:
 - 1. Tabulate types, sizes and points of application of all seismic restraints, anchorages, sway bracing and other support elements to be used complete with report on numbers and rated strength in tension and shear, as evaluated by an agency acceptable to authorities having jurisdiction.
 - 2. Annotate to indicate application point of each product submitted and to document compliance with requirements.
- B. Shop Drawings submitted shall indicate materials and dimensions as well as identify hardware, (including attachment and anchorage devices), identify seismic support locations, all signed and sealed by a qualified registered professional engineer. Professional engineer qualification requirements are specified in Division 1 of this Specification include the following, as a minimum:
 - 1. Fabricated Supports: Representations of field-fabricated supports for all required locations.
 - 2. Seismic Restraints: Detailing anchorage bracing, and location. Include the following:
 - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads. Include location of designed restraint.
 - b. Details: Fabrication and arrangement, as well as attachments of restraints to the restrained items and to the structure shall be detailed. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events.
 - c. Pre-approval and Evaluation Documentation from by an agency acceptable to authorities having jurisdiction shall be submitted, showing maximum ratings of restraint items and the basis for approval (tests or calculations).
 - d. Location: Identify by tables or drawings all required seismic restraint locations and associated restraints for this Project.

3. Contractor is hereby cautioned that the design of the anchorages, sway bracing, seismic restraints, and other support elements required to be completed under this Section of this Specification by a qualified, registered professional engineer may NOT be accomplished solely by means of general references to published design manuals, tables, standard details, or other such references from Accepted Engineering Practice documents. However, incorporating such information, tables, details, or other published reference material directly into the specific design of such anchorages, sway bracing, seismic restraints, and other support elements required to be completed under this Section of this Specification (that will ultimately be signed and sealed by the registered professional engineer prior to submittal) is permissible.
- C. Coordination Drawings shall show coordination of seismic bracing for mechanical, plumbing and fire protection components with other systems and equipment in the vicinity, including other supports and seismic restraints.
- D. Welding certificates shall be submitted, as appropriate.
- E. Qualification Data for registered professional design engineer and testing agency shall be submitted.
- F. Field quality-control test reports shall be submitted.

1.5 QUALITY ASSURANCE

- A. Comply with seismic-restraint requirements in the IBC, unless requirements in these Contract Documents are more stringent.
- B. Testing of Seismic Anchorage Devices: Comply with testing requirements in Part 3 of this Specification Section.
- C. Welding: Qualify welding procedures and welding personnel capabilities according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Seismic restraint devices shall have been subjected to both horizontal and vertical load testing and analysis acceptable to authorities having jurisdiction, showing maximum seismic restraint ratings.
- E. Ratings based on independent testing are preferred to ratings based on calculations. Testing and/or calculations must include both shear and tensile loads (including combined shear and tensile loads), and one test or analysis at 45 degrees to the weakest mode.

1.6 PROJECT CONDITIONS

- A. See Table(s) on Contract Drawings for specific project conditions.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists of acceptable manufacturers, the following requirements apply to product selection:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified or Engineer-approved equal.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed on mechanical and plumbing system components for this Project, with a minimum structural safety factor of five (5) times the applied force.
- B. Steel Slotted Support Systems shall comply with MFMA-3, factory-fabricated components for field assembly.
 - 1. Acceptable Manufacturers:
 - a. Cooper B-Line; a division of Cooper Industries.
 - b. ERICO International Corporation.
 - c. Allied Support Systems; Power-Strut Unit.
 - d. GS Metals Corp.
 - e. Michigan Hanger Co., Inc.; O-Strut Div.
 - f. National Pipe Hanger Corp.
 - g. Thomas & Betts Corporation.
 - h. Unistrut; Tyco International, Ltd.
 - i. Wesanco, Inc.
 - j. Engineer-approved equal.
 - 2. Finishes:
 - a. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-3.
 - b. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-3.
 - 3. Channel Dimension shall be selected for structural loading condition and applicable seismic forces.
- C. Raceway and Cable Tray Support shall be as described in the IBC and ASCE 7 documents.
- D. Conduit and Cable Support Device shall be steel hangers, clamps, and associated fittings, specifically designed for the types and sizes of raceway or pipe to be supported.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Requirements for items for fastening mechanical or plumbing items or their supports to building surfaces shall include the following:
 - 1. Verify suitability of all fasteners for use with lightweight concrete or concrete slabs less than 4 inches thick.

2. Powder-Actuated Fasteners shall be threaded-steel stud, for use in hardened portland cement concrete, steel, or wood; with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - a. Acceptable Manufacturers:
 - 1) Hilti, Inc.
 - 2) ITW Construction Products.
 - 3) MKT Fastening, LLC.
 - 4) Simpson Strong-Tie Co. Inc.
 - 5) Engineer-approved equal.
3. Mechanical-Expansion Anchors shall be insert-wedge-type, stainless steel, for use in hardened portland cement concrete; with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
 - a. Acceptable Manufacturers:
 - 1) Cooper B-Line; a division of Cooper Industries.
 - 2) Empire Tool and Manufacturing Co., Inc
 - 3) Hilti, Inc.
 - 4) ITW Construction Products.
 - 5) MKT Fastening, LLC.
 - 6) Powers Fasteners.
 - 7) Engineer-approved equal.
4. Concrete Inserts shall be steel or malleable-iron slotted-support-system units similar to MSS Type 18; complying with MFMA-3 or MSS SP-58.
5. Clamps for Attachment to Steel Structural Elements shall conform to MSS SP-58, type suitable for attached structural element.
6. Through Bolts shall be structural type, hex head, high-strength. Comply with ASTM A 325.
7. Toggle Bolts shall be all-steel springhead type.
8. Hanger Rods shall be threaded steel.

2.3 SEISMIC RESTRAINT COMPONENTS

- A. Manufacturers:
 1. Amber/Booth Company, Inc.
 2. B-Line Systems, Inc.
 3. California Dynamics Corp.
 4. Kinetics Noise Control, Inc.
 5. Loos & Co., Inc.; Cableware Technology Division.
 6. Mason Industries, Inc.
 7. Unistrut Diversified Products Co.; Wayne Manufacturing Division.
 8. Vibration Eliminator Co., Inc.
 9. Vibration Isolation Co., Inc.
 10. Vibration Mountings & Controls/Korfund.
- B. Rated Strength, Features, and Application Requirements for Restraint Components shall be as defined by an agency acceptable to authorities having jurisdiction.
 1. Structural Safety Factor: Strength in tension, shear, and pullout force of components used shall be at least five (5) times the maximum seismic forces to which they will be subjected.

- C. Angle and Channel-Type Brace Assemblies: Steel angles or steel slotted-support-system components; with accessories for attachment to braced component at one end and to building structure at the other end.
- D. Cable Restraints: ASTM A 603, zinc-coated, steel wire rope attached to steel or stainless-steel thimbles, brackets, swivels, and bolts designed for restraining cable service.
- E. Seismic Mountings, Anchors, and Attachments: For this application, items shall be selected to resist seismic forces.
 - 1. Hanger Rod Stiffeners shall be steel tube or steel slotted-support-system sleeves with internally bolted connections or reinforcing steel angle clamped to hanger rod, of design recognized by an agency acceptable to authorities having jurisdiction.
 - 2. Bushings for Floor-Mounted Equipment Anchors shall be neoprene units designed for seismically rated rigid equipment mountings and matched to type and size of anchor bolts and studs used.
 - 3. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves shall be designed for seismically rated rigid equipment mountings, and matched to type and size of attachment devices used.
- F. Seismic Snubbers: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.
 - 1. Anchor bolts for attaching to concrete shall be seismic-rated, drill-in, and stud-wedge or female-wedge type.
 - 2. Resilient Isolation Washers and Bushings: 1-piece, molded, bridge-bearing neoprene complying with AASHTO M 251 and having a durometer of 50, plus or minus 5.

2.4 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

PART 3 - EXECUTION

3.1 GENERAL REQUIREMENTS

- A. Comply with IBC for specific application requirements for hangers and supports for mechanical and plumbing equipment and systems, except if requirements in these Contract Documents are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway or Pipes: Space supports as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- C. Multiple Raceways or Pipes: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits; and:
 - 1. Secure raceways and pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.

2. Secure raceways and pipes to these supports with two-bolt pipe clamps.
- D. Spring-steel clamps designed for supporting single pipes without bolts may be used for 1-1/2-inch and smaller raceways, and for fastening raceways to trapeze supports.
- E. Install all supports, restraints, attachments, and other elements specified in this Section of this Specification in strict conformance with the written installation requirements of the manufacturers of each support, restraint, attachment, or other element.

3.2 SUPPORT AND SEISMIC RESTRAINT INSTALLATION

- A. Comply with SMACNA and MSS for installation requirements, except as otherwise specified in this Article of this Section of this Specification.
- B. Install seismic restraint components using methods approved by the evaluation service providing required submittals for component.
- C. Strength of Support and Seismic Restraint Assemblies: Where not otherwise indicated, select sizes of components so that strength will be adequate to carry present and future static and seismic loads within specified loading limits. Minimum static design load used for strength determination shall be the weight of the supported components plus 200 lb.
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten mechanical and plumbing items and their supports to building structural elements by the following methods, unless otherwise indicated by code:
 1. To Wood: Fasten with lag screws or through bolts.
 2. To New Concrete: Bolt to concrete inserts.
 3. To Masonry: Use approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 4. To Existing Concrete: Fasten with expansion anchors.
 5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches thick.
 6. To Steel: Use welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts or beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69 or Spring-tension clamps.
 7. To Light Steel: Use sheet metal screws.
 8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount such devices on slotted-channel racks attached to substrate by means that meet seismic restraint strength and anchorage requirements.
- E. Drill holes for expansion anchors in reinforced concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- B. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

- A. Concrete Bases: Anchor equipment to concrete base according to equipment manufacturer's written instructions and seismic requirements for Project.
- B. Construct concrete bases of dimensions indicated but not less than 4 inches larger in both directions than supported unit, and such that expansion anchors will be a minimum of 10 bolt diameters from edge of the base; and:
 - 1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around full perimeter of the base.
 - 2. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base, and anchor into structural concrete floor.
 - 3. Place and secure anchorage devices using the equipment to be supported manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - 5. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
 - 6. Use 3000-psi 28-day compressive-strength concrete, minimum.

3.5 INSTALLATION OF SEISMIC RESTRAINT COMPONENTS

- A. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- B. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- C. Restraint Cables shall be installed with slack within maximum tolerance recommended by cable manufacturer.
- D. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, upper truss chords of bar joists, or at concrete members.

3.6 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Make flexible connections in runs of raceways and piping where they cross expansion and seismic control joints, where adjacent sections or branches are supported by different structural elements, and where they terminate with connection to mechanical and plumbing equipment that is anchored to a different structural element from the one supporting them as they approach equipment.

3.7 FIELD QUALITY CONTROL TESTS

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Record test results and submit to Engineer.
- C. Test pullout resistance of seismic anchorage devices, and:
 - 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
 - 2. Schedule test with Owner and Engineer present before connecting anchorage devices to components to be restrained (unless post-connection testing has been approved by Engineer in advance). Provide at least 7 days advance notice of scheduled test.
 - 3. Obtain Engineer's concurrence before transferring test loads to structure. Provide temporary load-spreading members.
 - 4. Test at least four of each type and size of installed anchorages and fasteners.
 - 5. Test anchorages and fasteners to 90 percent of rated proof load of item.
 - 6. If any item fails test, modify all installations of same type for project, then retest item until satisfactory test result is achieved.

3.8 PAINTING AND FINISHING

- A. Refer to Section 09900 – Protective Coatings of this Specification for field painting requirements.
- B. Damage and Touch-Up: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.9 CUTTING AND PATCHING

- A. Cut, channel, chase, and drill floors, walls, partitions, ceilings, and other surfaces necessary for mechanical installations. Perform cutting by skilled mechanics of the trades involved.
- B. Repair cut surfaces to match adjacent surfaces.

3.10 GROUTING

- A. Install non-metallic, non-shrink grout for mechanical equipment base bearing surfaces, pump and other equipment base plates and anchors. Mix grout according to manufacturer's printed instructions.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms for placement of grout, as required.
- D. Avoid air entrapment when placing grout.

- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases to provide a smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout according to manufacturer's printed instructions.

3.11 ERECTION OF WOOD SUPPORTS AND ANCHORAGE

- A. Cut, fit, and place wood grounds, nailers, blocking, and anchorage to support and anchor mechanical materials and equipment.
- B. Select fastener sizes that will not penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood members.
- C. Attach to substrates as required to support applied loads.

END OF SECTION 22 05 49

SECTION 22 06 00

PLUMBING HANGERS AND SUPPORTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes hangers and supports for mechanical system piping and equipment.
- B. Related Sections include the following:
 - 1. Division 5 Section "Metal Fabrications" for materials for attaching hangers and supports to building structure.
 - 2. Division 21 Sections on fire-suppression piping for fire-suppression pipe hangers.
 - 3. Section 22 05 48 "Mechanical Systems Vibration Control" for vibration isolation.
 - 4. Section 22 05 49 "Plumbing Systems; Supports, Bracing and Seismic Requirements".
 - 5. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for the Valve and Fittings Industry.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.4 PERFORMANCE REQUIREMENTS

- A. Design channel support systems for piping to support multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
- B. Design heavy-duty steel trapezes for piping to support multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
- C. Design seismic restraint hangers and supports for piping and equipment.
- D. Design and obtain approval from authorities having jurisdiction for seismic restraint hangers and supports for piping and equipment.

1.5 SUBMITTALS

- A. Product Data: For each type of pipe hanger, channel support system component, and thermal-hanger shield insert indicated.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer for multiple piping supports and trapeze hangers. Include design calculations and indicate size and characteristics of components and fabrication details.
- C. Welding Certificates: Copies of certificates for welding procedures and operators.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
- B. Engineering Responsibility: Design and preparation of Shop Drawings and calculations for each multiple pipe support and trapeze by a qualified professional engineer.
- C. Engineering Responsibility: Design and preparation of Shop Drawings and calculations for each multiple pipe support, trapeze, and seismic restraint by a qualified professional engineer.
 - 1. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of hangers and supports that are similar to those indicated for this Project in material, design, and extent.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Pipe Hangers:
 - a. B-Line Systems, Inc.
 - b. Globe Pipe Hanger Products, Inc.
 - c. Grinnell Corp.
 - d. Michigan Hanger Co., Inc.
 - e. National Pipe Hanger Corp.
 - 2. Channel Support Systems:
 - a. B-Line Systems, Inc.
 - b. Grinnell Corp.; Power-Strut Unit.
 - c. Michigan Hanger Co., Inc.; O-Strut Div.
 - d. National Pipe Hanger Corp.
 - e. Unistrut Corp.
 - 3. Thermal-Hanger Shield Inserts:
 - a. Michigan Hanger Co., Inc.
 - b. Pipe Shields, Inc.

2.2 MANUFACTURED UNITS

- A. Pipe Hangers, Supports, and Components: MSS SP-58, factory-fabricated components. Refer to "Hanger and Support Applications" Article in Part 3 for where to use specific hanger and support types.
 - 1. Galvanized, Metallic Coatings: For piping and equipment that will not have field-applied finish.
 - 2. Nonmetallic Coatings: On attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- B. Channel Support Systems: MFMA-2, factory-fabricated components for field assembly.
 - 1. Coatings: Manufacturer's standard finish, unless bare metal surfaces are indicated.
 - 2. Nonmetallic Coatings: On attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- C. Thermal-Hanger Shield Inserts: 100-psi minimum compressive-strength insulation, encased in sheet metal shield.
 - 1. Material for Cold Piping: ASTM C 552, Type I cellular glass with vapor barrier.
 - 2. Material for Hot Piping: ASTM C 552, Type I cellular glass.
 - 3. For Trapeze or Clamped System: Insert and shield cover entire circumference of pipe.
 - 4. For Clevis or Band Hanger: Insert and shield cover lower 180 degrees of pipe.
 - 5. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.3 MISCELLANEOUS MATERIALS

- A. Mechanical-Anchor Fasteners: Insert-type attachments with pull-out and shear capacities appropriate for supported loads and building materials where used.
- B. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars, black and galvanized.
- C. Grout: ASTM C 1107, Grade B, factory-mixed and -packaged, nonshrink and nonmetallic, dry, hydraulic-cement grout.
 - 1. Characteristics: Post hardening and volume adjusting; recommended for both interior and exterior applications.
 - 2. Properties: Nonstaining, noncorrosive, and nongaseous.
 - 3. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger requirements are specified in Sections specifying equipment and systems.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Specification Sections.

- C. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Adjustable Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 2-1/2 to NPS 30. Provide Plastic coated hangers for hot piping.
 2. Adjustable Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 2. provide plastic coated hangers for hot piping.
 3. Adjustable Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 2.
 4. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes, NPS 2-1/2 to NPS 36, if vertical adjustment is required, with steel pipe base stanchion support and cast-iron floor flange.
 5. Single Pipe Rolls (MSS Type 41): For suspension of pipes, NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
 6. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes, NPS 2-1/2 to NPS 20, from single rod if horizontal movement caused by expansion and contraction might occur.
 7. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes, NPS 2 to NPS 30, if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- D. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.
- E. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 2. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 3. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
- F. Building Attachments: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.

9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
 11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 13. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 14. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where head room is limited.
- G. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended by manufacturer to prevent crushing insulation.
 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe, 360-degree insert of high-density, 100-psi minimum compressive-strength, water-repellent-treated calcium silicate or cellular-glass pipe insulation, same thickness as adjoining insulation with vapor barrier and encased in 360-degree sheet metal shield.
- H. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from base support.
 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from trapeze support.
 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Pipe Hanger and Support Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- B. Channel Support System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled channel systems.
 - 1. Field assemble and install according to manufacturer's written instructions.
- C. Heavy-Duty Steel Trapeze Installation: Arrange for grouping of parallel runs of horizontal piping and support together on field-fabricated, heavy-duty trapezes.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified above for individual pipe hangers.
 - 2. Field fabricate from ASTM A 36/A 36M, steel shapes selected for loads being supported. Weld steel according to AWS D-1.1.
- D. Install building attachments within concrete slabs or attach to structural steel. Space attachments within maximum piping span length indicated in MSS SP-69. Install additional attachments at concentrated loads, including valves, flanges, guides, strainers, and expansion joints, and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- E. Install mechanical-anchor fasteners in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- F. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.
- G. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- H. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- I. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and so maximum pipe deflections allowed by ASME B31.9, "Building Services Piping," is not exceeded.
- J. Insulated Piping: Comply with the following:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits according to ASME B31.9.
 - 2. Install MSS SP-58, Type 39 protection saddles, if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - 3. Install MSS SP-58, Type 40 protective shields on cold piping with vapor barrier. Shields shall span arc of 180 degrees.
 - 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.

- b. NPS 4: 12 inches long and 0.06 inch thick.
- c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
- d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
- e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
- 5. Pipes NPS 8 and Larger: Include wood inserts.
- 6. Insert Material: Length at least as long as protective shield.
- 7. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure above or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.

3.4 METAL FABRICATION

- A. Cut, drill, and fit miscellaneous metal fabrications for heavy-duty steel trapezes and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field-weld connections that cannot be shop-welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1 procedures for shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work, and with the following:
 - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 - 2. Obtain fusion without undercut or overlap.
 - 3. Remove welding flux immediately.
 - 4. Finish welds at exposed connections so no roughness shows after finishing and contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustment: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

3.6 PAINTING

- A. Touching Up: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
 - 1. Apply paint by brush or spray to provide a minimum dry film thickness of 2.0 mils.
- B. Touching Up: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 9 Section "Painting."

- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 22 06 00

SECTION 22 07 50

PLUMBING IDENTIFICATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following mechanical identification materials and their installation:
 - 1. Equipment nameplates.
 - 2. Equipment markers.
 - 3. Pipe markers.
 - 4. Valve tags.
 - 5. Valve schedules.
 - 6. Warning tags.
- B. Related Sections include the following:
 - 1. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system. Furnish extra copies (in addition to mounted copies) to include in maintenance manuals.

1.4 QUALITY ASSURANCE

- A. ASME Compliance: Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.

1.5 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with location of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 EQUIPMENT IDENTIFICATION DEVICES

- A. Equipment Nameplates: Metal, with data engraved or stamped, for permanent attachment on equipment.
 - 1. Data:
 - a. Manufacturer, product name, model number, and serial number.
 - b. Capacity, operating and power characteristics, and essential data.
 - c. Labels of tested compliances.
 - 2. Location: Accessible and visible.
 - 3. Fasteners: As required to mount on equipment.
- B. Equipment Markers: Engraved, color-coded laminated plastic. Include contact-type, permanent adhesive.
 - 1. Terminology: Match schedules as closely as possible.
 - 2. Data:
 - a. Name and plan number.
 - b. Equipment service.
 - c. Design capacity.
 - d. Other design parameters such as pressure drop, entering and leaving conditions, and speed.
 - 3. Size: 2-1/2 by 4 inches for control devices, dampers, and valves; 4-1/2 by 6 inches for equipment.

2.2 PIPING IDENTIFICATION DEVICES

- A. Manufactured Pipe Markers, General: Preprinted, color-coded, with lettering indicating service, and showing direction of flow.
 - 1. Colors: Comply with ASME A13.1, unless otherwise indicated.
 - 2. Lettering: Use piping system terms indicated and abbreviate only as necessary for each application length.
 - 3. Pipes with OD, Including Insulation, Less Than 6 Inches: Full-band pipe markers extending 360 degrees around pipe at each location.
 - 4. Pipes with OD, Including Insulation, 6 Inches and Larger: Either full-band or strip-type pipe markers at least three times letter height and of length required for label.
 - 5. Arrows: Integral with piping system service lettering to accommodate both directions; or as separate unit on each pipe marker to indicate direction of flow.

- B. Shaped Pipe Markers: Preformed semirigid plastic formed to partially cover circumference of pipe and to attach to pipe with mechanical fasteners that do not penetrate insulation vapor barrier.
- C. Self-Adhesive Pipe Markers: Plastic with pressure-sensitive, permanent-type, self-adhesive back.
- D. Plastic Tape: Continuously printed, vinyl tape at least 3 mils thick with pressure-sensitive, permanent-type, self-adhesive back.
 - 1. Width for Markers on Pipes with OD, Including Insulation, Less Than 6 Inches: 3/4 inch minimum.
 - 2. Width for Markers on Pipes with OD, Including Insulation, 6 Inches or Larger: 1-1/2 inches minimum.

2.3 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers, with numbering scheme approved by Owner. Provide 5/32-inch hole for fastener.
 - 1. Material: 3/32-inch- thick laminated plastic with 2 black surfaces and white inner layer.
 - 2. Valve-Tag Fasteners: Brass wire-link or beaded chain; or S-hook.

2.4 VALVE SCHEDULES

- A. Valve Schedules: For each piping system, on standard-size bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.
 - 1. Valve-Schedule Frames: Glazed display frame for removable mounting on masonry walls for each page of valve schedule. Include mounting screws.
 - 2. Frame: Extruded aluminum.
 - 3. Glazing: ASTM C 1036, Type I, Class 1, Glazing Quality B, 2.5-mm, single-thickness glass.

2.5 WARNING TAGS

- A. Warning Tags: Preprinted or partially preprinted, accident-prevention tags; of plasticized card stock with matte finish suitable for writing.
 - 1. Size: 3 by 5-1/4 inches minimum.
 - 2. Fasteners: Brass grommet and wire.
 - 3. Nomenclature: Large-size primary caption such as DANGER, CAUTION, or DO NOT OPERATE.
 - 4. Color: Yellow background with black lettering.

PART 3 - EXECUTION

3.1 APPLICATIONS, GENERAL

- A. Products specified are for applications referenced in other Division 22 Sections. If more than single-type material, device, or label is specified for listed applications, selection is Installer's option.

3.2 EQUIPMENT IDENTIFICATION

- A. Install and permanently fasten equipment nameplates on each major item of mechanical equipment that does not have nameplate or has nameplate that is damaged or located where not easily visible. Locate nameplates where accessible and visible. Include nameplates for the following general categories of equipment:
 - 1. Fuel-burning units, including boilers, furnaces, heaters, stills, and absorption units.
 - 2. Pumps, compressors, chillers, condensers, and similar motor-driven units.
- B. Install equipment markers with permanent adhesive on or near each major item of mechanical equipment. Data required for markers may be included on signs, and markers may be omitted if both are indicated.
 - 1. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
 - 2. Data: Distinguish among multiple units, indicate operational requirements, indicate safety and emergency precautions, warn of hazards and improper operations, and identify units.
 - 3. Locate markers where accessible and visible. Include markers for the following general categories of equipment:
 - a. Main control and operating valves, including safety devices and hazardous units such as gas outlets.
 - b. Meters, gages, thermometers, and similar units.
 - c. Fuel-burning units, including boilers, furnaces, heaters, stills, and absorption units.
 - d. Pumps, compressors, chillers, condensers, and similar motor-driven units.
 - e. Tanks and pressure vessels.
 - f. Strainers, filters, water-treatment systems, and similar equipment.
- C. Install equipment signs with screws or permanent adhesive on or near each major item of mechanical equipment. Locate signs where accessible and visible.
 - 1. Identify mechanical equipment with equipment markers in the following color codes:
 - a. Green: For cooling equipment and components.
 - b. Yellow: For heating equipment and components.
 - c. Brown: For energy-reclamation equipment and components.
 - 2. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
 - 3. Data: Distinguish among multiple units, indicate operational requirements, indicate safety and emergency precautions, warn of hazards and improper operations, and identify units.
 - 4. Include signs for the following general categories of equipment:
 - a. Main control and operating valves, including safety devices and hazardous units such as gas outlets.
 - b. Fuel-burning units, including boilers, furnaces, heaters, stills, and absorption units.

- c. Pumps, compressors, chillers, condensers, and similar motor-driven units.
 - d. Tanks and pressure vessels.
 - e. Strainers, filters, water-treatment systems, and similar equipment.
- D. Install access panel markers with screws on equipment access panels.

3.3 PIPING IDENTIFICATION

- A. Install manufactured pipe markers indicating service on each piping system. Install with flow indication arrows showing direction of flow.
 - 1. Pipes with OD, Including Insulation, Less Than 6 Inches: Self-adhesive pipe markers. Use color-coded, self-adhesive plastic tape, at least 3/4 inch wide, lapped at least 1-1/2 inches at both ends of pipe marker, and covering full circumference of pipe.
 - 2. Pipes with OD, Including Insulation, 6 Inches and Larger: Self-adhesive pipe markers. Use color-coded, self-adhesive plastic tape, at least 1-1/2 inches wide, lapped at least 3 inches at both ends of pipe marker, and covering full circumference of pipe.
- B. Locate pipe markers and color bands where piping is exposed in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior nonconcealed locations as follows:
 - 1. Near each valve and control device.
 - 2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
 - 3. Near penetrations through walls, floors, ceilings, and nonaccessible enclosures.
 - 4. At access doors, manholes, and similar access points that permit view of concealed piping.
 - 5. Near major equipment items and other points of origination and termination.
 - 6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
 - 7. On piping above removable acoustical ceilings. Omit intermediately spaced markers.

3.4 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; plumbing fixture supply stops; shutoff valves; faucets; convenience and lawn-watering hose connections; and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following:
 - 1. Valve-Tag Size and Shape:
 - a. Cold Water: 2 inches, round.
 - b. Hot Water: 2 inches, round.
 - c. Gas: 2 inches, round.
 - 2. Valve-Tag Color:
 - a. Cold Water: Blue.
 - b. Hot Water: Blue
 - c. Gas: Green
 - 3. Letter Color:

- a. Cold Water: White.
- b. Hot Water: White.
- c. Gas: White.

3.5 VALVE-SCHEDULE INSTALLATION

- A. Mount valve schedule on wall in accessible location in each major equipment room.

3.6 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

3.7 ADJUSTING

- A. Relocate mechanical identification materials and devices that have become visually blocked by other work.

3.8 CLEANING

- A. Clean faces of mechanical identification devices and glass frames of valve schedules.

END OF SECTION 22 07 50

SECTION 22 08 40

PLUMBING PIPE INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

1.3 DEFINITIONS

- A. Hot Surfaces: Normal operating temperatures of 100 deg F or higher.
- B. Dual-Temperature Surfaces: Normal operating temperatures that vary from hot to cold.
- C. Cold Surfaces: Normal operating temperatures less than 75 deg F.
- D. Thermal Resistivity: "r-values" represent the reciprocal of thermal conductivity (k-value). Thermal conductivity is the rate of heat flow through a homogenous material exactly 1 inch thick. Thermal resistivities are expressed by the temperature difference in degrees F between two exposed faces required to cause one Btu to flow through one square foot of material, in one hour, at a given mean temperature.
- E. Density: Is expressed in lb/sq.ft.

1.4 SUBMITTALS

- A. General: Submit the following in accordance with Conditions of Contract and Division 1 Specification Sections.
- B. Product data for each type of mechanical insulation identifying k-value, thickness, and accessories.

1.5 QUALITY ASSURANCE

- A. Fire Performance Characteristics: Conform to the following characteristics for insulation including facings, cements, and adhesives, when tested according to ASTM E 84, by UL or other testing or inspecting organization acceptable to the authority having jurisdiction. Label insulation with appropriate markings of testing laboratory.
 - 1. Interior Insulation: Flame spread rating of 25 or less and a smoke developed rating of 50 or less.

2. Exterior Insulation: Flame spread rating of 75 or less and a smoke developed rating of 150 or less.

1.6 SEQUENCING AND SCHEDULING

- A. Schedule insulation application after testing of piping systems.
- B. Schedule insulation application after installation and testing of heat trace tape.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated in the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Glass Fiber:
 - a. CertainTeed Corporation.
 - b. Knauf Fiberglass GmbH.
 - c. Manville.
 - d. Owens-Corning Fiberglas Corporation.
 2. Flexible Elastomeric Cellular:
 - a. Armacell
 - b. Aeroflex

2.2 GLASS FIBER

- A. Material: Inorganic glass fibers, bonded with a thermosetting resin.
- B. Jacket: All-purpose, factory-applied, laminated glass-fiber-reinforced, flame-retardant kraft paper and aluminum foil having self-sealing lap.
- C. Preformed Pipe Insulation: ASTM C 547, Class 1, rigid pipe insulation, jacketed.
 1. Thermal Conductivity: 0.26 average maximum at 75 deg F mean temperature.
 2. Density: 10 average maximum.
- D. Adhesive: Produced under the UL Classification and Follow-up service.
 1. Type: Non-flammable, solvent-based.
 2. Service Temperature Range: Minus 20 to 180 deg F.
- E. Vapor Barrier Coating: Waterproof coating recommended by insulation manufacturer for outside service.

2.3 FLEXIBLE ELASTOMERIC CELLULAR

- A. Material: Flexible expanded closed-cell structure with smooth skin on both sides.
 - 1. Tubular Materials: ASTM C 534, Type I.
 - 2. Sheet Materials: ASTM C 534, Type II.
- B. Thermal Conductivity: 0.30 average maximum at 75 deg F.
- C. Coating: Water based latex enamel coating recommended by insulation manufacturer.

2.4 ADHESIVES

- A. Flexible Elastomeric Cellular Insulation Adhesive: Solvent-based, contact adhesive recommended by insulation manufacturer.
- B. Lagging Adhesive: MIL-A-3316C, non-flammable adhesive in the following Classes and Grades:
 - 1. Class 1, Grade A for bonding glass cloth and tape to unfaced glass fiber insulation, sealing edges of glass fiber insulation, and bonding lagging cloth to unfaced glass fiber insulation.
 - 2. Class 2, Grade A for bonding glass fiber insulation to metal surfaces.

2.5 JACKETS

- A. General: ASTM C 921, Type 1, except as otherwise indicated.
- B. Foil and Paper Jacket: Laminated glass-fiber-reinforced, flame-retardant kraft paper and aluminum foil.
 - 1. Water Vapor Permeance: 0.02 perm maximum, when tested according to ASTM E 96.
 - 2. Puncture Resistance: 50 beach units minimum, when tested according to ASTM D 781.
- C. PVC Jacketing: High-impact, ultra-violet-resistant PVC, 20-mils thick, roll stock ready for shop or field cutting and forming to indicated sizes.
 - 1. Adhesive: As recommended by insulation manufacturer.
- D. PVC Fitting Covers: Factory-fabricated fitting covers manufactured from 20-mil-thick, high-impact, ultra-violet-resistant PVC.
 - 1. Adhesive: As recommended by insulation manufacturer.
- E. Aluminum Jacket: ASTM B 209, 3003 Alloy, H-14 temper, roll stock ready for shop or field cutting and forming to indicated sizes.
 - 1. Finish and Thickness: Smooth finish, 0.010 inch thick.
 - 2. Moisture Barrier: 3-mil Dupont Surlyn.
 - 3. Elbows: Preformed 45-degree and 90-degree, short- and long-radius elbows, same material, finish, and thickness as jacket.

2.6 ACCESSORIES AND ATTACHMENTS

- A. Glass Tape: Woven glass fiber fabrics, plain weave, presized a minimum of 8 ounces per sq. yd.
 - 1. Tape Width: 4 inches.
 - 2. Tape Standard: MIL-C-20079H, Type II.

- B. Bands: 3/4-inch wide, in one of the following materials compatible with jacket:
 - 1. Aluminum: 0.007 inch thick.

2.7 SEALING COMPOUNDS

- A. Vapor Barrier Compound: Water-based, fire-resistive composition.
 - 1. Water Vapor Permeance: 0.08 perm maximum.
 - 2. Temperature Range: Minus 20 to 180 deg F.
- B. Weatherproof Sealant: Flexible-elastomer-based, vapor-barrier sealant designed to seal metal joints.
 - 1. Water Vapor Permeance: 0.02 perm maximum.
 - 2. Temperature Range: Minus 50 to 250 deg F.
 - 3. Color: Aluminum.

PART 3 - EXECUTION

3.1 PREPARATION

- A. Surface Preparation: Clean, dry, and remove foreign materials such as rust, scale, and dirt.

3.2 INSTALLATION, GENERAL

- A. Refer to schedules at the end of this Section for materials, forms, jackets, and thicknesses required for each plumbing system.
- B. Select accessories compatible with materials suitable for the service. Select accessories that do not corrode, soften, or otherwise attack the insulation or jacket in either the wet or dry state.
- C. Install vapor barriers on insulated pipes and equipment having surface operating temperatures below 60 deg F.
- D. Apply insulation material, accessories, and finishes according to the manufacturer's printed instructions.
- E. Install insulation with smooth, straight, and even surfaces.
- F. Seal joints and seams to maintain vapor barrier on insulation requiring a vapor barrier.
- G. Seal penetrations for hangers, supports, anchors, and other projections in insulation requiring a vapor barrier.
- H. Seal Ends: Except for flexible elastomeric insulation, taper ends at 45 degree angle and seal with lagging adhesive. Cut ends of flexible elastomeric cellular insulation square and seal with adhesive.
- I. Apply adhesives and coatings at manufacturer's recommended coverage-per-gallon rate.
- J. Keep insulation materials dry during application and finishing.

- K. Items Not Insulated: Unless otherwise indicated do not apply insulation to the following systems, materials, and equipment:
1. Flexible connectors for pipes.
 2. Vibration control devices.
 3. Testing laboratory labels and stamps.
 4. Nameplates and data plates.
 5. Access panels and doors in air distribution systems.
 6. Fire protection piping systems.
 7. Sanitary drainage and vent piping.
 8. Below grade piping.
 9. Chrome-plated pipes and fittings, except for plumbing fixtures for the disabled.
 10. Piping specialties including unions, strainers, check valves and flow regulators.

3.3 PIPE INSULATION INSTALLATION, GENERAL

- A. Tightly butt longitudinal seams and end joints. Bond with adhesive.
- B. Stagger joints on double layers of insulation.
- C. Apply insulation continuously over fittings, valves, and specialties, except as otherwise indicated.
- D. Apply insulation with a minimum number of joints.
- E. Apply insulation with integral jackets as follows:
1. Pull jacket tight and smooth.
 2. Cover circumferential joints with butt strips, at least 3-inches wide, and of same material as insulation jacket. Secure with adhesive and outward clinching staples along both edges of butt strip and space 4 inches on center.
 3. Longitudinal Seams: Overlap seams at least 1-1/2 inches. Apply insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 4 inches on center.
 4. Vapor Barrier Coatings: Where vapor barriers are indicated, apply on seams and joints, over staples, and at ends butt to flanges, unions, valves, and fittings.
 5. At penetrations in jackets for thermometers and pressure gages, fill and seal voids with vapor barrier coating.
 6. Repair damaged insulation jackets, except metal jackets, by applying jacket material around damaged jacket. Adhere, staple, and seal. Extend patch at least 2 inches in both directions beyond damaged insulation jacket and around the entire circumference of the pipe.
- F. Roof Penetrations: Apply insulation for interior applications to a point even with the top of the roof flashing. Seal with vapor barrier coating. Apply insulation for exterior applications butted tightly to interior insulation ends. Extend metal jacket for exterior insulation outside roof flashing at least 2 inches below top of roof flashing. Seal metal jacket to roof flashing with vapor barrier coating.
- G. Exterior Wall Penetrations: For penetrations of below grade exterior walls, terminate insulation flush with mechanical sleeve seal. Seal terminations with vapor barrier coating.
- H. Exterior Wall Penetrations: For penetrations of below grade exterior walls, extend metal jacket for exterior insulation through penetration to a point 2 inches from interior surface of wall inside the building. Seal ends of metal jacket with vapor barrier coating. Secure metal jacket ends with metal

band. At point where insulation metal jacket contacts mechanical sleeve seal, insert cellular glass preformed pipe insulation to allow sleeve seal tightening against metal jacket. Tighten and seal sleeve to jacket to form a watertight seal.

- I. Interior Walls and Partitions Penetrations: Apply insulation continuously through walls and partitions, except fire-rated walls and partitions.
- J. Fire-Rated Walls and Partitions Penetrations: Terminate insulation at penetrations through fire-rated walls and partitions. Seal insulation ends with vapor barrier coating. Seal around penetration with firestopping or fire-resistant joint sealer.
- K. Floor Penetrations: Apply insulation continuously through floors.
- L. Flanges, Fittings, and Valves - Interior Exposed and Concealed: Coat pipe insulation ends with vapor barrier coating. Apply premolded, precut, or field-fabricated segments of insulation around flanges, unions, valves, and fittings. Make joints tight. Bond with adhesive.
 - 1. Use same material and thickness as adjacent pipe insulation.
 - 2. Overlap nesting insulation by 2 inches or 1-pipe diameter, whichever is greater.
 - 3. Apply materials with adhesive, fill voids with mineral fiber insulating cement. Secure with wire or tape.
 - 4. Insulate elbows and tees smaller than 3-inches pipe size with premolded insulation.
 - 5. Insulate elbows and tees 3 inches and larger with premolded insulation or insulation material segments. Use at least 3 segments for each elbow.
 - 6. Cover insulation, except for metal jacketed insulation, with PVC fitting covers and seal circumferential joints with butt strips.
 - 7. Cover insulation, except for metal jacketed insulation, with 2 layers of lagging adhesive to a minimum thickness of 1/16 inch. Install glass cloth between layers. Overlap adjacent insulation by 2 inches in both directions from joint with glass cloth and lagging adhesive.
- M. Hangers and Anchors: Apply insulation continuously through hangers and around anchor attachments. Install saddles, shields, and inserts as specified in Division 15150. For cold surface piping, extend insulation on anchor legs a minimum of 12 inches and taper and seal insulation ends.
 - 1. Inserts and Shields: Cover hanger inserts and shields with jacket material matching adjacent pipe insulation.

3.4 GLASS FIBER PIPE INSULATION INSTALLATION

- A. Bond insulation to pipe with lagging adhesive.
- B. Seal exposed ends with lagging adhesive.
- C. Seal seams and joints with vapor barrier compound.

3.5 FLEXIBLE ELASTOMERIC CELLULAR PIPE INSULATION INSTALLATION

- A. Slip insulation on the pipe before making connections wherever possible. Seal joints with adhesive. Where the slip-on technique is not possible, cut one side longitudinally and apply to the pipe. Seal seams and joints with adhesive.

- B. Valves, Fittings, and Flanges: Cut insulation segments from pipe or sheet insulation. Bond to valve, fitting, and flange and seal joints with adhesive.
 - 1. Miter cut materials to cover soldered elbows and tees.
 - 2. Fabricate sleeve fitting covers from flexible elastomeric cellular insulation for screwed valves, fittings, and specialties. Miter cut materials. Overlap adjoining pipe insulation.

3.6 JACKETS

- A. Foil and Paper Jackets (FP): Install jackets drawn tight. Install lap or butt strips at joints with material same as jacket. Secure with adhesive. Install jackets with 1-1/2-inch laps at longitudinal joints and 3-inch-wide butt strips at end joints.
- B. Seal openings, punctures, and breaks in vapor barrier jackets and exposed insulation with vapor barrier compound.
- C. Exterior Exposed Insulation: Install continuous aluminum jackets and seal all joints and seams with waterproof sealant.
- D. Install metal jacket with 2-inch overlap at longitudinal and butt joints. Overlap longitudinal joints to shed water. Seal butt joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel draw bands 12 inches on center and at butt joints.

3.7 FINISHES

- A. Flexible Elastomeric Cellular Insulation: After adhesive has fully cured, apply 2 coats of protective coating to exposed insulation.

3.8 APPLICATIONS

- A. General: Materials and thicknesses are specified in schedules at the end of this Section.
- B. Interior Piping Systems: Unless otherwise indicated, insulate the following piping systems:
 - 1. Domestic cold water.
 - 2. Storm water. Insulate roof drain bodies, vertical and horizontal rainwater leaders of storm water piping.
 - 3. Domestic hot water.
 - 4. Recirculated hot water.

3.9 PIPE INSULATION SCHEDULES

- A. General: Abbreviations used in the following schedules include:
 - 1. Field-Applied Jackets: P - PVC, K - Foil and Paper, A - Aluminum, SS - Stainless Steel.
 - 2. Pipe Sizes: NPS - Nominal Pipe Size.

3.10 .PVC PIPE INSULATION IN PLENUM SPACES

- A. Insulate all existing PVC pipe and fittings in the return air plenum spaces on the first and second floor areas with 1" thick, 3M Fire Barrier Plenum Wrap 5A pipe insulation. Install per manufactures instructions.

INTERIOR DOMESTIC HOT WATER AND RECIRCULATED HOT WATER

PIPE SIZES (NPS)	MATERIALS	THICKNESS IN INCHES	VAPOR BARRIER REQ'D	FIELD- APPLIED JACKET
1/2 TO 2	GLASS FIBER	1/2	NO	NONE
	CELLULAR GLASS	1	NO	NONE
	FLEXIBLE	1/2	NO	NONE
	ELASTOMERIC			
2-1/2 TO 4	GLASS FIBER	1	NO	NONE
	CELLULAR GLASS	1	NO	NONE
5 TO 10	GLASS FIBER	1-1/2	NO	NONE
	CELLULAR GLASS	1-1/2	NO	NONE

INTERIOR DOMESTIC COLD WATER AND STORM WATER

PIPE SIZES (NPS)	MATERIALS	THICKNESS IN INCHES	VAPOR BARRIER REQ'D	FIELD- APPLIED JACKET
1/2 TO 2	GLASS FIBER	1/2	YES	NONE
	CELLULAR GLASS	1	YES	NONE
	FLEXIBLE	1/2	YES	NONE
	ELASTOMERIC			
2-1/2 TO 4	GLASS FIBER	1	YES	NONE
	CELLULAR GLASS	1	YES	NONE
5 TO 15	GLASS FIBER	1-1/2	YES	NONE
	CELLULAR GLASS	1-1/2	YES	NONE

END OF SECTION 22 08 40

SECTION 22 11 00

PLUMBING VALVES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes general duty valves common to plumbing piping systems.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Special purpose valves are specified in Division 22 piping system Sections.
 - 2. Valve tags and charts are specified in Division 22 Section "Plumbing Identification."
 - 3. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.3 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Section 22 Specification Sections.
- B. Product Data for each valve type. Include body material, valve design, pressure and temperature classification, end connection details, seating materials, trim material and arrangement, dimensions and required clearances, and installation instructions. Include list indicating valve and its application.
- C. Maintenance data for valves to include in the operation and maintenance manual specified in Division 1. Include detailed manufacturer's instructions on adjusting, servicing, disassembling, and repairing.

1.4 QUALITY ASSURANCE

- A. ASTM Compliance: Brass valves- ASTM B-61, ASTM B-62, and ASTM B-584. Silicon Brass- ASTM B-371 Alloy 694 or ASTM B-99 Alloy 651. Only valves containing 15% or less of zinc will be acceptable.
- B. ASME Compliance: Comply with ASME B31.9 for building services piping and ASME B31.1 for power piping.
- C. ASME Compliance for Ferrous Valves: ASME B16.10 and ASME B16.34 for dimension and design criteria.
- D. MSS Compliance: Comply with the various MSS Standard Practice documents referenced.

- E. NSF Compliance: NSF 61 for valve materials for potable water.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
 - 1. Protect internal parts against rust and corrosion.
 - 2. Protect threads, flange faces, and grooves.
 - 3. Set ball valves open to minimize exposure of functional surfaces.
 - 4. Set butterfly valves closed or slightly open.
 - 5. Block check valves in either closed or open position.
- B. Use the following precautions during storage:
 - 1. Maintain valve end protection.
 - 2. Store indoors and maintain valve temperature higher than ambient dew-point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use a sling to handle large valves. Rig to avoid damage to exposed parts. Do not use handwheels and stems as lifting or rigging points.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Ball Valves:
 - a. Conbraco Industries, Inc.; Apollo Division.
 - b. Hammond Valve Corporation.
 - c. NIBCO Inc.
 - d. Watts
 - 2. Swing Check Valves:
 - a. Hammond Valve Corporation.
 - b. NIBCO Inc.
 - c. Watts
 - 3. Calibrated Balancing Valves:
 - a. Armstrong Pumps, Inc.
 - b. ITT Fluid Technology Corp.; ITT Bell & Gossett Div.
 - c. Taco, Inc.

2.2 BASIC, COMMON FEATURES

- A. Pressure and Temperature Ratings: As indicated in the "Application Schedule" of Part 3 of this Section and as required to suit system pressures and temperatures.
- B. Sizes: Same size as upstream pipe, unless otherwise indicated.
- C. Operators: Use specified operators and handwheels, except provide the following special operator features:

1. Handwheels: For valves other than quarter turn.
 2. Lever Handles: For quarter-turn valves 4 inches and smaller.
 3. Gear-Drive Operators: For quarter-turn valves 6 inches and larger.
- D. Extended Stems: Where insulation is indicated or specified, provide extended stems arranged to receive insulation.
- E. Bypass and Drain Connections: Comply with MSS SP-45 bypass and drain connections.
- F. Threads: ASME B1.20.1.
- G. Flanges: ASME B16.1 for cast iron, ASME B16.5 for steel, and ASME B16.24 for bronze valves.

2.3 BALL VALVES

- A. Ball Valves, 3 Inches and Smaller: MSS SP-110, Class 150, 600-psi CWP, ASTM B 584 bronze body and bonnet, 2-piece construction; stainless steel ball, full port; blowout proof; stainless steel stem; teflon seats and seals; threaded or soldered end connections:
1. Operator: Vinyl-covered steel lever handle.
 2. Operator: Lever operators with lock where called for on the drawings.
 3. Stem Extension: For valves installed in insulated piping.
 4. Memory Stop: For operator handles.

2.4 CHECK VALVES

- A. Swing Check Valves, 2-1/2 Inches and Smaller: MSS SP-80; Class 125, 200-psi CWP, or Class 150, 300-psi CWP; horizontal swing, Y-pattern, ASTM B 62 cast-bronze body and cap, rotating bronze disc with rubber seat or composition seat, threaded or soldered end connections:

2.5 BALANCING VALVES

- A. Furnish and install in the hot water recirculating branches a Bell and Gossett Bronze Circuit Setter with provisions for connecting portable differential pressure meter. An integral pointer shall be installed to provide degree of valve opening. A calibrated chart shall accompany the Circuit Setter and may be used to determine flow rate. Each Circuit Setter shall be constructed for 125 lbs. working pressure at 250°F, and supplied with a preformed polyurethane package that can be reused for insulation on the piping system. Before the job is turned over to the owner the Circuit Setters shall be adjusted to balance the circulation of hot water in all branches.
- B. Similar valves by Armstrong will be acceptable. NOTE: If Armstrong balancing valves are used the Plumbing Contractor may eliminate the shut-off valve at each balancing valve as shown on the drawings.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine piping system for compliance with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.
- B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- C. Operate valves from fully open to fully closed positions. Examine guides and seats made accessible by such operation.
- D. Examine threads on valve and mating pipe for form and cleanliness.
- E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Check gasket material for proper size, material composition suitable for service, and freedom from defects and damage.
- F. Do not attempt to repair defective valves; replace with new valves.

3.2 INSTALLATION

- A. Install valves as indicated, according to manufacturer's written instructions.
- B. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.
- C. Install valves with unions or flanges at each piece of equipment arranged to allow servicing, maintenance, and equipment removal without system shutdown.
- D. Locate valves for easy access and provide separate support where necessary.
- E. Install valves in horizontal piping with stem at or above the center of the pipe.
- F. Install valves in a position to allow full stem movement.
- G. Installation of Check Valves: Install for proper direction of flow as follows:
 - 1. Swing Check Valves: Horizontal position with hinge pin level.

3.3 THREADED CONNECTIONS

- A. Note the internal length of threads in valve ends and proximity of valve internal seat or wall to determine how far pipe should be threaded into valve.
- B. Align threads at point of assembly.
- C. Apply appropriate tape or thread compound to the external pipe threads, except where dry seal threading is specified.
- D. Assemble joint, wrench tight. Wrench on valve shall be on the valve end into which the pipe is being threaded.

3.4 VALVE END SELECTION

- A. Select valves with the following ends or types of pipe/tube connections:
 - 1. Copper Tube Size, 2 Inches and Smaller: Threaded or Soldered ends.

3.5 APPLICATION SCHEDULE

- A. General Application: Use ball shutoff duty. Refer to piping system Specification Sections for specific valve applications and arrangements.
- B. Domestic Water Systems: Use the following valve types:
 - 1. Ball Valves: Class 150, 600-psi CWP, with stem extension.
 - 2. Check Valves: Class 125, swing type.

3.6 DOMESTIC HOT WATER RETURN SYSTEM BALANCING

- A. This Contractor shall obtain the services of an independent firm to perform the hot water return system balancing. A Professional Engineer shall supervise all work and certify the balance report.
- B. The Plumbing Contractor shall:
 - 1. Install all domestic hot water recirculating balancing valves indicated to be installed under this contract in a manner that will leave them accessible and readily adjustable. All hose connections and dial face shall be turned down or horizontal for ease of attachments and reading.
 - 2. He shall pre-set all balancing valves installed by him as directed by the Engineer.
 - 3. Provide the balance firm with one copy of the plumbing plans indicating the exact location of all devices.
 - 4. Place the plumbing equipment into full operation, domestic hot water heaters and hot water recirculating pumps and continue operating the equipment during the balancing.
 - 5. Open all valves throughout the domestic hot water system.
 - 6. Aid the balancing firm in locating and adjusting all balancing valves.
- C. The balance firm shall adjust the flow through all balancing elements to within 5% of design conditions.
- D. The balance firm shall prepare and submit to the Engineer four copies of the test and balance report.
- E. The balance firm shall provide a one-year warranty during which time additional adjustments may be required.

3.7 ADJUSTING

- A. Adjust or replace packing after piping systems have been tested and put into service, but before final adjusting and balancing. Replace valves if leak persists.

END OF SECTION 22 11 00

This page intentionally left blank.

SECTION 22 14 00

PLUMBING METERS AND GAGES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including the General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes meters and gages used in plumbing and fire protection systems.
- B. Related Sections: Division 22 piping Sections contain requirements that relate to this Section.
 - 1. Meters and gages furnished as part of factory-fabricated equipment are specified as part of the equipment assembly in other Division 22 Sections.
 - 2. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.3 SUBMITTALS

- A. General: Submit the following according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product data for each type of meter, gage, and fitting specified. Include scale range, ratings, and calibrated performance curves, certified where indicated. Submit a meter and gage schedule showing manufacturer's figure number, scale range, location, and accessories for each meter and gage.
- C. Product certificates signed by manufacturers of meters and gages certifying accuracies under specified operating conditions and compliance with specified requirements.
- D. Maintenance data to include in the "Operating and Maintenance Manuals" specified in Division 1 Section "Project Closeout." Include data for the following:
 - 1. Test plugs.
 - 2. Flow measuring systems.
 - 3. Flow meters.

1.4 QUALITY ASSURANCE

- A. Comply with applicable portions of American Society of Mechanical Engineers (ASME) and Instrument Society of America (ISA) standards pertaining to construction and installation of meters and gages.

- B. Design Criteria: Meters and gages having equal performance characteristics by other manufacturers may be considered, provided that deviations do not change the design concept or intended performance as judged by the Engineer. The burden of proof for equality of meters and gages is on the proposer.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Direct-Mounting Filled-System Dial Thermometers:
 - a. Ashcroft Instrument Div. of Dresser Industries.
 - b. Marsh Instrument Co.
 - c. H.O. Trerice Co.
 - d. Weiss Instruments, Inc.
 - e. Weksler Instruments Corp.
 2. Insertion Dial Thermometers:
 - a. Ashcroft by Dresser Industries, Instrument Div.
 - b. H.O. Trerice Co.
 - c. Weiss Instruments, Inc.
 - d. Weksler Instruments Corp.
 3. Pressure Gages:
 - a. Ashcroft by Dresser Industries, Instrument Div.
 - b. Marsh Instrument Co.
 - c. H.O. Trerice Co.
 - d. Weiss Instruments, Inc.
 - e. Weksler Instruments Corp.
 4. Test Plugs:
 - a. Flow Design, Inc.
 - b. MG Piping Products Co.
 - c. Peterson Equipment Co., Inc.
 - d. Sisco Co., Spedco, Inc.
 - e. H.O. Trerice Co.
 - f. Watts Regulator Co.

2.2 THERMOMETERS, GENERAL

- A. Scale Range: Temperature ranges for services listed as follows:
1. Domestic Hot Water: 30 to 240 deg F, with 2-degree scale divisions (0 to 115 deg C, with 1-degree scale divisions).
 2. Domestic Cold Water: 0 to 100 deg F, with 2-degree scale divisions (minus 18 to 38 deg C, with 1-degree scale divisions).
- B. Accuracy: Plus or minus 1 percent of range span or plus or minus one scale division to maximum of 1.5 percent of range span.

2.3 DIRECT-MOUNTING FILLED-SYSTEM DIAL THERMOMETERS

- A. Description: Vapor-actuated universal-angle dial thermometer.
- B. Case: Drawn steel or cast aluminum, with 4-1/2-inch (115mm) -diameter glass lens.
- C. Adjustable Joint: Finish to match case, 180-degree (3.1rad) adjustment in vertical plane, 360-degree (6.3rad) adjustment in horizontal plane, with locking device.
- D. Thermal Bulb: Copper with phosphor-bronze Bourdon pressure tube.
- E. Movement: Brass, precision geared.
- F. Scale: Progressive satin-faced nonreflective aluminum with permanently etched markings.
- G. Stem: Copper-plated steel, aluminum, or brass for a separable socket of length to suit installation.

2.4 INSERTION DIAL THERMOMETERS

- A. Description: Bimetal dial thermometer.
- B. Dial: 4-1/2-inch diameter.
- C. Case: Stainless steel.
- D. Stem: Dustproof and leakproof 1/8-inch (3mm) -diameter tapered-end stem with nominal length of 5 inches (125 mm).

2.5 THERMOMETER WELLS

- A. Description: Brass or stainless-steel thermometer well.
- B. Pressure Rating: Not less than piping system design pressure.
- C. Stem Length: To extend 2 inches (50 mm) into fluid.
- D. Extension for Insulated Piping: 2 inches (50 mm) nominal, but not less than thickness of insulation.
- E. Threaded Cap Nut: With chain permanently fastened to well and cap.

2.6 PRESSURE GAGES

- A. Description: ASME B40.1, Grade A phosphor-bronze Bourdon-tube pressure gage, with bottom connection.
- B. Case: Drawn steel, brass, or aluminum with 4-1/2-inch (115mm) -diameter glass lens.
- C. Connector: Brass, 1/4-inch (8mm) NPS.

- D. Scale: White-coated aluminum, with permanently etched markings.
- E. Accuracy: Plus or minus 1 percent of range span.
- F. Range: Conform to the following:
 - 1. Fluids Under Pressure: 2 times operating pressure.

2.7 PRESSURE-GAGE ACCESSORIES

- A. Syphons: 1/4-inch (8mm) straight coil of brass tubing with threads on each end.
- B. Snubbers: 1/4-inch (8mm) brass bushing with corrosion-resistant porous-metal disc of material suitable for system fluid and working pressure.

2.8 TEST PLUGS

- A. Description: Nickel-plated brass-body test plug in 1/2-inch (15mm) fitting.
- B. Body: Length as required to extend beyond insulation.
- C. Pressure Rating: 500 psig (3450 kPa) minimum.
- D. Core Inserts: 2 self-sealing valve types, suitable for inserting a 1/8-inch (3mm) outside-diameter probe from a dial thermometer or pressure gage.
- E. Core Material: According to the following for fluid and temperature range:
 - 1. Air, Water, Oil, and Gas: 20 to 200 deg F (minus 7 to 93 deg C), neoprene rubber.
 - 2. Air and Water: Minus 30 deg to 275 deg F (minus 35 to 136 deg C), ethylene-propylene-diene-terpolymer (EPDM) rubber.
- F. Test-Plug Cap: Gasketed and threaded cap, with retention chain.
- G. Test Kit: Provide test kit consisting of 1 pressure gage and gage adapter with probe, 2 bimetal dial thermometers and a carrying case.
- H. Pressure Gage and Thermometer Ranges: Approximately 2 times systems operating conditions.

PART 3 - EXECUTION

- A. METER AND GAGE APPLICATIONS
 - 1. General: Where indicated, install meters and gages of types, sizes, capacities, and with features indicated.
- B. METER AND GAGE INSTALLATION, GENERAL
 - 1. Install meters, gages, and accessories according to manufacturers' written instructions for applications where used.
- C. THERMOMETER INSTALLATION
 - 1. Install thermometers and adjust vertical and tilted positions.

2. Install in the following locations and elsewhere as indicated:
 - a. At inlet and outlet of each domestic hot water heater.
 - b. At inlet of each domestic hot water return pump.
 - c. At inlet and outlet of each hot water storage tank.
 - d. On incoming domestic water service at entrance to building.
3. Remote-Reading Dial Thermometers: Install in control panels with tubing connecting panel and thermometer bulb supported to prevent kinks. Use minimum tubing length.
4. Thermometer Wells: Install in vertical position in piping tees where thermometers are indicated.
 - a. Install wells with stem extending minimum of 2 inches (50 mm) into fluid.
 - b. Install wells with stem extending to center of pipe.
 - c. Fill wells with oil or graphite and secure caps.

D. PRESSURE GAGE INSTALLATION

1. Install pressure gages in piping tee with pressure gage valve located on pipe at most readable position.
2. Install in the following locations and elsewhere as indicated:
 - a. At suction and discharge of each pump.
 - b. At inlet and discharge of each pressure-reducing valve.
 - c. At building water service entrance.
 - d. At inlet and outlet of each mineral tank on water softener.
3. Pressure Gage Needle Valves: Install in piping tee with snubber. Install syphon instead of snubber for steam pressure gages.

E. TEST PLUG INSTALLATION

1. Install test plugs in piping tees where indicated, located on pipe at most readable position. Secure cap.

F. CONNECTIONS

1. Piping installation requirements are specified in other Division 22 Sections. The Drawings indicate the general arrangement of piping, fittings, and specialties.
2. Install meters and gages adjacent to machines and equipment to allow servicing and maintenance.
3. Connect flow-measuring-system elements to meters.
4. Connect flow-meter transmitters to meters.
5. Make electrical connections to power supply and electrically operated meters and devices.

G. ADJUSTING AND CLEANING

1. Calibrate meters according to manufacturer's written instructions, after installation.
2. Adjusting: Adjust faces of meters and gages to proper angle for best visibility.
3. Cleaning: Clean windows of meters and gages and factory-finished surfaces. Replace cracked and broken windows and repair scratched and marred surfaces with manufacturer's touchup paint.

END OF SECTION 22 14 00

This page intentionally left blank.

SECTION 22 34 00 - FUEL-FIRED, DOMESTIC-WATER HEATERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.2 SUMMARY

- A. Section Includes:
 - 1. Commercial, power-burner, gas-fired, storage, domestic-water heaters.
 - 2. Domestic-water heater accessories.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.
- B. Shop Drawings:
 - 1. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Seismic Qualification Data: Certificates, for fuel-fired, domestic-water heaters, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- B. Product Certificates: For each type of domestic-water heater.
- C. Domestic-Water Heater Labeling: Certified and labeled by testing agency acceptable to authorities having jurisdiction.
- D. Source quality-control reports.
- E. Field quality-control reports.

- F. Sample Warranty: For special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fuel-fired, domestic-water heaters to include in emergency, operation, and maintenance manuals.

1.6 COORDINATION

- A. Coordinate sizes and locations of concrete bases with actual equipment provided.

1.7 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of fuel-fired, domestic-water heaters that fail in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:
 - a. Structural failures including storage tank and supports.
 - b. Faulty operation of controls.
 - c. Deterioration of metals, metal finishes, and other materials beyond normal use.
 - 2. Warranty Periods: From date of Substantial Completion.
 - a. Commercial, Gas-Fired, Storage, Domestic-Water Heaters:
 - 1) Storage Tank: Three years.
 - 2) Controls and Other Components: Three years.
 - b. Expansion Tanks: Five years.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and use.
- B. ASHRAE/IES Compliance: Fabricate and label fuel-fired, domestic-water heaters to comply with ASHRAE/IES 90.1.
- C. ASME Compliance:
 - 1. Where ASME-code construction is indicated, fabricate and label commercial, domestic-water heater storage tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
- D. NSF Compliance: Fabricate and label equipment components that will be in contact with potable water to comply with NSF 61 and NSF 372.

2.2 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Storage, Gas Water Heaters:
 - a. Smith: A. O. Smith Water Products Co.
 - b. State Water Heater Co.
 - 2. Compression Tanks
 - a. A. O. Smith
 - b. Amtrol

2.3 COMMERCIAL, GAS-FIRED, STORAGE, DOMESTIC-WATER HEATERS

- A. Commercial, Atmospheric, Power Burner, Sealed Combustion, Gas-Fired, Storage, Domestic-Water Heaters:
 - 1. Source Limitations: Obtain domestic-water heaters from single source from single manufacturer.
 - 2. See schedule on drawings for basis of design and equipment characteristics.
 - 3. Direct-Vent System: Through wall or roof as defined in schedule coaxial- or double-channel vent assembly with domestic-water heater manufacturers' outside intake/exhaust screen.

2.4 DOMESTIC-WATER HEATER ACCESSORIES

- A. Domestic-Water Expansion Tanks:
 - 1. Source Limitations: Obtain domestic-water heaters from single source from single manufacturer.
 - 2. Description: Steel, pressure-rated tank constructed with welded joints and factory-installed, butyl-rubber diaphragm. Include air precharge to minimum system-operating pressure at tank.
 - 3. Construction:
 - a. Tappings: Factory-fabricated steel, welded to tank before testing and labeling. Include ASME B1.20.1 pipe thread.
 - b. Interior Finish: Comply with NSF 61 and NSF 372 barrier materials for potable-water tank linings, including extending finish into and through tank fittings and outlets.
 - c. Air-Charging Valve: Factory installed.
 - 4. Capacity and Characteristics:
 - a. Working-Pressure Rating: 150 psig (1035 kPa.
 - b. Capacity Acceptable: As shown on schedule
 - c. Air Precharge Pressure: 60psig.
- B. Drain Pans: Corrosion-resistant metal with raised edge. Include dimensions not less than base of domestic-water heater, and include drain outlet not less than NPS 3/4 with ASME B1.20.1 pipe threads.
- C. Piping-Type Heat Traps: Field-fabricated piping arrangement in accordance with ASHRAE/IES 90.1.
- D. Heat-Trap Fittings: ASHRAE 90.2.

- E. Gas Shutoff Valves: ANSI Z21.15/CSA 9.1, manually operated. Furnish for installation in piping.
- F. Gas Pressure Regulators: ANSI Z21.18/CSA 6.3, appliance type. Include 1/2-psig 2-psig pressure rating as required to match gas supply.
- G. Automatic Gas Valves: ANSI Z21.21/CSA 6.5, appliance, electrically operated, on-off automatic valve.
- H. Combination Temperature-and-Pressure Relief Valves: Include relieving capacity at least as great as heat input, and include pressure setting less than working-pressure rating of domestic-water heater. Select relief valves with sensing element that extends into storage tank.
 - 1. Gas-Fired, Domestic-Water Heaters: ANSI Z21.22/CSA 4.4.
- I. Vacuum Relief Valves: ANSI Z21.22/CSA 4.4.

2.5 SOURCE QUALITY CONTROL

- A. Factory Tests: Test and inspect assembled domestic-water heaters and storage tanks specified to be ASME-code construction, in accordance with ASME Boiler and Pressure Vessel Code.
- B. Hydrostatically test domestic-water heaters and storage tanks to minimum of one and one-half times pressure rating before shipment.
- C. Domestic-water heaters will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 DOMESTIC-WATER HEATER INSTALLATION

- A. Commercial, Domestic-Water Heater Mounting: Install commercial domestic-water heaters on concrete base. Comply with requirements for concrete base specified in Section 03 30 00 "Cast-in-Place Concrete."
 - 1. Exception: Omit concrete bases for commercial domestic-water heaters if installation on stand, bracket, suspended platform, or directly on floor is indicated.
 - 2. Maintain manufacturer's recommended clearances.
 - 3. Arrange units so controls and devices that require servicing are accessible.
 - 4. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch (450-mm) centers around the full perimeter of concrete base.
 - 5. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
 - 6. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 7. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - 8. Anchor domestic-water heaters to substrate.

- B. Install domestic-water heaters level and plumb, in accordance with layout drawings, original design, and referenced standards. Maintain manufacturer's recommended clearances. Arrange units so controls and devices needing service are accessible.
 - 1. Install shutoff valves on domestic-water-supply piping to domestic-water heaters and on domestic-hot-water outlet piping. Comply with requirements for shutoff valves specified in Section 22 11 00 Plumbing Valves
- C. Install gas-fired, domestic-water heaters in accordance with NFPA 54.
 - 1. Install gas shutoff valves on gas supply piping to gas-fired, domestic-water heaters without shutoff valves.
 - 2. Install gas pressure regulators on gas supplies to gas-fired, domestic-water heaters without gas pressure regulators if gas pressure regulators are required to reduce gas pressure at burner.
 - 3. Install automatic gas valves on gas supplies to gas-fired, domestic-water heaters if required for operation of safety control.
 - 4. Comply with requirements for gas shutoff valves, gas pressure regulators, and automatic gas valves specified in Section 23 11 23 Natural-Gas Piping
- D. Install commercial domestic-water heaters with seismic-restraint devices. Comply with requirements for seismic-restraint devices specified in Section 22 05 48 "Vibration and Seismic Controls for Plumbing Piping and Equipment"
- E. Install combination temperature-and-pressure relief valves in top portion of storage tanks. Use relief valves with sensing elements that extend into tanks. Extend domestic-water-heater relief-valve outlet, with drain piping same as domestic-water piping in continuous downward pitch, and discharge by positive air gap onto closest floor drain.
- F. Install vacuum relief valves on incoming cold water piping for all bottom fed water heaters and tanks and where indicated on the drawings.
- G. Install water-heater drain piping as indirect waste to spill by positive air gap into open drains or over floor drains. Install hose-end drain valves at low points in water piping for domestic-water heaters that do not have tank drains.
- H. Install thermometer on outlet piping of domestic-water heaters.
- I. Install piping-type heat traps on inlet and outlet piping of domestic-water heater storage tanks without integral or fitting-type heat traps.
- J. Fill domestic-water heaters with water.
- K. Charge domestic-water expansion tanks with air to required system pressure.
- L. Install dielectric fittings in all locations where piping of dissimilar metals is to be joined. The wetted surface of the dielectric fitting contacted by potable water shall contain less than 0.25 percent of lead by weight.

3.2 PIPING CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.

- B. Where installing piping adjacent to fuel-fired, domestic-water heaters, allow space for service and maintenance of water heaters. Arrange piping for easy removal of domestic-water heaters.

3.3 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- B. Tests and Inspections:
 - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Operational Test: After electrical circuitry has been energized, start units to confirm proper operation.
 - 3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- C. Domestic-water heaters will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain domestic-water heaters.

END OF SECTION 22 34 00

SECTION 22 41 10

WATER DISTRIBUTION PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes water distribution piping from locations indicated to fixtures and equipment inside building.
- B. Related Sections include the following:
 - 1. Division 22 14 00 Section "Meters and Gages" for water meters, thermometers, pressure gages, and fittings.
 - 2. Division 22 43 00 Section "Plumbing Specialties" for water distribution piping specialties.
 - 3. Section 22 05 49 "Plumbing Systems; Supports, Bracing and Seismic Requirements".
 - 4. Section 22 05 00 "Basic Mechanical Materials and Methods"..

1.3 DEFINITIONS

- A. Water Service Piping: Water piping outside building that conveys water to building.
- B. Service Entrance Piping: Water piping at entry into building between water service piping and water distribution piping.
- C. Water Distribution Piping: Water piping inside building that conveys water to fixtures and equipment throughout the building.
- D. The following are industry abbreviations for plastic piping materials:
 - 1. CPVC: Chlorinated polyvinyl chloride.
 - 2. PVC: Polyvinyl chloride.

1.4 SYSTEM PERFORMANCE REQUIREMENTS

- A. Provide components and installation capable of producing piping systems with the following minimum working-pressure ratings, unless otherwise indicated:
 - 1. Combined Fire-Protection and Domestic, Service Entrance Piping: 200 psig.
 - 2. Service Entrance Piping: 150 psig.
 - 3. Water Distribution Piping: 150 psig.

1.5 QUALITY ASSURANCE

- A. Provide listing/approval stamp, label, or other marking on piping made to specified standards.

PART 2 - PRODUCTS

2.1 COPPER TUBE AND FITTINGS

- A. Hard Copper Tube: ASTM B 88, Type L.
- B. Soft Copper Tube: ASTM B 88, Type K water tube, annealed temper.
- C. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.
- D. Copper Unions:
 - 1. MSS SP-123.
 - 2. Cast-copper-alloy, hexagonal-stock body.
 - 3. Ball-and-socket, metal-to-metal seating surfaces.
 - 4. Solder-joint or threaded ends.

2.2 JOINING MATERIALS

- A. General: Applications of the following piping joining materials are indicated in Part 3 "Piping Applications" Article.
- B. Solder: ASTM B 32, Alloy Sn95; lead free.
- C. Transition Couplings: Coupling or other manufactured fitting same size as, with pressure rating at least equal to, and with ends compatible with piping to be joined.

2.3 VALVES

- A. Refer to Division 22110 Section "Plumbing Valves" for general-duty valves.

PART 3 - EXECUTION

3.1 EXCAVATION

- A. Refer to Division 22 Section "Excavation and Backfilling" for excavating, trenching, and backfilling.

3.2 PIPING APPLICATIONS

- A. Transition and special fittings with pressure ratings at least equal to piping pressure rating may be used in applications below, unless otherwise indicated.

- B. Flanges may be used on aboveground piping, unless otherwise indicated.
- C. Aboveground, Water Distribution Piping: Use the following:
 - 1. 3-Inch NPS and Smaller: Hard copper tube, Type L; copper, solder-joint fittings; and soldered joints.
- D. Underground, Water Distribution Piping: Do not use flanges or valves underground. Use the following:
 - 1. 2-Inch NPS and Smaller: Soft copper tube, Type K; rolled tube.

3.3 VALVE APPLICATIONS

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
 - 1. Shutoff Duty: Use ball, or butterfly valves.
- B. Grooved-end butterfly valves may be used with grooved-end piping.

3.4 PIPING INSTALLATION, GENERAL

- A. Refer to Division 22 Section "Basic Mechanical Materials and Methods" for basic piping installation.

3.5 SERVICE ENTRANCE PIPING INSTALLATION

- A. Extend service entrance piping to exterior water service piping in sizes and locations indicated for service entrances into building. Refer to Division 2 Section "Water Systems" for water service piping.
- B. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve, inside building at each service entrance pipe.
- C. Ductile-Iron, Service Entrance Piping: Comply with AWWA C600. Install buried piping between shutoff valve and connection to water service piping with restrained joints. Anchor pipe to wall or floor at entrance. Include thrust-block supports at vertical and horizontal offsets.
 - 1. Encase piping with polyethylene film according to ASTM A 674 or AWWA C105.
- D. Install cast-iron sleeve with water stop and mechanical sleeve seal at each service entrance pipe penetration through foundation wall. Select number of interlocking rubber links required to make installation watertight. Refer to Division 22 Section "Basic Mechanical Materials and Methods" for sleeves and mechanical sleeve seals.
- E. Install wall penetration system at each service entrance pipe penetration through foundation wall. Make installation watertight. Refer to Division 22 Section "Basic Mechanical Materials and Methods" for wall penetration systems.

3.6 WATER DISTRIBUTION PIPING INSTALLATION

- A. Install piping level and plumb.

3.7 JOINT CONSTRUCTION

- A. Refer to Division 22 Section "Basic Mechanical Materials and Methods" for basic piping joint construction.

3.8 VALVE INSTALLATION

- A. Sectional Valves: Install sectional valves close to main on each branch and riser serving plumbing fixtures or equipment and where indicated. Use ball valves for piping 3-inch NPS and smaller.
- B. Shutoff Valves: Install shutoff valve on each water supply to equipment, on each supply to plumbing fixtures without supply stops, and where indicated. Use ball valves for piping 3-inch NPS and smaller.
- C. Drain Valves: Install drain valves for equipment, at base of each water riser, at low points in horizontal piping, and where required to drain water piping.
 - 1. Install hose-end drain valves at low points in water mains, risers, and branches.
- D. Balancing Valves: Install in each hot-water circulation return branch, discharge side of each pump and circulator, and where indicated. Refer to Division 22110 Section "Plumbing Valves" for balancing valves.

3.9 HANGER AND SUPPORT INSTALATION

- A. Comply with requirements in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- B. Comply with requirements in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support products and installation.
- C. Support piping and tubing not listed in this article according to MSS SP-69 and manufacturer's written instructions.

3.10 CONNECTIONS

- A. Connect service entrance piping to exterior water service piping. Use transition fitting to join dissimilar piping materials.
- B. Connect water distribution piping to service entrance piping at shutoff valve, and extend to and connect to the following:
 - 1. Booster Systems: Connect cold-water suction and discharge piping.
 - 2. Water Heaters: Connect cold-water supply and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
 - 3. Plumbing Fixtures: Connect hot- and cold-water supply piping in sizes indicated, but not smaller than required by plumbing code. Refer to Division 22 Section "Plumbing Fixtures."

4. Equipment: Connect hot- and cold-water supply piping as indicated. Provide shutoff valve and union for each connection. Use flanges instead of unions for connections 2-1/2-inch NPS and larger.

3.11 FIELD QUALITY CONTROL

- A. Inspect water distribution piping as follows:
- B. Inspect service entrance piping and water distribution piping as follows:
 1. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
 2. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
- C. Roughing-In Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
- D. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
 1. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
 2. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- E. Test service entrance piping and water distribution piping as follows:
 1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
 2. Leave uncovered and unconcealed new, altered, extended, or replaced water piping until it has been tested and approved. Expose work that has been covered or concealed before it has been tested and approved.
 3. Cap and subject piping to static water pressure of 150 psig. Isolate test source and allow to stand for 4 hours. Leaks and loss in test pressure constitute defects that must be repaired.
 4. Repair leaks and defects with new materials and retest piping or portion thereof until satisfactory results are obtained.
 5. Prepare reports for tests and required corrective action.

3.12 CLEANING

- A. Clean and disinfect service entrance piping and water distribution piping as follows:
 1. Purge new piping and parts of existing water piping that have been altered, extended, or repaired before using.
 2. Use purging and disinfecting procedure prescribed by authorities having jurisdiction or, if method is not prescribed, procedure described in either AWWA C651 or AWWA C652 or as described below:
 - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
 - b. Fill and isolate system according to either of the following:
 - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.

- 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for 3 hours.
 - c. Flush system with clean, potable water until chlorine is no longer in water coming from system after the standing time.
 - d. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedure if biological examination shows contamination.
- B. Prepare and submit reports for purging and disinfecting activities.
- C. Clean interior of piping system. Remove dirt and debris as work progresses.

3.13 COMMISSIONING

- A. Fill water piping. Check components to determine that they are not air bound and that piping is full of water.
- B. Perform the following steps before putting into operation:
 - 1. Close drain valves, hydrants, and hose bibbs.
 - 2. Open shutoff valves to fully open position.
 - 3. Set ballancing valves to proper setting.
 - 4. Remove plugs used during testing of piping and plugs used for temporary sealing of piping during installation.
 - 5. Remove and clean strainer screens. Close drain valves and replace drain plugs.
 - 6. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and that cartridges are clean and ready for use.
- C. Check plumbing equipment and verify proper settings, adjustments, and operation. Do not operate water heaters before filling with water.
- D. Check plumbing specialties and verify proper settings, adjustments, and operation.
 - 1. Water-Pressure Regulators: Set outlet pressure at 80 psig maximum, unless otherwise indicated.
- E. Energize pumps and verify proper operation.

END OF SECTION 22 41 10

SECTION 22 42 00

DRAINAGE AND VENT PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes sanitary drainage and vent piping, and storm drainage piping inside building and to locations indicated.
- B. Related Sections include the following:
 - 1. Division 224300 Section "Plumbing Specialties" for drainage and vent piping system specialties.
 - 2. Section 22 05 49 "Plumbing Systems; Supports, Bracing and Seismic Requirements".
 - 3. Section 22 05 00 "Basic Plumbing Materials and Methods".

1.3 DEFINITIONS

- A. Sewerage Piping: Building sewer piping outside building that conveys sanitary sewage from building.
- B. Drainage Piping: Building sewer piping outside building that conveys storm drainage from building.
- C. Service Entrance Piping: Drainage piping at entry into building between outside building sewer piping and inside drainage piping.
- D. Drainage and Vent Piping: Piping inside building that conveys waste water and vapors from fixtures and equipment throughout the building.
- E. The following are industry abbreviations for plastic and other piping materials:
 - 1. ABS: Acrylonitrile-butadiene-styrene.
 - 2. EPDM: Ethylene-propylene-diene polymer, rubber.
 - 3. NBR: Acrylonitrile-butadiene rubber.
 - 4. PVC: Polyvinyl chloride.

1.4 SYSTEM PERFORMANCE REQUIREMENTS

- A. Provide components and installation capable of producing piping systems with the following minimum working-pressure ratings, unless otherwise indicated:

1. Soil, Waste, and Vent Systems: 10-foot head of water.
2. Storm Drainage Systems: 10-foot head of water.

1.5 SUBMITTALS

- A. Test Results and Reports: Specified in "Field Quality Control" Article.

1.6 QUALITY ASSURANCE

- A. Provide listing/approval stamp, label, or other marking on piping made to specified standards.
- B. Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.
- C. Comply with NSF 14, "Plastics Piping Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping; "NSF-drain" for plastic drain piping; "NSF-tubular" for plastic continuous waste piping; and "NSF-sewer" for plastic sewer piping.

PART 2 - PRODUCTS

2.1 PIPES AND TUBES

- A. General: Applications of the following pipe and tube materials are indicated in Part 3 "Piping Applications" Article.
- B. Hubless, Cast-Iron Soil Pipe: ASTM A 888 or CISPI 301.
- C. Hard Copper Tube: ASTM B 306, drainage tube, drawn temper.
- D. PVC Plastic Pipe: ASTM D 1784, Schedule 40 Solid Wall PVC.

2.2 PIPE AND TUBE FITTINGS

- A. General: Applications of the following pipe and tube fitting materials are indicated in Part 3 "Piping Applications" Article.
- B. Hubless, Cast-Iron, Soil-Pipe Fittings: CISPI 301.
- C. Copper, Solder-Joint Drainage Fittings: ASME B16.23 cast copper or ASME B16.29 wrought copper.
- D. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311 drain, waste, and vent pipe patterns.

2.3 JOINING MATERIALS

- A. General: Applications of the following piping joining materials are indicated in Part 3 "Piping Applications" Article.
- B. Refer to Division 22 Section "Basic Mechanical Materials and Methods" for commonly used joining materials.
- C. Solder: ASTM B 32, Alloy Sn95, Sn94, or E; lead free.
- D. Hubless, Cast-Iron, Soil-Piping Couplings: ASTM C 1277 assembly of metal housing, corrosion-resistant fasteners, and ASTM C 564 rubber sleeve or gasket with integral, center pipe stop. Include the following:
 - 1. Heavy-Duty, Stainless-Steel Couplings: ASTM A 666, Type 304, stainless-steel housing or shield; and stainless-steel clamps. Include gasket. Couplings Shall be Made By Anaheim Foundry "Husky" Series 4000 Coupling.
- E. Transition Couplings: Coupling or other manufactured fitting same size as, with pressure rating at least equal to, and with ends compatible with piping to be joined.
- F. Flexible, Transition Couplings for Underground, Nonpressure Piping: ASTM C 1173 with elastomeric sleeve. Include ends same sizes as piping to be joined and include corrosion-resistant metal band on each end.
 - 1. Sleeve Type for Plain-End Piping: Rubber or elastomeric sleeve and stainless-steel band assembly, fabricated to match outside diameters of piping to be joined. Include the following:
 - a. Sleeves for Cast-Iron Soil Piping: ASTM C 564 rubber.
 - b. Sleeves for Plastic Piping: ASTM F 477 elastomeric seal.
 - c. Sleeves for Dissimilar Piping: Compatible with piping materials to be joined.
 - d. Bands: Stainless steel, one at each pipe insert.
 - 2. Gasket Type for Dissimilar-End Piping: Rubber or elastomeric compression gasket, made to match inside diameter of pipe or hub, and outside diameter of adjoining pipe. Include the following:
 - a. Gaskets for Cast-Iron Soil Piping: ASTM C 564 rubber.
 - b. Gaskets for Plastic Piping: ASTM F 477 elastomeric seal.
 - c. Gaskets for Dissimilar Piping: Compatible with piping materials to be joined.

PART 3 - EXECUTION

3.1 EXCAVATION

- A. Refer to Division 22 Section "Excavation and Backfilling" for excavating, trenching, and backfilling.

3.2 PIPING APPLICATIONS

- A. Transition and special fittings with pressure ratings at least equal to piping pressure rating may be used in applications below, unless otherwise indicated.
- B. Flanges may be used on aboveground piping, unless otherwise indicated.

- C. Aboveground, Soil, Waste, and Vent Piping: Use the following:
 - 1. 1-1/4- and 1-1/2-Inch NPS: Hard copper drainage tube; copper, solder-joint drainage fittings; and soldered joints.
 - 2. 1-1/4- and 1-1/2-Inch NPS: PVC plastic pipe, PVC socket fittings, and solvent-cemented joints.
 - 3. 2- to 4-Inch NPS: Hubless, cast-iron soil pipe; hubless, cast-iron, soil-pipe fittings; cast-iron, heavy duty soil-piping couplings:
 - 4. 5- Inch and Larger NPS: Hubless, cast-iron soil pipe; hubless, cast-iron, soil-pipe fittings; heavy duty soil-piping couplings:
 - 5. 2- to 4-Inch NPS: PVC plastic pipe, PVC socket fittings, and solvent-cemented joints.
 - 6. 5-Inch and Larger NPS: PVC plastic pipe, PVC socket fittings, and solvent-cemented joints.
- D. Underground, Soil, Waste, and Vent Piping: Use the following:
 - 1. 2-Inch and Larger NPS: PVC plastic pipe, PVC socket fittings, and solvent-cemented joints.
- E. INDIRECT WASTE AND DRAIN PIPING
 - 1. All indirect waste or drain piping from plumbing fixtures or equipment shall be type "DWV" hard temper copper tube with "DWV" copper fittings with joints made up with 50-50 solder.

3.3 PIPING INSTALLATION, GENERAL

- A. Refer to Division 22 "Basic Mechanical Materials and Methods" for basic piping installation.

3.4 SERVICE ENTRANCE PIPING INSTALLATION

- A. Extend building sanitary drain piping and connect to sanitary sewer piping in sizes and locations indicated for service entrances into building. Install cleanout and extension to grade at connections of building sanitary drains with building sanitary sewers.
- B. Extend building storm drain piping and connect to storm sewer piping in sizes and locations indicated for service entrances into building. Install cleanout and extension to grade at connections of building storm drains and building storm sewers.
- C. Install cast-iron sleeve with water stop and mechanical sleeve seal at each service entrance pipe penetration through foundation wall. Select number of interlocking rubber links required to make installation watertight. Refer to Division 22 "Basic Mechanical Materials and Methods" for sleeves and mechanical sleeve seals.
- D. Install wall penetration system at each service entrance pipe penetration through foundation wall. Make installation watertight. Refer to Division 22 "Basic Mechanical Materials and Methods" for wall penetration systems.

3.5 DRAINAGE AND VENT PIPING INSTALLATION

- A. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
- B. Make changes in direction for drainage and vent piping using appropriate branches, bends, and long-sweep bends. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if

change in direction of flow is from horizontal to vertical. Use long-turn, double Y-branch and 1/8-bend fittings if 2 fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not make change in direction of flow greater than 90 degrees. Use proper size of standard increasers and reducers if different sizes of piping are connected. Reducing size of drainage piping in direction of flow is prohibited.

- C. Lay buried building drain piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.
- D. Install drainage and vent piping at the following minimum slopes, unless otherwise indicated:
 - 1. Sanitary Building Drain: 2 percent downward in direction of flow for piping 3-inch NPS and smaller; 1 percent downward in direction of flow for piping 4-inch NPS and larger.
 - 2. Horizontal, Sanitary Drainage Piping: 1 percent downward in direction of flow.
 - 3. Horizontal, Storm Drainage Piping: 1 percent downward in direction of flow.
 - 4. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- E. Install engineered, sanitary drainage and vent systems in locations indicated and as follows:
 - 1. Combination Waste and Vent: Comply with standards of authorities having jurisdiction.
- F. Sleeves are not required for cast-iron soil piping passing through concrete slab on grade if slab is without membrane waterproofing.
- G. Install PVC plastic drainage piping according to ASTM D 2665.
- H. Install underground, PVC plastic drainage piping according to ASTM D 2321.

3.6 JOINT CONSTRUCTION

- A. Refer to Division 22 "Basic Mechanical Materials and Methods" for basic piping joint construction.
- B. Cast-Iron, Soil-Piping Joints: Make joints according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
 - 1. Compression Joints: Make with rubber gasket matching class of pipe and fittings.
 - 2. Hubless Joints: Make with rubber gasket and sleeve or clamp.
- C. PVC Piping Joints: Join drainage piping according to ASTM D 2665.
- D. Handling of Solvent Cements, Primers, and Cleaners: Comply with procedures in ASTM F 402 for safe handling during joining of plastic pipe and fittings.

3.7 HANGER AND SUPPORT INSTALLATION

- A. Seismic-restraint devices are specified in Division 22 Section "Mechanical Vibration Controls and Seismic Restraints."
- B. Pipe hangers and supports are specified in Division 22 Section "Hangers and Supports." Install the following:
 - 1. Vertical Piping: MSS Type 8 or Type 42, clamps.

2. Install individual, straight, horizontal piping runs according to the following:
 - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
 - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
 - c. Longer Than 100 Feet, if Indicated: MSS Type 49, spring cushion rolls.
 3. Multiple, Straight, Horizontal Piping Runs 100 Feet (30 m) or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Install supports according to Division 22 Section "Hangers and Supports."
- D. Support vertical piping and tubing at base and at each floor.
- E. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- F. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
1. NPS 1-1/2 and NPS 2 (DN 40 and DN 50): 60 inches (1500 mm) with 3/8-inch (10-mm) rod.
 2. NPS 3 (DN 80): 60 inches (1500 mm) with 1/2-inch (13-mm) rod.
 3. NPS 4 and NPS 5 (DN 100 and DN 125): 60 inches (1500 mm) with 5/8-inch (16-mm) rod.
 4. NPS 6 (DN 150): 60 inches (1500 mm) with 3/4-inch (19-mm) rod.
 5. NPS 8 to NPS 12 (DN 200 to DN 300): 60 inches (1500 mm) with 7/8-inch (22-mm) rod.
- G. Install supports for vertical cast-iron soil piping every 15 feet.
- H. Install hangers for steel piping with the following maximum horizontal spacing and minimum rod diameters:
1. NPS 1-1/4 (DN 32): 84 inches (2100 mm) with 3/8-inch (10-mm) rod.
 2. NPS 1-1/2 (DN 40): 108 inches (2700 mm) with 3/8-inch (10-mm) rod.
 3. NPS 2 (DN 50): 10 feet (3 m) with 3/8-inch (10-mm) rod.
 4. NPS 2-1/2 (DN 65): 11 feet (3.4 m) with 1/2-inch (13-mm) rod.
 5. NPS 3 (DN 80): 12 feet (3.7 m) with 1/2-inch (13-mm) rod.
 6. NPS 4 and NPS 5 (DN 100 and DN 125): 12 feet (3.7 m) with 5/8-inch (16-mm) rod.
 7. NPS 6 (DN 150): 12 feet (3.7 m) with 3/4-inch (19-mm) rod.
 8. NPS 8 to NPS 12 (DN 200 to DN 300): 12 feet (3.7 m) with 7/8-inch (22-mm) rod.
- I. Install supports for vertical steel piping every 15 feet.
- J. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
1. NPS 1-1/4 (DN 32): 72 inches (1800 mm) with 3/8-inch (10-mm) rod.
 2. NPS 1-1/2 and NPS 2 (DN 40 and DN 50): 96 inches (2400 mm) with 3/8-inch (10-mm) rod.
- K. Install supports for vertical copper tubing every 10 feet.
- L. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters:
1. NPS 1-1/2 and NPS 2 (DN 40 and DN 50): 48 inches (1200 mm) with 3/8-inch (10-mm) rod.
 2. NPS 3 (DN 80): 48 inches (1200 mm) with 1/2-inch (13-mm) rod.

3. NPS 4 and 5 (DN 100 and 125): 48 inches (1200 mm) with 5/8-inch (16-mm) rod.
4. NPS 6 (DN 150): 48 inches (1200 mm) with 3/4-inch (19-mm) rod.
5. NPS 8 to NPS 12 (DN 200 to DN 300): 48 inches (1200 mm) with 7/8-inch (22-mm) rod.

M. Install supports for vertical ABS and PVC piping every 48 inches.

N. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

3.8 CONNECTIONS

A. Connect service entrance piping to exterior sewerage and drainage piping. Use transition fitting to join dissimilar piping materials.

B. Connect drainage piping to service entrance piping, and extend to and connect to the following:

1. Plumbing Fixtures: Connect drainage piping in sizes indicated, but not smaller than required by plumbing code. Refer to Division 22 Section "Plumbing Fixtures."
2. Plumbing Specialties: Connect drainage and vent piping in sizes indicated, but not smaller than required by plumbing code. Refer to Division 22 Section "Plumbing Specialties."
3. Equipment: Connect drainage piping as indicated. Provide shutoff valve, if indicated, and union for each connection. Use flanges instead of unions for connections 2-1/2-inch NPS and larger.

C. Connect force-main piping to service entrance piping, and extend to and connect to the following:

1. Sump Pumps: Connect force-main piping to sump-pump discharge.
2. Sewage Pumps: Connect force-main piping to sewage-pump discharge.

3.9 FIELD QUALITY CONTROL

A. Inspect drainage and vent piping as follows:

1. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
2. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
 - a. Roughing-In Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
 - b. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
3. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
4. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.

B. Test drainage and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedure, as follows:

1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.

2. Leave uncovered and unconcealed new, altered, extended, or replaced drainage and vent piping until it has been tested and approved. Expose work that has been covered or concealed before it has been tested and approved.
3. Roughing-In Plumbing Test Procedure: Test drainage and vent piping, except outside leaders, on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10 feet of head. Water level must not drop from 15 minutes before inspection starts through completion of inspection. Inspect joints for leaks.
4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg. Use U-tube or manometer inserted in trap of water closet to measure this pressure. Air pressure must remain constant without introducing additional air throughout period of inspection. Inspect plumbing fixture connections for gas and water leaks.
5. Repair leaks and defects using new materials and retest piping or portion thereof until satisfactory results are obtained.
6. Prepare reports for tests and required corrective action.

3.10 CLEANING AND PROTECTING

- A. Clean interior of piping system. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.
- D. Exposed PVC Piping: Protect plumbing vents exposed to sunlight with 2 coats of water-based latex paint.

END OF SECTION 22 42 00

SECTION 22 43 00

PLUMBING SPECIALTIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes plumbing specialties for the following:
 - 1. Water distribution systems.
 - 2. Soil, waste, and vent systems.
- B. Related Sections include the following:
 - 1. Division 22 05 00 Section "Basic Plumbing Materials and Methods"
 - 2. Section 22 05 49 "Plumbing Systems; Supports, Bracing and Seismic Requirements".
 - 3. Division 22 11 00 Section "Valves" for general-duty ball, butterfly, check, gate, and globe valves.
 - 4. Division 22 14 00 Section "Meters and Gages" for thermometers, pressure gages, fittings, and water meters.
 - 5. Division 22 41 10 Section "Water Distribution Piping" for water-supply piping and connections.
 - 6. Division 22 42 00 Section "Drainage and Vent Piping" for drainage and vent piping and connections.

1.3 SYSTEM PERFORMANCE REQUIREMENTS

- A. Provide components and installation capable of producing piping systems with following minimum working-pressure ratings, unless otherwise indicated:
 - 1. Water Distribution Piping: 150 psig
 - 2. Soil, Waste, and Vent Piping: 10-foot head of water

1.4 SUBMITTALS

- A. Product Data: For each plumbing specialty indicated. Include rated capacities of selected equipment and shipping, installed, and operating weights. Indicate materials, finishes, dimensions, required clearances, and methods of assembly of components; and piping and wiring connections for the following plumbing specialty products:
 - 1. Backflow preventers.
 - 2. Water regulators.
 - 3. Strainers.
 - 4. Thermostatic water mixing valves and water tempering valves.
 - 5. Water hammer arresters.

6. Drain valves.
7. Hose bibbs and wall hydrants.
8. Cleanouts.
9. Floor drains, open receptors, and trench drains.
10. Floor sinks.
11. Air-admittance valves.
12. Gas / Oil interceptors, gas / oil storage tanks, and solids interceptors.

B. Reports: Specified in "Field Quality Control" Article.

C. Maintenance Data: For specialties to include in the maintenance manuals specified in Division 1. Include the following:

1. Backflow preventers.
2. Water regulators.
3. Water filters.
4. Thermostatic water mixing valves and water tempering valves.
5. Wall and roof hydrants and hose bibbs.
6. Backwater valves.
7. Gas / Oil interceptors, and solids interceptors.

1.5 QUALITY ASSURANCE

A. Product Options: Drawings indicate size, profiles, dimensional requirements, and characteristics of plumbing specialties and are based on the specific types and models indicated. Other manufacturers' products with equal performance characteristics may be considered. Refer to Division 1 Section "Substitutions."

B. Provide listing/approval stamp, label, or other marking on plumbing specialties made to specified standards.

C. Listing and Labeling: Provide electrically operated plumbing specialties specified in this Section that are listed and labeled.

1. Terms "Listed" and "Labeled": As defined in National Electrical Code, Article 100.

D. Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.

E. Comply with NFPA 70, "National Electrical Code," for electrical components.

F. Comply with NSF 14, "Plastics Piping Components and Related Materials," for plastic potable-water piping components. Include marking "NSF-pw" on plastic potable-water piping and "NSF-dwv" on plastic drain, waste, and vent piping.

1.6 EXTRA MATERIALS

A. Deliver extra materials to Owner. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.

1. Water Filter Cartridges: Furnish quantity not less than 100 percent of amount of each type and size installed.

2. Operating Key Handles: Furnish one extra key for each key-operated hose bibb and hydrant installed.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Backflow Preventers:
 - a. Watts Industries, Inc.; Water Products Div.
 - b. Zurn Industries, Inc.; Wilkins Div.
 2. Dishwasher Air-Gap Fittings:
 - a. Brass Craft.
 - b. Moen, Inc.; Dearborn Brass Co. Div.
 - c. Sioux Chief Manufacturing Co., Inc.
 3. Water Regulators:
 - a. Watts Industries, Inc.; Water Products Div.
 4. Hydrants:
 - a. Smith: Jay R. Smith Mfg. Co.
 - b. Watts Industries, Inc.; Water Products Div.
 - c. Woodford Manufacturing Co.
 5. Water Hammer Arresters:
 - a. Precision Plumbing Products, Inc.
 - b. Sioux Chief Manufacturing Co., Inc.
 - c. Watts Industries, Inc.; Water Products Div.
 6. Air-Admittance Valves:
 - a. Oatey Co.
 - b. Sioux Chief Manufacturing Co., Inc.
 7. Foundry Items
 - a. Wade
 - b. Smith
 - c. Zurn
 8. Trap Primers:
 - a. PPP Industries.
 - b. Watts Industries, Inc.; Water Products Div.
 - c. Sioux Chief

2.2 TRAP PRIMERS

- A. Install trap seal primers on all floor drains. Trap seal primers shall be equal to PPP model PR-500 or equal.

2.3 BACKFLOW PREVENTERS

- A. Backflow Preventers 2" and Smaller

1. Furnish and install Watts No 909S-QT reduced pressure backflow preventer in the domestic water piping system to protect the potable water system against backflow and back-siphonage from connections of the potable water system.
 2. Complete assembly shall consist of a strainer with test cock, the backflow preventer with three test cocks, and two ball valves, all bronze construction. Also furnish for each backflow preventer a Watts Series No. AG-C or AG-F air gap fitting with drain outlet. Pipe all drains from the outlet fitting to the nearest available floor drain terminating over the floor drain with a 6" air gap.
- B. Backflow Preventer 2-1/2" and Larger
1. Furnish and install Watts No 909-OSY-RW reduced pressure backflow preventer in the domestic water piping system to protect the potable water system against backflow and back-siphonage from connections of the potable water system.
 2. Complete assembly shall consist of the backflow preventer with test cocks, and two OS&Y gate valves with resilient wedge, epoxy coated cast iron construction. Also furnish for each backflow preventer a Watts Series No. AG-C or AG-F air gap fitting with drain outlet. Pipe all drains from the outlet fitting to the nearest available floor drain terminating over the floor drain with a 6" air gap. General: ASSE standard, backflow preventers, of size indicated for maximum flow rate and maximum pressure loss indicated.

2.4 VACUUM BREAKERS

- A. Vacuum breakers where required or indicated on the drawings, shall be equal to Watts Anti-Siphon vacuum Breaker No. 288A in sizes 1/4" to 3". Where exposed vacuum breaker shall have a polished
- B. Hose-Connection Vacuum Breakers: ASSE 1011, nickel plated, with nonremovable and manual drain features, and ASME B1.20.7 garden-hose threads on outlet. Units attached to rough-bronze-finish hose connections may be rough bronze.

2.5 DISHWASHER AIR-GAP FITTINGS

- A. Description: ASSE 1021, fitting suitable for use with domestic dishwashers and for deck mounting; with plastic body, chrome-plated brass cover; and capacity of at least 5 gpm; and inlet pressure of at least 5 psig at temperature of at least 140 deg F. Include 5/8-inch- ID inlet and 7/8-inch- ID outlet hose connections.

2.6 PIPE STRAINERS

- A. Furnish and install a strainer ahead of all pressure regulating valves, etc. as indicated in this specification and on the contract drawings.
- B. Strainers shall be equal to Mueller Steam Specialty #351 or #352 bronze body, self cleaning "Y" type strainer with 20 mesh stainless steel screen (1/32" openings) in all sizes through 2", and 1/16" diameter perforations for 2-1/2" size through 4". Install a blow-off valve with hose thread outlet for cleaning purposes. Strainers to have F.I.P. threaded connections and be rated for a minimum of 250 psi W.W.P.
1. Similar strainers as manufactured by Watts Regulator Company Model No. 777S or 77S will be acceptable in 2-1/2" size and smaller.

2.7 CLEANOUTS

- A. Cleanout Plugs: Cast bronze or brass, threads complying with ANSI B2.1; countersunk type.
- B. Floor Cleanouts: Cast iron body and frame; cleanout plug; adjustable nickel-bronze top, flush type, standard non-slip scored or abrasive finish similar to J. R. Smith 4108C.
- C. Wall Cleanouts: Cast iron body adaptable to pipe with cast bronze or brass cleanout plug; stainless steel cover including screw similar to J. R. Smith 4532S.
- D. Cleanouts that terminate at grade, in driveways, parking areas, etc. shall be J. R. Smith 4248C-G-CSS all galvanized cast iron cleanout with adjustable housing, cut-off ferrule, internal threaded brass plug, and round cast iron loose scoriated tractor type screwed down cover. Center cleanouts at grade within a 18" x 18" x 6" thick concrete pad. Set top of pad flush with finished grade.
- E. Sanitary soil and waste system: Install cleanouts to floor in all underground piping where shown on the drawings and in the vertical riser at the base of the stack a minimum of three (3) feet above the floor.
- F. Storm drainage system: Install cleanouts to floor in all underground piping where shown on the drawings and in the vertical riser at the base of the riser a minimum of three (3) feet above the floor.
- G. Cleanouts shall be of the same nominal size as the pipes up to 6 inches and not less than 6 inches for larger piping.
- H. Cleanouts on concealed piping shall be extended through and terminate flush with the finished wall or floor.

2.8 FLOOR DRAINS

- A. Install trap seal primers on all floor drains. Trap seal primers shall be equal to PPP model PR-500.
- B. See schedule on drawings

2.9 FLOOR SINKS

- A. Install trap seal primers on all floor drains. Trap seal primers shall be equal to PPP model PR-500.
- B. See schedule on drawings

2.10 GARAGE DRAINS

- A. See schedule on drawings.

2.11 WALL HYDRANTS

- A. See schedule on drawings.

2.12 HOSE BIBB

- A. Hose bibbs with the supply piping concealed behind a wall shall be Chicago Faucet No. 952-633, or approved equal inside sill faucet with vacuum breaker, 3/4" flanged female I.P. inlet, chromium plated.
- B. Hose bibbs with supply piping exposed to view shall be Chicago Faucet No. 998, or approved equal, outside sill faucet with vacuum breaker, 3/4" hose thread outlet, No. 633 four-arm handle, and 3/4" female I.P. inlet, rough chromium finish.

2.13 SHOCK ABSORBERS

- A. Furnish and install where indicated on the drawings, Sioux Chief or equivalent Series 650 Dual 'O' Ring Piston, Copper Chamber, Shock Absorbers according to the following schedule.

<u>Shock Absorber Designation</u>	<u>Sioux Chief No.</u>
"A"	652-AS
"B"	653-BS
"C"	654-CS
"D"	655-DS
"E"	656-ES
"F"	657-FS

- B. Install the shock absorbers in the piping between the manual shut-off valve and the connection to the equipment noted on the drawings.
- C. Contractor shall be responsible for final sizing of shock absorbers if field installation differs from documents.
- D. Shock Absorbers must meet PDI-WH-201 standards.
- E. Only Dual 'O' Ring Piston, Copper Chamber style shock absorbers will be accepted.

PART 3 - EXECUTION

3.1 PLUMBING SPECIALTY INSTALLATION

- A. General: Install plumbing specialty components, connections, and devices according to manufacturer's written instructions.
- B. Install backflow preventers of type, size, and capacity indicated, at each water-supply connection to mechanical equipment and systems, and to other equipment and water systems as indicated. Comply with authorities having jurisdiction. Locate backflow preventers in same room as connected equipment. Install air-gap fitting on units with atmospheric-vent connection and pipe relief outlet drain to nearest floor drain. Do not install bypass around backflow preventer.
- C. Install pressure regulators with inlet and outlet shutoff valves and balance valve bypass. Install pressure gages on inlet and outlet.

- D. Install strainers on supply side of each control valve, pressure regulator, and solenoid valve, and where indicated.
- E. Install hose bibbs with integral or field-installed vacuum breaker.
- F. Install wall hydrants with integral or field-installed vacuum breaker.
- G. Install trap seal primer valves with valve outlet piping pitched down toward drain trap a minimum of one percent and connect to floor-drain body, trap, or inlet fitting. Adjust valve for proper flow.
- H. Install expansion joints on vertical risers, stacks, and conductors as indicated.
- I. Install cleanouts in aboveground piping and building drain piping as indicated, and where not indicated, according to the following:
 - 1. Size same as drainage piping up to 64-inch NPS. Use 6-inch NPS for larger drainage piping unless larger cleanout is indicated.
 - 2. Locate at each change in direction of piping greater than 45 degrees.
 - 3. Locate at minimum intervals of 50 feet for piping 4-inch NPS and smaller and 100 feet for larger piping.
 - 4. Locate at base of each vertical soil, storm water and waste stack.
- J. Install cleanout deck plates, of types indicated, with top flush with finished floor, for floor cleanouts for piping below floors.
- K. Install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall, for cleanouts located in concealed piping.
- L. Install flashing flange and clamping device with each stack and cleanout passing through floors with waterproof membrane.
- M. Install vent flashing sleeves on stacks passing through roof. Secure over stack flashing according to manufacturer's written instructions.
- N. Install frost-proof vent caps on each vent pipe passing through roof. Maintain 1-inch clearance between vent pipe and roof substrate.
- O. Install floor drains at low points of surface areas to be drained. Set grates of drains flush with finished floor or as indicated. Size outlets as indicated.
- P. Install individual traps for floor drains connected to sanitary building drain, unless otherwise indicated.
- Q. Install floor-drain flashing collar or flange so no leakage occurs between drain and adjoining flooring. Maintain integrity of waterproof membranes where penetrated.
- R. Position floor drains for easy access and maintenance.
- S. Install interceptors, including trapping, venting, and flow-control fitting, according to authorities having jurisdiction and with clear space for servicing.
 - 1. Above-Floor Installation: Set unit with bottom resting on floor, unless otherwise indicated.
 - 2. Flush with Floor Installation: Set unit and extension if required, with cover flush with finished floor.

3. Recessed Floor Installation: Set unit in receiver housing having bottom or cradle supports, with receiver housing cover flush with finished floor.
 4. Pit Installation: Set unit in pit as indicated.
 5. Install cleanout immediately downstream from interceptors not having integral cleanout on outlet.
 6. Coordinate oil-interceptor storage tank and gravity drain with Division 2 Section "Oil Distribution Systems."
- T. Fasten wall-hanging plumbing specialties securely to supports attached to building substrate if supports are specified and to building wall construction if no support is indicated.
- U. Fasten recessed, wall-mounting plumbing specialties to reinforcement built into walls.
- V. Secure supplies to supports or substrate.
- W. Install individual stop valve in each water supply to plumbing specialties. Use ball, gate, or globe valve if specific valve is not indicated.
- X. Install water-supply stop valves in accessible locations.
- Y. Install traps on plumbing specialty drain outlets. Omit traps on indirect wastes unless trap is indicated.
- Z. Locate drainage piping as close as possible to bottom of floor slab supporting fixtures and drains.
- AA. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.
- BB. Include wood-blocking reinforcement for recessed and wall-mounting plumbing specialties.

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties. The following are specific connection requirements:
1. Install piping connections between plumbing specialties and piping specified in other Division 22 Sections.
 2. Install piping connections indicated between appliances and equipment specified in other Sections; connect directly to plumbing piping systems.
 3. Install piping connections indicated as indirect wastes from appliances and equipment specified in other Sections, to spill over receptors connected to plumbing piping systems.
- B. Install hoses between plumbing specialties and appliances as required for connections.
- C. Arrange for electric-power connections to plumbing specialties and devices that require power. Electric power is specified in Division 16 Sections.
- D. Supply Runouts to Plumbing Specialties: Install hot- and cold-water-supply piping of sizes indicated, but not smaller than required by authorities having jurisdiction.
- E. Drainage Runouts to Plumbing Specialties: Install drainage and vent piping, with approved trap, of sizes indicated, but not smaller than required by authorities having jurisdiction.

- F. Interceptor Connections: Connect piping, flow-control fittings, and accessories as indicated.
 - 1. Oil Interceptors: Connect inlet, outlet, vent, and gravity drawoff piping to unit; flow-control fitting and vent to unit inlet piping; and gravity drawoff and suction piping to oil storage tank.
- G. Ground electric-powered plumbing specialties.
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- H. Arrange for electric-power connections to plumbing specialties and devices that require power. Electric power, wiring, and disconnect switches are specified in Division 16 Sections.

3.3 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Provide services of factory-authorized service representative to supervise the field assembly of components and installation of grease recovery units, including piping and electrical connections, and to report results in writing.
 - 1. Test and adjust plumbing specialty controls and safeties. Replace damaged and malfunctioning controls and components.

3.4 COMMISSIONING

- A. Before startup, perform the following checks:
 - 1. System tests are complete.
 - 2. Damaged and defective specialties and accessories have been replaced or repaired.
 - 3. Clear space is provided for servicing specialties.
- B. Before operating systems, perform the following steps:
 - 1. Close drain valves, hydrants, and hose bibbs.
 - 2. Open general-duty valves to fully open position.
 - 3. Remove and clean strainers.
 - 4. Verify that drainage and vent piping are clear of obstructions. Flush with water until clear.
- C. Startup Procedures: Follow manufacturer's written instructions. If no procedures are prescribed by manufacturer, proceed as follows:
 - 1. Energize circuits for electrically operated units. Start and run units through complete sequence of operations.
- D. Adjust operation and correct deficiencies discovered during commissioning.

3.5 DEMONSTRATION

- A. Startup Services: Engage a factory-authorized service representative to perform startup services and train Owner's maintenance personnel as specified below:
 - 1. Train Owner's maintenance personnel on procedures and schedules related to startup of and servicing interceptors.
 - 2. Train Owner's maintenance personnel on procedures and schedules related to startup of and servicing grease recovery units.

3. Review data in the maintenance manuals. Refer to Division 1 Section "Contract Closeout."
4. Review data in the maintenance manuals. Refer to Division 1 Section "Operation and Maintenance Data."
5. Schedule training with Owner with at least 7 days' advance notice.

3.6 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION 22 43 00

SECTION 22 44 00

PLUMBING FIXTURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes plumbing fixtures and trim, faucets, other fittings, and related components.
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 7 Section "Joint Sealants" for sealing between fixtures and walls, floors, and counters.
 - 2. Division 22 Section "Valves" for general-duty valves used as supply stops.
 - 3. Section 22 05 49 "Plumbing Systems; Supports, Bracing and Seismic Requirements".
 - 4. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.3 DEFINITIONS

- A. Accessible: Plumbing fixture, building, facility, or portion thereof that can be approached, entered, and used by physically handicapped, disabled, and elderly people.
- B. Fitting: Device that controls flow of water into or out of plumbing fixture. Fittings specified in this Section include supplies and stops, faucets and spouts, shower heads and tub spouts, drains and tailpieces, traps and waste pipes. Pipe fittings, tube fittings, and general-duty valves are included where indicated.

1.4 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product Data for each plumbing fixture category and type specified. Include selected fixture, trim, fittings, accessories, appliances, appurtenances, equipment, and supports. Indicate materials and finishes, dimensions, construction details, and flow-control rates.
- C. Maintenance data for plumbing fixtures and components to include in the operation and maintenance manuals specified in Division 1.

1.5 QUALITY ASSURANCE

- A. Source Limitations: Obtain plumbing fixtures, faucets, and other components of each category from one source and by a single manufacturer.
 - 1. Exception: Where fixtures, faucets, or other components are not available from a single manufacturer, obtain similar products from other manufacturers specified for this category.
- B. Energy Policy Act Requirements: Comply with requirements of Public Law 102-486, "Energy Policy Act," regarding water flow rate and water consumption of plumbing fixtures.
- C. Listing and Labeling: Provide electrically operated fixtures and components specified in this Section that are listed and labeled.
 - 1. The Terms "Listed" and "Labeled": As defined in the National Electrical Code, Article 100.
- D. Select combinations of fixtures and trim, faucets, fittings, and other components that are compatible.
- E. Product Options: Drawings indicate size, profiles, dimensional requirements, and characteristics of plumbing fixtures and are based on specific types and models indicated. Other manufacturers' fixtures with equal performance characteristics may be considered. Refer to Division 1 Section "Substitutions."
- F. Comply with the following applicable standards and other requirements specified for plumbing fixtures:
 - 1. Plastic Mop-Service Basins: ANSI Z124.6.
 - 2. Plastic Shower Enclosures: ANSI Z124.2.
 - 3. Slip-Resistant Bathing Surfaces: ASTM F 462.
 - 4. Stainless-Steel Fixtures Other Than Service Sinks: ASME A112.19.3M.
 - 5. Vitreous-China Fixtures: ASME A112.19.2M.
 - 6. Water-Closet, Flush Valve, Tank Trim: ASME A112.19.5.
 - 7. Water-Closet, Flushometer Tank Trim: ASSE 1037.
- G. Comply with the following applicable standards and other requirements specified for lavatory and sink faucets:
 - 1. Backflow Protection Devices for Faucets with Side Spray: ASME A112.18.3M.
 - 2. Backflow Protection Devices for Faucets with Hose-Thread Outlet: ASME A112.18.3M.
 - 3. Diverter Valves for Faucets with Hose Spray: ASSE 1025.
 - 4. Faucet Hose: ASTM D 3901.
 - 5. Faucets: ASME A112.18.1M.
 - 6. Hose-Connection Vacuum Breakers: ASSE 1011.
 - 7. Hose-Coupling Threads: ASME B1.20.7.
 - 8. Integral, Atmospheric Vacuum Breakers: ASSE 1001.
 - 9. NSF Materials: NSF 61.
 - 10. Pipe Threads: ASME B1.20.1.
 - 11. Sensor-Actuated Faucets and Electrical Devices: UL 1951.
 - 12. Supply and Drain Fittings: ASME A112.18.1M.
- H. Comply with the following applicable standards and other requirements specified for shower faucets:
 - 1. Backflow Protection Devices for Hand-Held Showers: ASME A112.18.3M.
 - 2. Combination, Pressure-Equalizing and Thermostatic-Control Antiscald Faucets: ASSE 1016.
 - 3. Faucets: ASME A112.18.1M.
 - 4. Hand-Held Showers: ASSE 1014.

5. High-Temperature-Limit Controls for Thermal-Shock-Preventing Devices: ASTM F 445.
6. Hose-Coupling Threads: ASME B1.20.7.
7. Manual-Control Antiscald Faucets: ASTM F 444.
8. Pipe Threads: ASME B1.20.1.
9. Pressure-Equalizing-Control Antiscald Faucets: ASTM F 444 and ASSE 1016.
10. Sensor-Actuated Faucets and Electrical Devices: UL 1951.
11. Thermostatic-Control Antiscald Faucets: ASTM F 444 and ASSE 1016.

I. Comply with the following applicable standards and other requirements specified for miscellaneous fittings:

1. Atmospheric Vacuum Breakers: ASSE 1001.
2. Brass and Copper Supplies: ASME A112.18.1M.
3. Manual-Operation Flushometers: ASSE 1037.
4. Plastic Tubular Fittings and Piping: ASTM F 409.
5. Sensor-Operation Flushometers: ASSE 1037 and UL 1951.
6. Tubular Brass Drainage Fittings and Piping: ASME A112.18.1M.

J. Comply with the following applicable standards and other requirements specified for miscellaneous components:

1. Disposers: ASSE 1008 and UL 430.
2. Floor Drains: ASME A112.21.1M.
3. Grab Bars: ASTM F 446.
4. Hose-Coupling Threads: ASME B1.20.7.
5. Off-Floor Fixture Supports: ASME A112.6.1M.
6. Pipe Threads: ASME B1.20.1.
7. Plastic Shower Receptors: ANSI Z124.2.
8. Plastic Toilet Seats: ANSI Z124.5.
9. Supply and Drain Protective Shielding Guards: ICC A117.1.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver plumbing fixtures in manufacturer's protective packing, crating, and covering.
- B. Store plumbing fixtures on elevated platforms in dry location.

1.7 PROJECT CONDITIONS

- A. Field Measurements: Coordinate roughing-in and final fixture locations and verify that plumbing fixtures can be installed to comply with original design and referenced standards.

1.8 EXTRA MATERIALS

- A. Deliver extra materials to Owner. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.
 1. Faucet Washers and O-Rings: Furnish quantity of identical units not less than 10 percent of each type and size installed.
 2. Supply, Flow-Control Fittings: Furnish quantity of identical units not less than 5 percent of each type and size installed.

3. Flushometer Valve, Repair Kits: Furnish quantity of identical units not less than 10 percent of each type installed.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. For fixture descriptions in other Part 2 articles where the subparagraph titles "Product" and "Manufacturers" introduce a list of manufacturers and their products or manufacturers only, the following requirements apply for product selection:
 1. Products: Subject to compliance with requirements, provide one of the products specified in other Part 2 articles.

2.2 PLUMBING FIXTURES AND TRIM

- A. Lavatory Faucet: Include hot- and cold-water indicators; coordinate faucet inlets with supplies and fixture holes and outlet with spout and fixture receptor.
 1. Products:
 - a. Chicago Faucet
 - b. American Standard
 2. Performance: See schedule on drawings.
- B. Sink Faucet: Include hot- and cold-water indicators; coordinate faucet inlets with supplies and fixture holes and outlet with spout and fixture receptor.
 1. Manufacturers:
 - a. Chicago Faucet
 - b. American Standard
 2. Performance: See schedule on drawings.
- C. Flushometer: Cast-brass body with corrosion-resistant internal components, non-hold-open feature, control stop with check valve, vacuum breaker, and copper or brass tubing, and polished chrome-plated finish on exposed parts.
 1. Manufacturers:
 - a. Sloan Valve Co.
 - b. Zurn Industries
 - c. American Standard
 2. Performance: See schedule on drawings.
- D. Toilet Seat: Solid plastic, antimicrobial, self-sustaining check hinge.
 1. Manufacturers:
 - a. Olsonite Corporation
 - b. Church
 - c. Bemis Manufacturing Co.
- E. Protective Shielding Guard: Manufactured, plastic covering for hot and cold-water supplies and trap and drain piping and complying with ADA requirements.
 1. Manufacturers:
 - a. Trubro, Inc.
 - b. McGuire Manufacturing Co., Inc.

- F. Urinal Support, Type I, urinal carrier with fixture support plates and coupling with seal and fixture bolts and hardware matching fixture Type II, urinal carrier with hanger and bearing plates. Include steel uprights with feet.
 - 1. Manufacturers:
 - a. Jay R. Smith Mfg. Co.
 - b. Zurn
 - c. Watts Industries, Inc.
 - 2. Accessible Fixture Support: Include rectangular steel uprights.
- G. Lavatory Support: Type I, lavatory carrier with exposed arms and tie rods Type II, lavatory carrier with concealed arms and tie rod Type III, lavatory carrier with hanger plate and tie rod. Include steel uprights with feet.
 - 1. Manufacturers:
 - a. Jay R. Smith Mfg. Co.
 - b. Zurn
 - c. Watts Industries, Inc.
 - 2. Accessible Fixture Support: Include rectangular steel uprights.
- H. Water Closets: Vitreous-china fixture designed for flushometer valve operation.
 - 1. Products:
 - a. American Standard, Inc.
 - b. Kohler Co.
 - c. TOTO, Inc.
- I. Urinals: Wall-hanging, back-outlet, vitreous-china fixture designed for flushometer valve operation.
 - 1. Products:
 - a. American Standard, Inc.
 - b. Kohler Co.
 - c. TOTO, Inc.
 - 2. Performance: See schedule on drawings.
- J. Lavatories: Wallhung, vitreous-china fixture.
 - 1. Products:
 - a. American Standard, Inc.
 - b. Kohler Co.
 - c. TOTO, Inc.
- K. Kitchen Sinks: Residential, counter-mounting, stainless-steel fixture.
 - 1. Products:
 - a. Elkay Manufacturing Co.
 - b. Just Manufacturing Co.
 - c. Acorn
- L. Service Basins MSB: Flush-to-wall, floor-mounting plastic basin.
 - 1. Products:
 - a. Fiat
 - b. Florestone Products Co.

2.3 FITTINGS

- A. Fittings for Plumbing Fixtures: Refer to plumbing fixture schedules at the end of this Section for materials for supplies, supply stops, supply risers, traps, and other fittings.
- B. Fittings for Equipment Specified in Other Sections: Fittings include the following:
 - 1. Supply Inlets: Brass pipe or copper tube, size required for final connection.
 - 2. Supply Stops: Chrome-plated brass, angle or straight; compression, loose-key type; same size as supply inlet and with outlet matching supply riser.
 - 3. Supply Risers: 3/8-inch NPS flexible copper tube with knob end. Use chrome-plated tube for exposed applications.
 - 4. Traps: Cast brass with slip-joint inlet, cleanout pipe nipple to wall, wall flange, escutcheons, and size to match equipment. Use chrome-plated tube for exposed applications.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in for potable, hot- and cold-water supply piping systems; soil, waste, and vent piping systems; and supports. Verify that locations and sizes of piping and locations and types of supports match those indicated, before installing and connecting fixtures. Use manufacturer's roughing-in data when roughing-in data are not indicated.
- B. Examine walls, floors, and cabinets for suitable conditions where fixtures are to be installed.
- C. Do not proceed until unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Include supports for plumbing fixtures according to the following:
 - 1. Carriers: For wall-hanging water closets and fixtures supported from wall construction. Carriers shall be equal to J. R. Smith 0115, 0175, 0209, 0210, 0230 & 0240 with suffix M51 foot support.
 - 2. Chair Carriers: For wall-hanging urinals, lavatories, sinks, drinking fountains, and electric water coolers. Carriers shall be equal to J. R. Smith 0635, 0700, 0830 & 0913 Pro-Set carriers.
- B. Include fitting insulation kits for accessible fixtures according to the following:
 - 1. Lavatories: Cover hot- and cold-water supplies, stops and handles, drain, trap, and waste to wall.
 - 2. Sinks: Cover hot- and cold-water supplies, stops and handles, drain, trap, and waste to wall.
 - 3. Fixtures with Offset Drain: Cover hot- and cold-water supplies, offset drain, trap, and waste to wall.
 - 4. Other Fixtures: Cover exposed fittings below fixture.

3.3 PLUMBING FIXTURE INSTALLATION

- A. Assemble plumbing fixtures and trim, fittings, faucets, and other components according to manufacturers' written instructions.

- B. Install fixtures level and plumb according to manufacturers' written instructions, roughing-in drawings, and referenced standards.
- C. Install wall-hanging, back-outlet water closets with support manufacturer's tiling frame or setting gage.
- D. Install toilet seats on water closets.
- E. Install wall-hanging, back-outlet urinals with gasket seals.
- F. Install Flushometer valves for accessible water closets and urinals with handle mounted on wide side of compartment. Install other actuators in locations that are easy for handicapped people to reach.
- G. Fasten recessed, wall-mounted fittings to reinforcement built into walls.
- H. Fasten wall-mounted fittings to reinforcement built into walls.
- I. Fasten counter-mounting plumbing fixtures to casework.
- J. Secure supplies to supports or substrate within pipe space behind fixture.
- K. Install individual stop valve in each water supply to fixture.
 - 1. Exception: Omit stop valves on supplies to emergency equipment, except when permitted by authorities having jurisdiction. When permitted, install valve chained and locked in OPEN position.
- L. Install water-supply stop valves in accessible locations.
- M. Install faucet, laminar-flow fittings with specified flow rates and patterns in faucet spouts when faucets are not available with required rates and patterns. Include adapters when required.
- N. Install traps on fixture outlets. Omit traps on fixtures having integral traps. Omit traps on indirect wastes, except where otherwise indicated.
- O. Install escutcheons at wall, floor, and ceiling penetrations in exposed, finished locations and within cabinets and millwork. Use deep-pattern escutcheons where required to conceal protruding pipe fittings.
- P. Seal joints between fixtures and walls, floors, and counters using sanitary-type, 1-part, mildew-resistant, silicone sealant according to sealing requirements specified in Division 7 Section "Joint Sealants." Match sealant color to fixture color.
- Q. Provide on all lavatories and sinks where hot water supplies a faucet a Symmons Series 7-210-CK Maxline, thermostatic mixing valve. Mixing valve shall supply tempered water to the hot water inlet side of each faucet. Set outlet temperature at 105 degrees Fahrenheit. Similar valves by Watts shall be acceptable.
- R. Set high limit temperature on all shower valves to 105 degrees Fahrenheit.

3.4 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties. The following are specific connection requirements:
 - 1. Install piping connections between plumbing fixtures and piping systems and plumbing equipment specified in other Division 22 Sections.
- B. Supply and Waste Connections to Plumbing Fixtures: Refer to plumbing fixture schedules at the end of this Section for fitting sizes and connection requirements for each plumbing fixture.
- C. Supply and Waste Connections to Equipment Specified in Other Sections: Connect equipment with supply inlets, supply stops, supply risers, and traps specified in this Section. Use fitting sizes required to match connected equipment. Connect fittings to plumbing piping.
- D. Ground equipment.
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.5 FIELD QUALITY CONTROL

- A. Verify that installed fixtures are categories and types specified for locations where installed.
- B. Check that fixtures are complete with trim, faucets, fittings, and other specified components.
- C. Inspect installed fixtures for damage. Replace damaged fixtures and components.
- D. Test installed fixtures after water systems are pressurized and demonstrate proper operation. Replace malfunctioning fixtures and components, then retest. Repeat procedure until units operate properly.

3.6 ADJUSTING AND CLEANING

- A. Operate and adjust faucets and controls. Replace damaged and malfunctioning fixtures, fittings, and controls.
- B. Operate and adjust disposers, hot-water dispensers, and controls. Replace damaged and malfunctioning units and controls.
- C. Adjust water pressure at Flushometer valves having controls, to produce proper flow and stream.
- D. Replace washers and seals of leaking and dripping faucets and stops.
- E. Clean fixtures, faucets, and other fittings with manufacturers' recommended cleaning methods and materials. Include the following:
 - 1. Remove faucet spouts and strainers, remove sediment and debris, and reinstall strainers and spouts.
 - 2. Remove sediment and debris from drains.

3.7 PROTECTION

- A. Provide protective covering for installed fixtures and fittings.
- B. Do not allow use of fixtures for temporary facilities, except when approved in writing by Owner.

END OF SECTION 22 44 00

This page intentionally left blank.

SECTION 22 44 35

DOMESTIC HOT WATER RETURN PUMPS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following systems:
 - 1. Domestic Hot water Return Pumps
- B. Related Sections: The following Sections contain requirements that relate to this Section:
 - 1. Division 7 Section "Joint Sealants" for sealing between fixtures and walls, floors, and counters.
 - 2. Division 22 Section "Valves" for general-duty valves used as supply stops.
 - 3. Section 22 05 49 "Plumbing Systems; Supports, Bracing and Seismic Requirements".
 - 4. Section 22 05 00 "Basic Mechanical Materials and Methods".

1.3 SUBMITTALS

- A. Product Data: For each type and size of equipment. Include rated capacities; shipping, installed; and operating weights; furnished specialties; and accessories.
- B. Shop Drawings: Detail assemblies and indicate dimensions, weights, loads, required clearances, methods of field assembly, components, and location and size of each field connection.
 - 1. Wiring Diagrams: Power signal, and control wiring. Differentiate between manufacturer-installed and field-installed wiring.
- C. Product Certificates: Signed by product manufacturers certifying that products furnished comply with requirements.
- D. Maintenance Data: For equipment to include in maintenance manuals specified in Division 1.
- E. Warranties: Special warranties specified in this Section.

1.4 QUALITY ASSURANCE

- A. Source Limitations: Obtain same type of equipment through one source from a single manufacturer.

- B. Product Options: Drawings indicate size, profiles, and dimensional requirements of equipment and are based on the specific units indicated. Other manufacturers' products complying with requirements may be considered. Refer to Division 1 Section "Substitutions."
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1.5 WARRANTY

- A. General Warranty: Special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.
- B. Special Warranty: Written warranty, executed by manufacturer agreeing to repair or replace components that fail in materials or workmanship within specified warranty period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Hot Water Recirculation Pumps
 - a. Bell and Gossett
 - b. Taco
 - c. Grundfos

2.2 DOMESTIC HOT WATER RECIRCULATING PUMPS

- A. In-line mounted all bronze pump.
 - 1. Install an eccentric reducer before and after the pump.
 - 2. Install a shut-off valve, strainer and check valve upstream of each pump.
 - 3. Install a shut-off valve and balance valve downstream of each pump
- B. Electrical connections by Electrical Contractor.

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION

- A. Install equipment, level and plum, according to layout drawings, original design, and referenced standards. Main manufacturer's recommended clearances. Arrange units so controls and devices needing service are accessible.

- B. Install seismic restraints for equipment. Anchor to substrate.

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Make connections with dielectric fittings where piping is made of dissimilar metal.
- C. Electrical Connections: Power wiring and disconnect switches are specified in Division 16 Sections. Arrange wiring to allow unit service.
- D. Ground equipment.
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.3 FIELD QUALITY CONTROL

- A. Engage a factory-authorized service representative to perform startup service.
- B. In addition to manufacturer's written installation and startup checks, perform the following:
 - 1. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 2. Verify that piping system tests are complete.
 - 3. Check for piping connection leaks.
 - 4. Test operation of safety controls, relief valves, and devices.
 - 5. Energize electric circuits.
 - 6. Adjust operating controls.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain water heaters.
 - 1. Review data in maintenance manuals. Refer to Division 1 Section "Contract Closeout."
 - 2. Review data in maintenance manuals. Refer to Division 1 Section "Operational and Maintenance Data."

END OF SECTION 22 44 35

This page intentionally left blank.

SECTION 23 00 00 - MECHANICAL GENERAL REQUIREMENTS

PART 1 - GENERAL

1.1 GENERAL

- A. Where the word contractor is used in this specification or on the drawings, the term shall apply to a prime contractor or a subcontractor. Where the term "this contractor" is used in this specification, the term shall apply to the mechanical contractors as applicable. Words such as "he" and "she" used in this specification is not intended to designate gender.
- B. This Contractor shall refer to the "Instructions to Bidders", General Conditions, Supplementary General Conditions and Special Conditions and Applicable Provisions for bidding requirements and items that effect his work.
- C. Pertinent Federal, State and Local requirements and regulations of OSHA, National Electrical Codes, and NFPA, are hereby made a part of this contract. Use of the term "code" in sections of this specification refers to applicable requirements and regulations of above listed agencies.
- D. It shall be the responsibility of this Contractor to promptly inform the Architects of all deviations in the drawings and specifications from the City, County and State Laws, Ordinances, Regulations or Rulings. This Contractor shall install all work strictly in accordance with all such requirements at no additional cost to Owner.
- E. In the event the specifications or drawings conflict with such laws or ordinances, the conflicting portion of the work affected shall be installed in strict accordance with the laws or ordinances above mentioned and the remainder of the drawings and specifications shall remain in full force.
- F. If the requirements of these specifications or drawings are more stringent than the conflicting laws or ordinances, the requirements of the specifications and drawings shall govern unless amended by the Engineer.
- G. It shall be the responsibility of this Contractor to review all installation requirements and to promptly inform the Architect of all deviations in the drawings and specifications from the manufacturer's installation requirements. The Contractor shall install all work strictly in accordance with all such requirements at no additional cost to Owner.

1.2 SUMMARY

- A. This Section includes general administrative, material, and procedural requirements for Division 23 to expand the requirements specified in Division 01.

1.3 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and the Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.4 REGULATORY REQUIREMENTS

- A. Work and materials shall conform to and be executed, inspected and tested in accordance with the latest edition of applicable Federal, State and local codes and with the other governing rules and regulations of Federal, State, and local governmental agencies.
- B. Specific codes and standards which will apply to this installation are listed in applicable specification sections.
- C. Other codes which will apply to this installation include the current editions of:
 - 1. NFPA 99 - Health Care Facilities.
 - 2. NFPA 101 - Life Safety Code.
 - 3. Underwriters Laboratories.
- D. Where governing codes indicate the Drawings and Specifications do not comply with the minimum requirements of applicable codes, be responsible for either notifying the Architect in writing during the bidding period of the revisions required to meet code requirements, or providing an installation which will comply with the code requirements.

1.5 PERMITS AND INSPECTIONS

- A. Permits: Obtain and pay for all permits, bonds, licenses, tap-in fees, etc., required by the City, State, or other authority having jurisdiction over the work, as a part of the work of the affected sections.
- B. Inspections: Arrange and pay for all inspections required by the above when they become due as part of the work of the sections affected. Conceal no work until approved by these governing authorities. Coordinate inspection period with Authorities Having Jurisdiction and Engineer. Present the Engineer with properly signed certificate of final inspection

1.6 DEFINITIONS

- A. Pipe, pipe fittings, and piping include tube, tube fittings, and tubing.
- B. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below the roof, spaces above ceilings, unexcavated spaces, crawl spaces, and tunnels.
- C. Exposed Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- D. Exposed Exterior Installations: Exposed to view outdoors, or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- E. Concealed Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in duct shafts.
- F. Concealed Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants, but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.

1.7 SHOP DRAWINGS

- A. This Contractor shall submit for the Engineer's review a list of all equipment and subcontractors he proposes to use. This list shall be submitted within thirty (30) days after signing of contracts or receiving "Letter of Intent". The engineer will review and comment on this list prior to submission of shop drawings.
- B. After the Contractor has received the comments from the engineer concerning the list of equipment and subcontractors, this Contractor shall submit shop drawings or manufacturer data sheets, certification and descriptive literature for ALL material and equipment furnished on this project.
- C. Submittals shall be transmitted to Horner & Shifrin (H&S) as paper documents, electronic documents via email attachments, or electronic documents via FTP file transfers. All submittals shall include a transmittal form identifying the project name, date, contents of submittal package, and names of subcontractor, manufacturer, and supplier. On an attached separate sheet clearly identify deviations from requirements in the Contract Documents, including minor variations and limitations.
 - 1. Documents transmitted in paper format shall be sent to the Architect who will forward these to H&S. If approved by the Architect prior to submitting documents, these documents may be submitted simultaneously to the Architect and H&S. H&S will return all documents to the Architect only regardless of how they were transmitted to H&S. Submit four (4) paper copies of all required Shop Drawings and material and equipment lists for the Engineer's and Owner's sole use. The Contractor shall submit additional paper copies that will be required for his own use and the Operation and Maintenance Manuals. The additional copies will be reviewed by the Engineer and returned to the Contractor marked accordingly.
 - 2. Documents transmitted as email attachments shall be sent simultaneously to the Architect and H&S. H&S will return one (1) electronic copy of these documents to the Architect only.
 - 3. Documents transmitted via FTP file transfers shall be retrieved from the FTP site after H&S has received an email notification that these documents have been posted to the site. H&S will return one (1) electronic copy of these documents to the Architect only unless another procedure is agreed to in writing by the Architect and the Engineer.
- D. Shop drawings, manufacturer data sheets and descriptive literature shall include parts lists, operating and maintenance manuals, etc.
- E. The Contractor shall review each shop drawing etc. before submitting to the engineer to determine that it is acceptable in terms of the means, methods, techniques, orientation, sequences, operations of construction, safety precautions and programs incidental there to, all of which are the contractor's responsibility.
- F. The engineer shall review each shop drawing, etc. for its conformity with design intent and compliance with information given in the construction documents.
- G. The Contractor shall bring to the engineer's attention any shop drawing, etc. that varies from the contract documents requirements.
- H. The engineers review time for all submittals will be 10 working days.

- I. The Contractor shall pay for the review of all shop drawings, etc. that varies from the requirements of the contract documents.
- J. Shop drawings, etc. submitted for equipment or material which was not specified, included in the specification or drawings by written addendum, or submitted by separate letter with the contractors bid will be returned without review and will not be considered for this project.
- K. At the completion of the project, this Contractor shall give the Owner three copies of all shop drawings, data sheets, operating manuals, parts lists, maintenance manuals, etc. which shall be bound in vinyl-covered three-ring binders with a complete index and index tabs. All manuals to be submitted to the Engineer's Office for review and acceptance prior to transmittal to the Owner.
- L. Failure to Submit: Contractor's failure to provide submittals does not alleviate the responsibility to provide the requirements in the Contract Document as interpreted by the Engineer. Correct noncompliant items.

1.8 SEQUENCING AND SCHEDULING

- A. Coordinate mechanical equipment installation with other building components.
- B. Permanent HVAC equipment shall not be started until such time as the building envelope is completely sealed and all dust producing activities have been completed and spaces cleaned or as required to begin testing and balancing activities, whichever is later.
- C. Arrange for chases, slots, and openings in building structure during progress of construction to allow for mechanical installations.
- D. Coordinate the installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- E. Sequence, coordinate, and integrate installations of mechanical materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning prior to closing in the building.
- F. Coordinate connection of electrical services.
- G. Coordinate requirements for access panels and doors where mechanical items requiring access are concealed behind finished surfaces. Access panels and doors are specified in this section.
- H. Coordinate installation of identifying devices after completing covering and painting where devices are applied to surfaces. Install identifying devices prior to installing acoustical ceilings and similar concealment.

1.9 COORDINATION DRAWINGS

- A. The Contractor shall oversee the preparation of coordination drawings as follows:
 - 1. Contractors responsible for the following items of work located in or above ceilings shall participate in preparation of Coordination Drawings.
 - a. Recessed light fixtures.

- b. Pneumatic tube systems.
 - c. Ductwork and appurtenances.
 - d. Plumbing waste and roof drainage.
 - e. Fire Protection (Sprinkler System).
 - f. HVAC piping
 - g. Plumbing vent, supply and medical gas piping.
 - h. Plumbing domestic water piping.
 - i. Medical gas piping.
 - j. Electrical conduit.
- B. In the event a Contractor fails to cooperate in the Coordination Program, he will be held responsible for all costs incurred for adjustments to the work of others made necessary to accommodate the uncooperative Contractor's installations.
- C. When a Change Order request is issued, the affected Contractors shall review the Coordination Drawings and bring to the attention of the General Contractor any revisions necessary to the work of others not directly affected by the Change Order.

1.10 OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUALS

- A. Upon completion of the job, the installing contractors and major suppliers shall instruct the Owner's representatives in the proper operation and maintenance of the systems installed. The installing Contractors shall submit documentation indicating the date of instruction; names and organization of persons providing and receiving the instructions; systems the instructions covered; and materials received.
- B. Contractor shall also submit four (4) complete sets of properly bound operating manuals to the Engineer for review. These manuals shall include the following:
 - 1. Complete set of shop drawings.
 - 2. Copies of all submittals.
 - 3. Parts lists, wiring diagrams, piping diagrams, etc.
 - 4. Manufacturers' operating and maintenance instructions.
 - 5. As-built drawings.
 - 6. Written operating and maintenance instructions for the system. This is a written version of Paragraph "1" above.
 - 7. Copies of warranties.
 - 8. Parts lists for each piece of equipment and name of local supplier.
 - 9. DVD of recorded Owner equipment training.
 - 10. Provide a Filter Change Out Schedule.

1.11 OWNERS RECORD SET OF DRAWINGS

- A. During construction, a separate set of plans at the jobsite shall be maintained by the Contractor to keep a record of all changes of locations. See additional requirements in General Conditions and Supplementary Conditions.
- B. Locations of piping, ductwork and other concealed facilities are to be shown by the Contractor if and when they differ from the drawings. Underground piping shall be dimensioned on those drawings.

- C. "As built" drawings are to be submitted to Architect/Engineer for review prior to the time of request for final payment. Submit as-built record drawings in accordance with the General Conditions.

1.12 GUARANTEE AND WARRANTY

- A. This Contractor shall guarantee and warrant all equipment, materials, workmanship, installation, etc., for a period of one year in accordance with the General Conditions. This one-year warranty shall commence on satisfactory completion of final punch list items. Satisfactory completion of the final punch list will be determined by the Engineer. If the Owner accepts a portion(s) of the project earlier than the rest, such as partial beneficial occupancy,

PART 2 - PRODUCTS

2.1 MATERIAL AND EQUIPMENT SELECTION

- A. Product Options: The specification of each item of major equipment required for the project may include a list of manufacturers, with one "basis of design" manufacturer, type, and model identified by virtue of their being the first listed manufacturer in the specifications. Where several manufacturers in addition to the "basis of design" manufacturer are listed in the specifications, it shall be understood that the words "or approved equal by" are implied to precede each of the other manufacturer's names.
- B. The manufacturers other than the "basis of design" may be furnished at the contractor's option in lieu of the "basis of design" product, provided that the selected manufacturer's product is equal in all material and functional respects. Additional work required for equipment that is other than the "basis of design", shall be at the expense of the contractor. In addition to submittal requirements that may be specified in this section, submit a line-by-line written verification of the applicable specification section(s) identifying compliance with or variations from the specified features, materials, performance, capacities, weight, size, durability, energy consumption and efficiency, warranty, and visual impact (if exposed to view by other than maintenance persons). The burden of proof of manufacturer/product equality is on the contractor.
- C. Where a product is not scheduled on the drawings and, therefore, where no "basis of design" is indicated, the first listed manufacturer in the specifications shall be deemed as "basis of design"
- D. Products of manufacturers not listed in the Contract Documents are considered Substitutions and are not permitted, except as provided under the General and Supplementary Conditions and Division 1 Specifications. Full compliance with section "Substitutions" below is mandatory for acceptance of products or manufacturers not listed.
- E. Listing of a manufacturer does not imply approval of that manufacturer's standard product or products. Rather, listing of a manufacturer indicates only a general acceptance of that manufacturer's name and reputation. Final approval is subject to full compliance with these Contract Documents.

- F. Model numbers identified on the Drawings notwithstanding, all equipment must comply with the requirements of these Contract Documents. Do not assume that a manufacturer's standard product is acceptable as is. For example, one or more custom modifications, custom colors or finishes, manufacturer's options, and/or accessories may be required to meet the specified requirements.
- G. Where drawings indicate sizes, profiles, connections, and dimensional requirements of material and equipment, these are based on the "basis of design" manufacturer, type and model indicated. In the event that equipment of power, dimensions, capacities, layout, connections, and/or ratings differing from the "basis of design" are selected by the contractor and approved by the Owner's representative, any necessary adjustments are the contractor's responsibility. All connecting mechanical and electrical services, circuit breakers, conduit, motors, bases, pipe and duct sizes, pipe and duct layout, and the like shall be adjusted by the contractor to suit the equipment provided. No additional costs will be approved for these changes. Should revisions to the design because of contractor's selection of manufacturer, type, or model other than the "basis of design" require additional review and/or redesign by an Architect or Engineer, the contractor shall reimburse the Owner for Owner's added professional fee expenses.
- H. Where two or more materials are listed in the "Part 2 – Products" subsection of any Division 23 section, do not assume that the selection of materials is the contractor's option. Refer to "Part 3 – Execution" subsection of that same Division 23 section for an explanation of which specific material(s) shall be used for which specific application(s). For example, Part 2 may list several types and grades of piping, and Part 3 will describe which type and grade of pipe to use for a given application.
- I. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems, and have been coordinated, as much as possible, based on available information and field observations. Deviations to layout that may require additional fittings, and are within 6'-0" of design document layout, shall be at the expense of the contractor. Deviations to layout shall be documented on the coordination drawings. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated, unless deviations to layout are approved on Coordination Drawings.

2.2 SUBSTITUTIONS

- A. Notwithstanding any reference in the specifications to any article, device, product, material, form or type of construction by name, or make, or catalog number, such references shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition; and the Contractor in such cases may, at his option, use any article, device, product, material, fixture, form or type of construction which in the judgment of the Engineer, expressed in writing, is equal to that specified.
- B. Any materials or products other than those specified shall be submitted in writing to the Engineer for approval at least 10 days prior to the submission of bids. Materials and products so approved will be so stated by addendum.
- C. No substitute equipment will be considered unless sufficient data is submitted with the request to allow adequate comparison with the specified equipment.

- D. The Engineer reserves the right to reject any or all substitute equipment, if, in his opinion, said equipment is not of equal quality, capacity or like design. In all cases, the decision of the Engineer shall be final.
- E. This Contractor, at his option, may submit any item of material or equipment in a separate letter listing voluntary alternatives. An additive or deduct price shall be indicated for each voluntary alternate submitted. Sufficient data shall accompany each voluntary alternate submitted to allow adequate comparison with the specified equipment. The Contractor shall pay all costs associated with reviewing proposed substitute material or equipment.
- F. This Contractor shall pay all costs arising from the use of substitute equipment or material. Such costs shall include but shall not be limited to architectural design costs, mechanical, electrical, plumbing, fire protection, civil & structural engineering costs & cost to other trades to accommodate the substitute equipment.

PART 3 - EXECUTION

3.1 GENERAL

- A. Contractor shall provide all material, equipment, labor, services, and supplies, required to execute all work shown on the mechanical drawings; described in these specifications; or made necessary by the work shown on the drawings and/or described in these specifications.
- B. Contractor shall schedule all work and furnish the required materials in such a manner that the work may progress from start to finish in an expeditious and efficient manner without undue interruption. This Contractor shall also schedule his work to coordinate with the construction staging for this project.
- C. Contractor shall hire the proper trades to accomplish the work described on the drawings or in the specifications.

3.2 COORDINATION OF TRADES

- A. Prior to the fabrication or installation of any materials, Contractor shall review the drawings indicating work to be performed by each trade. If conflicts occur, they shall be brought to the attention of the Engineer for resolution.
- B. If Contractor installs the work without coordinating with the other trades, then, if requested by the Owner, Architect, or Engineer, Contractor shall remove and rework some installed work to resolve a conflict, and such change shall be done at no change in contract price.
- C. The Contractor supplying the equipment shall furnish all motors and components which are part of the equipment.

- D. Control wiring is defined as that wiring which conducts electrical energy at a voltage of less than 100 volts. Interlock wiring is defined as that wiring which performs a control function, but at a voltage of 100 volts or greater. All other wiring shall be considered power wiring.
- E. The Electrical Contractor shall provide power wiring to, and including connection to the equipment. Unless specifically noted otherwise, all interlock wiring shall be provided by the Electrical Contractor. Unless noted otherwise, the control wiring shall be provided by the Contractor furnishing the controlled equipment.
- F. Unless noted otherwise, the Electrical Contractor shall provide all starters, disconnects, switches, push-button stations, etc., except those which are furnished with the equipment as a part of a factory-assembled package. Heater elements for overload relays on magnetic motor starters (except the starters factory pre-wired with equipment) shall be sized, furnished and installed by the Electrical Contractor. Magnetic motor starters for mechanical equipment (except starters factory pre-wired with equipment such as chillers and packaged air conditioners) shall be provided by the Electrical Contractor. Magnetic motor starters will be provided with:
 - 1. Auxiliary contacts as required by the interlocks defined on the drawings or in the specifications.
 - 2. Control Power Transformer - 120 volt secondary, minimum 40 Volt Amps.
- G. Each Contractor furnishing motor-operated equipment shall furnish a list of motor characteristics to the Electrical Contractor so that properly sized heater elements may be provided. The list shall include equipment identification by name and by number, the full load current, locked rotor current, voltage rating, and suggested service factor to compensate for operating duty cycle and ambient temperatures.
- H. Unless specifically noted otherwise, pilot controllers (pressure switches, etc.) shall be furnished and mounted by the Contractor furnishing the controlled equipment.
- I. Unless specifically noted otherwise, control dampers shall be furnished by the Temperature Control Contractor and installed by the Mechanical Contractor.
- J. Electrical Work For Mechanical Equipment: Electrical Contractor shall wire all mechanical equipment furnished by various contractors in accordance with the following general provisions:
 - 1. Power wiring from panel to motor controllers, relays, etc., and from controller to motor terminals per equipment manufacturer's wiring diagram.
 - 2. Receive, unload, set and align all separately shipped motors. Adjust and align drive and adjust belt tension.
 - 3. Field lubricate all motors prior to initial operation of same.
 - 4. Install individual motor starters specifically called for to be furnished by other Contractors when not a factory pre-wired component.
- K. HVAC Contractor shall provide the following:
 - 1. All motors, disconnect switches or control devices specifically called for.
 - 2. Automatic control and interlock wiring diagrams as called for in the specifications.
 - 3. Complete and accurate wiring diagrams to Electrical Contractor for all equipment requiring electrical power wiring including motor terminal connection diagrams.
 - 4. Adjustable motor bases and all bolts and nuts required for installation of base and motor.

5. Supervision of Electrical Contractor in lubrication of motors to eliminate possibility of motor starting or operating without proper lubrication and control systems.

3.3 PROTECTION OF EQUIPMENT AND WORK

- A. This Contractor shall, at all times, protect and preserve all materials, supplies, equipment, piping, etc., from damage due to weather, corrosion, dirt, vandalism, theft, etc., and shall further provide all enclosures or special protection as indicated by circumstances.
- B. Should any of the materials, equipment, etc., be damaged as a result of his negligence, then this Contractor shall be held responsible for all such damage and costs incurred for repair or replacement.

3.4 CONSTRUCTION STAGING

- A. See schedule in Division 0 and Division 1. This Contractor shall cooperate with and coordinate to plan and schedule the work to satisfy the schedule.

3.5 CLEANING AND CLEANUP

- A. Upon completion of this work, the Contractor shall clean all pipe, ductwork, fixtures, and equipment. Contractor shall leave all work in a finished, clean, and satisfactory working condition.
- B. Each contractor shall be responsible for his own cleanup to a central location designated by the Construction Manager. Contractor shall periodically remove all rubbish, crating, unused material, outfall, and any other debris created by him during the course of the work.

3.6 OWNER TRAINING

- A. Provide Owner training where indicated in the specifications. Video tape training sessions. Save and bookmark to DVD's for future reference.

3.7 FILTER CHANGE OUT SCHEDULE

- A. Provide a list and quantity of all filters provided with the equipment on the project. Indicate a recommended schedule for Owner to replace the filters.

END OF SECTION 23 00 00

SECTION 23 00 50 - BASIC MECHANICAL MATERIALS AND METHODS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and the Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. Section 23 00 00 "Mechanical General Requirements".

1.2 SUMMARY

- A. This Section includes the following basic mechanical materials and methods to complement other Division 23 Sections.
 - 1. Piping materials and installation instructions common to most piping systems.
 - 2. Concrete equipment base construction requirements.
 - 3. Equipment nameplate data requirements.
 - 4. Nonshrink grout for equipment installations.
 - 5. Field-fabricated metal and wood equipment supports.
 - 6. Installation requirements common to equipment specification Sections.
 - 7. Mechanical demolition.
 - 8. Cutting and patching.
 - 9. Touchup painting and finishing.
 - 10. Firestopping
- B. Pipe and pipe fitting materials are specified in piping system Sections.

PART 2 - PRODUCTS

2.1 PRODUCT CRITERIA

- A. Material and equipment shall be the standard product of a manufacturer regularly engaged in the manufacture of the product for at least 5 years.
- B. Products shall be supported by a service organization which maintains an inventory of repair parts and is located within 100 miles of the jobsite.

2.2 PIPE AND PIPE FITTINGS

- A. Refer to individual piping system specification Sections for pipe and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

2.3 PIPING JOINING MATERIALS

- A. Refer to individual piping system specification Sections in Division 23 for special joining materials not listed below.
- B. Pipe Flange Gasket Materials: Suitable for the chemical and thermal conditions of the piping system contents.
 - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch (3mm) maximum thickness, except where thickness or specific material is indicated.
 - a. Full-Face Type: For flat-face, Class 125 cast-iron and cast-bronze flanges.
 - b. Narrow-Face Type: For raised-face, Class 250 cast-iron and steel flanges.
 - 2. ASME B16.20 for grooved, ring-joint, steel flanges.
 - 3. AWWA C110, rubber, flat face, 1/8 inch (3 mm) thick, except where other thickness is indicated; and full-face or ring type, except where type is indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, stainless steel, except where other material is indicated.
- D. Plastic Pipe Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer, except where other type or material is indicated.
- E. Solder Filler Metal: ASTM B 32.
 - 1. Alloy Sn95: Lead Free
 - 2. Alloy Sn50: Tin (50 percent) and lead (50 percent).
 - 3. Alloy E: Tin (approximately 95 percent) and copper (approximately 5 percent).
 - 4. Alloy HA: Tin-antimony-silver-copper-zinc.
 - 5. Alloy HB: Tin-antimony-silver-copper-nickel.
- F. Brazing Filler Metals: AWS A5.8.
 - 1. BCuP Series: Stay Silv 15
 - 2. BAg1: Silver alloy.
- G. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- H. Solvent Cements: Manufacturer's standard solvents complying with the following:
 - 1. Acrylonitrile-Butadiene-Styrene (ABS): ASTM D 2235.
 - 2. Chlorinated Poly(Vinyl Chloride) (CPVC): ASTM F 493.
 - 3. Poly(Vinyl Chloride) (PVC): ASTM D 2564.
 - 4. PVC to ABS Transition: Made to requirements of ASTM D 3138, color other than orange.
- I. Plastic Pipe Seals: ASTM F 477, elastomeric gasket.
- J. Flanged, Ductile-Iron Pipe Gasket, Bolts, and Nuts: AWWA C110, rubber gasket, carbon steel bolts and nuts.

- K. Couplings: Iron body sleeve assembly, fabricated to match outside diameters of plain-end pressure pipes.

1. Sleeve: ASTM A 126, Class B, gray iron.
2. Followers: ASTM A 47 (ASTM A 47M), Grade 32510 or ASTM A 536 ductile iron.
3. Gaskets: Rubber.
4. Bolts and Nuts: AWWA C111.
5. Finish: Enamel paint.

2.4 ESCUTCHEONS

- A. Manufactured wall, ceiling, and floor plates; deep-pattern type where required to conceal protruding fittings and sleeves.

1. Inside Diameter: Closely fit around pipe, tube, and insulation.
2. Outside Diameter: Completely cover opening.
3. Cast Brass: One-piece, with set-screw.
 - a. Finish: Polished chrome plate.
4. Cast Brass: Split casting, with concealed hinge and set-screw.
 - a. Finish: Polished chrome plate.

2.5 DIELECTRIC FITTINGS

- A. Assembly or fitting having insulating material isolating joined dissimilar metals to prevent galvanic action and stop corrosion.

1. Description: Combination of copper alloy and ferrous; threaded, solder, plain, and weld neck end types and matching piping system materials.
2. Insulating Material: Suitable for system fluid, pressure, and temperature.
3. Dielectric Unions: Factory-fabricated, union assembly for 250-psig (1725kPa) minimum working pressure at a 180 deg F (82 deg C) temperature.
4. Dielectric Flanges: Factory-fabricated, companion-flange assembly for 150- or 300-psig (1035kPa or 2070kPa) minimum pressure to suit system pressures.
5. Dielectric-Flange Insulation Kits: Field-assembled, companion-flange assembly, full-face or ring type. Components include neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
 - a. Provide separate companion flanges and stainless steel bolts and nuts for 150- or 300-psig (1035kPa or 2070kPa) minimum working pressure to suit system pressures.
6. Dielectric Couplings: Galvanized-steel coupling, having inert and noncorrosive, thermoplastic lining, with threaded ends and 300-psig (2070kPa) minimum working pressure at 225 deg F (107 deg C) temperature.
7. Dielectric Nipples: Electroplated steel nipple, having inert and noncorrosive thermoplastic lining, with combination of plain, threaded, or grooved end types and 300-psig (2070kPa) working pressure at 225 deg F (107 deg C) temperature.

2.6 SLEEVES

- A. The following materials are for wall, floor, slab, and roof penetrations:
1. Steel Sheet-Metal: 24-gage (0.70mm) or heavier galvanized sheet metal, round tube closed with welded longitudinal joint.
 2. Steel Pipe: ASTM A 53, Type E, Grade A, Schedule 40, galvanized, plain ends.
 3. Cast-Iron: Cast or fabricated wall pipe equivalent to ductile-iron pressure pipe, having plain ends and integral water stop, except where other features are specified.
 4. Wall Penetration Systems: Wall sleeve assembly, consisting of housing, gaskets, and pipe sleeve, with 1 mechanical-joint end conforming to AWWA C110 and 1 plain pipe-sleeve end.
 - a. Penetrating Pipe Deflection: 5 percent without leakage.
 - b. Housing: Ductile-iron casting having waterstop and anchor ring, with ductile-iron gland, steel studs and nuts, and rubber gasket conforming to AWWA C111, of housing and gasket size as required to fit penetrating pipe.
 - c. Pipe Sleeve: AWWA C151, ductile-iron pipe.
 - d. Housing-to-Sleeve Gasket: Rubber or neoprene push-on type of manufacturer's design.
 5. Cast-Iron Sleeve Fittings: Commercially made sleeve having an integral clamping flange, with clamping ring, bolts, and nuts for membrane flashing.
 - a. Underdeck Clamp: Clamping ring with set-screws.
 6. PVC Plastic: Manufactured, permanent, with nailing flange for attaching to wooden forms.
 7. PVC Plastic Pipe: ASTM D 1785, Schedule 40.
 8. PE Plastic: Manufactured, reusable, tapered, cup-shaped, smooth outer surface, with nailing flange for attaching to wooden forms.
- B. Mechanical Sleeve Seals: Modular, watertight mechanical type. Components include interlocking synthetic rubber links shaped to continuously fill annular space between pipe and sleeve. Connecting bolts and pressure plates cause rubber sealing elements to expand when tightened.

2.7 LINTELS:

- A. Unless otherwise indicated on plans, all lintels required for the support of building construction above pipes, boxes, panels, ducts, etc., shall be furnished and installed by the Contractor requiring the opening.
- B. Lintels furnished shall be ASTM A 36 structural steel angles, channels, or tees of proper size and sections for the load being supported.

2.8 GROUT

- A. Nonshrink, Nonmetallic Grout: ASTM C 1107, Grade B.
 - 1. Characteristics: Post-hardening, volume-adjusting, dry, hydraulic-cement grout, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
 - 2. Design Mix: 5000-psi (34.50MPa), 28-day compressive strength.
 - 3. Packaging: Premixed and factory-packaged.

2.9 ACCESS PANELS

- A. Access panels shall be constructed of heavy gauge steel with factory applied prime coat of baked enamel.
- B. Panel doors shall be attached to the frame with concealed hinges.
- C. Cam locks shall be provided in not less than the following quantities:
- D. Panel Height (Opposite side of hinges)
 - 1. 0 to 18" 1 cam lock
 - 2. 18-1/16" to 30" 2 cam locks
 - 3. 30-1/16" to 48" 3 cam locks
 - 4. 48-1/16" to 60" 4 cam locks
- E. Panel Width
 - 1. 0 to 18" No cam locks on top or bottom
 - 2. 18-1/16" to 30" 1 cam lock top and bottom
 - 3. 30-1/16" to 48" 2 cam locks top and bottom
- F. On the panel height, one of the cam locks described above shall be a key operated cylinder lock in lieu of the cam lock. One key shall operate all panels.
- G. Cam locks shall have tamper-proof heads. Provide 10 tools to the owner.
- H. For masonry, tile or wallboard surfaces, provide access panels with extruded aluminum frames, 3/4" border, aluminum piano hinges, screwdriver-operated cam lock, brushed satin aluminum finish. Final painting to match interior decor by others. Paintable finish to be provided when the adjacent construction is paintable.
- I. Access panels will not be required in accessible type ceilings.
- J. For plastered ceiling or wall, concealed flange, recessed door panel to receive plaster by others, continuous hinges, flush latch, white prime coat finish. Final painting to match interior decor by others.
- K. For locations concealed from public, snap catch latches may be used.
- L. Manufacturer - Panels shall be equal to Inryco/Milcor type K for plaster, type DW for drywall, type M for masonry.

2.10 MISCELLANEOUS MATERIALS

- A. Powder-Actuated Drive-Pin Fasteners: Powder-actuated-type, drive-pin attachments with pull-out and shear capacities appropriate for supported loads and building materials where used. Acceptable manufacturers: Gunnebo Fastening Corp., Hilti, Inc., ITW Ramset/Red Head., or Masterset Fastening Systems, Inc.
- B. Mechanical-Anchor Fasteners: Insert-type attachments with pull-out and shear capacities appropriate for supported loads and building materials where used.
- C. Drilled Inserts: Self-drilling expansion shields and machine bolt expansion anchors: permitted in concrete not less than four inches thick. Applied load shall not exceed one-fourth the proof test load listed by the manufacturer. Phillips Red-head, wedge anchors or equal.
- D. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars, black and galvanized.
- E. Bolts and nuts, except as required for piping applications, shall be carbon steel in accordance with ASTM A 307 and shall be cadmium-plated, zinc-coated steel, or Type 304 stainless steel. Each bolt shall be provided with neoprene and cadmium-plated steel washers under the heads.

2.11 PREFABRICATED ROOF CURBS

- A. Prefabricated curbs shall be heavy-gage, galvanized steel with mitered and welded corners; 1 1/2-inch-thick, rigid, fiberglass insulation adhered to inside walls; built-in cant and mounting flange for flat roof decks; and 2-inch wood nailer. Provide 14 inches high where no other height is indicated. Curbs shall be Thycurb TC-3 for roof decks that are not surface insulated, and Thycurb TC-1 for decks that are surface insulated.
- B. Equivalent products, complying with these specifications, by the following manufacturers are acceptable:
 - 1. Pate
 - 2. Thybar
 - 3. Roof Products & Systems

2.12 PREFABRICATED SEISMIC RATED ROOF CURBS

- A. Prefabricated curbs shall be made of heavy-gage galvanized steel with mitered and welded corners (steel gauge as required to meet local codes) and have angle reinforcement, supply and return duct channels, insulated pans, 1-1/2-inch-thick rigid fiberglass insulation adhered to inside walls, built-in cant and mounting flange for flat roof decks and 2-inch wood nailer. Curbs shall be Thycurb TC-3 for roof decks that are not surface insulated, and Thycurb TC-1 for decks that are surface insulated.
- B. Provide 14 inches high, where no other height is shown.
- C. Seismic rated curbs shall be designed/constructed to meet the required local seismic codes, designed to mate perfectly with the rooftop manufacturers equipment.
- D. Seismic calculations shall be provided with shop drawings.

- E. Equivalent products, complying with these specifications, by the following manufacturers are acceptable:
 - 1. Pate
 - 2. Thybar
 - 3. Roof Products & Systems

2.13 PREFABRICATED PIPE CURB ASSEMBLIES

- A. Prefabricated pipe curb assemblies shall be heavy-gage, galvanized steel curb with mitered and welded corners; 1-1/2-inch-thick, rigid, fiberglass insulation adhered to inside walls; built-in cant and mounting flange for flat roof decks; and 2-inch wood nailer. Provide 14 inches high, where no other height is shown. Unit shall be furnished with an acrylic clad thermoplastic cover, fastening screws, and graduated step boots with stainless steel clamps. Units shall be Thycurb model TCC.
- B. Equal products, complying with these specifications by the following manufacturers are acceptable:
 - 1. Pate
 - 2. Roof Products & Systems
 - 3. Thycurb
 - 4. Approved Equal

2.14 PREFABRICATED PIPE SEALS

- A. Seals for Roof Penetrations
 - 1. Prefabricated pipe seals shall have a one piece spun aluminum base with a 5" high roof surface flange sloped for runoff. Unit shall have a PVC boot with graduated widths and adjustable stainless steel clamps. Unit shall withstand expansion, and vibration and shall fit pipe sizes from 1/2" through 10".be heavy-gage, galvanized steel curb with mitered and welded corners; 1-1/2-inch-thick.
 - 2. Equal products, complying with these specifications by the following manufacturers are acceptable:
 - a. Pate
 - b. Roof Products & Systems
 - c. Thycurb
 - d. Approved Equal
- B. Seals for Floor or Foundation Wall Penetrations
 - 1. Mechanical Seal: Link-Seal or approved equal. A modular mechanical sealing assembly consisting of interlocking rubber links shaped to fill the annular space between the pipe and sleeve; corrosion-protected carbon steel bolts, nuts, and pressure plates. After the assembly is positioned in the sleeve, tightening the bolts shall cause the rubber links to provide a watertight seal between the pipe and the sleeve. Seal assembly shall be sized as recommended by the manufacturer. Provide sleeves of proper diameters.

2.15 PREFABRICATED PIPE STANDS

- A. Pipe Stands, General: Shop or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
 - 1. Manufacturers:
 - a. ERICO/Michigan Hanger Co.
 - b. MIRO Industries.
 - c. Portable Pipe Hangers.
 - d. Or Equal
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod-roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
- C. Low-Type, Single-Pipe Stand: One-piece plastic base unit with plastic roller, for roof installation without membrane penetration.

2.16 DUCT IDENTIFICATION DEVICES

- A. Duct Markers: Engraved, color-coded laminated plastic. Include direction and quantity of airflow and duct service (such as supply, return, and exhaust). Include contact-type, permanent adhesive.

2.17 PIPING AND EQUIPMENT SYSTEMS MARKERS

- A. Markers shall be by Allen Systems, Inc., W.H. Brady Co.- Signmark Div., Industrial Safety Supply Co., Inc. or equal.
- B. Pipe banding shall consist of 1" wide single tape wrapped completely around the circumference of the pipe or insulation.
- C. All color coding shall comply with ANSI A13.1 1975.
- D. Pipe markers shall be manufacturer's standard pre-printed, semi-rigid plastic, snap-on type or vinyl, pressure-sensitive type with permanent adhesive.
- E. Valve tags shall be brass, plastic laminate, or plastic valve tags that are 1½" diameter or square. Indicate piping system abbreviation in ¼" high letters and sequenced valve numbers with ½" high letters. Provide manufacturer's standard solid brass or plated steel chain, or plated steel S-hooks of the sizes required for attachment of tags to valves.
- F. Equipment markers shall be manufacturer's standard laminated plastic type. Include the following, matching terminology on schedules as closely as possible: 1) Name, 2) tag number, and 3) Equipment service. Provide approximate 2½" x 4" markers for control devices, dampers, and valves; and 4½" x 6" for equipment.
- G. Underground Piping Markers
 - 1. Tape: Triple-laminate, consisting of aluminum foil, polyester film, and polyethylene, 6" wide.

2. Colored background, black lettering, two lines wide, and 2" tall letters. Provide different color tape for each piping service.
3. Acceptable Manufacturer, subject to compliance with requirements: Panduit Corporation.

PART 3 - EXECUTION

3.1 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end-caps. Maintain end-caps through shipping, storage, and handling to prevent pipe-end damage and prevent entrance of dirt, debris, and moisture.
- B. Protect stored pipes and tubes from moisture and dirt. Elevate above grade. When stored inside, do not exceed structural capacity of the floor.
- C. Protect flanges, fittings, and piping specialties from moisture and dirt.
- D. Protect stored plastic pipes from direct sunlight. Support to prevent sagging and bending.
- E. Pipe and duct protection during construction: Protect pipe and duct interiors with plastic plugs or plastic sheeting during construction to protect from moisture, construction debris and dust, and other foreign materials.

3.2 PIPING SYSTEMS--COMMON REQUIREMENTS

- A. General: Install piping as described below, except where system Sections specify otherwise. Individual piping system specification Sections in Division 23 specify piping installation requirements unique to the piping system.
- B. General Locations and Arrangements: Drawings (plans, schematics, and diagrams) indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated, except where deviations to layout are approved on coordination drawings.
- C. Install piping at indicated slope.
- D. Install components having pressure rating equal to or greater than system operating pressure.
- E. Install piping in concealed interior and exterior locations, except in equipment rooms and service areas.
- F. Install piping free of sags and bends.
- G. Install exposed interior and exterior piping at right angles or parallel to building walls. Diagonal runs are prohibited, except where indicated.

- H. Install piping tight to slabs, beams, joists, columns, walls, and other building elements. Allow sufficient space above removable ceiling panels to allow for ceiling panel removal.
- I. Install piping to allow application of insulation plus 1-inch (25mm) clearance around insulation.
- J. Locate groups of pipes parallel to each other, spaced to permit valve servicing.
- K. Install fittings for changes in direction and branch connections.
- L. Install couplings according to manufacturer's printed instructions.
- M. Install pipe escutcheons for pipe penetrations of concrete and masonry walls, wallboard partitions, and suspended ceilings according to the following:
 - 1. Chrome-Plated Piping: Cast-brass, one-piece, with set-screw, and polished chrome-plated finish. Use split-casting escutcheons, where required, for existing piping.
 - 2. Uninsulated Piping Wall Escutcheons: Cast-brass or stamped-steel, with set-screw.
 - 3. Uninsulated Piping Floor Plates in Utility Areas: Cast-iron floor plates.
 - 4. Insulated Piping: Cast-brass or stamped-steel, with concealed hinge, spring clips, and chrome-plated finish.
 - 5. Piping in Utility Areas: Cast-brass or stamped-steel, with set-screw or spring clips.
- N. Sleeves are not required for core drilled holes.
- O. Above Grade, Exterior Wall, Pipe Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Size sleeve for 1-inch (25mm) annular clear space between pipe and sleeve for installation of mechanical seals.
 - 1. Install steel pipe for sleeves smaller than 6 inches (150 mm).
 - 2. Install cast-iron wall pipes for sleeves 6 inches (150 mm) and larger.
 - 3. Assemble and install mechanical seals according to manufacturer's printed instructions.
- P. Fire Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestopping sealant material.
- Q. Verify final equipment locations for roughing in.
- R. Refer to equipment specifications in other Sections for roughing-in requirements.
- S. Piping Joint Construction: Join pipe and fittings as follows and as specifically required in individual piping system Sections.
 - 1. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
 - 2. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
 - 3. Soldered Joints: Construct joints according to AWS "Soldering Manual," Chapter 22 "The Soldering of Pipe and Tube."
 - 4. Brazed Joints: Construct joints according to AWS "Brazing Manual" in the "Pipe and Tube" chapter.
 - 5. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full inside diameter. Join pipe fittings and valves as follows:

- a. Note the internal length of threads in fittings or valve ends, and proximity of internal seat or wall, to determine how far pipe should be threaded into joint.
 - b. Apply appropriate tape or thread compound to external pipe threads (except where dry seal threading is specified).
 - c. Align threads at point of assembly.
 - d. Tighten joint with wrench. Apply wrench to valve end into which pipe is being threaded.
 - e. Damaged Threads: Do not use pipe or pipe fittings having threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
6. Welded Joints: Construct joints according to AWS D10.12 "Recommended Practices and Procedures for Welding Low Carbon Steel Pipe" using qualified processes and welding operators according to the "Quality Assurance" Article.
7. Flanged Joints: Align flange surfaces parallel. Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Assemble joints by sequencing bolt tightening to make initial contact of flanges and gaskets as flat and parallel as possible. Use suitable lubricants on bolt threads. Tighten bolts gradually and uniformly using torque wrench.
8. Plastic Pipe and Fitting Solvent-Cement Joints: Clean and dry joining surfaces by wiping with clean cloth or paper towels. Join pipe and fittings according to the following standards:
 - a. Comply with ASTM F 402 for safe handling of solvent-cement and primers.
 - b. Acrylonitrile-Butadiene-Styrene (ABS): ASTM D 2235 and ASTM D 2661.
 - c. Chlorinated Poly(Vinyl Chloride) (CPVC): ASTM D 2846 and ASTM F 493.
 - d. Poly(Vinyl Chloride) (PVC) Pressure Application: ASTM D 2672.
 - e. Poly(Vinyl Chloride) (PVC) Non-Pressure Application: ASTM D 2855.
 - f. PVC to ABS (Non-Pressure) Transition: Procedure and solvent cement described in ASTM D 3138.
 - g.
9. Plastic Pipe and Fitting Heat-Fusion Joints: Prepare pipe and fittings and join with heat-fusion equipment according to manufacturer's printed instructions.
 - a. Plain-End Pipe and Fittings: Butt joining.
 - b. Plain-End Pipe and Socket-Type Fittings: Socket joining.
- T. Piping Connections: Except as otherwise indicated, make piping connections as specified below.
 1. Install unions in piping 2 inches (50 mm) and smaller adjacent to each valve and at final connection to each piece of equipment having a 2-inch (50mm) or smaller threaded pipe connection.
 2. Install flanges in piping 2-1/2 inches (65 mm) and larger adjacent to flanged valves and at final connection to each piece of equipment having flanged pipe connection.
 3. Dry Piping Systems (Gas, Compressed Air, and Vacuum): Install dielectric unions and flanges to connect piping materials of dissimilar metals.
 4. Wet Piping Systems (Water): Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

3.3 EQUIPMENT INSTALLATION--COMMON REQUIREMENTS

- A. Install equipment to provide the maximum possible headroom where mounting heights are not indicated.
- B. Install equipment according to approved submittal data. Portions of the Work are shown only in diagrammatic form. Refer conflicts to the Architect.
- C. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, except where otherwise indicated.
- D. Install mechanical equipment to facilitate servicing, maintenance, and repair or replacement of equipment components. Connect equipment for ease of disconnecting, with minimum of interference with other installations. Extend grease fittings to an accessible location.
- E. Install equipment giving right-of-way to piping systems installed at a required slope.
- F. Equipment Supports
 - 1. This Contractor shall provide all bases, concrete inserts, anchor bolts, and structural steel to support the equipment, ductwork, piping, etc installed by him. Any equipment legs, guy wire, anchors, etc., or any pipe that passes through the roof shall be sealed by a method approved by the Architect.
 - 2. Provide concrete housekeeping pads a minimum of 3-½" high, unless detailed otherwise, under all equipment, pumps, etc., in equipment rooms that have piping containing water. The horizontal distance from the equipment support to the edge of the pad shall be at least 2", but not more than 4". All exposed edges of each pad shall be ½" chamfer and all surfaces shall be smooth. The housekeeping pads shall be reinforced with wire mesh and shall be doweled to the floor.
 - 3. Plywood backboards shall be provided for all wall mounted equipment and controls (with the exception of surface mounted cabinets). Backboards shall be constructed of ¾" plywood grade B-C. The "B" face shall be exposed. All boards shall be painted before attachment of any surface equipment.
 - 4. Provide prefabricated seismic roof curbs or rails for roof mounted equipment except where otherwise indicated on the drawings.
 - 5. Curbs and rails shall be set on the roof structure and shall have a vertical insulation stop equal to the thickness of the roof insulation. (Field verify insulation for each curb and rail.) Install roof curbs and rails level and plumb, in accordance with manufacturer's written instructions. Coordinate with other elements of the work, including installation of roof deck, substrates, vapor barriers, roof insulation, roofing and flashing, as required to insure that the roof system is waterproof and weather tight.
 - a. Anchor curbs and rails securely to supporting structural substrates with bolts or by welding, adequate to withstand lateral and thermal stresses as well as inward and outward loading pressures.
 - b. Secure equipment to roof curbs with cadmium-plated screws or bolts or hardware approved by the Engineer. Install 3/8" thick sponge type gasket on top of curb to seal gaps between equipment and curb, unless otherwise approved by the Engineer.

3.4 LABELING AND IDENTIFYING

- A. Piping Systems: Install pre-printed, color-coded, pipe markers on each system. Include lettering indicating service, and arrows showing normal direction of flow.
1. Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.
 2. Locate pipe markers wherever piping is exposed in finished spaces, machine rooms, accessible maintenance spaces (shafts, tunnels, plenums), and exposed exterior locations as follows:
 - a. Near each valve and control device.
 - b. Near each branch, excluding short take-offs for fixtures and terminal units. Mark each pipe at branch, where flow pattern is not obvious.
 - c. Near locations where pipes pass through walls, floors, ceilings, or enter inaccessible enclosures.
 - d. At access doors, manholes, and similar access points that permit view of concealed piping.
 - e. Near major equipment items and other points of origination and termination.
 - f. Spaced at a maximum of 50-foot (15m) intervals along each run. Reduce intervals to 25 feet (7.5 m) in congested areas of piping and equipment.
 - g. On piping above removable acoustical ceilings, except omit intermediately spaced markers.
 - h.
 3. Pipe markers shall identify piping systems terms indicated and abbreviate only as necessary application length. Pipe marker materials shall be as follows:
 - a. Preformed semi-rigid plastic formed to partially cover circumference of pipe and to attach to pipe with mechanical fasteners that do not penetrate insulation vapor barrier.
 - b. Plastic with pressure-sensitive, permanent-type, self-adhesive back.
 - c. Continuously printed, vinyl tape at least 3 mils thick with pressure-sensitive, permanent-type, self-adhesive back.
 - 1) Width for Markers on Pipes with OD, Including Insulation, Less Than 6 Inches: 3/4 inch minimum.
 - 2) Width for Markers on Pipes with OD, Including Insulation, 6 Inches or Larger: 1-1/2 inches minimum.
- B. Equipment: Install engraved plastic laminate sign or equipment marker on or near each major item of mechanical equipment.
1. Lettering Size: Minimum 1/4-inch (6mm) -high lettering for name of unit where viewing distance is less than 2 feet (0.6 m), 1/2-inch (13mm) -high for distances up to 6 feet (1.8 m), and proportionately larger lettering for greater distances. Provide secondary lettering 2/3 to 3/4 of size of principal lettering.
 2. Text of Signs: Provide text to distinguish between multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to name of identified unit.
 3. Where equipment is hidden above ceilings or behind partitions, provide a label on ceiling grid underneath location of equipment or on access door. Text shall be 3/4" and shall indicate equipment name/type.
- C. Duct Systems: Identify air supply, return, exhaust, intake, and relief ducts with duct markers; or provide stenciled signs and arrows, showing duct system service and direction of flow.

1. Comply with ASME A13.1, "Scheme for the Identification of Piping Systems," for letter size, length of color field, colors, and viewing angles of identification devices for piping.
2. Letter Size: Minimum 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
3. Stenciled Duct Marker Option: Stenciled markers, showing service and direction of flow, may be provided instead of laminated-plastic duct markers, at Installer's option, if lettering larger than 1 inch high is needed for proper identification because of distance from normal location of required identification.
4. Locate markers near points where ducts are exposed or concealed by removable ceiling system, locate signs near points where ducts enter into space and at maximum intervals of 50 feet (15 m).

D. CONTROL DEVICES:

1. Wall Mounted Sensors: Provide label with 1/2" lettering indicating what piece of equipment the sensor controls.

E. VALVE-TAG INSTALLATION

- 1.
2. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; plumbing fixture supply stops; shutoff valves; faucets; convenience and lawn-watering hose connections; and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
3. Tag valves according to size, shape, and color scheme and with captions similar to those indicated with 0.032-inch thick 1-1/2" diameter brass valve tags with brass-breaded chain. Stamp or engrave with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers, with numbering scheme approved by Engineer. Letter color is to be black. Provide 5/32-inch hole for fastener.

- F. Adjusting: Relocate identifying devices which become visually blocked by work of this Division or other Divisions.

3.5 PAINTING AND FINISHING

- A. Damage and Touch Up: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.6 CONCRETE BASES

- A. All concrete equipment bases will be furnished and installed by the contractor for concrete work. It will, however, be the responsibility of this Contractor to provide the concrete contractor with the exact location and size of all bases required after the purchased equipment is known.
- B. All concrete equipment bases shall be furnished and installed by this Contractor. Bases shall be reinforced with 10/10 steel mesh. Edges shall have a 1"-45° chamfer. The top surface shall

have a steel trowel finish. The exact size and location of all bases shall be determined after the purchased equipment is known and prior to pouring the bases.

- C. Bases of insufficient size for the equipment which it was designed to support shall be removed and a new base of adequate size installed.
- D. Construct concrete equipment bases less than 4 inches (100 mm) larger than supported unit in both directions. Follow supported equipment manufacturer's setting templates for anchor bolt and tie locations. Use 3000-psi (20.70MPa), 28-day compressive strength concrete and reinforcement as specified in Division 3 Section "Cast-in-Place Concrete."

3.7 ERECTION OF METAL SUPPORTS AND ANCHORAGE

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor mechanical materials and equipment.
- B. Field Welding: Comply with AWS D1.1 "Structural Welding Code--Steel."

3.8 DEMOLITION

- A. Disconnect, demolish, and remove work specified under Division 23 and as indicated.
- B. Where pipe, ductwork, insulation, or equipment to remain is damaged or disturbed, remove damaged portions and install new products of equal capacity and quality.
- C. Accessible Work: Remove indicated exposed pipe and ductwork in its entirety.
- D. Removal: Remove indicated equipment from the Project site.
- E. Temporary Disconnection: Remove, store, clean, reinstall, reconnect, and make operational equipment indicated for relocation.

3.9 CUTTING AND PATCHING

- A. This Contractor shall sleeve all holes in the new construction for the installation of his work.
- B. This Contractor shall cut all holes in floors, walls, ceiling, and roof necessary for the installation of the work in the existing building, except work shown on the Architectural Wrecking Drawings to be performed by the General Contractor.
- C. The holes for piping shall be cut with a diamond edge core drill. Under no circumstances shall a pneumatic or electric hammer be used to cut holes in walls or floors with the exception of the floor on ground. Saw cutting of concrete slab on grade will not be required; however, the floors shall be scored with a sharp instrument to outline the trench before breaking floor to obtain a fairly straight line trench. Provide watertight receptacle, wedged to bottom of structure, where core drilling occurs; preventing water from staining finishes of floors below.

- D. Before cutting holes in floors and ceilings; make careful field measurements at floor and ceiling to determine location of structural beams, and under no circumstances shall structural beams be cut or damaged during the cutting of these holes.
- E. This Contractor shall coordinate the cutting of existing construction with the (Construction Manager, Owner, General Contractor) and shall obtain approval prior to commencing any demolition work.
- F. The patching of all holes shall be by this Contractor. Where holes are left after removal of pipes or equipment, the openings shall be closed. All plaster ceiling, ceiling tile, floor tile, wall covering, etc. which must be removed in areas which will not receive new finishes under the General Contract Work must be replaced by this Contractor including all necessary painting to match existing colors. If the painted area does not blend into and match the adjacent area of a ceiling panel or wall panel, the entire ceiling or wall panel must be repainted. All such patching and painting shall restore areas to like conditions at time of starting work, subject to the direction and satisfaction of the Architect and Owner. This Contractor shall hire mechanics skilled in their trades to perform all patching work and painting where required. Refer to the Architectural Plans and to the Room Finish Schedules to determine the scope of other Contractors work.
- G. Where holes are left after removal of pipes or plumbing equipment or due to revisions, alteration, changes or errors, the openings shall be closed.
- H. This Contractor shall hire mechanics skilled in their trades to perform all patching such as concrete work, plastering, painting, etc. Such patching shall restore areas to like conditions at time of starting work, and shall be subject to the approval of the Architect.

3.10 CAULKING AND SEALANT

- A. This Contractor shall furnish and install caulking and sealant for all piping passing through fire rated floor structural slab and partition walls. this shall apply to all piping whether concealed in chases, above dropped ceiling areas, or exposed.
- B. A Fire-Stop System equivalent to 3M brand fire protection products as required for the specific application shall be used to seal penetrations of pipes and conduits through fire-rated walls and floors per NEC 300-21, NEC 800-3 (C), and ASTM E-814.
- C. All piping shall be firmly secured prior to installation of putty or caulk. Inspect and clean opening of all loose foreign material prior to the installation of the putty or caulk.
- D. Install caulk or putty as recommended by the manufacturer.

3.11 ACCESS TO EQUIPMENT

- A. All control devices, specialties, etc., shall be so located as to provide for easy access for operation, repair and maintenance; if concealed, access doors shall be provided by this Contractor.
- B. The doors shall be Acudor Products Inc (www.acudor.com) of the following types:

1. Plaster ceilings-----Type "PS5030"
2. Plaster walls-----Type "PS5030"
3. Masonry walls-----Type "UF5000"
4. Gypsum drywall walls-----Type "DW5040"
5. Gypsum drywall ceilings-----Type "DW5040"
6. Gypsum drywall above finished ceiling -----Type "UF5000"

- C. No access doors shall be smaller than 18" x 18".
- D. SPECIAL NOTE: Install "FW5050" "B" labeled access doors in all 1-hour and 2 -hour fire rated walls and ceilings.
- E. Furnish all ceiling panels with a factory applied baked-on off-white enamel finish, and all wall panels with a factory applied prime coat, baked-on enamel finish.
- F. Where valves, control devices, etc., are located above removable ceiling panels, this Contractor shall furnish and install color coded screws or tacks installed in the ceiling tile to identify the location.
- G. All access panels will be installed by the contractor for the installation of the walls or the ceilings in locations designated by this Contractor.
- H. Comparable access panels by CESCO or Milcor will be acceptable.

3.12 SEISMIC RESTRAINTS

- A. The contractor shall furnish and install seismic restraints as indicated in the "Anchorage and Sway Bracing for Mechanical System Components Schedule" on the Drawings and as specified in Section 23 05 49 "Mechanical, Plumbing and Fire Protection Systems Supports, Bracing and Seismic Restraints".

3.13 ROOF PENETRATIONS

- A. Any penetration of the roof shall be provided with a roof curb, pitch pocket, or other appropriate roof penetration apparatus as herein described.
- B. Cutting of the metal decking for all unframed openings is the responsibility of the Contractor requiring the opening. Cutting, patching and flashing of roof shall be the responsibility of the Contractor needing the opening. Roof cutting and patching shall be coordinated with the roof installer. The original roof warranty shall be maintained.
- C. Roof mounted equipment shall be supported on roof curbs.
- D. Piping penetrations shall be made using pipe portals in roof curbs.
- E. When penetrations occur in new roofs, the installation of the roofing materials to the connection and the waterproofing of the roofing at the roof penetration apparatus shall be by the General Contractor. This Contractor shall schedule his work so all roof curbs, etc., are in place when required for installation of roofing.

- F. When penetrations occur in an existing roof, the penetrations shall be made in the presence of the Owner, roof installer or General Contractor. If the penetration reveals any indication of wet or damaged roof, insulation, sub-roof or structure, all roof work by this contractor shall stop and the General Contractor shall be notified in writing as to the conditions found.
- G. At all times during construction, this Contractor shall provide temporary covers, enclosures, etc., required at roof openings to prevent injury to personnel and to prevent outdoor elements (water, wind, etc.) from entering the opening.

3.14 FLASHING:

- A. Provide flexible flashing and metal counter flashing where piping and ductwork penetrate weather or waterproofed walls, floors, and roofs.
- B. Provide acoustical lead flashing around ducts and pipes penetrating equipment rooms, installed in accordance with manufacturer's instructions for sound control where indicated on the drawings.

3.15 GROUTING

- A. Install nonmetallic nonshrink grout for mechanical equipment base bearing surfaces, pump and other equipment base plates, and anchors. Mix grout according to manufacturer's printed instructions.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms for placement of grout, as required.
- D. Avoid air entrapment when placing grout.
- E. Place grout to completely fill equipment bases.
- F. Place grout on concrete bases to provide a smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout according to manufacturer's printed instructions.

END OF SECTION 23 00 50

PART 1 - Copyright 1999, The American Institute of Architects (AIA)

SECTION 23 05 13 - MOTORS

PART 2 - GENERAL

2.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

2.2 SUMMARY

- A. This Section includes basic requirements for factory-installed and field-installed motors.
- B. Related Sections include the following:
- C.
 - 1. Section 23 05 48 "Mechanical Systems Vibration Control" for mounting motors and vibration isolation.
 - 2. Section 23 05 49 "Mechanical Systems, Supports, Bracing and Seismic Requirements".
 - 3. Division 23 Sections for application of motors and reference to specific motor requirements for motor-driven equipment.
 - 4. Section 23 00 00 "Mechanical General Requirements".
 - 5. Section 23 00 50 "Basic Mechanical Materials and Methods".

2.3 DEFINITIONS

- A. Factory-Installed Motor: A motor installed by motorized-equipment manufacturer as a component of equipment.
- B. Field-Installed Motor: A motor installed at Project site and not factory installed as an integral component of motorized equipment.

2.4 SUBMITTALS

- A. Product Data for Field-Installed Motors: For each type and size of motor, provide nameplate data and ratings; shipping, installed, and operating weights; mounting arrangements; size, type, and location of winding terminations; conduit entry and ground lug locations; and information on coatings or finishes.
- B. Shop Drawings for Field-Installed Motors: Dimensioned plans, elevations, sections, and details, including required clearances and service space around equipment. Include the following:
 - 1. Each installed unit's type and details.
 - 2. Nameplate legends.

3. Diagrams of power and control wiring. Provide schematic wiring diagram for each type of motor and for each control scheme.
- C. Coordination Drawings: Floor plans showing dimensioned layout, required working clearances, and required area above and around field-installed motors. Show motor layout, mechanical power transfer link, driven load, and relationship between electrical components and adjacent structural and mechanical elements. Show support locations, type of support, and weight on each support. Indicate field measurements.
 - D. Manufacturer Seismic Qualification Certification: Submit certification that motors, accessories, and components will withstand seismic forces defined in Division 23 Section "Mechanical Supports, Bracing, and Seismic Requirements." Include the following:
 1. Basis of Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - a. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
 2. Dimensioned Outline Drawings of Motorized Equipment: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
 - E. Qualification Data: For testing agency.
 - F. Test Reports: Written reports specified in Parts 2 and 3.
 - G. Operation and Maintenance Data: For field-installed motors to include in emergency, operation, and maintenance manuals.

2.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, with the experience and capability to conduct the testing indicated, as documented according to ASTM E 548.
- B. Source Limitations: Obtain field-installed motors of a single type through one source from a single manufacturer.
- C. Product Options for Field-Installed Motors: Drawings indicate size, profiles, and dimensional requirements of motors and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- E. Comply with NFPA 70.

2.6 PROJECT CONDITIONS

- A. Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
 - 1. Notify Architect at least two days in advance of proposed utility interruptions. Identify extent and duration of utility interruptions.
 - 2. Indicate method of providing temporary utilities.
 - 3. Do not proceed with utility interruptions without Architect's written permission.

2.7 COORDINATION

- A. Coordinate features of motors, installed units, and accessory devices. Provide motors that are:
 - 1. Compatible with the following:
 - a. Magnetic controllers.
 - b. Multispeed controllers.
 - c. Reduced-voltage controllers.
 - 2. Designed and labeled for use with variable frequency controllers, and suitable for use throughout speed range without overheating.
 - 3. Matched to torque and horsepower requirements of the load.
 - 4. Matched to ratings and characteristics of supply circuit and required control sequence.
 - 5. Rated for ambient and environmental conditions of installation location.
- B. Coordinate motor support with requirements for driven load; access for maintenance and motor replacement; installation of accessories, belts, belt guards; and adjustment of sliding rails for belt tensioning.
- C. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 3 Section.

PART 3 - PRODUCTS

3.1 MOTOR REQUIREMENTS

- A. Motor requirements apply to factory-installed and field-installed motors except as follows:
 - 1. Different ratings, performance, or characteristics for a motor are specified in another Section.
 - 2. Manufacturer for a factory-installed motor requires ratings, performance, or characteristics, other than those specified in this Section, to meet performance specified.
- B. Comply with NEMA MG 1 unless otherwise indicated
- C. Comply with IEEE 841 for severe-duty motors.

3.2 MOTOR CHARACTERISTICS

- A. Motors 1/2 HP and Larger: Three phase.
- B. Motors Smaller Than 1/2 HP: Single phase.

- C. Frequency Rating: 60 Hz.
- D. Voltage Rating: NEMA standard voltage selected to operate on nominal circuit voltage to which motor is connected.
- E. Service Factor: 1.15 for open dripproof motors; 1.0 for totally enclosed motors.
- F. Duty: Continuous duty at ambient temperature of 105 deg F and at altitude of 3300 feet above sea level.
- G. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.
- H. Enclosure: Open dripproof.

PART 4 - POLYPHASE MOTORS

- A. Description: NEMA MG 1, Design B, medium induction motor.
- B. Efficiency: Premium efficiency.
- C. Stator: Copper windings, unless otherwise indicated.
 - 1. Multispeed motors shall have separate winding for each speed.
- D. Rotor: Squirrel cage, unless otherwise indicated.
- E. Bearings: Double-shielded, prelubricated ball bearings suitable for radial and thrust loading.
- F. Temperature Rise: Match insulation rating, unless otherwise indicated.
- G. Insulation: Class F, unless otherwise indicated.
- H. Code Letter Designation:
 - 1. Motors 15 HP and Larger: NEMA starting Code F or G.
 - 2. Motors Smaller Than 15 HP: Manufacturer's standard starting characteristic.
- I. Enclosure: Cast iron for motors 7.5 hp and larger; rolled steel for motors smaller than 7.5 hp.
 - 1. Finish: Gray enamel.

4.2 POLYPHASE MOTORS WITH ADDITIONAL REQUIREMENTS

- A. Motors Used with Reduced-Inrush Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.
- B. Motors Used with Variable Frequency Controllers: Ratings, characteristics, and features coordinated with and approved by controller manufacturer.
 - 1. Designed with critical vibration frequencies outside operating range of controller output.
 - 2. Temperature Rise: Matched to rating for Class F insulation.

3. Insulation: Class H.
 4. Thermal Protection: Comply with NEMA MG 1 requirements for thermally protected motors.
 5. Furnish with shaft grounding rings.
- C. Rugged-Duty Motors: Totally enclosed, with 1.25 minimum service factor, greased bearings, integral condensate drains, and capped relief vents. Windings insulated with nonhygroscopic material.
1. Finish: Chemical-resistant paint over corrosion-resistant primer.
- D. Severe-Duty Motors: Comply with IEEE 841, with 1.15 minimum service factor.
- E. Source Quality Control: Perform the following tests on each motor according to NEMA MG 1:
1. Measure winding resistance.
 2. Read no-load current and speed at rated voltage and frequency.
 3. Measure locked rotor current at rated frequency.
 4. Perform high-potential test.

4.3 SINGLE-PHASE MOTORS

- A. Type: One of the following, to suit starting torque and requirements of specific motor application:
1. Permanent-split capacitor.
 2. Split-phase start, capacitor run.
 3. Capacitor start, capacitor run.
- B. Shaded-Pole Motors: For motors 1/20 hp and smaller only.
- C. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range.
- D. Bearings: Ball type for belt-connected motors and other motors with high radial forces on motor shaft; sealed, prelubricated-sleeve type for other single-phase motors.
- E. Source Quality Control: Perform the following tests on each motor according to NEMA MG 1:
1. Measure winding resistance.
 2. Read no-load current and speed at rated voltage and frequency.
 3. Measure locked rotor current at rated frequency.
 4. Perform high-potential test.

PART 5 - EXECUTION

5.1 EXAMINATION

- A. Examine areas to receive field-installed motors for compliance with requirements, installation tolerances, and other conditions affecting performance.

- B. Examine roughing-in of conduit systems to verify actual locations of conduit connections before motor installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

5.2 MOTOR INSTALLATION

- A. Anchor each motor assembly to base, adjustable rails, or other support, arranged and sized according to manufacturer's written instructions. Attach by bolting. Level and align with load transfer link.
- B. Install motors on concrete bases complying with Division 3.
- C. Comply with mounting and anchoring requirements specified in Division 23 Section "Mechanical Supports, Bracing, and Seismic Requirements."

5.3 FIELD QUALITY CONTROL

- A. Prepare for acceptance tests as follows:
 - 1. Run each motor with its controller. Demonstrate correct rotation, alignment, and speed at motor design load.
 - 2. Test interlocks and control features for proper operation.
 - 3. Verify that current in each phase is within nameplate rating.
- B. Testing: Owner will engage a qualified testing agency to perform the following field quality-control testing:
- C. Testing: Engage a qualified testing agency to perform the following field quality-control testing:
- D. Testing: Perform the following field quality-control testing:
 - 1. Perform each electrical test and visual and mechanical inspection stated in NETA ATS, Section 7.15.1. Certify compliance with test parameters.
 - 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
- E. Manufacturer's Field Service: Engage a factory-authorized service representative to perform the following:
 - 1. Inspect field-assembled components, equipment installation, and piping and electrical connections for compliance with requirements.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 3. Verify bearing lubrication.
 - 4. Verify proper motor rotation.
 - 5. Test Reports: Prepare a written report to record the following:
 - a. Test procedures used.
 - b. Test results that comply with requirements.
 - c. Test results that do not comply with requirements and corrective action taken to achieve compliance.

5.4 ADJUSTING

- A. Align motors, bases, shafts, pulleys and belts. Tension belts according to manufacturer's written instructions.

5.5 CLEANING

- A. After completing equipment installation, inspect unit components. Remove paint splatters and other spots, dirt, and debris. Repair damaged finish to match original finish.
- B. Clean motors, on completion of installation, according to manufacturer's written instructions.

END OF SECTION 23 05 13

This page intentionally left blank.

SECTION 23 05 29 - HANGERS AND SUPPORTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes hangers and supports for mechanical system piping and equipment.
- B. Related Sections include the following:
 - 1. Division 5 Section "Metal Fabrications" for materials for attaching hangers and supports to building structure.
 - 2. Section 23 05 48 "Mechanical Systems Vibration Control" for vibration isolation.
 - 3. Section 23 05 49 "Mechanical Supports, Bracing and Seismic Requirements".
 - 4. Section 23 00 00 "Mechanical General Requirements".
 - 5. Section 23 00 50 "Basic Mechanical Materials and Methods".

1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for the Valve and Fittings Industry.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

1.4 PERFORMANCE REQUIREMENTS

- A. Design channel support systems for piping to support multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
- B. Design heavy-duty steel trapezes for piping to support multiple pipes capable of supporting combined weight of supported systems, system contents, and test water.
- C. Design seismic restraint hangers and support for piping and equipment.
- D. Design and obtain approval from authorities having jurisdiction for seismic restraint hangers and supports for piping and equipment.

1.5 SUBMITTALS

- A. Product Data: For each type of pipe hanger, channel support system component, and thermal-hanger shield insert indicated.

- B. Shop Drawings: Signed and sealed by a qualified professional engineer for multiple piping supports and trapeze hangers. Include design calculations and indicate size and characteristics of components and fabrication details.
- C. Welding Certificates: Copies of certificates for welding procedures and operators.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."
- B. Engineering Responsibility: Design and preparation of Shop Drawings and calculations for each multiple pipe support, trapeze, and seismic restraint by a qualified professional engineer.
 - 1. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of hangers and supports that are similar to those indicated for this Project in material, design, and extent.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Pipe Hangers:
 - a. B-Line Systems, Inc.
 - b. Globe Pipe Hanger Products, Inc.
 - c. Grinnell Corp.
 - d. Michigan Hanger Co., Inc.
 - e. National Pipe Hanger Corp.
 - 2. Channel Support Systems:
 - a. B-Line Systems, Inc.
 - b. Grinnell Corp.; Power-Strut Unit.
 - c. Michigan Hanger Co., Inc.; O-Strut Div.
 - d. National Pipe Hanger Corp.
 - e. Unistrut Corp.
 - 3. Thermal-Hanger Shield Inserts:
 - a. Michigan Hanger Co., Inc.
 - b. Pipe Shields, Inc.

2.2 MANUFACTURED UNITS

- A. Pipe Hangers, Supports, and Components: MSS SP-58, factory-fabricated components. Refer to "Hanger and Support Applications" Article in Part 3 for where to use specific hanger and support types.

1. Galvanized, Metallic Coatings: For piping and equipment that will not have field-applied finish.
 2. Nonmetallic Coatings: On attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- B. Channel Support Systems: MFMA-2, factory-fabricated components for field assembly.
1. Coatings: Manufacturer's standard finish, unless bare metal surfaces are indicated.
 2. Nonmetallic Coatings: On attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- C. Thermal-Hanger Shield Inserts: 100-psi minimum compressive-strength insulation, encased in sheet metal shield.
1. Material for Cold Piping: ASTM C 552, Type I cellular glass with vapor barrier.
 2. Material for Hot Piping: ASTM C 552, Type I cellular glass.
 3. For Trapeze or Clamped System: Insert and shield cover entire circumference of pipe.
 4. For Clevis or Band Hanger: Insert and shield cover lower 180 degrees of pipe.
 5. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

2.3 MISCELLANEOUS MATERIALS

- A. Mechanical-Anchor Fasteners: Insert-type attachments with pull-out and shear capacities appropriate for supported loads and building materials where used.
- B. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars, black and galvanized.
- C. Grout: ASTM C 1107, Grade B, factory-mixed and -packaged, nonshrink and nonmetallic, dry, hydraulic-cement grout.
1. Characteristics: Post hardening and volume adjusting; recommended for both interior and exterior applications.
 2. Properties: Nonstaining, noncorrosive, and nongaseous.
 3. Design Mix: 5000-psi, 28-day compressive strength.

PART 3 - EXECUTION

3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger requirements are specified in Sections specifying equipment and systems.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Specification Sections.
- C. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Adjustable Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 2-1/2 to NPS 30. Provide Plastic coated hangers for hot piping.

2. Adjustable Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 2. provide plastic coated hangers for hot piping.
 3. Adjustable Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 2.
 4. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes, NPS 2-1/2 to NPS 36, if vertical adjustment is required, with steel pipe base stanchion support and cast-iron floor flange.
 5. Single Pipe Rolls (MSS Type 41): For suspension of pipes, NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
 6. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes, NPS 2-1/2 to NPS 20, from single rod if horizontal movement caused by expansion and contraction might occur.
 7. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes, NPS 2 to NPS 30, if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- D. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
 2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.
- E. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
 2. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
 3. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
- F. Building Attachments: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
 2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
 3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
 4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
 5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
 6. C-Clamps (MSS Type 23): For structural shapes.
 7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
 8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
 9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
 10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.

11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
 12. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
 13. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
 14. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where head room is limited.
- G. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Steel Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
 2. Protection Shields (MSS Type 40): Of length recommended by manufacturer to prevent crushing insulation.
 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe, 360-degree insert of high-density, 100-psi minimum compressive-strength, water-repellent-treated calcium silicate or cellular-glass pipe insulation, same thickness as adjoining insulation with vapor barrier and encased in 360-degree sheet metal shield.
- H. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Specification Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from hanger.
 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from base support.
 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from trapeze support.
 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
 - a. Horizontal (MSS Type 54): Mounted horizontally.
 - b. Vertical (MSS Type 55): Mounted vertically.
 - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.

3.2 HANGER AND SUPPORT INSTALLATION

- A. Pipe Hanger and Support Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.

- B. Channel Support System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled channel systems.
 - 1. Field assemble and install according to manufacturer's written instructions.
- C. Heavy-Duty Steel Trapeze Installation: Arrange for grouping of parallel runs of horizontal piping and support together on field-fabricated, heavy-duty trapezes.
 - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified above for individual pipe hangers.
 - 2. Field fabricate from ASTM A 36/A 36M, steel shapes selected for loads being supported. Weld steel according to AWS D-1.1.
- D. Install building attachments within concrete slabs or attach to structural steel. Space attachments within maximum piping span length indicated in MSS SP-69. Install additional attachments at concentrated loads, including valves, flanges, guides, strainers, and expansion joints, and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- E. Install mechanical-anchor fasteners in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions.
- F. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.
- G. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- H. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- I. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and so maximum pipe deflections allowed by ASME B31.9, "Building Services Piping," is not exceeded.
- J. Insulated Piping: Comply with the following:
 - 1. Attach clamps and spacers to piping.
 - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
 - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
 - c. Do not exceed pipe stress limits according to ASME B31.9.
 - 2. Install MSS SP-58, Type 39 protection saddles, if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
 - 3. Install MSS SP-58, Type 40 protective shields on cold piping with vapor barrier. Shields shall span arc of 180 degrees.
 - 4. Shield Dimensions for Pipe: Not less than the following:
 - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
 - b. NPS 4: 12 inches long and 0.06 inch thick.
 - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
 - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
 - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.

5. Pipes NPS 8 and Larger: Include wood inserts.
6. Insert Material: Length at least as long as protective shield.
7. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure above or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.

3.4 METAL FABRICATION

- A. Cut, drill, and fit miscellaneous metal fabrications for heavy-duty steel trapezes and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field-weld connections that cannot be shop-welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1 procedures for shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work, and with the following:
 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
 2. Obtain fusion without undercut or overlap.
 3. Remove welding flux immediately.
 4. Finish welds at exposed connections so no roughness shows after finishing and contours of welded surfaces match adjacent contours.

3.5 ADJUSTING

- A. Hanger Adjustment: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.

3.6 PAINTING

- A. Touching Up: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 9 Section "Painting."
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 23 05 29

This page intentionally left blank.

SECTION 23 05 48

MECHANICAL SYSTEMS VIBRATION CONTROL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. Related Technical Specifications:
 - 1. Section 23 05 29 – Hangers and Supports.
 - 2. Section 23 05 49 – System Supports, Bracing and Seismic Restraints.
 - 3. Section 23 00 50 “Basic Mechanical Materials and Methods.”
 - 4. Other applicable Sections of Division 23 – Mechanical.

1.2 SUMMARY

- A. This Section includes furnishing and installing the following, as specified herein and shown on the Drawings:
 - 1. Elastomeric isolation pads and mounts.
 - 2. Restrained elastomeric isolation mounts.
 - 3. Freestanding and restrained spring isolators.
 - 4. Housed spring mounts.
 - 5. Elastomeric hangers.
 - 6. Spring hangers.
 - 7. Spring hangers with vertical-limit stops.
 - 8. Thrust limits.
 - 9. Pipe riser resilient supports.
 - 10. Resilient pipe guides.

1.3 DEFINITIONS

- A. IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.

1.4 PERFORMANCE REQUIREMENTS

- A. Component Amplification Factor: Refer to ASCE 7-05 “Minimum Design Loads for Buildings and Other Structures, Table 13.6-1.
- B. Component Amplification Factor: Refer to ASCE 7-10 “Minimum Design Loads for Buildings and Other Structures, Table 12.2-1.

1.5 SUBMITTALS

- A. Product Data: Include load deflection curves for each vibration isolation device.
- B. Shop Drawings: Signed and sealed by a qualified, registered professional engineer. Include the following, at a minimum:
 - 1. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
 - 2. Riser Supports: Include riser diagrams and calculations showing anticipated expansion and contraction at each support point, initial and final loads on building structure, spring deflection changes, and seismic loads. Include certification that riser system has been examined for excessive stress and that none will exist.
 - 3. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, base weights, equipment static loads, power transmission, component misalignment, and cantilever loads.
 - 4. Submittals for Interlocking Snubbers: Include load deflection curves up to 1/2-inch deflection in x, y, and z planes.
- C. Welding certificates.
- D. Manufacturer Seismic Qualification Certification: Submit certification that all specified equipment will withstand seismic forces identified in "Performance Requirements" Article above. Include the following:
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculations.
 - a. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

1.6 QUALITY ASSURANCE

- A. Vibration isolation devices shall have been subjected to horizontal and vertical load testing and analysis acceptable to authorities having jurisdiction, showing maximum ratings. Ratings based on independent testing are preferred to ratings based on calculations. Calculations (including combining shear and tensile loads) to support vibration isolation designs must be signed and sealed by a qualified professional engineer. Testing and calculations must include both shear and tensile loads and one test or analysis at 45 degrees to the weakest mode.
- B. Welding: Qualify procedures and personnel according to AWS D1.1, "Structural Welding Code--Steel."

1.7 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into base. Concrete, reinforcement, and formwork requirements are specified in Division 3 of this Specification.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the manufacturers named below for each different product category.

2.2 VIBRATION ISOLATORS

- A. Acceptable Manufacturers:
 - 1. Ace Mounting Co., Inc.
 - 2. Amber/Booth Company, Inc.
 - 3. B-Line Systems, Inc.
 - 4. Isolation Technology, Inc.
 - 5. Vibration Mountings & Controls/Korfund.
 - 6. Mason Industries.
 - 7. Vibro-Acoustics
- B. Elastomeric Mounts (ASHRAE TYPE 2): Double-deflection type, with molded, oil-resistant rubber or neoprene isolator elements with factory-drilled, encapsulated top plate for bolting to equipment and with baseplate for bolting to structure. Color-code or otherwise identify to indicate capacity range.
- C. Spring Isolators (ASHRAE TYPE 3): Freestanding, laterally stable, open-spring isolators.
 - 1. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 - 2. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 - 3. Lateral Stiffness: More than 80 percent of the rated vertical stiffness.
 - 4. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 - 5. Base plates: Factory drilled for bolting to structure and bonded to 1/4-inch-thick, rubber isolator pad attached to baseplate underside. Base plates shall limit floor load to 100 psig.
 - 6. Top Plate and Adjustment Bolt: Threaded top plate with adjustment bolt and cap screw to fasten and level equipment.
- D. Restrained Spring Isolators(ASHRAE TYPE 4): Freestanding, steel, open-spring isolators with seismic restraint.
 - 1. Housing: Steel with resilient vertical-limit stops to prevent spring extension due to wind loads or if weight is removed; factory-drilled baseplate bonded to 1/4-inch-thick, elastomeric isolator pad attached to baseplate underside; and adjustable equipment mounting and leveling bolt that acts as blocking during installation.

2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 4. Lateral Stiffness: More than 80 percent of the rated vertical stiffness.
 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
- E. Spring Hangers(AHRAE TYPE 3): Combination coil-spring and elastomeric-insert hanger with spring and insert in compression.
1. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 4. Lateral Stiffness: More than 80 percent of the rated vertical stiffness.
 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
- F. Spring Hangers with Vertical-Limit Stop(ASHRAE TYPE 3): Combination coil-spring and elastomeric-insert hanger with spring and insert in compression and with a vertical-limit stop.
1. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
 4. Lateral Stiffness: More than 80 percent of the rated vertical stiffness.
 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
 7. Adjustable Vertical Stop: Steel washer with neoprene washer "up-stop" on lower threaded rod.
- G. Thrust Limits (ASHRAE TYPE 5): Combination coil spring and elastomeric insert with spring and insert in compression and with a load stop. Include rod and angle-iron brackets for attaching to equipment.
1. Frame: Steel, fabricated for connection to threaded rods and to allow for a maximum of 30 degrees of angular rod misalignment without binding or reducing isolation efficiency.
 2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
 3. Minimum Additional Travel: 50 percent of required deflection at rated load.
 4. Lateral Stiffness: More than 80 percent of the rated vertical stiffness.
 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
 6. Elastomeric Element: Molded, oil-resistant rubber or neoprene.
 7. Coil Spring: Factory set and field adjustable for a maximum of 1/4-inch movement at start and stop.

- H. Pipe Riser Resilient Support: All-directional, acoustical pipe anchor consisting of 2 steel tubes separated by a minimum of 1/2-inch-thick, 60-durometer neoprene. Include steel and neoprene vertical-limit stops arranged to prevent vertical travel in both directions. Design support for a maximum load on the isolation material of 500 psig and for equal resistance in all directions.
- I. Resilient Pipe Guides: Telescopic arrangement of 2 steel tubes separated by a minimum of 1/2-inch-thick, 60-durometer neoprene. Factory set guide height with a shear pin to allow vertical motion due to pipe expansion and contraction. Shear pin shall be removable and re-insertable to allow for selection of pipe movement. Guides shall be capable of motion to meet location requirements.

2.3 FACTORY FINISHES

- A. Manufacturer's standard prime-coat finish ready for field painting.
- B. Finish: Manufacturer's standard paint applied to factory-assembled and -tested equipment before shipping.
 - 1. Powder coating on springs and housings.
 - 2. All hardware shall be electro-galvanized. Hot-dip galvanized metal components for exterior use.
 - 3. Baked enamel for metal components on isolators for interior use.
 - 4. Color-code or otherwise mark vibration isolation and seismic-control devices to indicate capacity range.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation and seismic-control devices for compliance with requirements, installation tolerances, and other conditions affecting performance.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install thrust limits at centerline of thrust, symmetrical on either side of equipment.
- B. Install steel angles or channel, sized to prevent buckling, clamped with ductile-iron clamps to hanger rods for trapeze and individual pipe hangers. At trapeze anchor locations, shackle piping to trapeze. Requirements apply equally to hanging equipment. Do not weld angles to rods.
- C. Install resilient bolt isolation washers on equipment anchor bolts.

3.3 EQUIPMENT BASES

- A. Concrete Bases: Anchor equipment to concrete base according to supported equipment manufacturer's written instructions for vibration isolation at Project site.
 - 1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of the base.
 - 2. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base and anchor into structural concrete floor.
 - 3. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - 5. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
 - 6. Cast-in-place concrete materials and placement requirements are specified in Section 03300 of this Specification.

3.4 FIELD QUALITY CONTROL TESTS

- A. Testing: Perform the following field quality-control testing:
 - 1. Isolator clearance.
 - 2. Isolator deflection.

3.5 ADJUSTING

- A. Adjust isolators after piping systems have been filled and equipment is at operating weight.
- B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- C. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop.
- D. Adjust active height of spring isolators.

3.6 CLEANING

- A. After completing equipment installation, inspect vibration isolation / control devices. Remove paint splatters and other spots, dirt, and debris.

END OF SECTION 23 05 48

SECTION 23 05 49

MECHANICAL SYSTEMS

SUPPORTS, BRACING AND SEISMIC RESTRAINTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. 2010 ASCE (American Society of Civil Engineers) 7 – Minimum Design Loads for Buildings and Other Structures.
- C. SMACNA Seismic Restraint Manual Guidelines for Mechanical Systems (latest edition).
- D. International Code Council (ICC) Evaluation Service Program-provided seismic restraint, anchorage, and only bracing guidelines and details (latest editions).
- E. Office of Statewide Health Planning and Development published seismic restraint manuals, guidelines and details (latest editions).

1.2 SUMMARY

- A. This Section includes designing, furnishing, and installing the following:
 - 1. Hangers and supports for mechanical (HVAC or process) and plumbing or fire protection equipment and systems.
 - 2. Seismic restraints for mechanical (HVAC or process) and plumbing or fire protection equipment and systems.
 - 3. Concrete bases for mechanical, plumbing or fire protection equipment.

1.3 DEFINITIONS

- A. ASTM: American Society for Testing and Materials
- B. AWS: American Welding Society
- C. IBC: International Building Code (2015 IBC).
- D. ICC: International Code Council.

- E. MFMA: Metal Framing Manufacturer's Association.
- F. MSS: Manufacturer's Standardization Society.
- G. NBC: National Building Code (latest edition).
- H. NFPA: National Fire Protection Association.
- I. OSHPD: Office of Statewide Health Planning and Development.
- J. SBC: Standard Building Code (latest edition).
- K. Seismic Restraint: A structural support element (such as a metal framing member, a cable, an anchor bolt or stud, a fastening device, or an assembly of these items) used to transfer seismic forces from an item of equipment or system to a building structural element and/or to limit movement of such item during a seismic event.
- L. SMACNA: Sheet Metal and Air Conditioning Contractor's National Association.
- M. UBC: Uniform Building Code (latest edition).

1.4 SUBMITTALS

- A. Product Data submitted shall illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of electrical support or seismic-restraint component used:
 - 1. Tabulate types, sizes and points of application of all seismic restraints, anchorages, sway bracing and other support elements to be used complete with report on numbers and rated strength in tension and shear, as evaluated by an agency acceptable to authorities having jurisdiction.
 - 2. Annotate to indicate application point of each product submitted and to document compliance with requirements.
- B. Shop Drawings submitted shall indicate materials and dimensions as well as identify hardware, (including attachment and anchorage devices), identify seismic support locations, all signed and sealed by a qualified registered professional engineer. Professional engineer qualification requirements are specified in Division 1 of this Specification include the following, as a minimum:
 - 1. Fabricated Supports: Representations of field-fabricated supports for all required locations.
 - 2. Seismic Restraints: Detailing anchorage bracing, and location. Include the following:
 - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads. Include location of designed restraint.
 - b. Details: Fabrication and arrangement, as well as attachments of restraints to the restrained items and to the structure shall be detailed. Show attachment locations,

- methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events.
- c. Pre-approval and Evaluation Documentation from by an agency acceptable to authorities having jurisdiction shall be submitted, showing maximum ratings of restraint items and the basis for approval (tests or calculations).
 - d. Location: Identify by tables or drawings all required seismic restraint locations and associated restraints for this Project.
3. Contractor is hereby cautioned that the design of the anchorages, sway bracing, seismic restraints, and other support elements required to be completed under this Section of this Specification by a qualified, registered professional engineer may NOT be accomplished solely by means of general references to published design manuals, tables, standard details, or other such references from Accepted Engineering Practice documents. However, incorporating such information, tables, details, or other published reference material directly into the specific design of such anchorages, sway bracing, seismic restraints, and other support elements required to be completed under this Section of this Specification (that will ultimately be signed and sealed by the registered professional engineer prior to submittal) is permissible.
- C. Coordination Drawings shall show coordination of seismic bracing for mechanical, plumbing and fire protection components with other systems and equipment in the vicinity, including other supports and seismic restraints.
 - D. Welding certificates shall be submitted, as appropriate.
 - E. Qualification Data for registered professional design engineer and testing agency shall be submitted.
 - F. Field quality-control test reports shall be submitted.

1.5 QUALITY ASSURANCE

- A. Comply with seismic-restraint requirements in the IBC, unless requirements in these Contract Documents are more stringent.
- B. Testing of Seismic Anchorage Devices: Comply with testing requirements in Part 3 of this Specification Section.
- C. Welding: Qualify welding procedures and welding personnel capabilities according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Seismic restraint devices shall have been subjected to both horizontal and vertical load testing and analysis acceptable to authorities having jurisdiction, showing maximum seismic restraint ratings.

Ratings based on independent testing are preferred to ratings based on calculations. Testing and/or calculations must include both shear and tensile loads (including combined shear and tensile loads), and one test or analysis at 45 degrees to the weakest mode.

1.6 PROJECT CONDITIONS

- A. See Table(s) on Contract Drawings for specific project conditions.
- B. Site Class = D.
- C. Spectral Response Factors: See Structural Drawings

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists of acceptable manufacturers, the following requirements apply to product selection:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified or Engineer-approved equal.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed on mechanical and plumbing system components for this Project, with a minimum structural safety factor of five (5) times the applied force.
- B. Steel Slotted Support Systems shall comply with MFMA-3, factory-fabricated components for field assembly.
 - 1. Acceptable Manufacturers:
 - a. Cooper B-Line; a division of Cooper Industries.
 - b. ERICO International Corporation.
 - c. Allied Support Systems; Power-Strut Unit.
 - d. GS Metals Corp.
 - e. Michigan Hanger Co., Inc.; O-Strut Div.
 - f. National Pipe Hanger Corp.
 - g. Thomas & Betts Corporation.
 - h. Unistrut; Tyco International, Ltd.
 - i. Wesanco, Inc.
 - j. Engineer-approved equal.
 - 2. Finishes:
 - a. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-3.
 - b. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-3.
 - 3. Channel Dimension shall be selected for structural loading condition and applicable seismic forces.

- C. Raceway and Cable Tray Support shall be as described in the IBC and ASCE 7 documents.
- D. Conduit and Cable Support Device shall be steel hangers, clamps, and associated fittings, specifically designed for the types and sizes of raceway or pipe to be supported.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Requirements for items for fastening mechanical or plumbing items or their supports to building surfaces shall include the following:
 - 1. Verify suitability of all fasteners for use with lightweight concrete or concrete slabs less than 4 inches thick.
 - 2. Powder-Actuated Fasteners shall be threaded-steel stud, for use in hardened portland cement concrete, steel, or wood; with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 - a. Acceptable Manufacturers:
 - 1) Hilti, Inc.
 - 2) ITW Construction Products.
 - 3) MKT Fastening, LLC.
 - 4) Simpson Strong-Tie Co. Inc.
 - 5) Engineer-approved equal.
 - 3. Mechanical-Expansion Anchors shall be insert-wedge-type, stainless steel, for use in hardened portland cement concrete; with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
 - a. Acceptable Manufacturers:
 - 1) Cooper B-Line; a division of Cooper Industries.
 - 2) Empire Tool and Manufacturing Co., Inc
 - 3) Hilti, Inc.
 - 4) ITW Construction Products.
 - 5) MKT Fastening, LLC.
 - 6) Powers Fasteners.
 - 7) Engineer-approved equal.
 - 4. Concrete Inserts shall be steel or malleable-iron slotted-support-system units similar to MSS Type 18; complying with MFMA-3 or MSS SP-58.
 - 5. Clamps for Attachment to Steel Structural Elements shall conform to MSS SP-58, type suitable for attached structural element.
 - 6. Through Bolts shall be structural type, hex head, high-strength. Comply with ASTM A 325.
 - 7. Toggle Bolts shall be all-steel springhead type.
 - 8. Hanger Rods shall be threaded steel.

2.3 SEISMIC RESTRAINT COMPONENTS

- A. Manufacturers:
1. Amber/Booth Company, Inc.
 2. B-Line Systems, Inc.
 3. California Dynamics Corp.
 4. Kinetics Noise Control, Inc.
 5. Loos & Co., Inc.; Cableware Technology Division.
 6. Mason Industries, Inc.
 7. Unistrut Diversified Products Co.; Wayne Manufacturing Division.
 8. Vibration Eliminator Co., Inc.
 9. Vibration Isolation Co., Inc.
 10. Vibration Mountings & Controls/Korfund.
- B. Rated Strength, Features, and Application Requirements for Restraint Components shall be as defined by an agency acceptable to authorities having jurisdiction.
1. Structural Safety Factor: Strength in tension, shear, and pullout force of components used shall be at least five (5) times the maximum seismic forces to which they will be subjected.
- C. Angle and Channel-Type Brace Assemblies: Steel angles or steel slotted-support-system components; with accessories for attachment to braced component at one end and to building structure at the other end.
- D. Cable Restraints: ASTM A 603, zinc-coated, steel wire rope attached to steel or stainless-steel thimbles, brackets, swivels, and bolts designed for restraining cable service.
- E. Seismic Mountings, Anchors, and Attachments: For this application, items shall be selected to resist seismic forces.
1. Hanger Rod Stiffeners shall be steel tube or steel slotted-support-system sleeves with internally bolted connections or reinforcing steel angle clamped to hanger rod, of design recognized by an agency acceptable to authorities having jurisdiction.
 2. Bushings for Floor-Mounted Equipment Anchors shall be neoprene units designed for seismically rated rigid equipment mountings, and matched to type and size of anchor bolts and studs used.
 3. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves shall be designed for seismically-rated rigid equipment mountings, and matched to type and size of attachment devices used.
- F. Seismic Snubbers: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.
1. Anchor bolts for attaching to concrete shall be seismic-rated, drill-in, and stud-wedge or female-wedge type.
 2. Resilient Isolation Washers and Bushings: 1-piece, molded, bridge-bearing neoprene complying with AASHTO M 251 and having a durometer of 50, plus or minus 5.

2.4 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

PART 3 - EXECUTION

3.1 GENERAL REQUIREMENTS

- A. Comply with IBC for specific application requirements for hangers and supports for mechanical and plumbing equipment and systems, except if requirements in these Contract Documents are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway or Pipes: Space supports as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.
- C. Multiple Raceways or Pipes: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits; and:
 - 1. Secure raceways and pipes to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.
 - 2. Secure raceways and pipes to these supports with two-bolt pipe clamps.
- D. Spring-steel clamps designed for supporting single pipes without bolts may be used for 1-1/2-inch and smaller raceways, and for fastening raceways to trapeze supports.
- E. Install all supports, restraints, attachments, and other elements specified in this Section of this Specification in strict conformance with the written installation requirements of the manufacturers of each support, restraint, attachment, or other element.

3.2 SUPPORT AND SEISMIC RESTRAINT INSTALLATION

- A. Comply with SMACNA and MSS for installation requirements, except as otherwise specified in this Article of this Section of this Specification.
- B. Install seismic restraint components using methods approved by the evaluation service providing required submittals for component.
- C. Strength of Support and Seismic Restraint Assemblies: Where not otherwise indicated, select sizes of components so that strength will be adequate to carry present and future static and seismic loads within specified loading limits. Minimum static design load used for strength determination shall be the weight of the supported components plus 200 lb.
- D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten mechanical and plumbing items and their supports to building structural elements by the following methods, unless otherwise indicated by code:

1. To Wood: Fasten with lag screws or through bolts.
2. To New Concrete: Bolt to concrete inserts.
3. To Masonry: Use approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
4. To Existing Concrete: Fasten with expansion anchors.
5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inchesthick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inchesthick.
6. To Steel: Use welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts or beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69 or Spring-tension clamps.
7. To Light Steel: Use sheet metal screws.
8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount such devices on slotted-channel racks attached to substrate by means that meet seismic restraint strength and anchorage requirements.

- E. Drill holes for expansion anchors in reinforced concrete at locations and to depths that avoid reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
- B. Field Welding: Comply with AWS D1.1/D1.1M.

3.4 CONCRETE BASES

- A. Concrete Bases: Anchor equipment to concrete base according to equipment manufacturer's written instructions and seismic requirements for Project.
- B. Construct concrete bases of dimensions indicated but not less than 4 incheslarger in both directions than supported unit, and such that expansion anchors will be a minimum of 10 bolt diameters from edge of the base; and:
1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inchcenters around full perimeter of the base.
 2. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base, and anchor into structural concrete floor.
 3. Place and secure anchorage devices using the equipment to be supported manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 4. Install anchor bolts to elevations required for proper attachment to supported equipment.
 5. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
 6. Use 3000-psi 28-day compressive-strength concrete, minimum.

3.5 INSTALLATION OF SEISMIC RESTRAINT COMPONENTS

- A. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolt and mounting hole in concrete base.
- B. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- C. Restraint Cables shall be installed with slack within maximum tolerance recommended by cable manufacturer.
- D. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, upper truss chords of bar joists, or at concrete members.

3.6 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Make flexible connections in runs of raceways and piping where they cross expansion and seismic control joints, where adjacent sections or branches are supported by different structural elements, and where they terminate with connection to mechanical and plumbing equipment that is anchored to a different structural element from the one supporting them as they approach equipment.

3.7 FIELD QUALITY CONTROL TESTS

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections and prepare test reports.
- B. Record test results and submit to Engineer.
- C. Test pullout resistance of seismic anchorage devices, and:
 - 1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
 - 2. Schedule test with Owner and Engineer present before connecting anchorage devices to components to be restrained (unless post-connection testing has been approved by Engineer in advance). Provide at least 7 days advance notice of scheduled test.
 - 3. Obtain Engineer's concurrence before transferring test loads to structure. Provide temporary load-spreading members.
 - 4. Test at least four of each type and size of installed anchorages and fasteners.
 - 5. Test anchorages and fasteners to 90 percent of rated proof load of item.
 - 6. If any item fails test, modify all installations of same type for project, then retest item until satisfactory test result is achieved.

3.8 PAINTING AND FINISHING

- A. Refer to Section 09900 – Protective Coatings of this Specification for field painting requirements.

- B. Damage and Touch-Up: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

3.9 CUTTING AND PATCHING

- A. Cut, channel, chase, and drill floors, walls, partitions, ceilings, and other surfaces necessary for mechanical installations. Perform cutting by skilled mechanics of the trades involved.
- B. Repair cut surfaces to match adjacent surfaces.

3.10 GROUTING

- A. Install non-metallic, non-shrink grout for mechanical equipment base bearing surfaces, pump and other equipment base plates and anchors. Mix grout according to manufacturer's printed instructions.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms for placement of grout, as required.
- D. Avoid air entrapment when placing grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases to provide a smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout according to manufacturer's printed instructions.

3.11 ERECTION OF WOOD SUPPORTS AND ANCHORAGE

- A. Cut, fit, and place wood grounds, nailers, blocking, and anchorage to support and anchor mechanical materials and equipment.
- B. Select fastener sizes that will not penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood members.
- C. Attach to substrates as required to support applied loads.

END OF SECTION 23 05 49

SECTION 23 05 93 - TESTING, ADJUSTING, AND BALANCING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes TAB to produce design objectives for the following:
 - 1. Air Systems:
 - a. Constant-volume air systems.
 - 2. Testing, Adjusting, and Balancing Equipment:
 - a. Motors.
 - b. Condensing units.
 - c. Heat-transfer coils.
 - 3. HVAC equipment quantitative-performance settings.
 - 4. Kitchen hood airflow balancing.
 - 5. Vibration measuring.
 - 6. Verifying that automatic control devices are functioning properly.
 - 7. Reporting results of activities and procedures specified in this Section.
- B. Related sections include the following:
 - 1. Section 23 00 00 "Mechanical General Requirements".
 - 2. Section 23 00 50 "Basic Mechanical Materials and Methods".

1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. Adjust: To regulate fluid flow rate and air patterns at the terminal equipment, such as to reduce fan speed or adjust a damper.
- C. Balance: To proportion flows within the distribution system, including submains, branches, and terminals, according to indicated quantities.
- D. Barrier or Boundary: Construction, either vertical or horizontal, such as walls, floors, and ceilings that are designed and constructed to restrict the movement of airflow, smoke, odors, and other pollutants.
- E. BAS: Building automation systems.

- F. Draft: A current of air, when referring to localized effect caused by one or more factors of high air velocity, low ambient temperature, or direction of airflow, whereby more heat is withdrawn from a person's skin than is normally dissipated.
- G. NC: Noise criteria.
- H. NEBB: National Environmental Balancing Bureau.
- I. Procedure: An approach to and execution of a sequence of work operations to yield repeatable results.
- J. RC: Room criteria.
- K. Report Forms: Test data sheets for recording test data in logical order.
- L. System Effect: A phenomenon that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
- M. System Effect Factors: Allowances used to calculate a reduction of the performance ratings of a fan when installed under conditions different from those presented when the fan was performance tested.
- N. TAB: Testing, adjusting, and balancing.
- O. TABB: Testing, Adjusting, and Balancing Bureau.
- P. TAB Specialist: An independent entity meeting qualifications to perform TAB work.
- Q. TDH: Total dynamic head.

- R. Terminal: A point where the controlled medium, such as fluid or energy, enters or leaves the distribution system.
- S. Test: A procedure to determine quantitative performance of systems or equipment.
- T. Testing, Adjusting, and Balancing (TAB) Firm: The entity responsible for performing and reporting TAB procedures.

1.4 SUBMITTALS

- A. Qualification Data: Within 30 days from Contractor's Notice to Proceed, submit 4 copies of evidence that TAB firm and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article.
- B. Contract Documents Examination Report: Within 45 days from Contractor's Notice to Proceed, submit 4 copies of the Contract Documents review report as specified in Part 3.

- C. Strategies and Procedures Plan: Within 60 days from Contractor's Notice to Proceed, submit 4 copies of TAB strategies and step-by-step procedures as specified in Part 3 "Preparation" Article. Include a complete set of report forms intended for use on this Project.
- D. Certified TAB Reports: Submit two copies of reports prepared, as specified in this Section, on approved forms certified by TAB firm.
- E. Sample Report Forms: Submit two sets of sample TAB report forms.
- F. Warranties specified in this Section.

1.5 QUALITY ASSURANCE

- A. TAB Firm Qualifications: Engage a TAB firm certified by AABC.
- B. TAB Conference: Meet with Owner's and Architect's representatives on approval of TAB strategies and procedures plan to develop a mutual understanding of the details. Ensure the participation of TAB team members, equipment manufacturers' authorized service representatives, HVAC controls installers, and other support personnel. Provide seven days' advance notice of scheduled meeting time and location.
 - 1. Agenda Items: Include at least the following:
 - a. Submittal distribution requirements.
 - b. The Contract Documents examination report.
 - c. TAB plan.
 - d. Work schedule and Project-site access requirements.
 - e. Coordination and cooperation of trades and subcontractors.
 - f. Coordination of documentation and communication flow.
- C. Certification of TAB Reports: Certify TAB field data reports. This certification includes the following:
 - 1. Review field data reports to validate accuracy of data and to prepare certified TAB reports.
 - 2. Certify that TAB team complied with approved TAB plan and the procedures specified and referenced in this Specification.
- D. TAB Report Forms: Use standard forms from AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems.
- E. Instrumentation Type, Quantity, and Accuracy: As described in AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems.
- F. Instrumentation Calibration: Calibrate instruments at least every six months or more frequently if required by instrument manufacturer.
 - 1. Keep an updated record of instrument calibration that indicates date of calibration and the name of party performing instrument calibration.

1.6 PROJECT CONDITIONS

- A. Full Owner Occupancy: Owner will occupy the site and existing building during entire TAB period. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

1.7 COORDINATION

- A. Coordinate the efforts of factory-authorized service representatives for systems and equipment, HVAC controls installers, and other mechanics to operate HVAC systems and equipment to support and assist TAB activities.
- B. Notice: Provide seven days' advance notice for each test. Include scheduled test dates and times.
- C. Perform TAB after leakage and pressure tests on air and water distribution systems have been satisfactorily completed.

1.8 WARRANTY

- A. National Project Performance Guarantee: Provide a guarantee on AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems" forms stating that AABC will assist in completing requirements of the Contract Documents if TAB firm fails to comply with the Contract Documents. Guarantee includes the following provisions:
 - 1. The certified TAB firm has tested and balanced systems according to the Contract Documents.
 - 2. Systems are balanced to optimum performance capabilities within design and installation limits.

PART 2 - PRODUCTS (Not Applicable)

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems' designs that may preclude proper TAB of systems and equipment.
 - 1. Contract Documents are defined in the General and Supplementary Conditions of Contract.
 - 2. Verify that balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers, are required by the Contract Documents. Verify that quantities and locations of these balancing devices are accessible and appropriate for effective balancing and for efficient system and equipment operation.
- B. Examine approved submittal data of HVAC systems and equipment.

- C. Examine Project Record Documents described in Division 1 Section "Project Record Documents."
- D. Examine design data, including HVAC system descriptions, statements of design assumptions for environmental conditions and systems' output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine equipment performance data including fan and pump curves. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system. Calculate system effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from those presented when the equipment was performance tested at the factory. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," Sections 7 through 10; or in SMACNA's "HVAC Systems--Duct Design," Sections 5 and 6. Compare this data with the design data and installed conditions.
- F. Examine system and equipment installations to verify that they are complete and that testing, cleaning, adjusting, and commissioning specified in individual Sections have been performed.
- G. Examine system and equipment test reports.
- H. Examine HVAC system and equipment installations to verify that indicated balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers, are properly installed, and that their locations are accessible and appropriate for effective balancing and for efficient system and equipment operation.
- I. Examine systems for functional deficiencies that cannot be corrected by adjusting and balancing.
- J. Examine HVAC equipment to ensure that clean filters have been installed, bearings are greased, belts are aligned and tight, and equipment with functioning controls is ready for operation.
- K. Examine plenum ceilings used for supply air to verify that they are airtight. Verify that pipe penetrations and other holes are sealed.
- L. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- M. Examine equipment for installation and for properly operating safety interlocks and controls.
- N. Examine automatic temperature system components to verify the following:
 - 1. Dampers, and other controlled devices are operated by the intended controller.
 - 2. Dampers are in the position indicated by the controller.
 - 3. Integrity of dampers for free and full operation and for tightness of fully closed and fully open positions. This includes dampers in multizone units, mixing boxes, and variable-air-volume terminals.
 - 4. Thermostats and humidistats are located to avoid adverse effects of sunlight, drafts, and cold walls.
 - 5. Sensors are located to sense only the intended conditions.
 - 6. Sequence of operation for control modes is according to the Contract Documents.

7. Controller set points are set at indicated values.
 8. Interlocked systems are operating.
 9. Changeover from heating to cooling mode occurs according to indicated values.
- O. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

3.2 PREPARATION

- A. Prepare a TAB plan that includes the following:
1. Strategies and step-by-step procedures for balancing the systems.
 2. Equipment and systems to be tested.
 3. Instrumentation to be used.
 4. Sample forms with specific identification for all equipment.
- B. Complete system readiness checks and prepare system readiness reports. Verify the following:
1. Permanent electrical power wiring is complete.
 2. Automatic temperature-control systems are operational.
 3. Equipment and duct access doors are securely closed.
 4. Airside:
 - a. Ductwork is complete with terminals installed.
 - b. Ceilings are installed in critical areas where air-pattern adjustments are required and access to balancing devices is provided.
 - c. Windows and doors can be closed so indicated conditions for system operations can be met.
 - d. Verify that leakage and pressure tests on air distribution systems have been satisfactorily completed.
 - e. Balance, smoke, and fire dampers are open and functional
 - f. Clean filters are installed.
 - g. Fans are operating, free of vibration, and rotating in correct direction.
 - h. Variable-frequency controllers' start-up is complete and safeties are verified.
 - i. Suitable access to balancing devices and equipment is provided.

3.3 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system according to the procedures contained in AABC's "National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems" or SMACNA's "HVAC Systems - Testing, Adjusting, and Balancing" and this Section.

- B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary to allow adequate performance of procedures. After testing and balancing, close probe holes and patch insulation with new materials identical to those removed. Restore vapor barrier and finish according to insulation Specifications for this Project.
- C. Mark equipment and balancing device settings with paint or other suitable, permanent identification material, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) units.

3.4 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's approved submittals and recommended testing procedures. Crosscheck the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. For return air plenum systems, balancing shall be done with all doors closed to verify return air paths are adequate.
- D. Determine the best locations in main and branch ducts for accurate duct airflow measurements.
- E. Check airflow patterns from the outside-air louvers and dampers and the return- and exhaust-air dampers, through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling unit components.
- L. Check for proper sealing of air duct system.

3.5 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
 - 1. Measure total airflow.
 - a. Set outside air, return air and relief air dampers for proper position that simulates minimum outdoor air conditions.

- b. Where duct conditions allow, measure airflow by Pitot-tube traverse. If necessary, perform multiple Pitot-tube traverses to obtain total airflow.
 - c. Where duct conditions are not suitable for Pitot-tube traverse measurements, a coil traverse may be acceptable.
 - d. If a reliable Pitot-tube traverse or coil traverse is not possible, measure airflow at terminals and calculate the total airflow.
- 2. Measure fan static pressures to determine actual static pressure as follows:
 - a. Measure outlet static pressure as far downstream from the fan as practicable and upstream from restrictions in ducts such as elbows and transitions.
 - b. Measure static pressure directly at the fan outlet or through the flexible connection.
 - c. Measure inlet static pressure of single-inlet fans in the inlet duct as near the fan as possible, upstream from flexible connection and downstream from duct restrictions.
 - d. Measure inlet static pressure of double-inlet fans through the wall of the plenum that houses the fan.
- 3. Measure static pressure across each component that makes up an air-handling unit, rooftop unit, and other air-handling and -treating equipment.
 - a. Simulate dirty filter operation and record the point at which maintenance personnel must change filters.
- 4. Measure static pressures entering and leaving other devices such as sound traps, heat recovery equipment, and air washers, under final balanced conditions.
- 5. Compare design data with installed conditions to determine variations in design static pressures versus actual static pressures. Compare actual system effect factors with calculated system effect factors to identify where variations occur. Recommend corrective action to align design and actual conditions.
- 6. Obtain approval from Architect for adjustment of fan speed higher or lower than indicated speed. Make required adjustments to pulley sizes, motor sizes, and electrical connections to accommodate fan-speed changes.
- 7. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload will occur. Measure amperage in full cooling, full heating, economizer, and any other operating modes to determine the maximum required brake horsepower.
- B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows within specified tolerances.
 - 1. Measure static pressure at a point downstream from the balancing damper and adjust volume dampers until the proper static pressure is achieved.
 - a. Where sufficient space in submain and branch ducts is unavailable for Pitot-tube traverse measurements, measure airflow at terminal outlets and inlets and calculate the total airflow for that zone.
 - 2. Remeasure each submain and branch duct after all have been adjusted. Continue to adjust submain and branch ducts to indicated airflows within specified tolerances.
- C. Measure terminal outlets and inlets without making adjustments.

1. Measure terminal outlets using a direct-reading hood or outlet manufacturer's written instructions and calculating factors.
- D. Adjust terminal outlets and inlets for each space to indicated airflows within specified tolerances of indicated values. Make adjustments using volume dampers rather than extractors and the dampers at air terminals.
1. Adjust each outlet in same room or space to within specified tolerances of indicated quantities without generating noise levels above the limitations prescribed by the Contract Documents.
 2. Adjust patterns of adjustable outlets for proper distribution without drafts.
- E. Verify final system conditions.
1. Re-measure and confirm minimum outdoor air, return and relief airflows are within design. Readjust to design if necessary.
 2. Re-measure and confirm total airflow is within design.
 3. Re-measure all final fan operating data, rpms, volts, amps, static profile.
 4. Mark all final settings.
 5. Test system in economizer mode. Verify proper operation and adjust, if necessary.
 6. Measure and record all operating data.
 7. Record final fan-performance data.

3.6 PROCEDURES FOR MOTORS

- A. Motors, 1/2 HP and Larger: Test at final balanced conditions and record the following data:
1. Manufacturer, model, and serial numbers.
 2. Motor horsepower rating.
 3. Motor rpm.
 4. Efficiency rating.
 5. Nameplate and measured voltage, each phase.
 6. Nameplate and measured amperage, each phase.
 7. Starter thermal-protection-element rating.
- B. Motors Driven by Variable-Frequency Controllers: Test for proper operation at speeds varying from minimum to maximum. Test the manual bypass for the controller to prove proper operation. Record observations, including controller manufacturer, model and serial numbers, and nameplate data.

3.7 PROCEDURES FOR CONDENSING UNITS

- A. Verify proper rotation of fans.
- B. Measure entering- and leaving-air temperatures.
- C. Record compressor data.

3.8 PROCEDURES FOR HEAT-TRANSFER COILS

- A. Electric-Heating Coils: Measure the following data for each coil:
 - 1. Nameplate data.
 - 2. Airflow.
 - 3. Entering- and leaving-air temperature at full load.
 - 4. Voltage and amperage input of each phase at full load and at each incremental stage.
 - 5. Calculated kilowatt at full load.
 - 6. Fuse or circuit-breaker rating for overload protection.
- B. Refrigerant Coils: Measure the following data for each coil:
 - 1. Dry-bulb temperature of entering and leaving air.
 - 2. Wet-bulb temperature of entering and leaving air.
 - 3. Airflow.
 - 4. Air pressure drop.
 - 5. Refrigerant suction pressure and temperature.

3.9 PROCEDURES FOR TEMPERATURE MEASUREMENTS

- A. During TAB, report the need for adjustment in temperature regulation within the automatic temperature-control system.
- B. Measure indoor wet- and dry-bulb temperatures every other hour for a period of two successive eight-hour days, in each separately controlled zone, to prove correctness of final temperature settings. Measure when the building or zone is occupied.
- C. Measure outside-air, wet- and dry-bulb temperatures.

3.10 TEMPERATURE-CONTROL VERIFICATION

- A. In conjunction with system balancing, perform the following:
 - 1. Verify temperature control system is operating within the design limitations.
 - 2. Confirm that the sequences of operation are in compliance with Contract Documents.
 - 3. Verify that controllers are calibrated and function as intended.
 - 4. Verify that controller set points are as indicated.
 - 5. Verify the operation of lockout or interlock systems.
 - 6. Verify the operation of valve and damper actuators.
 - 7. Verify that controlled devices are properly installed and connected to correct controller.
 - 8. Verify that controlled devices travel freely and are in position indicated by controller: open, closed, or modulating.

9. Verify location and installation of sensors to ensure that they sense only intended temperature, humidity, or pressure.
 10. Check the operation of limiting controllers (i.e., high- and low-temperature controllers.)
 11. Note operation of electric actuators using spring return for proper fail-safe operations.
- B. Reporting: Include a summary of verifications performed, remaining deficiencies, and variations from indicated conditions.

3.11 TOLERANCES

- A. Set HVAC system airflow and water flow rates within the following tolerances:
1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus 5 to plus 10 percent.
 2. Air Outlets and Inlets: 0 to minus 10 percent.

3.12 REPORTING

- A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for systems' balancing devices. Recommend changes and additions to systems' balancing devices to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance measuring and balancing devices.
- B. Status Reports: As Work progresses, prepare reports to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors.

3.13 FINAL REPORT

- A. General: Typewritten, or computer printout in letter-quality font, on standard bond paper, in three-ring binder, tabulated and divided into sections by tested and balanced systems.
- B. The report shall be a complete record of the HVAC system performance, including conditions of operation, items outstanding, and any deviations found during the T&B process. The final report also provides a reference of actual operating conditions for the owner and/or operations personnel. All measurements and test results that appear in the reports must be made on site and dated by the certified technicians or test and balance engineers.
- C. The report must be organized by systems.
- D. Include a certification sheet in front of binder signed and sealed by the certified testing and balancing engineer.
1. Include a list of instruments used for procedures, along with proof of calibration.
- E. Final Report Contents: In addition to certified field report data, include the following:
1. Fan curves.

2. Manufacturers' test data.
3. Field test reports prepared by system and equipment installers.
4. Other information relative to equipment performance, but do not include Shop Drawings and Product Data.

F. General Report Data: In addition to form titles and entries, include the following data in the final report, as applicable:

1. Title page.
2. Name and address of TAB firm.
3. Project name.
4. Project location.
5. Architect's name and address.
6. Engineer's name and address.
7. Contractor's name and address.
8. Report date.
9. Signature of TAB firm who certifies the report.
10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.
11. Summary of contents including the following:
 - a. Indicated versus final performance.
 - b. Notable characteristics of systems.
 - c. Description of system operation sequence if it varies from the Contract Documents.
12. Nomenclature sheets for each item of equipment.
13. Data for terminal units, including manufacturer, type size, and fittings.
14. Notes to explain why certain final data in the body of reports varies from indicated values.
15. Test conditions for fans and pump performance forms including the following:
 - a. Settings for outside-, return-, and exhaust-air dampers.
 - b. Conditions of filters.
 - c. Cooling coil, wet- and dry-bulb conditions.
 - d. Face and bypass damper settings at coils.
 - e. Fan drive settings including settings and percentage of maximum pitch diameter.
 - f. Inlet vane settings for variable-air-volume systems.
 - g. Settings for supply-air, static-pressure controller.
 - h. Other system operating conditions that affect performance.

G. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:

1. Quantities of outside, supply, return, and exhaust airflows.
2. Water and steam flow rates.
3. Duct, outlet, and inlet sizes.
4. Pipe and valve sizes and locations.
5. Terminal units.
6. Balancing stations.
7. Position of balancing devices.

H. Air-Handling Unit Test Reports: For air-handling units with coils, include the following:

1. Unit Data: Include the following:
 - a. Unit identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and unit size.
 - e. Manufacturer's serial number.
 - f. Unit arrangement and class.
 - g. Discharge arrangement.
 - h. Sheave make, size in inches, and bore.
 - i. Sheave dimensions, center-to-center, and amount of adjustments in inches.
 - j. Number of belts, make, and size.
 - k. Number of filters, type, and size.
2. Motor Data:
 - a. Make and frame type and size.
 - b. Horsepower and rpm.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Sheave dimensions, center-to-center, and amount of adjustments in inches.
3. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.
 - b. Total system static pressure in inches wg.
 - c. Fan rpm.
 - d. Discharge static pressure in inches wg.
 - e. Filter static-pressure differential in inches wg.
 - f. Preheat coil static-pressure differential in inches wg.
 - g. Cooling coil static-pressure differential in inches wg.
 - h. Heating coil static-pressure differential in inches wg.
 - i. Outside airflow in cfm.
 - j. Return airflow in cfm.
 - k. Outside-air damper position.
 - l. Return-air damper position.
 - m. Vortex damper position.

I. Apparatus-Coil Test Reports:

1. Coil Data:
 - a. System identification.
 - b. Location.
 - c. Coil type.
 - d. Number of rows.
 - e. Fin spacing in fins per inch o.c.
 - f. Make and model number.
 - g. Face area in sq. ft..
 - h. Tube size in NPS.
 - i. Tube and fin materials.
 - j. Circuiting arrangement.
2. Test Data (Indicated and Actual Values):

- a. Airflow rate in cfm.
- b. Average face velocity in fpm.
- c. Air pressure drop in inches wg.
- d. Outside-air, wet- and dry-bulb temperatures in deg F.
- e. Return-air, wet- and dry-bulb temperatures in deg F.
- f. Entering-air, wet- and dry-bulb temperatures in deg F.
- g. Leaving-air, wet- and dry-bulb temperatures in deg F.
- h. Water flow rate in gpm.
- i. Water pressure differential in feet of head or psig.
- j. Entering-water temperature in deg F.
- k. Leaving-water temperature in deg F.
- l. Refrigerant expansion valve and refrigerant types.
- m. Refrigerant suction pressure in psig.
- n. Refrigerant suction temperature in deg F.
- o. Inlet steam pressure in psig.

J. Gas- and Oil-Fired Heat Apparatus Test Reports: In addition to manufacturer's factory startup equipment reports, include the following:

1. Unit Data:
 - a. System identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and unit size.
 - e. Manufacturer's serial number.
 - f. Fuel type in input data.
 - g. Output capacity in Btuh.
 - h. Ignition type.
 - i. Burner-control types.
 - j. Motor horsepower and rpm.
 - k. Motor volts, phase, and hertz.
 - l. Motor full-load amperage and service factor.
 - m. Sheave make, size in inches, and bore.
 - n. Sheave dimensions, center-to-center, and amount of adjustments in inches.
2. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.
 - b. Entering-air temperature in deg F.
 - c. Leaving-air temperature in deg F.
 - d. Air temperature differential in deg F.
 - e. Entering-air static pressure in inches wg.
 - f. Leaving-air static pressure in inches wg.
 - g. Air static-pressure differential in inches wg.
 - h. Low-fire fuel input in Btuh.
 - i. High-fire fuel input in Btuh.
 - j. Manifold pressure in psig.
 - k. High-temperature-limit setting in deg F.
 - l. Operating set point in Btuh.
 - m. Motor voltage at each connection.
 - n. Motor amperage for each phase.
 - o. Heating value of fuel in Btuh.

K. Fan Test Reports: For supply, return, and exhaust fans, include the following:

1. Fan Data:
 - a. System identification.
 - b. Location.
 - c. Make and type.
 - d. Model number and size.
 - e. Manufacturer's serial number.
 - f. Arrangement and class.
 - g. Sheave make, size in inches, and bore.
 - h. Sheave dimensions, center-to-center, and amount of adjustments in inches.
2. Motor Data:
 - a. Make and frame type and size.
 - b. Horsepower and rpm.
 - c. Volts, phase, and hertz.
 - d. Full-load amperage and service factor.
 - e. Sheave make, size in inches, and bore.
 - f. Sheave dimensions, center-to-center, and amount of adjustments in inches.
 - g. Number of belts, make, and size.
3. Test Data (Indicated and Actual Values):
 - a. Total airflow rate in cfm.
 - b. Total system static pressure in inches wg.
 - c. Fan rpm.
 - d. Discharge static pressure in inches wg.
 - e. Suction static pressure in inches wg.

L. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:

1. Report Data:
 - a. System and air-handling unit number.
 - b. Location and zone.
 - c. Traverse air temperature in deg F.
 - d. Duct static pressure in inches wg.
 - e. Duct size in inches.
 - f. Duct area in sq. ft..
 - g. Indicated airflow rate in cfm.
 - h. Indicated velocity in fpm.
 - i. Actual airflow rate in cfm.
 - j. Actual average velocity in fpm.
 - k. Barometric pressure in psig.

M. System-Coil Reports: For reheat coils and water coils of terminal units, include the following:

1. Unit Data:
 - a. System and air-handling unit identification.
 - b. Location and zone.
 - c. Room or riser served.
 - d. Coil make and size.

- e. Flowmeter type.
2. Test Data (Indicated and Actual Values):
 - a. Airflow rate in cfm.
 - b. Entering-water temperature in deg F.
 - c. Leaving-water temperature in deg F.
 - d. Water pressure drop in feet of head or psig.
 - e. Entering-air temperature in deg F.
 - f. Leaving-air temperature in deg F.
- N. Compressor and Condenser Reports: For refrigerant side of unitary systems, stand-alone refrigerant compressors, air-cooled condensing units, or water-cooled condensing units, include the following:
1. Unit Data:
 - a. Unit identification.
 - b. Location.
 - c. Unit make and model number.
 - d. Compressor make.
 - e. Compressor model and serial numbers.
 - f. Refrigerant weight in lb.
 - g. Low ambient temperature cutoff in deg F.
 2. Test Data (Indicated and Actual Values):
 - a. Inlet-duct static pressure in inches wg.
 - b. Outlet-duct static pressure in inches wg.
 - c. Entering-air, dry-bulb temperature in deg F.
 - d. Leaving-air, dry-bulb temperature in deg F.
 - e. Control settings.
 - f. Unloader set points.
 - g. Suction pressure in psig.
 - h. Suction temperature in deg F.
 - i. Condenser refrigerant pressure in psig.
 - j. Condenser refrigerant temperature in deg F.
 - k. Oil pressure in psig.
 - l. Oil temperature in deg F.
 - m. Voltage at each connection.
 - n. Amperage for each phase.
 - o. Kilowatt input.
 - p. Crankcase heater kilowatt.
 - q. Number of fans.
 - r. Condenser fan rpm.
 - s. Condenser fan airflow rate in cfm.
 - t. Condenser fan motor make, frame size, rpm, and horsepower.
 - u. Condenser fan motor voltage at each connection.
 - v. Condenser fan motor amperage for each phase.
- O. Instrument Calibration Reports:
1. Report Data:
 - a. Instrument type and make.

- b. Serial number.
- c. Application.
- d. Dates of use.
- e. Dates of calibration.

3.14 INSPECTIONS

A. Initial Inspection:

1. After testing and balancing are complete, operate each system and randomly check measurements to verify that the system is operating according to the final test and balance readings documented in the Final Report.
2. Randomly check the following for each system:
 - a. Measure airflow of at least 10 percent of air outlets.
 - b. Measure water flow of at least 5 percent of terminals.
 - c. Measure room temperature at each thermostat/temperature sensor. Compare the reading to the set point.
 - d. Measure sound levels at two locations.
 - e. Measure space pressure of at least 10 percent of locations.
 - f. Verify that balancing devices are marked with final balance position.
 - g. Note deviations to the Contract Documents in the Final Report.

B. Final Inspection:

1. After initial inspection is complete and evidence by random checks verifies that testing and balancing are complete and accurately documented in the final report, request that a final inspection be made by Architect.
2. TAB firm test and balance engineer shall conduct the inspection in the presence of Architect.
3. Architect shall randomly select measurements documented in the final report to be rechecked. The rechecking shall be limited to either 10 percent of the total measurements recorded, or the extent of measurements that can be accomplished in a normal 8-hour business day.
4. If the rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
5. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.
6. TAB firm shall recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes and resubmit the final report.
7. Request a second final inspection. If the second final inspection also fails, Owner shall contract the services of another TAB firm to complete the testing and balancing in accordance with the Contract Documents and deduct the cost of the services from the final payment.

3.15 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional testing and balancing to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional testing, inspecting, and adjusting during near-peak summer and winter conditions.

END OF SECTION 23 05 93

SECTION 23 07 00 - MECHANICAL INSULATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Related Sections include the following:
 - 1. Division 7 Section "Firestopping" for firestopping materials and requirements for penetrations through fire and smoke barriers.
 - 2. Division 23 Section "Metal Ducts" for duct liner.
 - 3. Section 23 00 00 "Mechanical General Requirements".
 - 4. Section 23 00 50 "Basic Mechanical Materials and Methods".
- B. Section includes insulating HVAC equipment that is not factory insulated.
- C. Section includes insulation for HVAC piping systems.
- D. Section includes insulating the following duct services:
 - 1. Indoor, concealed supply and outdoor air.
 - 2. Indoor, exposed supply and outdoor air.
 - 3. Indoor, concealed return located in unconditioned space.
 - 4. Indoor, exposed return located in unconditioned space.
 - 5. Indoor, concealed oven and warewash exhaust.
 - 6. Indoor, exposed oven and warewash exhaust.
 - 7. Indoor, concealed exhaust between isolation damper and penetration of building exterior.
 - 8. Indoor, exposed exhaust between isolation damper and penetration of building exterior.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied if any).
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
 - 1. Detail removable insulation at equipment connections.
 - 2. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
 - 3. Detail attachment and covering of heat tracing inside insulation.
 - 4. Detail insulation application at pipe expansion joints for each type of insulation.

5. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.
6. Detail removable insulation at piping specialties.
7. Detail insulation application at elbows, fittings, dampers, specialties and flanges for each type of insulation.
8. Detail application of field-applied jackets.
9. Detail application at linkages of control devices.

1.4 QUALITY ASSURANCE

- A. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
 1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
 2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

1.6 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 23 05 29 "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- C. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.
- D. Coordinate installation and testing of heat tracing.

1.7 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing.. Insulation application may begin on segments that have satisfactory test results.

- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- 1. Mineral-Fiber Insulation:

- a. CertainTeed Corporation.
- b. Johns Manville; a Berkshire Hathaway company.
- c. Knauf Insulation.
- d. Manson Insulation Inc.
- e. Owens Corning.

- 2. Flexible Elastomeric Thermal Insulation:

- a. Aeroflex USA, Inc.
- b. Armacell LLC.
- c. Armstrong World Industries, Inc.
- d. Rubatex Corp.

2.2 INSULATION MATERIALS

- A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule," and "Aboveground, Outdoor Duct and Plenum Insulation Schedule" articles for where insulating materials shall be applied.
- B. Comply with requirements in "Breeching Insulation Schedule," "Indoor Equipment Insulation Schedule," and "Outdoor, Aboveground Equipment Insulation Schedule" articles for where insulating materials shall be applied.
- C. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.
- D. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- E. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C871.
- F. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C795.

- G. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- H. Calcium Silicate: Flat-, curved-, and grooved-block sections of noncombustible, inorganic, hydrous calcium silicate with a non-asbestos fibrous reinforcement. Comply with ASTM C533, Type I or Type II.
 - 1. Prefabricated Fitting Covers: Comply with ASTM C450 and ASTM C585 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.
- I. Calcium Silicate: Preformed Pipe Sections: Flat-, curved-, and grooved-block sections of noncombustible, inorganic, hydrous calcium silicate with a non-asbestos fibrous reinforcement. Comply with ASTM C533, Type I.
 - 1. Prefabricated Fitting Covers: Comply with ASTM C450 and ASTM C585 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.
- J. Cellular Glass: Inorganic, incombustible, foamed or cellulated glass with annealed, rigid, hermetically sealed cells. Comply with ASTM C552.
 - 1. Block Insulation: Type I.
 - 2. Special-Shaped Insulation: Type III.
 - 3. Board Insulation: Type IV.
 - 4. Preformed Pipe Insulation: Type II, Class 1, without jacket.
 - 5. Preformed Pipe Insulation: Type II, Class 2, with factory-applied ASJ-SSL jacket.
 - 6. Factory fabricate shapes in accordance with ASTM C450 and ASTM C585.
 - 7. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
- K. Mineral-Fiber Blanket Insulation: Glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
- L. Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 612, Type IA or Type IB. Provide insulation with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
- M. High-Temperature, Mineral-Fiber Blanket: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C553, Type V, without factory-applied jacket.
- N. High-Temperature, Mineral-Fiber Board: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C612, Type III, without factory-applied jacket.
- O. Flexible Elastomeric Thermal Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C534/C534M, Type I for tubular materials, Type II for sheet materials.
 - 1. Adhesive: As recommended by insulation material manufacturer.
 - 2. Ultraviolet-Protective Coating: As recommended by insulation manufacturer.
- P. Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting resin.
 - 1. Semirigid board material with factory-applied ASJ jacket complying with ASTM C1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C612, Type IB.

2. Nominal density is 2.5 lb/cu. ft. or more.
3. Thermal conductivity (k-value) at 100 deg F is 0.29 Btu x in./h x sq. ft. x deg F or less.
4. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

Q. Mineral-Fiber, Preformed Pipe: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C547.

1. Preformed Pipe Insulation: Type I, Grade A with factory-applied ASJ-SSL.
2. 850 deg F.
3. Factory fabricate shapes in accordance with ASTM C450 and ASTM C585.
4. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article

R. Phenolic: Preformed pipe insulation of rigid, expanded, closed-cell structure. Comply with ASTM C1126.

1. Preformed Pipe Insulation: Type III, with factory-applied ASJ.
2. Factory fabricate shapes in accordance with ASTM C450 and ASTM C585.
3. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

S. Polyisocyanurate: Preformed, rigid cellular polyisocyanurate material intended for use as thermal insulation. Comply with ASTM C591.

1. Preformed insulation with factory-applied ASJ-SSL.
2. Type I or Type IV, except thermal conductivity (k-value) shall not exceed 0.19 Btu x in./h x sq. ft. x deg F at 75 deg F after 180 days of aging.
3. Flame-spread index shall be 25 or less and smoke-developed index shall be 50 or less for thicknesses of up to 1 inch as tested in accordance with ASTM E84.
4. Fabricate shapes in accordance with ASTM C450 and ASTM C585.
5. Factory-Applied Jacket: Requirements are specified in "Factory-Applied Jackets" Article.

a. Equipment Applications: ASJ.

T. Polyolefin: Unicellular, polyethylene thermal plastic insulation. Comply with ASTM C534 or ASTM C1427, Type I, Grade 1 for tubular materials and Type II, Grade 1 for sheet materials.

U. Polystyrene: Rigid, extruded cellular polystyrene intended for use as thermal insulation. Comply with ASTM C578, Type IV, VIII, or XIII, except thermal conductivity (k-value) shall not exceed 0.26 Btu x in./h x sq. ft. x deg F after 180 days of aging.

1. Fabricate shapes in accordance with ASTM C450 and ASTM C585.

2.3 FIRE-RATED INSULATION SYSTEMS

A. Fire-Rated Blanket: High-temperature, flexible, blanket insulation with FSK jacket that is tested and certified to provide a 2-hour fire rating by an NRTL acceptable to authorities having jurisdiction. Blanket shall be manufactured from calcia, magnesia, silica chemistry designed to enhance biosolubility, 8 lb/cubic feet, ASTM E84 with flame spread less than 25 and smoke developed rating less than 50.

2.4 ACCESSORIES

A. Insulation Pipe Support

1. Manufacturers:
 - a. Armacell
 - b. Reftekk
2. PET bearing core with flexible elastomeric foam outer for connection to insulation material or Closed-cell rigid polymeric foam lined with closed-cell EPDM rubber.

2.5 FACTORY-APPLIED JACKETS

- A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
 1. ASJ: White, kraft-paper, fiberglass-reinforced scrim with aluminum-foil backing; complying with ASTM C1136, Type I.
 2. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C1136, Type I.
 3. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.

2.6 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C921, Type I, unless otherwise indicated.
- B. FSK Jacket: Aluminum-foil-face, fiberglass-reinforced scrim with kraft-paper backing.
- C. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
 1. Adhesive: As recommended by jacket material manufacturer.
 2. Color: White.
 3. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
 - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.
 4. Factory-fabricated tank heads and tank side panels.

2.7 white DUCTWORK INSULATION ACCESSORIES

- A. Provide staples, bands, tape, anchors, corner angles, glues, and similar accessories as recommended by insulation manufacturer for applications indicated.

2.8 DUCTWORK INSULATION COMPOUNDS:

- A. Provide cements, adhesives, coatings, sealers, protective finishes and similar compounds as recommended by insulation manufacturer for applications indicated.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
 - 1. Verify that systems to be insulated have been tested and are free of defects.
 - 2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Clean and prepare surfaces to be insulated. Before insulating, apply a corrosion coating to insulated surfaces as follows:
 - 1. Stainless Steel: Coat 300 series stainless steel with an epoxy primer 5 mils thick and an epoxy finish 5 mils thick if operating in a temperature range of between 140 and 300 deg F. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
 - 2. Carbon Steel: Coat carbon steel operating at a service temperature of between 32 and 300 deg F with an epoxy coating. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
- C. Coordinate insulation installation with the tradesman installing heat tracing. Comply with requirements for heat tracing that apply to insulation.
- D. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless steel surfaces, use demineralized water.

3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.
- B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.
- C. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping, including fittings, valves, and specialties.
- D. Install insulation materials, forms, vapor barriers or retarders, jackets, and of thicknesses required for each item of pipe system, as specified in insulation system schedules.

- E. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- F. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- G. Install multiple layers of insulation with longitudinal and end seams staggered.
- H. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- I. Provide rigid inserts between piping and supports that are compatible with specified insulation material. No wood supports will be allowed.
- J. Keep insulation materials dry during application and finishing.
- K. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- L. Install insulation with least number of joints practical.
- M. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
 - 1. Install insulation continuously through hangers and around anchor attachments.
 - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
 - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
 - 4. Cover inserts with jacket material matching adjacent insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- N. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- O. Install insulation with factory-applied jackets as follows:
 - 1. Draw jacket tight and smooth.
 - 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
 - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at 4 inches o.c.
 - a. For below ambient services, apply vapor-barrier mastic over staples.
 - 4. Joints and Seams: Cover with tape and vapor retarder as recommended by insulation material manufacturer to maintain vapor seal.
 - 5. Vapor-Retarder Mastics: Where vapor retarders are indicated, apply mastic on seams and joints and at ends adjacent to duct flanges and fittings.

- P. Cut insulation in a manner to avoid compressing insulation more than 25 percent of its nominal thickness.
- Q. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- R. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- S. For above-ambient services, do not install insulation to the following:
 - 1. Vibration-control devices.
 - 2. Testing agency labels and stamps.
 - 3. Nameplates and data plates.
 - 4. Manholes.
 - 5. Handholes.
 - 6. Cleanouts.
- T. Exterior Applications:
 - 1. Mineral-Fiber Board Insulation: Cover with aluminum jacket with seams located on bottom side of horizontal ductwork. Insulate fittings and joints with insulation of like material and thickness as adjoining pipe, and finish with glass mesh reinforced vapor barrier cement.
 - 2. Flexible Elastomeric Insulation: Coat with flexible elastomeric foam finish per manufacturer's instructions.

3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
 - 1. Seal penetrations with flashing sealant.
 - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
 - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
 - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
 - 1. Seal penetrations with flashing sealant.

2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
 4. Seal jacket to wall flashing with flashing sealant.
- D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
1. Comply with requirements in Division 07 "Penetration Firestopping" and fire-resistive joint sealers.
- F. Insulation Installation at Floor Penetrations:
1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
 2. Pipe: Install insulation continuously through floor penetrations.
 3. Seal penetrations through fire-rated assemblies. Comply with requirements in Division 07 "Penetration Firestopping."

3.5 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials, except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, Mechanical Couplings, and Unions:
1. Install insulation over fittings, valves, strainers, flanges, mechanical couplings, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
 2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as that of adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
 3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as that used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
 4. For services not specified to receive a field-applied jacket, except for flexible elastomeric and polyolefin, install fitted PVC cover over elbows, tees, strainers, valves, flanges, and

unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing, using PVC tape.

- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.

3.6 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
 - 1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for 50 percent coverage of duct and plenum surfaces.
 - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
 - 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
 - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not overcompress insulation during installation.
 - e. Impale insulation over pins and attach speed washers.
 - f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
 - 4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
 - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
 - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
 - 5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.

6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

B. Board Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.

1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for **50** percent coverage of duct and plenum surfaces.
2. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
 - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
 - b. On duct sides with dimensions larger than 18 inches, space pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
 - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
 - d. Do not overcompress insulation during installation.
 - e. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
3. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
 - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
 - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
4. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
5. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch-wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

C. Insulation Installation on Straight Pipes and Tubes:

1. Secure each layer of preformed pipe insulation to pipe with wire or bands, and tighten bands without deforming insulation materials.

2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward-clinched staples at 6 inches o.c.
4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive, as recommended by insulation material manufacturer, and seal with vapor-barrier mastic and flashing sealant.

D. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as that of straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

3.7 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

B. Insulation Installation on Pipe Fittings and Elbows:

1. Install mitered sections of pipe insulation.
2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

3.8 FINISHES

A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Section 09 91 13 "Exterior Painting" and Section 09 91 23 "Interior Painting."

1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.

- a. Finish Coat Material: Interior, flat, latex-emulsion size.

B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.

C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.

D. Do not field paint aluminum or stainless-steel jackets.

3.9 FIELD QUALITY CONTROL

A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

B. Perform tests and inspections.

C. Tests and Inspections:

1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location(s) for each duct system defined in the "Duct Insulation Schedule, General" Article.

D. two All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

E. Prepare test and inspection reports.

3.10 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

A. Supply and outdoor air ductwork above ceilings, in chases, and other concealed locations, insulation shall be one of the following:

1. Flexible Elastomeric: 1-1/2 inch thick. Minimum installed R-Value of 6.0.
2. Mineral-Fiber Blanket: 2 inches thick and 1.5-lb/cu. nominal density. Minimum installed R-Value of 6.0.

B. Supply and outdoor air ductwork, exposed, rectangular, insulation shall be one of the following:

1. Mineral-Fiber Board: 1-1/2 inchesthick and 2-lb/cu. ft. nominal density.

C. Exposed, round and flat-oval, supply and outdoor-air duct insulation shall be the following:

1. Mineral-Fiber Blanket: 1-1/2 inches thick and 0.75-lb/cu. ft. nominal density.

D. Outdoor air plenum above ceilings, in chases, and other concealed locations, insulation shall be one of the following:

1. Mineral-Fiber Blanket: 2 inches thick and 1.5-lb/cu. ft. Minimum installed R-value of 6.
2. Mineral-Fiber Board: 1-1/2 inches thick and 2-lb/cu. ft. nominal density. Minimum installed R-value of 6.

E. Outdoor air plenum, exposed, insulation shall be the following:

1. Mineral-Fiber Board: 2 inches thick and 6-lb/cu. ft.

F. Air Device Plenums and back of air device pans above ceilings, in chases, and other concealed locations, insulation shall match ductwork insulation.

G. Concealed, rectangular, exhaust-air duct insulation between isolation damper and penetration of building exterior shall be **one of** the following:

1. Flexible Elastomeric: 1 inch thick.
2. Mineral-Fiber Blanket: 1-1/2 inches thick and 0.75-lb/cu. ft.nominal density.
3. Mineral-Fiber Board: 1-1/2 inches thick and 2-lb/cu. ft nominal density.

H. Concealed, Type I, Commercial, Kitchen Hood Exhaust Duct and Plenum Insulation: Fire-rated blanket or board; thickness as required to achieve 2-hour fire rating.

I. Items Not Insulated:

1. Fibrous-glass ducts.
2. Metal ducts with duct liner of sufficient thickness to comply with energy code and ASHRAE/IESNA 90.1.
3. Factory-insulated flexible ducts.
4. Factory-insulated plenums and casings.
5. Flexible connectors.
6. Vibration-control devices.
7. Factory-insulated access panels and doors.
8. Name plates and data plates.

3.11 PIPING INSULATION SCHEDULE, GENERAL

- A. Insulation conductivity and thickness per pipe size shall comply with schedules in this Section or with requirements of authorities having jurisdiction, whichever is more stringent.
- B. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- C. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
 1. Underground piping.
 2. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

3.12 INDOOR PIPING INSULATION SCHEDULE

- A. Condensate and Equipment Drain Water below 60 Deg F:
 1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 1 inch thick.
- B. Refrigerant Suction and Hot-Gas Piping:
 1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 1 inch thick.
- C. Refrigerant Suction and Hot-Gas Flexible Tubing:
 1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 1 inch thick.
- D. Refrigerant Liquid Piping:
 1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 1-1/2 inch thick.

3.13 OUTDOOR, ABOVEGROUND PIPING INSULATION SCHEDULE

A. Refrigerant Suction and Hot-Gas Piping:

1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 2 inches thick.

B. Refrigerant Suction and Hot-Gas Flexible Tubing:

1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 2 inches thick.

C. Refrigerant Liquid Piping:

1. All Pipe Sizes: Insulation shall be the following:
 - a. Flexible Elastomeric: 1 inch thick.

END OF SECTION 23 07 00

SECTION 23 09 00 – DIRECT DIGITAL CONTROL SYSTEMS

PART 1 - GENERAL

1.1 Furnished but Not Installed under This Section

- A. None

1.2 Products Installed but Not Furnished under This Section

- A. None

1.3 Products Not Furnished or Installed under but Integrated with the Work of This Section

- A. Coordination Meeting: The Installer furnishing the DDC network shall meet with the Installer(s) furnishing each of the following products to coordinate details of the interface between these products and the DDC network. The Owner or his designated representative shall be present at this meeting. Each Installer shall provide the Owner and all other Installers with details of the proposed interface including PICS for BACnet equipment, hardware and software identifiers for the interface points, network identifiers, wiring requirements, communication speeds, and required network accessories. The purpose of this meeting shall be to insure there are no unresolved issues regarding the integration of these products into the DDC network. Submittals for these products shall not be approved prior to the completion of this meeting.
- B. Section 23 70 00 - Central HVAC Equipment
 - 1. Packaged AHU or evaporative cooler controls: Unit shall be furnished configured to accept control inputs from an external building automation system controller as specified in Section 23 09 93. Factory mounted safeties and other controls shall not interfere with this controller.

1.4 Related Sections

- A. The General Conditions of the Contract, Supplementary Conditions, and General Requirements are part of this specification and shall be used in conjunction with this section as part of the contract documents.
- B. The following sections constitute related work:
 - 1. Section 01 30 00 - Administrative Requirements
 - 2. Section 01 60 00 - Product Requirements
 - 3. Section 23 05 00 - Common Work Results for HVAC
 - 4. Section 23 30 00 - HVAC Air Distribution
 - 5. Section 26 05 00 - Common Work Results for Electrical
 - 6. Section 26 09 00 - Instrumentation and Control for Electrical Systems
 - 7. Section 26 20 00 - Low Voltage Electrical Transmission
 - 8. Section 26 29 00 - Low-Voltage Controllers (Motor Controllers and VFD Drives)

9. Section 26 30 00 - Facility Electrical Power Generating and Storing Equipment (UPS, Backup Generators)
10. Section 28 00 00 - Electronic Safety and Security (includes Fire and Smoke)

C. Description

1. General: The control system shall consist of a high-speed, peer-to-peer network of DDC controllers, a control system server, and a web-based operator interface.
2. System software shall be based on a server/thin client architecture, designed around the open standards of web technology. The control system server shall be accessed using a Web browser over the control system network, the owner's local area network, and (at the owner's discretion) over the Internet.
The intent of the thin-client architecture is to provide operators complete access to the control system via a Web browser. No special software other than a web browser shall be required to access graphics, point displays, and trends, configure trends, configure points and controllers, or to download programming into the controllers.
3. System shall use the BACnet protocol for communication to the operator workstation or web server and for communication between control modules. I/O points, schedules, setpoints, trends and alarms specified in 23 09 93 – “Sequence of Operations for HVAC Controls” shall be BACnet objects.

1.5 Approved Control system Manufacturers

- A. Use control system hardware and software that meet the requirements of this specification.

1.6 Quality Assurance

A. Installer and Manufacturer Qualifications

1. Installer shall have an established working relationship with Control System Manufacturer.
2. Installer shall have successfully completed Control System Manufacturer's control system training. Upon request, Installer shall present record of completed training including course outlines.

1.7 Codes and Standards

- A. Work, materials, and equipment shall comply with the most restrictive of local, state, and federal authorities' codes and ordinances or these plans and specifications. As a minimum, the installation shall comply with the current editions in effect 30 days prior to the receipt of bids of the following codes:

1. National Electric Code (NEC)
2. International Building Code (IBC)
 - a. Section 719 Ducts and Air Transfer Openings
 - b. Section 907 Fire Alarm and Detection Systems
 - c. Section 909 Smoke Control Systems
 - d. Chapter 28 Mechanical
3. International Mechanical Code (IMC)
4. ANSI/ASHRAE Standard 135, BACnet - A Data Communication Protocol for Building Automation and Control Systems

1.8 System Performance

- A. Performance Standards. System shall conform to the following minimum standards over network connections. Systems shall be tested using manufacturer's recommended hardware and software for operator workstation (server and browser for web-based systems).
1. Graphic Display. A graphic with 20 dynamic points shall display with current data within 10 sec.
 2. Graphic Refresh. A graphic with 20 dynamic points shall update with current data within 8 sec. and shall automatically refresh every 15 sec.
 3. Configuration and Tuning Screens. Screens used for configuring, calibrating, or tuning points, PID loops, and similar control logic shall automatically refresh within 6 sec.
 4. Object Command. Devices shall react to command of a binary object within 2 sec. Devices shall begin reacting to command of an analog object within 2 sec.
 5. Alarm Response Time. An object that goes into alarm shall be annunciated at the workstation within 45 sec.
 6. Program Execution Frequency. Custom and standard applications shall be capable of running as often as once every 5 sec. Select execution times consistent with the mechanical process under control.
 7. Performance. Programmable controllers shall be able to completely execute DDC PID control loops at a frequency adjustable down to once per sec. Select execution times consistent with the mechanical process under control.
 8. Multiple Alarm Annunciation. Each workstation on the network shall receive alarms within 5 sec of other workstations.
 9. Reporting Accuracy. System shall report values with minimum end-to-end accuracy listed in Table 1.
 10. Control Stability and Accuracy. Control loops shall maintain measured variable at setpoint within tolerances listed in Table 2.

Table-1
Reporting Accuracy

Measured Variable	Reported Accuracy
Space Temperature	$\pm 0.5^{\circ}\text{C}$ ($\pm 1^{\circ}\text{F}$)
Ducted Air	$\pm 0.5^{\circ}\text{C}$ ($\pm 1^{\circ}\text{F}$)
Outside Air	$\pm 1.0^{\circ}\text{C}$ ($\pm 2^{\circ}\text{F}$)
Dew Point	$\pm 1.5^{\circ}\text{C}$ ($\pm 3^{\circ}\text{F}$)
Water Temperature	$\pm 0.5^{\circ}\text{C}$ ($\pm 1^{\circ}\text{F}$)
Delta-T	$\pm 0.15^{\circ}$ ($\pm 0.25^{\circ}\text{F}$)
Relative Humidity	$\pm 5\%$ RH
Water Flow	$\pm 2\%$ of full scale
Airflow (terminal)	$\pm 10\%$ of full scale (see Note 1)
Airflow (measuring stations)	$\pm 5\%$ of full scale
Airflow (pressurized spaces)	$\pm 3\%$ of full scale
Air Pressure (ducts)	± 25 Pa (± 0.1 in. w.g.)
Air Pressure (space)	± 3 Pa (± 0.01 in. w.g.)
Water Pressure	$\pm 2\%$ of full scale (see Note 2)
Electrical	$\pm 1\%$ of reading (see Note 3)
Carbon Monoxide (CO)	$\pm 5\%$ of reading
Carbon Dioxide (CO ₂)	± 50 ppm

Note 1: Accuracy applies to 10%–100% of scale
 Note 2: For both absolute and differential pressure
 Note 3: Not including utility-supplied meters

Table 2
 Control Stability and Accuracy

Controlled Variable	Control Accuracy	Range of Medium
Air Pressure	± 50 Pa (± 0.2 in. w.g.) ± 3 Pa (± 0.01 in. w.g.)	0–1.5 kPa (0–6 in. w.g.) -25 to 25 Pa (-0.1 to 0.1 in. w.g.)
Airflow	$\pm 10\%$ of full scale	
Space Temperature	$\pm 1.0^{\circ}\text{C}$ ($\pm 2.0^{\circ}\text{F}$)	
Duct Temperature	$\pm 1.5^{\circ}\text{C}$ ($\pm 3^{\circ}\text{F}$)	
Humidity	$\pm 5\%$ RH	
Fluid Pressure	± 10 kPa (± 1.5 psi) ± 250 Pa (± 1.0 in. w.g.)	MPa (1–150 psi) 0–12.5 kPa (0–50 in. w.g.) differential

1.9 Submittals

- A. Product Data and Shop Drawings: Meet requirements of Section 01 30 00 on Shop Drawings, Product Data, and Samples. In addition, the contractor shall provide shop drawings or other submittals on hardware, software, and equipment to be installed or provided. No work may begin on any segment of this project until submittals have been approved for conformity with design intent. Provide drawings as AutoCAD compatible files on magnetic or optical disk (file format: .DWG, .DXF, .VSD, or comparable) and three 11" x 17" prints of each drawing. When manufacturer's cutsheets apply to a product series rather than a specific product, the data specifically applicable to the project shall be highlighted or clearly indicated by other means. Each submitted piece of literature and drawing shall clearly reference the specification and/or drawing that the submittal is to cover. General catalogs shall not be accepted as cutsheets to fulfill submittal requirements. Select and show submittal quantities appropriate to scope of work. Submittal approval does not relieve Contractor of responsibility to supply sufficient quantities to complete work. Submittals shall be provided within 12 weeks of contract award. Submittals shall include:

1. DDC System Hardware

- a. A complete bill of materials to be used indicating quantity, manufacturer, model number, and relevant technical data of equipment to be used.
- b. Manufacturer's description and technical data such as performance curves, product specifications, and installation and maintenance instructions for items listed below and for relevant items not listed below:
 - 1) Direct digital controllers (controller panels)
 - 2) Transducers and transmitters
 - 3) Sensors (including accuracy data)
 - 4) Actuators
 - 5) Valves
 - 6) Relays and switches
 - 7) Control panels
 - 8) Power supplies
 - 9) Batteries
 - 10) Operator interface equipment
 - 11) Wiring

- c. Wiring diagrams and layouts for each control panel. Show termination numbers.
 - d. Schematic diagrams for all field sensors and controllers. Provide floor plans of all sensor locations and control hardware. Riser diagrams showing control network layout, communication protocol, and wire types.
- 2. Central System Hardware and Software
 - a. A complete bill of material of equipment used indicating quantity, manufacturer, model number, and relevant technical.
 - b. Manufacturer's description and technical data such as product specifications and installation and maintenance instructions for items listed below and for relevant items furnished under this contract not listed below:
 - 1) Central Processing Unit (CPU) or web server
 - 2) Monitors
 - 3) Keyboards
 - 4) Power supplies
 - 5) Battery backups
 - 6) Interface equipment between CPU or server and control panels
 - 7) Operating System software
 - 8) Operator interface software
 - 9) Color graphic software
 - 10) Third-party software
 - c. Schematic diagrams for all control, communication, and power wiring. Provide a schematic drawing of the central system installation. Label all cables and ports with computer manufacturers' model numbers and functions. Show interface wiring to control system.
 - d. Network riser diagrams of wiring between central control unit and control panels.
- 3. Controlled Systems
 - a. Riser diagrams showing control network layout, communication protocol, and wire types.
 - b. A schematic diagram of each controlled system. The schematics shall have all control points labeled with point names shown or listed. The schematics shall graphically show the location of all control elements in the system.
 - c. A schematic wiring diagram of each controlled system. Label control elements and terminals. Where a control element is also shown on control system schematic, use the same name.
 - d. An instrumentation list (Bill of Materials) for each controlled system. List each control system element in a table. Show element name, type of device, manufacturer, model number, and product data sheet number.
 - e. A mounting, wiring, and routing plan-view drawing. The design shall take into account HVAC, electrical, and other systems' design and elevation requirements. The drawing shall show the specific location of all concrete pads and bases and any special wall bracing for panels to accommodate this work.
 - f. A complete description of the operation of the control system, including sequences of operation. The description shall include and reference a schematic diagram of the controlled system.
 - g. A point list for each control system. List I/O points and software points specified in Section 23 09 93. Indicate alarmed and trended points.
- 4. Quantities of items submitted shall be reviewed but are the responsibility of the Contractor.
- 5. A description of the proposed process along with all report formats and checklists to be used in Section 23 09 23 Article 3.16 (Control System Demonstration and Acceptance).
- 6. BACnet Protocol Implementation Conformance Statement (PICS) for each submitted type of controller and operator interface.

B. Schedules

1. Within one month of contract award, provide a schedule of the work indicating the following:
 - a. Intended sequence of work items
 - b. Start date of each work item
 - c. Duration of each work item
 - d. Planned delivery dates for ordered material and equipment and expected lead times
 - e. Milestones indicating possible restraints on work by other trades or situations
2. Monthly written status reports indicating work completed and revisions to expected delivery dates. Include updated schedule of work.

C. Project Record Documents. Upon completion of installation, submit three copies of record (as-built) documents. The documents shall be submitted for approval prior to final completion and shall include:

1. Project Record Drawings. As-built versions of submittal shop drawings provided as AutoCAD compatible files on magnetic or optical media (file format: .DWG, .DXF, .VSD, or comparable) and as 11" x 17" prints.
2. Testing and Commissioning Reports and Checklists. Completed versions of reports, checklists, and trend logs used to meet requirements of Section 23 09 23 Article 3.16 (Control System Demonstration and Acceptance).
3. Operation and Maintenance (O&M) Manual.
4. As-built versions of submittal product data.
5. Names, addresses, and telephone numbers of installing contractors and service representatives for equipment and control systems.
6. Operator's manual with procedures for operating control systems: logging on and off, handling alarms, producing point reports, trending data, overriding computer control, and changing setpoints and variables.
7. Programming manual or set of manuals with description of programming language and syntax, of statements for algorithms and calculations used, of point database creation and modification, of program creation and modification, and of editor use.
8. Engineering, installation, and maintenance manual or set of manuals that explains how to design and install new points, panels, and other hardware; how to perform preventive maintenance and calibration; how to debug hardware problems; and how to repair or replace hardware.
9. Documentation of programs created using custom programming language including setpoints, tuning parameters, and object database. Electronic copies of programs shall meet this requirement if control logic, setpoints, tuning parameters, and objects can be viewed using furnished programming tools.
10. Graphic files, programs, and database on magnetic or optical media.
11. List of recommended spare parts with part numbers and suppliers.
12. Complete original-issue documentation, installation, and maintenance information for furnished third-party hardware including computer equipment and sensors.
13. Complete original-issue copies of furnished software, including operating systems, custom programming language, operator workstation or web server software, and graphics software.
14. Licenses, guarantees, and warranty documents for equipment and systems.
15. Recommended preventive maintenance procedures for system components, including schedule of tasks such as inspection, cleaning, and calibration; time between tasks; and task descriptions.

- D. Training Materials: Provide course outline and materials for each class at least six weeks before first class. Training shall be furnished via instructor-led sessions, computer-based training, or web-based training. Engineer will modify course outlines and materials if necessary to meet Owner's needs. Engineer will review and approve course outlines and materials at least three weeks before first class.

1.10 Warranty

A. Warrant work as follows:

1. Warrant labor and materials for specified control system free from defects for a period of 12 months after final acceptance. Control system failures during warranty period shall be adjusted, repaired, or replaced at no additional cost or reduction in service to Owner. Respond during normal business hours within 24 hours of Owner's warranty service request.
2. Work shall have a single warranty date, even if Owner receives beneficial use due to early system start-up. If specified work is split into multiple contracts or a multi-phase contract, each contract or phase shall have a separate warranty start date and period.
3. If the engineer determines that equipment and systems operate satisfactorily at the end of final start-up, testing, and commissioning phase, the engineer will certify in writing that control system operation has been tested and accepted in accordance with the terms of this specification. Date of acceptance shall begin warranty period.
4. Provide updates to operator workstation or web server software, project-specific software, graphic software, database software, and firmware that resolve the contractor-identified software deficiencies at no charge during warranty period. If available, Owner can purchase in-warranty service agreement to receive upgrades for functional enhancements associated with above-mentioned items. Do not install updates or upgrades without Owner's written authorization.
5. Exception: Contractor shall not be required to warrant reused devices except those that have been rebuilt or repaired. Installation labor and materials shall be warranted. Demonstrate operable condition of reused devices at time of Engineer's acceptance.

1.11 Ownership of Proprietary Material

- A. Project-specific software and documentation shall become Owner's property. This includes, but is not limited to:
1. Graphics
 2. Record drawings
 3. Database
 4. Application programming code
 5. Documentation

1.12 Definitions

Term	Definition
BACnet Interoperability Building Blocks (BIBB)	A BIBB defines a small portion of BACnet functionality that is needed to perform a particular task. BIBBS are combined to build the BACnet functional requirements for a device in a specification.

Term	Definition
BACnet/BACnet Standard	BACnet communication requirements as defined by the latest version of ASHRAE/ANSI 135 and approved addenda.
Control Systems Server	A computer(s) that maintain(s) the systems configuration and programming database.
Controller	Intelligent stand-alone control device. Controller is a generic reference to building controllers, custom application controllers, and application specific controllers.
Direct Digital Control	Microprocessor-based control including Analog/Digital conversion and program logic.
Gateway	Bi-directional protocol translator connecting control systems that use different communication protocols.
Local Area Network	Computer or control system communications network limited to local building or campus.
Master-Slave/Token Passing	Data link protocol as defined by the BACnet standard.
Point-to-Point	Serial communication as defined in the BACnet standard.
Primary Controlling LAN	High speed, peer-to-peer controller LAN connecting BCs and optionally AACs and ASCs. Refer to System Architecture below.
Protocol Implementation Conformance Statement	A written document that identifies the particular options specified by BACnet that are implemented in a device.
Router	A device that connects two or more networks at the network layer.
Wiring	Raceway, fittings, wire, boxes and related items.

PART 2 - PRODUCTS

2.1 Materials

- A. Use new products the manufacturer is currently manufacturing and selling for use in new installations. Do not use this installation as a product test site unless explicitly approved in writing by Owner. Spare parts shall be available for at least five years after completion of this contract.

2.2 Communication

- A. Control products, communication media, connectors, repeaters, hubs, and routers shall comprise a BACnet internetwork. Controller and operator interface communication shall conform to ANSI/ASHRAE Standard 135, BACnet.
- B. Install new wiring and network devices as required to provide a complete and workable control network.

- C. Each controller shall have a communication port for temporary connection to a laptop computer or other operator interface. Connection shall support memory downloads and other commissioning and troubleshooting operations.
- D. Internetwork operator interface and value passing shall be transparent to internetwork architecture.
 - 1. An operator interface connected to a controller shall allow the operator to interface with each internetwork controller as if directly connected. Controller information such as data, status, and control algorithms shall be viewable and editable from each internetwork controller.
 - 2. Inputs, outputs, and control variables used to integrate control strategies across multiple controllers shall be readable by each controller on the internetwork. Program and test all cross-controller links required to execute control strategies specified in Section 23 09 93. An authorized operator shall be able to edit cross-controller links by typing a standard object address or by using a point-and-click interface.
- E. Workstations, Building Control Panels, and Controllers with real-time clocks shall use the BACnet Time Synchronization service. System shall automatically synchronize system clocks daily from an operator-designated device via the internetwork. The system shall automatically adjust for daylight saving and standard time as applicable.
- F. System shall be expandable to at least twice the required input and output objects with additional controllers, associated devices, and wiring.
- G. System shall support Web services data exchange with any other system that complies with XML (extensible markup language) and SOAP (simple object access protocol) standards. Web services support shall as a minimum be provided at the workstation or web server level and shall enable data to be read from or written to the system.
 - 1. System shall support Web services read data requests by retrieving requested trend data or point values (I/O hardware points, analog value software points, or binary value software points) from any system controller or from the trend history database.
 - 2. System shall support Web services write data request to each analog and binary object that can be edited through the system operator interface by downloading a numeric value to the specified object.
 - 3. For read or write requests, the system shall require user name and password authentication and shall support SSL (Secure Socket Layer) or equivalent data encryption.
 - 4. System shall support discovery through a Web services connection or shall provide a tool available through the Operator Interface that will reveal the path/identifier needed to allow a third party Web services device to read data from or write data to any object in the system which supports this service.

2.3 Operator Interface

- A. Operator Interface. Web server shall reside on high-speed network with building controllers. Each standard browser connected to server shall be able to access all system information. The Operator Workstation or server shall conform to the BACnet Operator Workstation (B-OWS) or BACnet Advanced Workstation (B-AWS) device profile as specified in ASHRAE/ANSI 135 BACnet Annex L.

- B. Communication. Web server or workstation and controllers shall communicate using BACnet protocol. Web server or workstation and control network backbone shall communicate using ISO 8802-3 (Ethernet) Data Link/Physical layer protocol and BACnet/IP addressing as specified in ANSI/ASHRAE 135, BACnet Annex J.
- C. Hardware.
1. Workstation or web server. Industry-standard hardware shall meet or exceed DDC system manufacturer's recommended specifications and shall meet response times specified elsewhere in this document. The following hardware requirements also apply:
 - a. The hard disk shall have sufficient memory to store:
 - 1) All required operator workstation software.
 - 2) A DDC database at least twice the size of the delivered system database.
 - 3) One year of trend data based on the points specified to be trended at their specified trend intervals.
 - b. Provide additional hardware (communication ports, video drivers, network interface cards, cabling, etc.) to facilitate all control functions and software requirements specified for the DDC system.
 - c. Minimum hardware configuration shall include the following:
 - 1) Quad Core Processor
 - 2) 8 GB RAM
 - 3) 1 TB hard disk providing data at 3.0 Gb/sec
 - 4) 16x DVD+/-RW drive
 - 5) Serial, parallel, and network communication ports and cables as required for proper DDC system operation
- D. System Software.
1. Operating System. Web server or workstation shall have an industry-standard professional-grade operating system. Operating system shall meet or exceed the DDC System manufacturers minimum requirements for their software. Acceptable systems include Microsoft Windows 7 or 8, Microsoft Vista, Windows Server 2008 or 2012, Red Hat Enterprise Linux, or Ubuntu Desktop 12.04.
 2. System Graphics. The operator interface software shall be graphically based and shall include at least one graphic per piece of equipment or occupied zone, graphics for each chilled water and hot water system, and graphics that summarize conditions on each floor of each building included in this contract. Indicate thermal comfort on floor plan summary graphics using dynamic colors to represent zone temperature relative to zone setpoint.
 - a. Functionality. Graphics shall allow operator to monitor system status, to view a summary of the most important data for each controlled zone or piece of equipment, to use point-and-click navigation between zones or equipment, and to edit setpoints and other specified parameters.
 - b. Animation. Graphics shall be able to animate by displaying different image files for changed object status.
 - c. Alarm Indication. Indicate areas or equipment in an alarm condition using color or other visual indicator.
 - d. Format. Graphics shall be saved in an industry-standard format such as BMP, JPEG, PNG, or GIF. Web-based system graphics shall be viewable on browsers compatible with World Wide Web Consortium browser standards. Web graphic format shall require no plug-in or shall only require widely available no-cost plug-ins (such as Adobe Flash).
 3. Custom Graphics. Custom graphic files shall be created with the use of a graphics generation package furnished with the system. The graphics generation package shall be a

- graphically based system that uses the mouse to create and modify graphics that are saved in the same formats as are used for system graphics.
4. Graphics Library. Furnish a complete library of standard HVAC equipment graphics such as chillers, boilers, air handlers, terminals, fan coils, and unit ventilators. This library also shall include standard symbols for other equipment including fans, pumps, coils, valves, piping, dampers, and ductwork. The library shall be furnished in a file format compatible with the graphics generation package program.
- E. System Applications. System shall provide the following functionality to authorized operators as an integral part of the operator interface or as stand-alone software programs. If furnished as part of the interface, the tool shall be available from each workstation or web browser interface. If furnished as a stand-alone program, software shall be installable on standard IBM-compatible PCs with no limit on the number of copies that can be installed under the system license.
1. Automatic System Database Configuration. Each workstation or web server shall store on its hard disk a copy of the current system database, including controller firmware and software. Stored database shall be automatically updated with each system configuration or controller firmware or software change.
 2. Manual Controller Memory Download. Operators shall be able to download memory from the system database to each controller.
 3. System Configuration. The workstation software shall provide a method of configuring the system. This shall allow for future system changes or additions by users under proper password protection. Operators shall be able to configure the system.
 4. On-Line Help. Provide a context-sensitive, on-line help system to assist the operator in operating and editing the system. On-line help shall be available for all applications and shall provide the relevant data for that particular screen. Additional help information shall be available through the use of hypertext.
 5. Security. Each operator shall be required to log on to the system with user name and password in order to view, edit, add, or delete data.
 - a. Operator Access. The user name and password combination shall define accessible viewing, editing, adding, and deleting privileges for that operator. Users with system administrator rights shall be able to create new users and edit the privileges of all existing users.
 - b. Automatic Log Out. Automatically log out each operator if no keyboard or mouse activity is detected. This auto logoff time shall be user adjustable.
 - c. Encrypted Security Data. Store system security data including operator passwords in an encrypted format. System shall not display operator passwords.
 6. System Diagnostics. The system shall automatically monitor the operation of all building management panels and controllers. The failure of any device shall be annunciated to the operator.
 7. Alarm Processing. System input and status objects shall be configurable to alarm on departing from and on returning to normal state. Operator shall be able to enable or disable each alarm and to configure alarm limits, alarm limit differentials, alarm states, and alarm reactions for each system object. Configure and enable alarm points as specified in Section 23 09 93 (Sequences of Operation). Alarms shall be BACnet alarm objects and shall use BACnet alarm services.
 8. Alarm Messages. Alarm messages shall use the English language descriptor for the object in alarm in such a way that the operator will be able to recognize the source, location, and nature of the alarm without relying on acronyms or mnemonics.
 9. Alarm Reactions. Operator shall be able to configure (by object) what, if any actions are to be taken during an alarm. As a minimum, the workstation or web server shall be able to

- log, print, start programs, display messages, send e-mail, send page, and audibly announce.
10. Alarm and Event log. Operators shall be able to view all system alarms and changes of state from any location in the system. Events shall be listed chronologically. An operator with the proper security level may acknowledge and delete alarms, and archive closed alarms to the workstation or web server hard disk.
 11. Trend Logs. The operator shall be able to configure trend sample or change of value (COV) interval, start time, and stop time for each system data object and shall be able to retrieve data for use in spreadsheets and standard database programs. Controller shall sample and store trend data and shall be able to archive data to the hard disk. Configure trends as specified in Section 23 09 93 (Sequences of Operation). Trends shall be BACnet trend objects.
 12. Object and Property Status and Control. Provide a method for the operator to view, and edit if applicable, the status of any object or property in the system. The status shall be available by menu, on graphics, or through custom programs.
 13. Reports and Logs. Operator shall be able to select, to modify, to create, and to print reports and logs. Operator shall be able to store report data in a format accessible by standard spreadsheet and word processing programs.
 14. Standard Reports. Furnish the following standard system reports:
 - a. Objects. System objects and current values filtered by object type, by status (in alarm, locked, normal), by equipment, by geographic location, or by combination of filter criteria.
 - b. Alarm Summary. Current alarms and closed alarms. System shall retain closed alarms for an adjustable period.
 - c. Logs. System shall log the following to a database or text file and shall retain data for an adjustable period:
 - 1) Alarm History.
 - 2) Trend Data. Operator shall be able to select trends to be logged.
 - 3) Operator Activity. At a minimum, system shall log operator log in and log out, control parameter changes, schedule changes, and alarm acknowledgment and deletion. System shall date and time stamp logged activity.
 15. Custom Reports. Operator shall be able to create custom reports that retrieve data, including archived trend data, from the system, that analyze data using common algebraic calculations, and that present results in tabular or graphical format. Reports shall be launched from the operator interface.
- F. Workstation Application Editors. Each PC or browser workstation shall support editing of all system applications. The applications shall be downloaded and executed at one or more of the controller panels.
1. Controller. Provide a full-screen editor for each type of application that shall allow the operator to view and change the configuration, name, control parameters, and set points for all controllers.
 2. Scheduling. An editor for the scheduling application shall be provided at each workstation. Provide a method of selecting the desired schedule and schedule type. Exception schedules and holidays shall be shown clearly on the calendar. The start and stop times for each object shall be adjustable from this interface.
 3. Custom Application Programming. Provide the tools to create, edit, debug, and download custom programs. System shall be fully operable while custom programs are edited, compiled, and downloaded. Programming language shall have the following features:

- a. Language. Language shall be graphically based and shall use function blocks arranged in a logic diagram that clearly shows control logic flow. Function blocks shall directly provide functions listed below, and operators shall be able to create custom or compound function blocks.
- b. Programming Environment. Tool shall provide a full-screen, cursor-and-mouse-driven programming environment that incorporates word processing features such as cut and paste. Operators shall be able to insert, add, modify, and delete custom programming code, and to copy blocks of code to a file library for reuse in other control programs.
- c. Independent Program Modules. Operator shall be able to develop independently executing program modules that can disable, enable and exchange data with other program modules.
- d. Debugging and Simulation. Operator shall be able to step through the program observing intermediate values and results. Operator shall be able to adjust input variables to simulate actual operating conditions. Operator shall be able to adjust each step's time increment to observe operation of delays, integrators, and other time-sensitive control logic. Debugger shall provide error messages for syntax and for execution errors.
- e. Conditional Statements. Operator shall be able to program conditional logic using compound Boolean (AND, OR, and NOT) and relational (EQUAL, LESS THAN, GREATER THAN, NOT EQUAL) comparisons.
- f. Mathematical Functions. Language shall support floating-point addition, subtraction, multiplication, division, and square root operations, as well as absolute value calculation and programmatic selection of minimum and maximum values from a list of values.
- g. Variables. Operator shall be able to use variable values in program conditional statements and mathematical functions.
 - 1) Time Variables. Operator shall be able to use predefined variables to represent time of day, day of the week, month of the year, and date. Other predefined variables or simple control logic shall provide elapsed time in seconds, minutes, hours, and days. Operator shall be able to start, stop, and reset elapsed time variables using the program language.
 - 2) System Variables. Operator shall be able to use predefined variables to represent status and results of Controller Software and shall be able to enable, disable, and change setpoints of Controller Software as described in Controller Software section.

- G. Portable Operator's Terminal. Provide all necessary software to configure an IBM-compatible laptop computer for use as a Portable Operator's Terminal. Operator shall be able to connect configured Terminal to the system network or directly to each controller for programming, setting up, and troubleshooting.

2.4 Controller Software

- A. Furnish the following applications for building and energy management. All software application shall reside and operate in the system controllers. Applications shall be editable through operator workstation, web browser interface, or engineering workstation.
- B. System Security. See Paragraph 2.3.E.5 (Security) and Paragraph 2.3.E.14.c.iii (Operator Activity).

- C. Scheduling. Provide the capability to execute control functions according to a user created or edited schedule. Each schedule shall provide the following schedule options as a minimum:
 - 1. Weekly Schedule. Provide separate schedules for each day of the week. Each schedule shall be able to include up to 5 occupied periods (5 start-stop pairs or 10 events).
 - 2. Exception Schedules. Provide the ability for the operator to designate any day of the year as an exception schedule. Exception schedules may be defined up to a year in advance. Once an exception schedule has executed, the system shall discard and replace the exception schedule with the standard schedule for that day of the week.
 - 3. Holiday Schedules. Provide the capability for the operator to define up to 24 special or holiday schedules. These schedules will be repeated each year. The operator shall be able to define the length of each holiday period.
- D. System Coordination. Operator shall be able to group related equipment based on function and location and to use these groups for scheduling and other applications.
- E. Binary Alarms. Each binary object shall have the capability to be configured to alarm based on the operator-specified state. Provide the capability to automatically and manually disable alarming.
- F. Analog Alarms. Each analog object shall have both high and low alarm limits. The operator shall be able to enable or disable these alarms.
- G. Alarm Reporting. The operator shall be able to determine the action to be taken in the event of an alarm. An alarm shall be able to start programs, print, be logged in the event log, generate custom messages, and display on graphics.
- H. Remote Communication. System shall automatically contact operator workstation or server on receipt of critical alarms. If no network connection is available, system shall use a modem connection.
- I. Demand Limiting.
 - 1. The demand-limiting program shall monitor building power consumption from a building power meter (provided by others) which generates pulse signals or a BACnet communications interface. An acceptable alternative is for the system to monitor a watt transducer or current transformer attached to the building feeder lines.
 - 2. When power consumption exceeds adjustable levels, system shall automatically adjust setpoints, de-energize low-priority equipment, and take other programmatic actions to reduce demand as specified in Section 23 09 93 (Sequences of Operation). When demand drops below adjustable levels, system shall restore loads as specified.
- J. Maintenance Management. The system shall be capable of generating maintenance alarms when equipment exceeds adjustable runtime, equipment starts, or performance limits. Configure and enable maintenance alarms as specified in 23 09 93 (Sequences of Operation).
- K. Sequencing. Application software shall sequence chillers, boilers, and pumps as specified in Section 23 09 93 (Sequences of Operation).
- L. PID Control. System shall provide direct- and reverse-acting PID (proportional-integral-derivative) algorithms. Each algorithm shall have anti-windup and selectable controlled variable, setpoint, and PID gains. Each algorithm shall calculate a time-varying analog value that can be

used to position an output or to stage a series of outputs. The calculation interval, PID gains, and other tuning parameters shall be adjustable by a user with the correct security level.

- M. Staggered Start. System shall stagger controlled equipment restart after power outage. Operator shall be able to adjust equipment restart order and time delay between equipment restarts.
- N. Energy Calculations.
 - 1. The system shall accumulate and convert instantaneous power (kW) or flow rates (L/s gpm) to energy usage data.
 - 2. The system shall calculate a sliding-window average (rolling average). Operator shall be able to adjust window interval to 15 minutes, 30 minutes, or 60 minutes.
- O. Anti-Short Cycling. All binary output objects shall be protected from short cycling by means of adjustable minimum on-time and off-time settings.
- P. On and Off Control with Differential. Provide an algorithm that allows a binary output to be cycled based on a controlled variable and a setpoint. The algorithm shall be direct-acting or reverse-acting.
- Q. Runtime Totalization. Provide software to totalize runtime for each binary input and output. Operator shall be able to enable runtime alarm based on exceeded adjustable runtime limit. Configure and enable runtime totalization and alarms as specified in Section 23 09 93 (Sequence of Operations).

2.5 Controllers

- A. General. Provide an adequate number of Building Controllers (BC), Advanced Application Controllers (AAC), Application Specific Controllers (ASC), Smart Actuators (SA), and Smart Sensors (SS) as required to achieve performance specified in Section 23 09 23 Article 1.9 (System Performance). Every device in the system which executes control logic and directly controls HVAC equipment must conform to a standard BACnet Device profile as specified in ANSI/ASHRAE 135, BACnet Annex L. Unless otherwise specified, hardwired actuators and sensors may be used in lieu of BACnet Smart Actuators and Smart Sensors.
- B. BACnet.
 - 1. Building Controllers (BCs). Each BC shall conform to BACnet Building Controller (B-BC) device profile as specified in ANSI/ASHRAE 135, BACnet Annex L, and shall be listed as a certified B-BC in the BACnet Testing Laboratories (BTL) Product Listing.
 - 2. Advanced Application Controllers (AACs). Each AAC shall conform to BACnet Advanced Application Controller (B-AAC) device profile as specified in ANSI/ASHRAE 135, BACnet Annex L and shall be listed as a certified B-AAC in the BACnet Testing Laboratories (BTL) Product Listing.
 - 3. Application Specific Controllers (ASCs). Each ASC shall conform to BACnet Application Specific Controller (B-ASC) device profile as specified in ANSI/ASHRAE 135, BACnet Annex L and shall be listed as a certified B-ASC in the BACnet Testing Laboratories (BTL) Product Listing.
 - 4. Smart Sensors (SSs). Each SS shall conform to BACnet Smart Sensor (B-SS) device profile as specified in ANSI/ASHRAE 135, BACnet Annex L and shall be listed as a certified B-SS in the BACnet Testing Laboratories (BTL) Product Listing.
 - 5. BACnet Communication.

6. Each BC shall reside on or be connected to a BACnet network using ISO 8802-3 (Ethernet) Data Link/Physical layer protocol and BACnet/IP addressing.
7. BACnet routing shall be performed by BCs or other BACnet device routers as necessary to connect BCs to networks of AACs and ASCs.
8. Each AAC shall reside on a BACnet network using ISO 8802-3 (Ethernet) Data Link/Physical layer protocol with BACnet/IP addressing, or it shall reside on a BACnet network using the ARCNET or MS/TP Data Link/Physical layer protocol.
9. Each ASC shall reside on a BACnet network using the ARCNET or MS/TP Data Link/Physical layer protocol.
10. Each SA shall reside on a BACnet network using the ARCNET or MS/TP Data Link/Physical layer protocol.
11. Each SS shall reside on a BACnet network using ISO 8802-3 (Ethernet) Data Link/Physical layer protocol with BACnet/IP addressing, or it shall reside on a BACnet network using ARCNET or MS/TP Data Link/Physical layer protocol.

C. Communication

1. Service Port. Each controller shall provide a service communication port for connection to a Portable Operator's Terminal. Connection shall be extended to space temperature sensor ports where shown on drawings.
2. Signal Management. BC and ASC operating systems shall manage input and output communication signals to allow distributed controllers to share real and virtual object information and to allow for central monitoring and alarms.
3. Data Sharing. Each BC and AAC shall share data as required with each networked BC and AAC.
4. Stand-Alone Operation. Each piece of equipment specified in Section 23 09 93 shall be controlled by a single controller to provide stand-alone control in the event of communication failure. All I/O points specified for a piece of equipment shall be integral to its controller. Provide stable and reliable stand-alone control using default values or other method for values normally read over the network such as outdoor air conditions, supply air or water temperature coming from source equipment, etc.

D. Environment. Controller hardware shall be suitable for anticipated ambient conditions.

1. Controllers used outdoors or in wet ambient conditions shall be mounted in waterproof enclosures and shall be rated for operation at -29°C to 60°C (-20°F to 140°F).
2. Controllers used in conditioned space shall be mounted in dust-protective enclosures and shall be rated for operation at 0°C to 50°C (32°F to 120°F).

E. Keypad. Provide a local keypad and display for each BC and AAC. Operator shall be able to use keypad to view and edit data. Keypad and display shall require password to prevent unauthorized use. If the manufacturer does not normally provide a keypad and display for each BC and AAC, provide the software and any interface cabling needed to use a laptop computer as a Portable Operator's Terminal for the system.

F. Real-Time Clock. Controllers that perform scheduling shall have a real-time clock.

G. Serviceability. Provide diagnostic LEDs for power, communication, and processor. All wiring connections shall be made to a field-removable modular terminal strip or to a termination card connected by a ribbon cable. Each BC and AAC shall continually check its processor and memory circuit status and shall generate an alarm on abnormal operation. System shall continuously check controller network and generate alarm for each controller that fails to respond.

- H. Memory.
 - 1. Controller memory shall support operating system, database, and programming requirements.
 - 2. Each BC and AAC shall retain BIOS and application programming for at least 72 hours in the event of power loss.
 - 3. Each ASC and SA shall use nonvolatile memory and shall retain BIOS and application programming in the event of power loss. System shall automatically download dynamic control parameters following power loss.
- I. Immunity to Power and Noise. Controllers shall be able to operate at 90% to 110% of nominal voltage rating and shall perform an orderly shutdown below 80% nominal voltage. Operation shall be protected against electrical noise of 5 to 120 Hz and from keyed radios up to 5 W at 1 m (3 ft).
- J. Transformer. ASC power supply shall be fused or current limiting and shall be rated at a minimum of 125% of ASC power consumption.

2.6 Input and Output Interface

- A. General. Hard-wire input and output points to BCs, AACs, ASCs, or SAs.
- B. Protection. All input points and output points shall be protected such that shorting of the point to itself, to another point, or to ground shall cause no damage to the controller. All input and output points shall be protected from voltage up to 24 V of any duration, such that contact with this voltage will cause no controller damage.
- C. Binary Inputs. Binary inputs shall allow the monitoring of ON/OFF signals from remote devices. The binary inputs shall provide a wetting current of at least 12 mA to be compatible with commonly available control devices and shall be protected against contact bounce and noise. Binary inputs shall sense dry contact closure without application of power external to the controller.
- D. Pulse Accumulation Inputs. Pulse accumulation inputs shall conform to binary input requirements and shall also accumulate up to 10 pulses per second.
- E. Analog Inputs. Analog inputs shall allow the monitoring of low-voltage (0–10 Vdc), current (4–20 mA), or resistance (thermistor or RTD) signals. Analog inputs shall be compatible with and field configurable to commonly available sensing devices.
- F. Binary Outputs. Binary outputs shall provide for ON/OFF operation or a pulsed low-voltage signal for pulse width modulation control. Binary outputs on Building Controllers shall have three-position (on-off-auto) override switches and status lights. Outputs shall be selectable for normally open or normally closed operation.
- G. Analog Outputs. Analog outputs shall provide a modulating signal for the control of end devices. Outputs shall provide either a 0–10 Vdc or a 4–20 mA signal as required to properly control output devices. Each Building Controller analog output shall have a two-position (auto-manual) switch, a manually adjustable potentiometer, and status lights. Analog outputs shall not drift more than 0.4% of range annually.

- H. Tri-State Outputs. Control three-point floating electronic actuators without feedback with tri-state outputs (two coordinated binary outputs). Tri-State outputs may be used to provide analog output control in zone control and terminal unit control applications such as VAV terminal units, duct-mounted heating coils, and zone dampers.
- I. Universal Inputs and Outputs. Inputs and outputs that can be designated as either binary or analog in software shall conform to the provisions of this section that are appropriate for their designated use.
- J. System Object Capacity. The system size shall be expandable to at least twice the number of input/ output objects required for this project. Additional controllers (along with associated devices and wiring) shall be all that is necessary to achieve this capacity requirement. The operator interfaces installed for this project shall not require any hardware additions or software revisions in order to expand the system

2.7 Power Supplies and Line Filtering

- A. Power Supplies. Control transformers shall be UL listed. Furnish Class 2 current-limiting type or furnish over-current protection in primary and secondary circuits for Class 2 service in accordance with NEC requirements. Limit connected loads to 80% of rated capacity.
 - 1. DC power supply output shall match output current and voltage requirements. Unit shall be full-wave rectifier type with output ripple of 5.0 mV maximum peak-to-peak. Regulation shall be 1.0% line and load combined, with 100-microsecond response time for 50% load changes. Unit shall have built-in over-voltage and over-current protection and shall be able to withstand 150% current overload for at least three seconds without trip-out or failure.
 - a. Unit shall operate between 0°C and 50°C (32°F and 120°F). EM/RF shall meet FCC Class B and VDE 0871 for Class B and MILSTD 810C for shock and vibration.
 - b. Line voltage units shall be UL recognized and CSA listed.
- B. Power Line Filtering.
 - 1. Provide internal or external transient voltage and surge suppression for workstations and controllers. Surge protection shall have:
 - a. Dielectric strength of 1000 V minimum
 - b. Response time of 10 nanoseconds or less
 - c. Transverse mode noise attenuation of 65 dB or greater
 - d. Common mode noise attenuation of 150 dB or greater at 40–100 Hz

2.8 Auxiliary Control Devices

- A. Motorized Control Dampers, unless otherwise specified elsewhere, shall be as follow.
 - 1. Type. Control dampers shall be the parallel or opposed-blade type as specified below or as scheduled on drawings.
 - a. Outdoor and return air mixing dampers and face-and-bypass dampers shall be parallel-blade and shall direct airstreams toward each other.
 - b. Other modulating dampers shall be opposed-blade.
 - c. Two-position shutoff dampers shall be parallel- or opposed-blade with blade and side seals.

2. Frame. Damper frames shall be 2.38 mm (13 gauge) galvanized steel channel or 3.175 mm (1/8 in.) extruded aluminum with reinforced corner bracing.
3. Blades. Damper blades shall not exceed 20 cm (8 in.) in width or 125 cm (48 in.) in length. Blades shall be suitable for medium velocity (10 m/s 2000 fpm) performance. Blades shall be not less than 1.5875 mm (16 gauge).
4. Shaft Bearings. Damper shaft bearings shall be as recommended by manufacturer for application, oil impregnated sintered bronze, or better.
5. Seals. Blade edges and frame top and bottom shall have replaceable seals of butyl rubber or neoprene. Side seals shall be spring-loaded stainless steel. Blade seals shall leak no more than 50 L/s·m² (10 cfm per ft²) at 1000 Pa (4 in. w.g.) differential pressure. Blades shall be airfoil type suitable for wide-open face velocity of 7.5 m/s (1500 fpm).
6. Sections. Individual damper sections shall not exceed 125 cm × 150 cm (48 in. × 60 in.). Each section shall have at least one damper actuator.
7. Modulating dampers shall provide a linear flow characteristic where possible.
8. Linkages. Dampers shall have exposed linkages.

B. Electric Damper and Valve Actuators.

1. Stall Protection. Mechanical or electronic stall protection shall prevent actuator damage throughout the actuator's rotation.
2. Spring-return Mechanism. Actuators used for power-failure and safety applications shall have an internal mechanical spring-return mechanism or an uninterruptible power supply (UPS).
3. Signal and Range. Proportional actuators shall accept a 0–10 Vdc or a 0–20 mA control signal and shall have a 2–10 Vdc or 4–20 mA operating range. (Floating motor actuators may be substituted for proportional actuators in terminal unit applications as described in paragraph 2.6H.)
4. Wiring. 24 Vac and 24 Vdc actuators shall operate on Class 2 wiring.
5. Manual Positioning. Operators shall be able to manually position each actuator when the actuator is not powered. Non-spring-return actuators shall have an external manual gear release. Spring-return actuators with more than 7 N·m (60 in.-lb) torque capacity shall have a manual crank.

C. Binary Temperature Devices.

1. Low-Voltage Space Thermostats. Low-voltage space thermostats shall be 24 V, bimetal-operated, mercury-switch type, with adjustable or fixed anticipation heater, concealed setpoint adjustment, 13°C–30°C (55°F–85°F) setpoint range, 1°C (2°F) maximum differential, and vented ABS plastic cover.
2. Line-Voltage Space Thermostats. Line-voltage space thermostats shall be bimetal-actuated, open-contact type or bellows-actuated, enclosed, snap-switch type or equivalent solid-state type, with heat anticipator, UL listing for electrical rating, concealed setpoint adjustment, 13°C–30°C (55°F–85°F) setpoint range, 1°C (2°F) maximum differential, and vented ABS plastic cover.
3. Low-Limit Thermostats. Low-limit airstream thermostats shall be UL listed, vapor pressure type. Element shall be at least 6 m (20 ft) long. Element shall sense temperature in each 30 cm (1 ft) section and shall respond to lowest sensed temperature. Low-limit thermostat shall be manual reset only.

D. Temperature Sensors.

1. Type. Temperature sensors shall be Resistance Temperature Device (RTD) or thermistor.
2. Duct Sensors. Duct sensors shall be single point or averaging as shown. Averaging sensors shall be a minimum of 1.5 m (5 ft) in length per 1 m² (10 ft²) of duct cross-section.

3. Immersion Sensors. Provide immersion sensors with a separable stainless steel well. Well pressure rating shall be consistent with system pressure it will be immersed in. Well shall withstand pipe design flow velocities.
 4. Space Sensors. Space sensors shall have setpoint adjustment, override switch, display, and communication port as shown.
 5. Differential Sensors. Provide matched sensors for differential temperature measurement.
- E. Humidity Sensors.
1. Duct and room sensors shall have a sensing range of 20%–80%.
 2. Duct sensors shall have a sampling chamber.
 3. Outdoor air humidity sensors shall have a sensing range of 20%–95% RH and shall be suitable for ambient conditions of -40°C–75°C (-40°F–170°F).
 4. Humidity sensors shall not drift more than 1% of full scale annually.
- F. Flow Switches. Flow-proving switches shall be paddle (water service only) or differential pressure type (air or water service) as shown. Switches shall be UL listed, SPDT snap-acting, and pilot duty rated (125 VA minimum).
1. Paddle switches shall have adjustable sensitivity and NEMA 1 enclosure unless otherwise specified.
 2. Differential pressure switches shall have scale range and differential suitable for intended application and NEMA 1 enclosure unless otherwise specified.
- G. Relays.
1. Control Relays. Control relays shall be plug-in type, UL listed, and shall have dust cover and LED “energized” indicator. Contact rating, configuration, and coil voltage shall be suitable for application.
 2. Time Delay Relays. Time delay relays shall be solid-state plug-in type, UL listed, and shall have adjustable time delay. Delay shall be adjustable $\pm 100\%$ from setpoint shown. Contact rating, configuration, and coil voltage shall be suitable for application. Provide NEMA 1 enclosure for relays not installed in local control panel.
- H. Override Timers.
1. Unless implemented in control software, override timers shall be spring-wound line voltage, UL Listed, with contact rating and configuration required by application. Provide 0–6 hour calibrated dial unless otherwise specified. Flush mount timer on local control panel face or where shown.
- I. Current Transmitters.
1. AC current transmitters shall be self-powered, combination split-core current transformer type with built-in rectifier and high-gain servo amplifier with 4–20 mA two-wire output. Full-scale unit ranges shall be 10 A, 20 A, 50 A, 100 A, 150 A, and 200 A, with internal zero and span adjustment. Unit accuracy shall be $\pm 1\%$ full-scale at 500 ohm maximum burden.
 2. Transmitter shall meet or exceed ANSI/ISA S50.1 requirements and shall be UL/CSA recognized.
 3. Unit shall be split-core type for clamp-on installation on existing wiring.
- J. Current Transformers.
1. AC current transformers shall be UL/CSA recognized and shall be completely encased (except for terminals) in approved plastic material.

2. Transformers shall be available in various current ratios and shall be selected for $\pm 1\%$ accuracy at 5 A full-scale output.
 3. Use fixed-core transformers for new wiring installation and split-core transformers for existing wiring installation.
- K. Voltage Transmitters.
1. AC voltage transmitters shall be self-powered single-loop (two-wire) type, 4–20 mA output with zero and span adjustment.
 2. Adjustable full-scale unit ranges shall be 100–130 Vac, 200–250 Vac, 250–330 Vac, and 400–600 Vac. Unit accuracy shall be $\pm 1\%$ full-scale at 500 ohm maximum burden.
 3. Transmitters shall meet or exceed ANSI/ISA S50.1 requirements and shall be UL/CSA recognized at 600 Vac rating.
- L. Voltage Transformers.
1. AC voltage transformers shall be UL/CSA recognized, 600 Vac rated, and shall have built-in fuse protection.
 2. Transformers shall be suitable for ambient temperatures of 4°C–55°C (40°F–130°F) and shall provide $\pm 0.5\%$ accuracy at 24 Vac and 5 VA load.
 3. Windings (except for terminals) shall be completely enclosed with metal or plastic.
- M. Power Monitors.
1. Selectable rate pulse output for kWh reading, 4–20 mA output for kW reading, N.O. alarm contact, and ability to operate with 5.0 amp current inputs or 0–0.33 volt inputs.
 2. 1.0% full-scale true RMS power accuracy, ± 0.5 Hz, voltage input range 120–600 V, and auto range select.
 3. Under voltage/phase monitor circuitry.
 4. NEMA 1 enclosure.
 5. Current transformers having a 0.5% FS accuracy, 600 VAC isolation voltage with 0–0.33 V output. If 0–5 A current transformers are provided, a three-phase disconnect/shorting switch assembly is required.
- N. Differential Pressure Switches. Differential pressure switches (air or water service) shall be UL listed, SPDT snap-acting, pilot duty rated (125 VA minimum) and shall have scale range and differential suitable for intended application and NEMA 1 enclosure unless otherwise specified.
- O. Pressure-Electric (PE) Switches.
1. Shall be metal or neoprene diaphragm actuated, operating pressure rated for 0–175 kPa (0–25 psig), with calibrated scale minimum setpoint range of 14–125 kPa (2–18 psig) minimum, UL listed.
 2. Provide one- or two-stage switch action (SPDT, DPST, or DPDT) as required by application. Electrically rated for pilot duty service (125 VA minimum) and/or for motor control.
 3. Switches shall be open type (panel-mounted) or enclosed type for remote installation. Enclosed type shall be NEMA 1 unless otherwise specified.
 4. Each pneumatic signal line to PE switches shall have permanent indicating gauge.
- P. Occupancy Sensors. Occupancy sensors shall utilize Passive Infrared (PIR) and/or Microphonic Passive technology to detect the presence of people within a room. Sensors shall be mounted as indicated on the approved drawings. The sensor output shall be accessible by any lighting and/or HVAC controller in the system. Occupancy sensors shall be capable of being powered from the lighting or HVAC control panel, as shown on the drawings. Occupancy sensor delay shall be

software adjustable through the user interface and shall not require manual adjustment at the sensor.

Q. Local Control Panels.

1. All indoor control cabinets shall be fully enclosed NEMA 1 construction with (hinged door) key-lock latch and removable subpanels. A single key shall be common to all field panels and subpanels.
2. Interconnections between internal and face-mounted devices shall be prewired with color-coded stranded conductors neatly installed in plastic troughs and/or tie-wrapped. Terminals for field connections shall be UL listed for 600 volt service, individually identified per control/ interlock drawings, with adequate clearance for field wiring. Control terminations for field connection shall be individually identified per control drawings.
3. Provide ON/OFF power switch with overcurrent protection for control power sources to each local panel.

R. Wiring and Raceways

1. General. Provide copper wiring, plenum cable, and raceways as specified in applicable sections of Division 26.
2. Insulated wire shall use copper conductors and shall be UL listed for 90°C (200°F) minimum service.

S. Fiber Optic Cable System

1. Optical Cable. Optical cables shall be duplex 900 mm tight-buffer construction designed for intra-building environments. Sheath shall be UL listed OFNP in accordance with NEC Article 770. Optical fiber shall meet the requirements of FDDI, ANSI X3T9.5 PMD for 62.5/125mm.
2. Connectors. Field terminate optical fibers with ST type connectors. Connectors shall have ceramic ferrules and metal bayonet latching bodies.

PART 3 - EXECUTION

3.1 Examination

- A. The contractor shall inspect the site to verify that equipment may be installed as shown. Any discrepancies, conflicts, or omissions shall be reported to the engineer for resolution before rough-in work is started.
- B. The contractor shall examine the drawings and specifications for other parts of the work. If head room or space conditions appear inadequate—or if any discrepancies occur between the plans and the contractor's work and the plans and the work of others—the contractor shall report these discrepancies to the engineer and shall obtain written instructions for any changes necessary to accommodate the contractor's work with the work of others. Any changes in the work covered by this specification made necessary by the failure or neglect of the contractor to report such discrepancies shall be made by—and at the expense of—this contractor.

3.2 Protection

- A. The contractor shall protect all work and material from damage by his/her work or employees and shall be liable for all damage thus caused.
- B. The contractor shall be responsible for his/her work and equipment until finally inspected, tested, and accepted. The contractor shall protect any material that is not immediately installed. The contractor shall close all open ends of work with temporary covers or plugs during storage and construction to prevent entry of foreign objects.

3.3 Coordination

- A. Site
 - 1. Where the mechanical work will be installed in close proximity to, or will interfere with, work of other trades, the contractor shall assist in working out space conditions to make a satisfactory adjustment. If the contractor installs his/her work before coordinating with other trades, so as to cause any interference with work of other trades, the contractor shall make the necessary changes in his/her work to correct the condition without extra charge.
 - 2. Coordinate and schedule work with other work in the same area and with work dependent upon other work to facilitate mutual progress.
- B. Submittals. See Section 23 09 23 Article 1.10 (Submittals).
- C. Test and Balance.
 - 1. The contractor shall furnish a single set of all tools necessary to interface to the control system for test and balance purposes.
 - 2. The contractor shall provide training in the use of these tools. This training will be planned for a minimum of 4 hours.
 - 3. In addition, the contractor shall provide a qualified technician to assist in the test and balance process, until the first 20 terminal units are balanced.
 - 4. The tools used during the test and balance process will be returned at the completion of the testing and balancing.
- D. Life Safety.
 - 1. Duct smoke detectors required for air handler shutdown are provided under Division 28. Interlock smoke detectors to air handlers for shutdown as specified in Section 23 09 93 (Sequences of Operation).
 - 2. Smoke dampers and actuators required for duct smoke isolation are provided under Division 23. Interlock smoke dampers to air handlers as specified in Section 23 09 93 (Sequences of Operation).
 - 3. Fire and smoke dampers and actuators required for fire-rated walls are provided under Division 23. Fire and smoke damper control is provided under Division 28.
- E. Coordination with controls specified in other sections or divisions. Other sections and/or divisions of this specification include controls and control devices that are to be part of or interfaced to the control system specified in this section. These controls shall be integrated into the system and coordinated by the contractor as follows:
 - 1. All communication media and equipment shall be provided as specified in Section 23 09 23 Article 2.2 (Communication).

2. Each supplier of a controls product is responsible for the configuration, programming, start up, and testing of that product to meet the sequences of operation described in Section 23 09 93.
3. The contractor shall coordinate and resolve any incompatibility issues that arise between control products provided under this section and those provided under other sections or divisions of this specification.
4. The contractor is responsible for providing all controls described in the contract documents regardless of where within the contract documents these controls are described.
5. The contractor is responsible for the interface of control products provided by multiple suppliers regardless of where this interface is described within the contract documents.

3.4 General Workmanship

- A. Install equipment, piping, and wiring/raceway parallel to building lines (i.e. horizontal, vertical, and parallel to walls) wherever possible.
- B. Provide sufficient slack and flexible connections to allow for vibration of piping and equipment.
- C. Install equipment in readily accessible locations as defined by Chapter 1 Article 100 Part A of the National Electrical Code (NEC).
- D. Verify integrity of all wiring to ensure continuity and freedom from shorts and grounds.
- E. All equipment, installation, and wiring shall comply with industry specifications and standards for performance, reliability, and compatibility and be executed in strict adherence to local codes and standard practices.

3.5 Field Quality Control

- A. All work, materials, and equipment shall comply with rules and regulations of applicable local, state, and federal codes and ordinances as identified in Section 23 09 23 Article 1.8 (Codes and Standards).
- B. Contractor shall continually monitor the field installation for code compliance and quality of workmanship.
- C. Contractor shall have work inspection by local and/or state authorities having jurisdiction over the work.

3.6 Wiring

- A. All control and interlock wiring shall comply with national and local electrical codes, and Division 26 of this specification. Where the requirements of this section differ from Division 26, the requirements of this section shall take precedence.
- B. All NEC Class 1 (line voltage) wiring shall be UL listed in approved raceway according to NEC and Division 26 requirements.

- C. All low-voltage wiring shall meet NEC Class 2 requirements. Low-voltage power circuits shall be subfused when required to meet Class 2 current limit.
- D. Where NEC Class 2 (current-limited) wires are in concealed and accessible locations, including ceiling return air plenums, approved cables not in raceway may be used provided that cables are UL listed for the intended application.
- E. All wiring in mechanical, electrical, or service rooms – or where subject to mechanical damage – shall be installed in raceway at levels below 3 m (10ft).
- F. Do not install Class 2 wiring in raceways containing Class 1 wiring. Boxes and panels containing high-voltage wiring and equipment may not be used for low-voltage wiring except for the purpose of interfacing the two (e.g. relays and transformers).
- G. Do not install wiring in raceway containing tubing.
- H. Where Class 2 wiring is run exposed, wiring is to be run parallel along a surface or perpendicular to it and neatly tied at 3 m (10 ft) intervals.
- I. Where plenum cables are used without raceway, they shall be supported from or anchored to structural members. Cables shall not be supported by or anchored to ductwork, electrical raceways, piping, or ceiling suspension systems.
- J. All wire-to-device connections shall be made at a terminal block or terminal strip. All wire-to-wire connections shall be at a terminal block.
- K. All wiring within enclosures shall be neatly bundled and anchored to permit access and prevent restriction to devices and terminals.
- L. Maximum allowable voltage for control wiring shall be 120 V. If only higher voltages are available, the contractor shall provide step-down transformers.
- M. All wiring shall be installed as continuous lengths, with no splices permitted between termination points.
- N. Install plenum wiring in sleeves where it passes through walls and floors. Maintain fire rating at all penetrations.
- O. Size of raceway and size and type of wire type shall be the responsibility of the contractor in keeping with the manufacturer's recommendations and NEC requirements, except as noted elsewhere.
- P. Include one pull string in each raceway 2.5 cm (1 in.) or larger.
- Q. Use color-coded conductors throughout with conductors of different colors.
- R. Control and status relays are to be located in designated enclosures only. These enclosures include packaged equipment control panel enclosures unless they also contain Class 1 starters.
- S. Conceal all raceways except within mechanical, electrical, or service rooms. Install raceway to maintain a minimum clearance of 15 cm (6 in.) from high-temperature equipment (e.g. steam pipes or flues).

- T. Secure raceways with raceway clamps fastened to the structure and spaced according to code requirements. Raceways and pull boxes may not be hung on flexible duct strap or tie rods. Raceways may not be run on or attached to ductwork.
- U. Adhere to this specification's Division 26 requirements where raceway crosses building expansion joints.
- V. Install insulated bushings on all raceway ends and openings to enclosures. Seal top end of vertical raceways.
- W. The contractor shall terminate all control and/or interlock wiring and shall maintain updated (as-built) wiring diagrams with terminations identified at the job site.
- X. Flexible metal raceways and liquid-tight flexible metal raceways shall not exceed 1 m (3 ft) in length and shall be supported at each end. Flexible metal raceway less than ½ in. electrical trade size shall not be used. In areas exposed to moisture, including chiller and boiler rooms, liquid-tight, flexible metal raceways shall be used.
- Y. Raceway must be rigidly installed, adequately supported, properly reamed at both ends, and left clean and free of obstructions. Raceway sections shall be joined with couplings (according to code). Terminations must be made with fittings at boxes, and ends not terminating in boxes shall have bushings installed.

3.7 Communication Wiring

- A. The contractor shall adhere to the items listed in the "Wiring" article in Part 3 of the specification.
- B. All cabling shall be installed in a neat and workmanlike manner. Follow manufacturer's installation recommendations for all communication cabling
- C. Do not install communication wiring in raceways and enclosures containing Class 1 or other Class 2 wiring.
- D. Maximum pulling, tension, and bend radius for the cable installation, as specified by the cable manufacturer, shall not be exceeded during installation.
- E. Contractor shall verify the integrity of the entire network following cable installation. Use appropriate test measures for each particular cable.
- F. When a cable enters or exits a building, a lightning arrestor must be installed between the lines and ground. The lightning arrestor shall be installed according to manufacturer's instructions.
- G. All runs of communication wiring shall be unspliced length when that length is commercially available.
- H. All communication wiring shall be labeled to indicate origination and destination data.
- I. Grounding of coaxial cable shall be in accordance with NEC regulations article on "Communications Circuits, Cable, and Protector Grounding."

- J. BACnet MS/TP communications wiring shall be installed in accordance with ASHRAE/ANSI Standard 135. This includes but is not limited to:
 - 1. The network shall use shielded, twisted-pair cable with characteristic impedance between 100 and 120 ohms. Distributed capacitance between conductors shall be less than 100 pF per meter (30 pF per foot.)
 - 2. The maximum length of an MS/TP segment is 1200 meters (4000 ft) with AWG 18 cable. The use of greater distances and/or different wire gauges shall comply with the electrical specifications of EIA-485.
 - 3. The maximum number of nodes per segment shall be 32, as specified in the EIA 485 standard. Additional nodes may be accommodated by the use of repeaters.
 - 4. An MS/TP EIA-485 network shall have no T connections.

3.8 Fiber Optic Cable

- A. Maximum pulling tensions as specified by the cable manufacturer shall not be exceeded during installation. Post-installation residual cable tension shall be within cable manufacturer's specifications.
- B. All cabling and associated components shall be installed in accordance with manufacturers' instructions. Minimum cable and unjacketed fiber bend radii, as specified by cable manufacturer, shall be maintained.
- C. Installation of Sensors
- D. Install sensors in accordance with the manufacturer's recommendations.
- E. Mount sensors rigidly and adequately for environment within which the sensor operates.
- F. Room temperature sensors shall be installed on concealed junction boxes properly supported by wall framing.
- G. All wires attached to sensors shall be sealed in their raceways or in the wall to stop air transmitted from other areas from affecting sensor readings.
- H. Sensors used in mixing plenums and hot and cold decks shall be of the averaging type. Averaging sensors shall be installed in a serpentine manner vertically across the duct. Each bend shall be supported with a capillary clip.
- I. Low-limit sensors used in mixing plenums shall be installed in a serpentine manner horizontally across duct. Each bend shall be supported with a capillary clip. Provide 3 m (1 ft) of sensing element for each 1 m²(1 ft²) of coil area.
- J. Do not install temperature sensors within the vapor plume of a humidifier. If installing a sensor downstream of a humidifier, install it at least 3 m (10 ft) downstream.
- K. All pipe-mounted temperature sensors shall be installed in wells. Install liquid temperature sensors with heat-conducting fluid in thermal wells.
- L. Install outdoor air temperature sensors on north wall, complete with sun shield at designated location.

- M. Differential Air Static Pressure.
1. Supply Duct Static Pressure. Pipe the high-pressure tap to the duct using a pitot tube. Pipe the low-pressure port to a tee in the high-pressure tap tubing of the corresponding building static pressure sensor (if applicable) or to the location of the duct high-pressure tap and leave open to the plenum.
 2. Return Duct Static Pressure. Pipe high-pressure tap to duct using a pitot tube. Pipe the low-pressure port to a tee in the low-pressure tap tubing of the corresponding building static pressure sensor.
 3. Building Static Pressure. Pipe the low-pressure port of the pressure sensor to the static pressure port located on the outside of the building through a high-volume accumulator. Pipe the high-pressure port to a location behind a thermostat cover.
 4. The piping to the pressure ports on all pressure transducers shall contain a capped test port located adjacent to the transducer.
 5. All pressure transducers, other than those controlling VAV boxes, shall be located in field device panels, not on the equipment monitored or on ductwork. Mount transducers in a location accessible for service without use of ladders or special equipment.
 6. All air and water differential pressure sensors shall have gauge tees mounted adjacent to the taps. Water gauges shall also have shut-off valves installed before the tee.
- N. Smoke detectors, freezestats, high-pressure cut-offs, and other safety switches shall be hard-wired to de-energize equipment as described in the sequence of operation. Switches shall require manual reset. Provide contacts that allow DDC software to monitor safety switch status.
- O. Install humidity sensors for duct mounted humidifiers at least 3 m (10 ft) downstream of the humidifier. Do not install filters between the humidifier and the sensor.

3.9 Actuators

- A. General. Mount and link control damper actuators according to manufacturer's instructions.
1. To compress seals when spring-return actuators are used on normally closed dampers, power actuator to approximately 5° open position, manually close the damper, and then tighten the linkage.
 2. Check operation of damper/actuator combination to confirm that actuator modulates damper smoothly throughout stroke to both open and closed positions.
 3. Provide all mounting hardware and linkages for actuator installation.
- B. Electric/Electronic
1. Dampers: Actuators shall be direct mounted on damper shaft or jackshaft unless shown as a linkage installation. For low-leakage dampers with seals, the actuator shall be mounted with a minimum 5° travel available for tightening the damper seal. Actuators shall be mounted following manufacturer's recommendations.
 2. Valves: Actuators shall be connected to valves with adapters approved by the actuator manufacturer. Actuators and adapters shall be mounted following the actuator manufacturer's recommendations.

3.10 Warning Labels

- A. Permanent warning labels shall be affixed to all equipment that can be automatically started by the control system.

1. Labels shall use white lettering (12-point type or larger) on a red background.
2. Warning labels shall read as follows.

C A U T I O N

This equipment is operating under automatic control and may start or stop at any time without warning.
Switch disconnect to "Off" position before servicing.

3. Permanent warning labels shall be affixed to all motor starters and control panels that are connected to multiple power sources utilizing separate disconnects.
4. Labels shall use white lettering (12-point type or larger) on a red background.
5. Warning labels shall read as follows.

C A U T I O N

This equipment is fed from more than one power source with separate disconnects. Disconnect all power sources before servicing.

3.11 Identification of Hardware and Wiring

- A. All wiring and cabling, including that within factory-fabricated panels shall be labeled at each end within 5 cm (2 in.) of termination with control system address or termination number.
- B. All pneumatic tubing shall be labeled at each end within 5 cm (2 in.) of termination with a descriptive identifier.
- C. Permanently label or code each point of field terminal strips to show the instrument or item served.
- D. Identify control panels with minimum 1 cm (½ in.) letters on laminated plastic nameplates.
- E. Identify all other control components with permanent labels. All plug-in components shall be labeled such that label removal of the component does not remove the label.
- F. Identify room sensors related to terminal boxes or valves with nameplates.
- G. Manufacturers' nameplates and UL or CSA labels shall be visible and legible after equipment is installed.
- H. Identifiers shall match record documents.

3.12 Controllers

- A. Provide a separate controller for each AHU or other HVAC system. A DDC controller may control more than one system provided that all points associated with the system are assigned to the same DDC controller. Points used for control loop reset, such as outside air or space temperature, are exempt from this requirement.

- B. Building Controllers and Custom Application Controllers shall be selected to provide the required I/O point capacity required to monitor all of the hardware points listed in Section 23 09 93 (Sequences of Operation).

3.13 Programming

- A. Provide sufficient internal memory for the specified sequences of operation and trend logging.
- B. Point Naming. Name points as shown on the equipment points list provided with each sequence of operation. See Section 23 09 93 (Sequences of Operation). If character limitations or space restrictions make it advisable to shorten the name, the abbreviations given in Appendix B to Section 23 09 93 may be used. Where multiple points with the same name reside in the same controller, each point name may be customized with its associated Program Object number. For example, "Zone Temp 1" for Zone 1, "Zone Temp 2" for Zone 2.
- C. Software Programming.
 - a. Provide programming for the system and adhere to the sequences of operation provided. All other system programming necessary for the operation of the system, but not specified in this document, also shall be provided by the contractor. Embed into the control program sufficient comment statements to clearly describe each section of the program. The comment statements shall reflect the language used in the sequences of operation. Use the appropriate technique based on the following programming types:
 - 1) Text-based:
 - a) Must provide actions for all possible situations
 - b) Must be modular and structured
 - c) Must be commented
 - 2) Graphic-based:
 - a) Must provide actions for all possible situations
 - b) Must be documented
 - 3) Parameter-based:
 - a) Must provide actions for all possible situations
 - b) Must be documented.
- D. Operator Interface.
 - 1. Standard Graphics. Provide graphics for all mechanical systems and floor plans of the building. This includes each chilled water system, hot water system, chiller, boiler, air handler, and all terminal equipment. Point information on the graphic displays shall dynamically update. Show on each graphic all relevant input and output points for that equipment. Also show relevant calculated points such as setpoints. As a minimum, show on each equipment graphic the input and output points and relevant calculated points as indicated on the applicable Points List in Section 23 09 93.
 - 2. The contractor shall provide all the labor necessary to install, initialize, start up, and troubleshoot all operator interface software and its functions as described in this section. This includes any operating system software, the operator interface database, and any third-party software installation and integration required for successful operation of the operator interface.

3.14 Control System Checkout and Testing

- A. Startup Testing. All testing listed in this article shall be performed by the contractor and shall make up part of the necessary verification of an operating control system. This testing shall be completed before the owner's representative is notified of the system demonstration.
1. The contractor shall furnish all labor and test apparatus required to calibrate and prepare for service of all instruments, controls, and accessory equipment furnished under this specification.
 2. Verify that all control wiring is properly connected and free of all shorts and ground faults. Verify that terminations are tight.
 3. Enable the control systems and verify calibration of all input devices individually. Perform calibration procedures according to manufacturers' recommendations.
 4. Verify that all binary output devices (relays, solenoid valves, two-position actuators and control valves, magnetic starters, etc.) operate properly and that the normal positions are correct.
 5. Verify that all analog output devices (I/Ps, actuators, etc.) are functional, that start and span are correct, and that direction and normal positions are correct. The contractor shall check all control valves and automatic dampers to ensure proper action and closure. The contractor shall make any necessary adjustments to valve stem and damper blade travel.
 6. Verify that the system operation adheres to the sequences of operation. Simulate and observe all modes of operation by overriding and varying inputs and schedules. Tune all DDC loops.
 7. Alarms and Interlocks:
 - a. Check each alarm separately by including an appropriate signal at a value that will trip the alarm.
 - b. Interlocks shall be tripped using field contacts to check the logic, as well as to ensure that the fail-safe condition for all actuators is in the proper direction.
 - c. Interlock actions shall be tested by simulating alarm conditions to check the initiating value of the variable and interlock action

3.15 Control System Demonstration and Acceptance

- A. Demonstration.
1. Prior to acceptance, the control system shall undergo a series of performance tests to verify operation and compliance with this specification. These tests shall occur after the Contractor has completed the installation, started up the system, and performed his/her own tests.
 2. The tests described in this section are to be performed in addition to the tests that the contractor performs as a necessary part of the installation, start-up, and debugging process and as specified in the "Control System Checkout and Testing" article in Part 3 of this specification. The engineer will be present to observe and review these tests. The engineer shall be notified at least 10 days in advance of the start of the testing procedures.
 3. The demonstration process shall follow that approved in Part 1, "Submittals." The approved checklists and forms shall be completed for all systems as part of the demonstration.
 4. The contractor shall provide at least two persons equipped with two-way communication and shall demonstrate actual field operation of each control and sensing point for all modes of operation including day, night, occupied, unoccupied, fire/smoke alarm, seasonal changeover, and power failure modes. The purpose is to demonstrate the calibration,

- response, and action of every point and system. Any test equipment required to prove the proper operation shall be provided by and operated by the contractor.
5. As each control input and output is checked, a log shall be completed showing the date, technician's initials, and any corrective action taken or needed.
 6. Demonstrate compliance with Part 1, "System Performance."
 7. Demonstrate compliance with sequences of operation through all modes of operation.
 8. Demonstrate complete operation of operator interface.
 9. Additionally, the following items shall be demonstrated:
 - a. DDC loop response. The contractor shall supply trend data output in a graphical form showing the step response of each DDC loop. The test shall show the loop's response to a change in set point, which represents a change of actuator position of at least 25% of its full range. The sampling rate of the trend shall be from 10 seconds to 3 minutes, depending on the speed of the loop. The trend data shall show for each sample the set point, actuator position, and controlled variable values. Any loop that yields unreasonably under-damped or over-damped control shall require further tuning by the Contractor.
 - b. Demand limiting. The contractor shall supply a trend data output showing the action of the demand limiting algorithm. The data shall document the action on a minute-by-minute basis over at least a 30-minute period. Included in the trend shall be building kW, demand limiting set point, and the status of sheddable equipment outputs.
 - c. Optimum start/stop. The contractor shall supply a trend data output showing the capability of the algorithm. The change-of-value or change-of-state trends shall include the output status of all optimally started and stopped equipment, as well as temperature sensor inputs of affected areas.
 - d. Interface to the building fire alarm system.
 - e. Operational logs for each system that indicate all set points, operating points, valve positions, mode, and equipment status shall be submitted to the architect/engineer. These logs shall cover three 48-hour periods and have a sample frequency of not more than 10 minutes. The logs shall be provided in both printed and disk formats.
 10. Any tests that fail to demonstrate the operation of the system shall be repeated at a later date. The contractor shall be responsible for any necessary repairs or revisions to the hardware or software to successfully complete all tests.

B. Acceptance.

1. All tests described in this specification shall have been performed to the satisfaction of both the engineer and owner prior to the acceptance of the control system as meeting the requirements of completion. Any tests that cannot be performed due to circumstances beyond the control of the contractor may be exempt from the completion requirements if stated as such in writing by the engineer. Such tests shall then be performed as part of the warranty.
2. The system shall not be accepted until all forms and checklists completed as part of the demonstration are submitted and approved as required in Part 1, "Submittals."

3.16 Cleaning

- A. The contractor shall clean up all debris resulting from his/her activities daily. The contractor shall remove all cartons, containers, crates, etc., under his/her control as soon as their contents have been removed. Waste shall be collected and placed in a designated location.

- B. At the completion of work in any area, the contractor shall clean all work, equipment, etc., keeping it free from dust, dirt, and debris, etc.
- C. At the completion of work, all equipment furnished under this section shall be checked for paint damage, and any factory-finished paint that has been damaged shall be repaired to match the adjacent areas. Any cabinet or enclosure that has been deformed shall be replaced with new material and repainted to match the adjacent areas.

3.17 Training

- A. Provide training for a designated staff of Owner's representatives. Training shall be provided via self-paced training, web-based or computer-based training, classroom training, or a combination of training methods.
- B. Training shall enable students to accomplish the following objectives.
 - 1. Day-to-day Operators:
 - a. Proficiently operate the system
 - b. Understand control system architecture and configuration
 - c. Understand DDC system components
 - d. Understand system operation, including DDC system control and optimizing routines (algorithms)
 - e. Operate the workstation and peripherals
 - f. Log on and off the system
 - g. Access graphics, point reports, and logs
 - h. Adjust and change system set points, time schedules, and holiday schedules
 - i. Recognize malfunctions of the system by observation of the printed copy and graphical visual signals
 - j. Understand system drawings and Operation and Maintenance manual
 - k. Understand the job layout and location of control components
 - l. Access data from DDC controllers and ASCs
 - m. Operate portable operator's terminals
 - 2. Advanced Operators:
 - a. Make and change graphics on the workstation
 - b. Create, delete, and modify alarms, including annunciation and routing of these
 - c. Create, delete, and modify point trend logs and graph or print these both on an ad-hoc basis and at user-definable time intervals
 - d. Create, delete, and modify reports
 - e. Add, remove, and modify system's physical points
 - f. Create, modify, and delete programming
 - g. Add panels when required
 - h. Add operator interface stations
 - i. Create, delete, and modify system displays, both graphical and others
 - j. Perform DDC system field checkout procedures
 - k. Perform DDC controller unit operation and maintenance procedures
 - l. Perform workstation and peripheral operation and maintenance procedures
 - m. Perform DDC system diagnostic procedures
 - n. Configure hardware including PC boards, switches, communication, and I/O points
 - o. Maintain, calibrate, troubleshoot, diagnose, and repair hardware
 - p. Adjust, calibrate, and replace system components
 - 3. System Managers/Administrators:

- a. Maintain software and prepare backups
- b. Interface with job-specific, third-party operator software
- c. Add new users and understand password security procedures
- 4. Organize the training into sessions or modules for the three levels of operators listed above. (Day-to-Day Operators, Advanced Operators, System Managers and Administrators). Students will receive one or more of the training packages, depending on knowledge level required.
- 5. Provide course outline and materials according to the "Submittals" article in Part 1 of this specification. Provide one copy of training material per student.
- 6. The instructor(s) shall be factory-trained and experienced in presenting this material.
- 7. Classroom training shall be done using a network of working controllers representative of installed hardware.

3.18 Control Damper Installation

- A. Damper submittals shall be coordinated for type, quantity, and size to ensure compatibility with sheet metal design.
- B. Duct openings shall be free of any obstruction or irregularities that might interfere with blade or linkage rotation or actuator mounting. Duct openings shall measure $\frac{1}{4}$ in. larger than damper dimensions and shall be square, straight, and level.
- C. Individual damper sections, as well as entire multiple section assemblies, must be completely square and free from racking, twisting, or bending. Measure diagonally from upper corners to opposite lower corners of each damper section. Both dimensions must be within 0.3 cm ($\frac{1}{8}$ in.) of each other.
- D. Follow the manufacturer's instructions for field installation of control dampers. Unless specifically designed for vertical blade application, dampers must be mounted with blade axis horizontal.
- E. Install extended shaft or jackshaft according to manufacturer's instructions. (Typically, a sticker on the damper face shows recommended extended shaft location. Attach shaft on labeled side of damper to that blade.)
- F. Damper blades, axles, and linkage must operate without binding. Before system operation, cycle damper after installation to ensure proper operation. On multiple section assemblies, all sections must open and close simultaneously.
- G. Provide a visible and accessible indication of damper position on the drive shaft end.
- H. Support ductwork in area of damper when required to prevent sagging due to damper weight.
- I. After installation of low-leakage dampers with seals, caulk between frame and duct or opening to prevent leakage around perimeter of damper.

3.19 Duct Smoke Detection

- A. Submit data for coordination of duct smoke detector interface to HVAC systems as required in Part 1, "Submittals."
- B. This Contractor shall provide a dry-contact alarm output in the same room as the HVAC equipment to be controlled.

3.20 Start-Up and Checkout Procedures

- A. Start up, check out, and test all hardware and software and verify communication between all components.
 - 1. Verify that all control wiring is properly connected and free of all shorts and ground faults. Verify that terminations are tight.
 - 2. Verify that all analog and binary input/output points read properly.
 - 3. Verify alarms and interlocks.
 - 4. Verify operation of the integrated system.

This page intentionally left blank.

SECTION 23 09 90 - HVAC INSTRUMENTATION AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes control equipment for HVAC systems and components, including control components for terminal heating and cooling units not supplied with factory-wired controls.
- B. Related Sections include the following:
 - 1. Division 28 Section "Fire Alarm" for fire and smoke detectors mounted in HVAC systems and equipment.
 - 2. Section 23 00 50 "Basic Mechanical Materials and Methods".

1.3 DEFINITIONS

- A. DDC: Direct-digital controls.
- B. LAN: Local area network.
- C. MS/TP: Master-slave/token-passing.
- D. PICS: Protocol Implementation Conformance Statement.

1.4 SYSTEM DESCRIPTION

- A. Control system consists of sensors, indicators, actuators, final control elements, interface equipment, other apparatus, accessories, and software connected to distributed controllers operating in multiuser, multitasking environment on token-passing network and programmed to control mechanical systems.
- B. Furnish material, labor and services necessary for and reasonably incidental to the installation of the following work where shown on the Plans and as hereinafter specified. Include all necessary work in the related sections of the Specifications to perform the Work completely.
- C. Start-Up: Upon completion of the installation, this subcontractor shall start up the system and perform all necessary testing and run diagnostics to ensure proper operation. A start-up test in the presence of the Owner's representative and the Engineer shall be performed. When the system performance is deemed satisfactory the system will be placed into operation.

D. Coordination with other Trades:

1. Control contractor shall cooperate with unit manufacturers to assure proper arrangement of control items. Control valves, dampers, thermostat wells, and other control devices that are to be built into the field assembled ductwork or piping systems shall be furnished by the temperature control subcontractor and installed by the Mechanical or Electrical Contractor as directed by the supplier and indicated in other portions of the specifications and drawings.
2. The control contractor shall provide coordination as required for a properly functioning system and as specified in this section via shop drawings, coordination drawings, site visits, etc. Final responsibility for proper application, installation, and operation of all control system components falls under this section of the specification including equipment provided for installation by others.

E. Control system includes the following:

1. Building clock control system specified in Division 13 Section "Clock Control."
2. Fire alarm system specified in Division 13 Section "Fire Alarm."

1.5 SUBMITTALS

A. Product Data: Include manufacturer's technical literature for each control device. Indicate dimensions, capacities, performance characteristics, electrical characteristics, finishes for materials, and installation and startup instructions for each type of product indicated.

1. Each control device labeled with setting or adjustable range of control.

B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.

1. Schematic flow diagrams showing fans, pumps, coils, dampers, valves, and control devices.
2. Wiring Diagrams: Power, signal, and control wiring. Differentiate between manufacturer-installed and field-installed wiring.
3. Details of control panel faces, including controls, instruments, and labeling.
4. Written description of sequence of operation.
5. Schedule of dampers including size, leakage, and flow characteristics.
6. Trunk cable schematic showing programmable control unit locations and trunk data conductors.
7. Listing of connected data points, including connected control unit and input device.
8. System graphics indicating monitored systems, data (connected and calculated) point addresses, and operator notations.
9. System configuration showing peripheral devices, batteries, power supplies, diagrams, modems, and interconnections.

C. ASHRAE BACnet Statement: PICS for each DDC system component (panel, zone controller, field devices, and operator workstation) proposed.

D. Software and Firmware Operational Documentation: Include the following:

1. Software operating and upgrade manuals.
 2. Program Software Backup: On a magnetic media or compact disc, complete with data files.
 3. Device address list.
 4. Printout of software application and graphic screens.
 5. Software license required by and installed for DDC workstations and control systems.
- E. Field Test Reports: Indicate and interpret test results for compliance with performance requirements.
- F. Maintenance Data: For systems to include in maintenance manuals specified in Division 1. Include the following:
1. Maintenance instructions and lists of spare parts for each type of control device and compressed-air station.
 2. Interconnection wiring diagrams with identified and numbered system components and devices.
 3. Keyboard illustrations and step-by-step procedures indexed for each operator function.
 4. Inspection period, cleaning methods, cleaning materials recommended, and calibration tolerances.
 5. Calibration records and list of set points.
- G. Qualification Data: For firms and persons specified in "Quality Assurance" Article.
- H. Project Record Documents: Record actual locations of control components, including control units, thermostats, and sensors. Revise Shop Drawings to reflect actual installation and operating sequences.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who is a certified installer of the automatic control system manufacturer for both installation and maintenance of units required for this Project.
- B. Manufacturer Qualifications: A firm experienced in manufacturing automatic temperature-control systems similar to those indicated for this Project and with a record of successful in-service performance.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- D. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilation Systems."
- E. Comply with ASHRAE 135 for DDC system control components.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Factory-Mounted Components: Where control devices specified in this Section are indicated to be factory mounted on equipment, arrange for shipping of control devices to unit manufacturer.

1.8 COORDINATION

- A. Coordinate location of thermostats, humidistats, and other exposed control sensors with plans and room details before installation.
- B. Coordinate equipment with Division 26 Section "Lighting Controls" to achieve compatibility with equipment that interfaces with that system.
- C. Coordinate equipment with Division 28 Section "Fire Alarm" to achieve compatibility with equipment that interfaces with that system.
- D. Coordinate supply of conditioned electrical circuits for control units and operator workstation.
- E. Coordinate equipment with Division 26 Section "Panelboards" to achieve compatibility with starter coils and annunciation devices.
- F. Coordinate equipment with Division 26 Section "Motor-Control Centers" to achieve compatibility with motor starters and annunciation devices.

1.9 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
- B. Replacement Materials: One replacement diaphragm or relay mechanism for each unique controller, thermostat and positioning relay.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Electric, Electronic, and DDC Systems:
 - a. Alerton Technologies, Inc.
 - b. Andover Controls Corp.
 - c. Automated Logic Corporation.
 - d. Auto-Matrix, Inc.; Auto-Flow Division.
 - e. CSI Control Systems International, Inc.
 - f. Danfoss Automatic Controls.
 - g. Delta Controls Inc.
 - h. EDA Controls Corp.

- i. Electronic Systems USA, Inc.
- j. G C Controls, Inc.
- k. Honeywell, Inc.; Home & Building Control.
- l. Impact Energy Controls Corp.
- m. Johnson Controls, Inc.; Controls Group.
- n. KMC Controls/Kreuter Manufacturing Company.
- o. Landis & Staefa, Inc.
- p. Luwa Bahnson Inc.
- q. McQuay International.
- r. Neles-Jamesbury.
- s. Pneuline Controls Co.; National Energy Controls Corp.
- t. Scientific-Atlanta, Inc.; Control Systems Div.
- u. Siebe Environmental Controls; Barber-Coleman/Robertshaw Products.
- v. Solidyne Corp.
- w. TCS/BASYS Controls; HVAC Sensors & Transducers Division.
- x. Teletrol Systems Inc.
- y. Trane Co. (The); North American Commercial Group.
- z. Triangle MicroSystems, Inc.
- aa. Uni-Line North America; Robertshaw Division.

2.2 DDC EQUIPMENT

A. Workstation:

- 1. Connect to DDC system Level one LAN through a communications port directly on LAN or through a communications port on a DDC controller.
- 2. Able to communicate with any device located on any DDC system LAN.
- 3. Able to communicate, with modems, remotely with any device connected to any DDC system LAN.
- 4. Performance Requirements: Energy Star compliant and hardware & software shall support local down-loading to DDC controllers.
- 5. A self-powered portable operator's terminal shall be provided by the owner to allow the operator to view and make changes to the BAS. The Workstation hardware platform shall be laptop or equivalent notebook computer meeting the following criteria:
 - a. System: Portable notebook with Intel Core i7 2.5 GHz, 16 GB RAM
 - b. Hard Disk: 240 GB SSD
 - c. Screen: 15 inch 1920x 1080-pixel display
 - d. Audio: Integrated with built-in speakers
 - e. Ports Minimum two (2) USB 3.0, DisplayPort or HDMI, and memory card reader
 - f. Connectivity: 10/100/1 G 10 Base-T Ethernet with 802.11 a/b/g/n wireless
 - g. Keyboard and touchpad: Pinch-to-zoom and scrolling, backlit keys
 - h. Battery: 9 cel with estimated 10 hours battery life
- 6. Software: Operating system shall be Windows compatible software.

B. Application Software: Include the following:

- 1. Input/output capability from operator station.

2. Operator system access levels via software password.
 3. Database creation and support.
 4. Dynamic color graphic displays.
 5. Alarm processing.
 6. Event processing.
 7. Automatic restart of field equipment on restoration of power.
 8. Data collection.
 9. Graphic development on workstation.
 10. Maintenance management.
- C. Control Units: Modular, comprising processor board with programmable, nonvolatile, random-access memory; local operator access and display panel; integral interface equipment; and backup power source.
1. Units monitor or control each input/output point; process information; execute commands from other control units, devices, and operator stations; and download from or upload to operator station.
 2. Stand-alone mode control functions operate regardless of network status. Functions include the following:
 - a. Global communications.
 - b. Discrete/digital, analog, and pulse input/output.
 - c. Monitoring, controlling, or addressing data points.
 - d. Testing and developing control algorithms without disrupting field hardware and controlled environment.
 3. Local operator interface provides for download from or upload to mobile operator station.
 4. BACnet Conformance: Reside on BACnet LAN in Ethernet IEEE 802.3, Class 3, minimum, with routers between LAN and other panels, with at least one communication port, and have minimum capabilities defined in PICS for the following areas:
 - a. Network.
 - b. Functional groups.
 - c. Standard application services supported.
 - d. Standard objects supported.
- D. Local Control Units: Modular, comprising processor board with electronically programmable, nonvolatile, read-only memory; and backup power source.
1. Units monitor or control each input/output point; process information; and download from or upload to operator station.
 2. Stand-alone mode control functions operate regardless of network status. Functions include the following:
 - a. Global communications.
 - b. Discrete/digital, analog, and pulse input/output.
 - c. Monitoring, controlling, or addressing data points.
 3. Local operator interface provides for download from or upload to mobile operator station.

4. BACnet Conformance: Reside on BACnet LAN using MS/TP, Class 2, minimum, with at least one communication port, and have minimum capabilities defined in PICS for the following areas:
 - a. Network.
 - b. Functional groups.
 - c. Standard application services supported.
 - d. Standard objects supported.
- E. LANs: Capacity for a minimum of 10 workstations connected to multiuser, multitasking environment with concurrent capability to access DDC network or control units.
 1. Media: MS/TP, EIA 485, operating at 9.6 kBps.
- F. Software: Update to latest version of software at Project completion. Include and implement the following capabilities from the control units:
 1. Units of Measure: Inch-pound and SI (metric).
 2. Load Control Programs: Demand limiting, duty cycling, automatic time scheduling, start/stop time optimization, night setback/setup, DDC with fine tuning, and trend logging.
 3. HVAC Control Programs: Optimal run time, supply-air reset, and enthalpy switchover.
 4. Programming Application Features: Include trend point, alarm messages, weekly scheduling, and interlocking.

2.3 CONTROL PANELS

- A. Central (Master) Control Panels: Fully enclosed, steel-rack-type cabinet with locking doors or locking removable backs. Match finish of panels and provide multicolor graphic displays, schematically showing system being controlled.
- B. Local Control Panels: Unitized cabinet with suitable brackets for wall or floor mounting, located adjacent to each system under automatic control. Provide common keying for all panels.
 1. Fabricate panels of 0.06-inch- thick, furniture-quality steel, or extruded-aluminum alloy, totally enclosed, with hinged doors and keyed lock and with manufacturer's standard shop-painted finish.
 2. Panel-Mounted Equipment: Temperature and humidity controllers, relays, and automatic switches; except safety devices. Mount devices with adjustments accessible through front of panel.
 3. Door-Mounted Equipment: Flush-mount (on hinged door) manual switches, including damper-positioning switches, changeover switches, thermometers, and gages.
 4. Graphics: Color-coded graphic, laminated-plastic displays on doors, schematically showing system being controlled, with protective, clear plastic sheet bonded to entire door.

2.4 ANALOG CONTROLLERS

- A. Step Controllers: Six- or 10-stage type, with heavy-duty switching rated to handle loads and operated by electric motor.
- B. Electric, Outdoor-Reset Controllers: Remote-bulb or bimetal rod-and-tube type, proportioning action with adjustable throttling range, adjustable set point, scale range minus 10 to plus 70 deg F, and single- or double-pole contacts.
- C. Electronic Controllers: Wheatstone-bridge-amplifier type, in steel enclosure with provision for remote-resistance readjustment. Identify adjustments on controllers, including proportional band and authority.
 - 1. Single controllers can be integral with control motor if provided with accessible control readjustment potentiometer.
- D. Fan-Speed Controllers: Solid-state model providing field-adjustable proportional control of motor speed from maximum to minimum of 55 percent and on-off action below minimum fan speed. Controller shall briefly apply full voltage, when motor is started, to rapidly bring motor up to minimum speed. Equip with filtered circuit to eliminate radio interference.
- E. Receiver Controllers: Single- or multiple-input models with control-point adjustment, direct or reverse acting with mechanical set-point adjustment with locking device, proportional band adjustment, authority adjustment, and proportional control mode.
 - 1. Remote-control-point adjustment shall be plus or minus 20 percent of sensor span, input signal of 3 to 13 psig.
 - 2. Proportional band shall extend from 2 to 20 percent for 5 psig.
 - 3. Authority shall be 20 to 200 percent.
 - 4. Air-supply pressure of 18 psig, input signal of 3 to 15 psig, and output signal 0 to supply pressure.
 - 5. Gages: 3-1/2 inches in diameter, 2.5 percent wide-scale accuracy, and range to match transmitter input or output pressure.

2.5 TIME CLOCKS

- A. Solid-state, programmable time control with 4 separate programs; 24-hour battery carryover; individual on-off-auto switches for each program; 365-day calendar with 20 programmable holidays; choice of fail-safe operation for each program; and system fault alarm.

2.6 SENSORS

- A. Electronic Sensors: Vibration and corrosion resistant; for wall, immersion, or duct mounting as required.
 - 1. Thermistor temperature sensors as follows:
 - a. Accuracy: Plus or minus 0.36 deg F at calibration point.
 - b. Wire: Twisted, shielded-pair cable.
 - c. Insertion Elements in Ducts: Single point, 8 inches long; use where not affected by temperature stratification or where ducts are smaller than 9 sq. ft..

- d. Averaging Elements in Ducts: 36 inches long, flexible; use where prone to temperature stratification or where ducts are larger than 9 sq. ft.; length as required.
 - e. Insertion Elements for Liquids: Brass socket with minimum insertion length of 2-1/2 inches.
 - f. Room Sensors: Match room thermostats, locking cover.
 - g. Outside-Air Sensors: Watertight inlet fitting, shielded from direct sunlight.
 - h. Room Security Sensors: Stainless-steel cover plate with insulated back and security screws.
2. Resistance Temperature Detectors: Platinum.
- a. Accuracy: Plus or minus 0.2 percent at calibration point.
 - b. Wire: Twisted, shielded-pair cable.
 - c. Insertion Elements in Ducts: Single point, 8 inches long; use where not affected by temperature stratification or where ducts are smaller than 9 sq. ft..
 - d. Averaging Elements in Ducts: 36 inches long, flexible; use where prone to temperature stratification or where ducts are larger than 9 sq. ft.; length as required.
 - e. Insertion Elements for Liquids: Brass socket with minimum insertion length of 2-1/2 inches.
 - f. Room Sensors: Match room thermostats, locking cover.
 - g. Outside-Air Sensors: Watertight inlet fitting, shielded from direct sunlight.
 - h. Room Security Sensors: Stainless-steel cover plate with insulated back and security screws.
3. Humidity Sensors: Bulk polymer sensor element.
- a. Accuracy: 5 percent full range with linear output.
 - b. Room Sensors: With locking cover matching room thermostats, span of 25 to 90 percent relative humidity.
 - c. Duct and Outside-Air Sensors: With element guard and mounting plate, range of 0 to 100 percent relative humidity.
4. Static-Pressure Transmitter: Nondirectional sensor with suitable range for expected input, and temperature compensated.
- a. Accuracy: 2 percent of full scale with repeatability of 0.5 percent.
 - b. Output: 4 to 20 mA.
 - c. Building Static-Pressure Range: 0 to 0.25 inch wg.
 - d. Duct Static-Pressure Range: 0 to 5 inches wg.
5. Pressure Transmitters: Direct acting for gas, liquid, or steam service; range suitable for system; proportional output 4 to 20 mA.
- B. Pneumatic Transmitters: Vibration and corrosion resistant.
- 1. Space-Temperature Sensors: Linear-output type, 50 to 100 deg F range, with blank locking covers matching room thermostats.

2. Room Return-Air Temperature Sensors: Linear-output type with bimetal sensing element and corrosion-proof construction, 50 to 100 deg F range, designed to be mounted in light troffers.
3. Duct-Mounted or Immersion-Type Temperature Sensors: Range as required for 3- to 15-psig output signal.
4. Temperature Transmitters: Rigid-stem type with bimetal sensing elements, unless averaging is required, 3- to 15-psig output signal.
 - a. Averaging-Element Sensors: Single- or multiple-unit capillary elements.
 - b. Tamperproof Sensors: Corrosion-resistant construction, suitable for mounting on vibrating surface with exposed capillary protected with temperature-compensated armor or protective tubing.
 - c. Pipe-Mounted Temperature-Sensing Elements: Rod-and-tube type, with separable wells filled with heat-conductive compound, mounting bracket.
 - d. Outdoors: Provide bulb shield with mounting bracket.
5. Space and Duct Humidity Transmitters: One pipe, directly proportional, with minimum sensing span of 20 to 80 percent relative humidity for 3- to 15-psig output signal, corrosion resistant and temperature compensated, and with factory-calibrated adjustment.
 - a. Space Mounting: With covers to match thermostats.
6. Differential-Pressure Transmitters: One pipe, direct acting for gas, liquid, or steam service; pressure sensor and transmitter of linear-output type; with range of 0 to 50 psig, and 3- to 15-psig output signal.
7. Differential-Air-Pressure Transmitters: One pipe, direct acting, double bell, unidirectional with suitable range for expected input, and temperature compensated.
 - a. Accuracy: 5 percent of full range and 2 percent of full scale at midrange.
 - b. Output Signal: 3 to 15 psig.

C. Equipment operation sensors as follows:

1. Status Inputs for Fans: Differential-pressure switch with adjustable range of 0 to 5 inches wg.
2. Status Inputs for Electric Motors: Current-sensing relay with current transformers, adjustable and set to 175 percent of rated motor current.

D. Digital-to-Pneumatic Transducers: Convert plus or minus 12-V dc pulse-width-modulation outputs, or continuous proportional current or voltage to 0 to 20 psig.

E. Pneumatic Valve/Damper Position Indication: Potentiometer mounted in enclosure with adjustable crank-arm assembly connected to damper to transmit 0 to 100 percent valve/damper travel.

F. Electronic Valve/Damper Position Indication: Visual scale indicating percent of travel and 2- to 10-V dc, feedback signal.

G. Carbon-Monoxide (Nitrogen Dioxide, Refrigerants) Detectors: Electronic detection system used to measure the concentration of various gases and provide feedback and automatic control. Line voltage (100-240 VAC), dual relay gas detector, controller and transducers with an internal

switching power supply that is capable of using line voltage between 100 and 240 VAC and 50-60 Hz.

1. Carbon Monoxide (CO) Range: 0-200 ppm.
 2. Nitrogen Dioxide (NO₂) Range: 0-20 ppm.
 3. Refrigerants Range: 0-1,000 ppm.
 4. Mounts on a standard 4-inch by 4-inch electrical box.
 5. 5 A SPDT relay controls valves, louvers or exhausts fans. Fan relay actuation: Selectable within sensor range.
 6. Supervised system design – detector problem will cause relay activation.
 7. ETL Listed to UL 61010-1, CAN/CSA C22.2 No 61010-1
 8. Operating Environment: 0 deg F to 125 deg F and 10 to 90% RH.
 9. Manufacturer: Aerionics, Model CM-12 or approved equal.
- H. Carbon-Dioxide Sensor and Transmitter: Single detectors, using solid-state infrared sensors, suitable over a temperature range of 23 to 130 deg F, calibrated for 0 to 2 percent, with continuous or averaged reading, 4 to 20 mA output, and wall mounted.
- I. Oxygen Sensor and Transmitter: Single detectors, using solid-state zircon cell sensing, suitable over a temperature range of minus 32 to plus 1100 deg F, calibrated for 0 to 5 percent, with continuous or averaged reading, 4 to 20 mA output, and wall mounted.
- J. Refrigerant Detectors: Dual-level detectors, using solid-state sensors, with alarm preset for 300 ppm, alarm indicator light, alarm silence light and button, alarm test light and button, and trouble light. Provide auxiliary relay preset for 150 ppm.
- K. Occupancy Sensor: Passive infrared, with time delay, daylight sensor lockout, sensitivity control, and 180-degree field of view with vertical sensing adjustment, for flush mounting.

2.7 THERMOSTATS

- A. Combination Thermostat and Fan Switches: Line-voltage thermostat with two-, three-, or four-position, push-button or lever-operated fan switch.
1. Label switches "FAN ON-OFF," "FAN HIGH-LOW-OFF," "FAN HIGH-MED-LOW-OFF." Provide unit for mounting on two-gang switch box.
- B. Electric solid-state, microcomputer-based room thermostat with remote sensor.
1. Automatic switching from heating to cooling.
 2. Preferential rate control to minimize overshoot and deviation from set point.
 3. Set up for four separate temperatures per day.
 4. Instant override of set point for continuous or timed period from 1 hour to 31 days.
 5. Short-cycle protection.
 6. Programming based on weekdays, Saturdays and Sundays.
 7. Selection features include deg F or deg C display, 12- or 24-hour clock, keyboard disable, remote sensor, fan on-auto.
 8. Battery replacement without program loss.
 9. Thermostat display features include the following:

- a. Time of day.
 - b. Actual room temperature.
 - c. Programmed temperature.
 - d. Programmed time.
 - e. Duration of timed override.
 - f. Day of week.
 - g. System mode indications include "heating," "off," "fan auto," and "fan on."
- C. Low-Voltage, On-Off Thermostats: NEMA DC 3, 24-V, bimetal-operated, mercury-switch type, with adjustable or fixed anticipation heater.
- D. Line-Voltage, On-Off Thermostats: Bimetal-actuated, open contact or bellows-actuated, enclosed, snap-switch type, or equivalent solid-state type, with heat anticipator, integral manual on-off-auto selector switch.
 - 1. Equip thermostats, which control electric heating loads directly, with off position on dial wired to break ungrounded conductors.
 - 2. Dead Band: Maximum 2 deg F.
- E. Remote-Bulb Thermostats: On-off or modulating type, liquid filled to compensate for changes in ambient temperature, with copper capillary and bulb, unless otherwise indicated.
 - 1. Bulbs in water lines with separate wells of same material as bulb.
 - 2. Bulbs in air ducts with flanges and shields.
 - 3. Averaging Elements: Copper tubing with either single- or multiple-unit elements, extended to cover full width of duct or unit, adequately supported.
 - 4. Scale settings and differential settings are clearly visible and adjustable from front of instrument.
 - 5. On-Off Thermostat: With precision snap switches, with electrical ratings required by application.
 - 6. Modulating Thermostats: Construct so complete potentiometer coil and wiper assembly is removable for inspection or replacement without disturbing calibration of instrument.
- F. Fire-Protection Thermostats: UL listed with fixed or adjustable settings to operate at not less than 75 deg F above normal maximum operating temperature, with the following:
 - 1. Reset: Manual.
- G. Room Thermostat Cover Construction: Manufacturer's standard locking covers.
- H. Room thermostat accessories include the following:
 - 1. Insulating Bases: For thermostats located on exterior walls.
 - 2. Thermostat Guards: Locking; heavy-duty, transparent plastic; mounted on separate base.
 - 3. Adjusting Key: As required for calibration and cover screws.
 - 4. Aspirating Boxes: For flush-mounted aspirating thermostats.
 - 5. Set-Point Adjustment: 1/2-inch- diameter, adjustment knob.
- I. Immersion Thermostat: Remote-bulb or bimetal rod-and-tube type, proportioning action with adjustable throttling range and adjustable set point.

- J. Airstream Thermostats: Two-pipe, fully proportional, single-temperature type, with adjustable set point in middle of range and adjustable throttling range, plug-in test fitting or permanent pressure gage, remote bulb, bimetal rod and tube, or averaging element.
- K. Electric Low-Limit Duct Thermostat: Snap-acting, single-pole, single-throw, manual- or automatic-reset switch that trips if temperature sensed across any 12 inches of bulb length is equal to or below set point.
 - 1. Bulb Length: Minimum 20 feet.
 - 2. Quantity: One thermostat for every 20 sq. ft. of coil surface.
- L. Electric High-Limit Duct Thermostat: Snap-acting, single-pole, single-throw, manual- or automatic-reset switch that trips if temperature sensed across any 12 inches of bulb length is equal to or above set point.
 - 1. Bulb Length: Minimum 20 feet.
 - 2. Quantity: One thermostat for every 20 sq. ft. of coil surface.
- M. Heating/Cooling Valve-Top Thermostats: Proportional acting for proportional flow, molded-rubber diaphragm, remote-bulb liquid-filled element, direct and reverse acting at minimum shutoff pressure of 25 psig, and cast housing with position indicator and adjusting knob.

2.8 HUMIDISTATS

- A. Pneumatic Room Humidistats: Wall-mounted, proportioning type with adjustable throttling range, 20 to 90 percent operating range, cover matching room thermostat cover.

2.9 ACTUATORS

- A. Electric Motors: Size to operate with sufficient reserve power to provide smooth modulating action or two-position action.
 - 1. Permanent Split-Capacitor or Shaded-Pole Type: Gear trains completely oil immersed and sealed. Equip spring-return motors with integral spiral-spring mechanism in housings designed for easy removal for service or adjustment of limit switches, auxiliary switches, or feedback potentiometer.
 - 2. Nonspring-Return Motors for Valves Larger Than NPS 2-1/2: Size for running torque of 150 in. x lbf and breakaway torque of 300 in. x lbf.
 - 3. Spring-Return Motors for Valves Larger Than NPS 2-1/2: Size for running and breakaway torque of 150 in. x lbf.
 - 4. Nonspring-Return Motors for Dampers Larger Than 25 Sq. Ft.: Size for running torque of 150 in. x lbf and breakaway torque of 300 in. x lbf.
 - 5. Spring-Return Motors for Dampers Larger Than 25 Sq. Ft.: Size for running and breakaway torque of 150 in. x lbf.
- B. Electronic Damper Actuators: Direct-coupled type designed for minimum 60,000 full-stroke cycles at rated torque.

1. Valves: Size for torque required for valve close-off at maximum pump differential pressure.
 2. Dampers: Size for running torque calculated as follows:
 - a. Parallel-Blade Damper with Edge Seals: 7 inch-pounds/sq. ft. of damper.
 - b. Opposed-Blade Damper with Edge Seals: 5 inch-pounds/sq. ft. of damper.
 - c. Parallel-Blade Damper without Edge Seals: 4 inch-pounds/sq. ft. of damper.
 - d. Opposed-Blade Damper without Edge Seals: 3 inch-pounds/sq. ft. of damper.
 - e. Dampers with 2 to 3 Inches wg of Pressure Drop or Face Velocities of 1000 to 2500 FPM: Multiply the minimum full-stroke cycles above by 1.5.
 - f. Dampers with 3 to 4 Inches wg of Pressure Drop or Face Velocities of 2500 to 3000 FPM: Multiply the minimum full-stroke cycles above by 2.0.
 3. Coupling: V-bolt and V-shaped, toothed cradle.
 4. Overload Protection: Electronic overload or digital rotation-sensing circuitry.
 5. Fail-Safe Operation: Mechanical, spring-return mechanism. Provide external, manual gear release on non-spring-return actuators.
 6. Power Requirements (Two-Position Spring Return): 24-V ac.
 7. Power Requirements (Modulating): Maximum 10 VA at 24-V ac or 8 W at 24-V dc.
 8. Proportional Signal: 2- to 10-V dc or 4 to 20 mA, and 2- to 10-V dc position feedback signal.
 9. Temperature Rating: Minus 22 to plus 122 deg F.
 10. Temperature Rating (Smoke Dampers): Minus 22 to plus 250 deg F.
 11. Run Time: 12 seconds open, 5 seconds closed.
- C. Pneumatic Valve Operators: Rolling-diaphragm, spring-loaded, piston type with spring range as required and start-point adjustment and positioning relay. Operator shall maintain full shutoff at maximum pump differential pressure.
- D. Pneumatic Damper Operators: Rolling-diaphragm, piston type with adjustable stops and spring return, sized to operate with sufficient reserve power to provide smooth modulating action or two-position action. Where actuators operate in sequence, provide pilot positioners.
1. Pilot Positioners: Start point adjustable from 2 to 12 psig, and operating span adjustable from 5 to 13 psig.
 2. Inlet-Vane Operators: High pressure with pilot positioners.

2.10 DAMPERS

- A. Dampers: AMCA-rated, opposed-blade design; 0.1084-inch minimum, galvanized-steel frames with holes for duct mounting; damper blades shall not be less than 0.0635-inch galvanized steel with maximum blade width of 8 inches.
1. Blades shall be secured to 1/2-inch- diameter, zinc-plated axles using zinc-plated hardware, with nylon blade bearings, blade-linkage hardware of zinc-plated steel and brass, ends sealed against spring-stainless-steel blade bearings, and thrust bearings at each end of every blade.
 2. Operating Temperature Range: From minus 40 to plus 200 deg F.
 3. For standard applications, include optional closed-cell neoprene edging.

4. For low-leakage applications, use parallel- or opposed-blade design with inflatable seal blade edging, or replaceable rubber seals, rated for leakage at less than 10 cfm per sq. ft. of damper area, at differential pressure of 4 inches wg when damper is being held by torque of 50 in. x lbf; when tested according to AMCA 500D.

2.11 CONTROL CABLE

- A. Electronic and Fiber-Optic Cable for Control Wiring: As specified in Division 26 Section "Control/Signal Transmission Media."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify that conditioned power supply is available to control units and operator workstation.
- B. Verify that duct-, pipe-, and equipment-mounted devices and wiring and pneumatic piping are installed before proceeding with installation.

3.2 INSTALLATION

- A. Install equipment level and plumb.
- B. Install software in control units and operator workstation. Implement all features of programs to specified requirements and as appropriate to sequence of operation.
- C. Connect and configure equipment and software to achieve sequence of operation specified.
- D. Verify location of thermostats, humidistats, and other exposed control sensors with plans and room details before installation. Locate all 60 inches above the floor.
 1. Install averaging elements in ducts and plenums in crossing or zigzag pattern.
- E. Install guards on thermostats in the following locations:
 1. Entrances.
 2. Public areas.
- F. Install automatic dampers according to Division 23 Section "Duct Accessories."
- G. Install damper motors on outside of duct in warm areas, not in locations exposed to outdoor temperatures.
- H. Install labels and nameplates to identify control components according to Division 23 Section "Basic Mechanical Materials and Methods."

- I. Install refrigerant instrument wells, valves, and other accessories according to Division 23 Section "Refrigerant Piping."
- J. Install duct volume-control dampers according to Division 23 Sections specifying air ducts.
- K. Install electronic and fiber-optic cables according to Division 26 Section "Control/Signal Transmission Media."

3.3 ELECTRICAL WIRING AND CONNECTION INSTALLATION

- A. Unless noted otherwise, all electrical wiring required to interconnect and/or operate the components of the control system shall be furnished and installed by the Controls Contractor. Perform all wiring in accordance with the requirements listed below, code requirements and Division 26.
- B. Power wiring required for all components, controllers, and control panels shall be furnished and installed by the Controls Contractor. Power for these components shall be dedicated power circuits for the express use of the individual component, controller, or control panel. Circuits shall be furnished and designated by the Electrical Contractor. All circuit breakers and other electrical components required to provide this dedicated circuit shall be the responsibility of the Electrical Contractor.
- C. Power wiring required for the Area Controller shall also be dedicated as specified above, and if available in the building, shall be an emergency power circuit.
- D. Power wiring required for the Host PC Workstation shall be through a wall receptacle. If available within the room location, connect to an emergency power receptacle.
- E. All line voltage wiring shall be installed within EMT conduit. Conduit shall be adequately supported in accordance with local codes and Division 26.
- F. All low voltage wiring shall be installed within EMT conduit, except when ran in ceiling spaces. Low voltage wiring installed in ceiling spaces must be plenum rated wiring in accordance with local codes. All wiring in ceiling spaces must be properly supported to the building so as not to droop. Install wiring as close to the deck as possible to avoid damage from other trades or materials.
- G. All conduit and wiring shall be installed in parallel lines to the building structure, corridors, and hallways.
- H. Communication wiring shall be installed using shielded cable. The communication network wiring shall be clearly marked with a specific color code. Communication wiring shall not be installed near noise producing equipment, such as ballasts, magnetic starters, etc.
- I. All analog inputs and analog outputs shall be wired using shielded cable.
- J. All digital outputs shall be wired using 18 gauge stranded wire.
- K. All wiring in mechanical rooms, walls shall be installed in EMT conduit. Concealed conduit and wiring is required in all finished spaces.

- L. Connect manual-reset limit controls independent of manual-control switch positions. Automatic duct heater resets may be connected in interlock circuit of power controllers.
- M. Connect hand-off-auto selector switches to override automatic interlock controls when switch is in hand position.
- N. Install raceways, boxes, and cabinets according to Division 26 Section "Raceways and Boxes."
- O. Install building wire and cable according to Division 26 Section "Conductors and Cables."
- P. Install signal and communication cable according to Division 26 Section "Control/Signal Transmission Media."
 - 1. Conceal cable, except in mechanical rooms and areas where other conduit and piping are exposed.
 - 2. Install exposed cable in raceway.
 - 3. Install concealed cable in raceway.
 - 4. Bundle and harness multiconductor instrument cable in place of single cables where several cables follow a common path.
 - 5. Fasten flexible conductors, bridging cabinets and doors, along hinge side; protect against abrasion. Tie and support conductors.
 - 6. Number-code or color-code conductors for future identification and service of control system, except local individual room control cables.

3.4 CONNECTIONS

- A. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
 - 1. Install piping adjacent to machine to allow service and maintenance.
- B. Ground equipment.
 - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.5 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect field-assembled components and equipment installation, including piping and electrical connections. Report results in writing.
 - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Operational Test: After electrical circuitry has been energized, start units to confirm proper unit operation. Remove malfunctioning units, replace with new units, and retest.
 - 3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment, and retest.

4. Pressure test control air piping at 30 psig or 1.5 times the operating pressure for 24 hours, with maximum 5-psig loss.
 5. Pressure test high-pressure control air piping at 150 psig and low-pressure control air piping at 30 psig for 2 hours, with maximum 1-psig loss.
 6. Calibration test electronic controllers by disconnecting input sensors and stimulating operation with compatible signal generator.
- B. Engage a factory-authorized service representative to perform startup service.
- C. Replace damaged or malfunctioning controls and equipment.
1. Start, test, and adjust control systems.
 2. Demonstrate compliance with requirements, including calibration and testing, and control sequences.
 3. Adjust, calibrate, and fine tune circuits and equipment to achieve sequence of operation specified.
- D. Verify DDC as follows:
1. Verify software including automatic restart, control sequences, scheduling, reset controls, and occupied/unoccupied cycles.
 2. Verify operation of operator workstation.
 3. Verify local control units including self-diagnostics.

3.6 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain control systems and components.
1. Train Owner's maintenance personnel on procedures and schedules for starting and stopping, troubleshooting, servicing, and maintaining equipment and schedules.
 2. Provide operator training on data display, alarm and status descriptors, requesting data, executing commands, calibrating and adjusting devices, resetting default values, and requesting logs. Include a minimum of 40 hours' dedicated instructor time on-site.
 3. Review data in maintenance manuals. Refer to Division 1 Section "Contract Closeout."
 4. Review data in maintenance manuals. Refer to Division 1 Section "Operation and Maintenance Data."
 5. Schedule training with Owner, through Architect, with at least seven days' advance notice.

3.7 ON-SITE ASSISTANCE

- A. Occupancy Adjustments: Within one year of date of Substantial Completion, provide up to three Project site visits, when requested by Owner, to adjust and calibrate components and to assist Owner's personnel in making program changes and in adjusting sensors and controls to suit actual conditions.

END OF SECTION 23 09 90

24057 - CCF&R House #06

23 09 90 - Page 18 of 18

HVAC
INSTRUMENTATION AND
CONTROLS

SECTION 23 11 23 - FACILITY NATURAL-GAS PIPING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

1. Pipes, tubes, and fittings.
2. Piping specialties.
3. Piping and tubing joining materials.
4. Manual gas shutoff valves.
5. Motorized gas valves.
6. Earthquake valves.
7. Pressure regulators.
8. Service meters.
9. Dielectric fittings.

1.3 DEFINITIONS

- A. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, crawlspaces, and tunnels.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of the following:
 1. Piping specialties.
 2. Corrugated, stainless-steel tubing with associated components.
 3. Valves. Include pressure rating, capacity, settings, and electrical connection data of selected models.
 4. Pressure regulators. Indicate pressure ratings and capacities.
 5. Dielectric fittings.

- B. Shop Drawings: For facility natural-gas piping layout. Include plans, piping layout and elevations, sections, and details for fabrication of pipe anchors, hangers, supports for multiple pipes, alignment guides, expansion joints and loops, and attachments of the same to building structure. Detail location of anchors, alignment guides, and expansion joints and loops.
 - 1. Shop Drawing Scale: 1/4 inch per foot.
- C. Delegated-Design Submittal: For natural-gas piping and equipment indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
 - 1. Detail fabrication and assembly of seismic restraints.
 - 2. Design Calculations: Calculate requirements for selecting seismic restraints.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Plans and details, drawn to scale, on which natural-gas piping is shown and coordinated with other installations, using input from installers of the items involved.
- B. Site Survey: Plans, drawn to scale, on which natural-gas piping is shown and coordinated with other services and utilities.
- C. Qualification Data: For qualified professional engineer.
- D. Welding certificates.
- E. Field quality-control reports.

1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For pressure regulators to include in emergency, operation, and maintenance manuals.

1.7 QUALITY ASSURANCE

- A. Steel Support Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- B. Pipe Welding Qualifications: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Handling Flammable Liquids: Remove and dispose of liquids from existing natural-gas piping according to requirements of authorities having jurisdiction.

- B. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- C. Store and handle pipes and tubes having factory-applied protective coatings to avoid damaging coating, and protect from direct sunlight.
- D. Protect stored PE pipes and valves from direct sunlight.

1.9 PROJECT CONDITIONS

- A. Perform site survey, research public utility records, and verify existing utility locations. Contact utility-locating service for area where Project is located.
- B. Interruption of Existing Natural-Gas Service: Do not interrupt natural-gas service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide purging and startup of natural-gas supply according to requirements indicated:
 - 1. Notify Owner no fewer than two days in advance of proposed interruption of natural-gas service.
 - 2. Do not proceed with interruption of natural-gas service without Owner's written permission.

1.10 COORDINATION

- A. Coordinate sizes and locations of concrete bases with actual equipment provided.
- B. Coordinate requirements for access panels and doors for valves installed concealed behind finished surfaces. Comply with requirements in Section 08 31 13 "Access Doors and Frames."

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Minimum Operating-Pressure Ratings:
 - 1. Piping and Valves: 100 psig minimum unless otherwise indicated.
 - 2. Service Regulators: 65 psig minimum unless otherwise indicated.
 - 3. Minimum Operating Pressure of Service Meter: 5 psig.
- B. Natural-Gas System Pressures within Buildings: Two pressure ranges. Primary pressure is more than 0.5 psig but not more than 2 psig, and is reduced to secondary pressure of 0.5 psig or less.

2.2 PIPES, TUBES, AND FITTINGS

- A. Steel Pipe: ASTM A53/A53M, black steel, Schedule 40, Type E or S, Grade B.

1. Malleable-Iron Threaded Fittings: ASME B16.3, Class 150, standard pattern.
 2. Wrought-Steel Welding Fittings: ASTM A234/A234M for butt welding and socket welding.
 3. Unions: ASME B16.39, Class 150, malleable iron with brass-to-iron seat, ground joint, and threaded ends.
 4. Forged-Steel Flanges and Flanged Fittings: ASME B16.5, minimum Class 150, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
 - a. Material Group: 1.1.
 - b. End Connections: Threaded or butt welding to match pipe.
 - c. Lapped Face: Not permitted underground.
 - d. Gasket Materials: ASME B16.20, metallic, flat, asbestos free, aluminum o-rings, and spiral-wound metal gaskets.
 - e. Bolts and Nuts: ASME B18.2.1, carbon steel aboveground and stainless steel underground.
 5. Protective Coating for Underground Piping: Factory-applied, three-layer coating of epoxy, adhesive, and PE.
 - a. Joint Cover Kits: Epoxy paint, adhesive, and heat-shrink PE sleeves.
 6. Mechanical Couplings:
 - a. Stainless-steel flanges and tube with epoxy finish.
 - b. Buna-nitrile seals.
 - c. Stainless-steel bolts, washers, and nuts.
 - d. Coupling shall be capable of joining PE pipe to PE pipe, steel pipe to PE pipe, or steel pipe to steel pipe.
 - e. Steel body couplings installed underground on plastic pipe shall be factory equipped with anode.
- B. Corrugated, Stainless-Steel Tubing: Comply with ANSI/IAS LC 1.
1. Tubing: ASTM A240/A240M, corrugated, Series 300 stainless steel.
 2. Coating: PE with flame retardant.
 - a. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1) Flame-Spread Index: 25 or less.
 - 2) Smoke-Developed Index: 50 or less.
 3. Fittings: Copper-alloy mechanical fittings with ends made to fit and listed for use with corrugated stainless-steel tubing and capable of metal-to-metal seal without gaskets. Include brazing socket or threaded ends complying with ASME B1.20.1.
 4. Striker Plates: Steel, designed to protect tubing from penetrations.
 5. Manifolds: Malleable iron or steel with factory-applied protective coating. Threaded connections shall comply with ASME B1.20.1 for pipe inlet and corrugated tubing outlets.
 6. Operating-Pressure Rating: 5 psig.
- C. Aluminum Tubing: Comply with ASTM B210 and ASTM B241/B241M.

1. Aluminum Alloy: Alloy 5456 is prohibited.
2. Protective Coating: Factory-applied coating capable of resisting corrosion on tubing in contact with masonry, plaster, insulation, water, detergents, and sewerage.
3. Flare Fittings: Comply with ASME B16.26 and SAE J513.
 - a. Copper-alloy fittings.
 - b. Metal-to-metal compression seal without gasket.
 - c. Dryseal threads shall comply with ASME B1.20.3.

D. PE Pipe: ASTM D2513, SDR 11.

1. PE Fittings: ASTM D2683, socket-fusion type or ASTM D3261, butt-fusion type with dimensions matching PE pipe.
2. PE Transition Fittings: Factory-fabricated fittings with PE pipe complying with ASTM D2513, SDR 11; and steel pipe complying with ASTM A53/A53M, black steel, Schedule 40, Type E or S, Grade B.
3. Anodeless Service-Line Risers: Factory fabricated and leak tested.
 - a. Underground Portion: PE pipe complying with ASTM D2513, SDR 11 inlet.
 - b. Casing: Steel pipe complying with ASTM A53/A53M, Schedule 40, black steel, Type E or S, Grade B, with corrosion-protective coating covering. Vent casing aboveground.
 - c. Aboveground Portion: PE transition fitting.
 - d. Outlet shall be threaded or flanged or suitable for welded connection.
 - e. Tracer wire connection.
 - f. Ultraviolet shield.
 - g. Stake supports with factory finish to match steel pipe casing or carrier pipe.
4. Transition Service-Line Risers: Factory fabricated and leak tested.
 - a. Underground Portion: PE pipe complying with ASTM D2513, SDR 11 inlet connected to steel pipe complying with ASTM A53/A53M, Schedule 40, Type E or S, Grade B, with corrosion-protective coating for aboveground outlet.
 - b. Outlet shall be threaded or flanged or suitable for welded connection.
 - c. Bridging sleeve over mechanical coupling.
 - d. Factory-connected anode.
 - e. Tracer wire connection.
 - f. Ultraviolet shield.
 - g. Stake supports with factory finish to match steel pipe casing or carrier pipe.
5. Steel Mechanical Couplings: Capable of joining plain-end PE pipe to PE pipe, steel pipe to PE pipe, or steel pipe to steel pipe.
 - a. Stainless-steel flanges and tube with epoxy finish.
 - b. Buna-nitrile seals.
 - c. Stainless-steel bolts, washers, and nuts.
 - d. Factory-installed anode for steel-body couplings installed underground.

2.3 PIPING SPECIALTIES

A. Appliance Flexible Connectors:

1. Indoor, Fixed-Appliance Flexible Connectors: Comply with ANSI Z21.24.
 2. Indoor, Movable-Appliance Flexible Connectors: Comply with ANSI Z21.69.
 3. Outdoor, Appliance Flexible Connectors: Comply with ANSI Z21.75.
 4. Corrugated stainless-steel tubing with polymer coating.
 5. Operating-Pressure Rating: 0.5 psig.
 6. End Fittings: Zinc-coated steel.
 7. Threaded Ends: Comply with ASME B1.20.1.
 8. Maximum Length: 72 inches
- B. Quick-Disconnect Devices: Comply with ANSI Z21.41.
1. Copper-alloy convenience outlet and matching plug connector.
 2. Nitrile seals.
 3. Hand operated with automatic shutoff when disconnected.
 4. For indoor or outdoor applications.
 5. Adjustable, retractable restraining cable.
- C. Y-Pattern Strainers:
1. Body: ASTM A126, Class B, cast iron with bolted cover and bottom drain connection.
 2. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
 3. Strainer Screen: 40 -mesh startup strainer, and perforated stainless-steel basket with 50 percent free area.
 4. CWP Rating: 125 psig.
- D. Basket Strainers:
1. Body: ASTM A126, Class B, high-tensile cast iron with bolted cover and bottom drain connection.
 2. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
 3. Strainer Screen: 40 -mesh startup strainer, and perforated stainless-steel basket with 50 percent free area.
 4. CWP Rating: 125 psig.
- E. T-Pattern Strainers:
1. Body: Ductile or malleable iron with removable access coupling and end cap for strainer maintenance.
 2. End Connections: Grooved ends.
 3. Strainer Screen: 40 -mesh startup strainer and perforated stainless-steel basket with 57 percent free area.
 4. CWP Rating: 750 psig.
- F. Weatherproof Vent Cap: Cast- or malleable-iron increaser fitting with corrosion-resistant wire screen, with free area at least equal to cross-sectional area of connecting pipe and threaded-end connection.

2.4 JOINING MATERIALS

- A. Joint Compound and Tape: Suitable for natural gas.
- B. Welding Filler Metals: Comply with AWS D10.12/D10.12M for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- C. Brazing Filler Metals: Alloy with melting point greater than 1000 deg F complying with AWS A5.8/A5.8M. Brazing alloys containing more than 0.05 percent phosphorus are prohibited.

2.5 MANUAL GAS SHUTOFF VALVES

- A. See "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles for where each valve type is applied in various services.
- B. General Requirements for Metallic Valves, NPS 2 and Smaller: Comply with ASME B16.33.
 - 1. CWP Rating: 125 psig.
 - 2. Threaded Ends: Comply with ASME B1.20.1.
 - 3. Dryseal Threads on Flare Ends: Comply with ASME B1.20.3.
 - 4. Tamperproof Feature: Locking feature for valves indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 5. Listing: Listed and labeled by an NRTL acceptable to authorities having jurisdiction for valves 1 inch and smaller.
 - 6. Service Mark: Valves 1-1/4 inches to NPS 2 shall have initials "WOG" permanently marked on valve body.
- C. General Requirements for Metallic Valves, NPS 2-1/2 and Larger: Comply with ASME B16.38.
 - 1. CWP Rating: 125 psig.
 - 2. Flanged Ends: Comply with ASME B16.5 for steel flanges.
 - 3. Tamperproof Feature: Locking feature for valves indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 4. Service Mark: Initials "WOG" shall be permanently marked on valve body.
- D. One-Piece, Bronze Ball Valve with Bronze Trim: MSS SP-110.
 - 1. Body: Bronze, complying with ASTM B584.
 - 2. Ball: Chrome-plated brass.
 - 3. Stem: Bronze; blowout proof.
 - 4. Seats: Reinforced TFE; blowout proof.
 - 5. Packing: Separate packnut with adjustable-stem packing threaded ends.
 - 6. Ends: Threaded, flared, or socket as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 7. CWP Rating: 600 psig.
 - 8. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
 - 9. Service: Suitable for natural-gas service with "WOG" indicated on valve body.

- E. Two-Piece, Full-Port, Bronze Ball Valves with Bronze Trim: MSS SP-110.
 - 1. Body: Bronze, complying with ASTM B584.
 - 2. Ball: Chrome-plated bronze.
 - 3. Stem: Bronze; blowout proof.
 - 4. Seats: Reinforced TFE; blowout proof.
 - 5. Packing: Threaded-body packnut design with adjustable-stem packing.
 - 6. Ends: Threaded, flared, or socket as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 7. CWP Rating: 600 psig.
 - 8. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
 - 9. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
- F. Bronze Plug Valves: MSS SP-78.
 - 1. Body: Bronze, complying with ASTM B584.
 - 2. Plug: Bronze.
 - 3. Ends: Threaded, socket, or flanged as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 4. Operator: Square head or lug type with tamperproof feature where indicated.
 - 5. Pressure Class: 125 psig.
 - 6. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
 - 7. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
- G. Cast-Iron, Nonlubricated Plug Valves: MSS SP-78.
 - 1. Body: Cast iron, complying with ASTM A126, Class B.
 - 2. Plug: Bronze or nickel-plated cast iron.
 - 3. Seat: Coated with thermoplastic.
 - 4. Stem Seal: Compatible with natural gas.
 - 5. Ends: Threaded or flanged as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 6. Operator: Square head or lug type with tamperproof feature where indicated.
 - 7. Pressure Class: 125 psig.
 - 8. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
 - 9. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
- H. Cast-Iron, Lubricated Plug Valves: MSS SP-78.
 - 1. Body: Cast iron, complying with ASTM A126, Class B.
 - 2. Plug: Bronze or nickel-plated cast iron.
 - 3. Seat: Coated with thermoplastic.
 - 4. Stem Seal: Compatible with natural gas.
 - 5. Ends: Threaded or flanged as indicated in "Underground Manual Gas Shutoff Valve Schedule" and "Aboveground Manual Gas Shutoff Valve Schedule" Articles.
 - 6. Operator: Square head or lug type with tamperproof feature where indicated.
 - 7. Pressure Class: 125 psig.
 - 8. Listing: Valves NPS 1 and smaller shall be listed and labeled by an NRTL acceptable to authorities having jurisdiction.
 - 9. Service: Suitable for natural-gas service with "WOG" indicated on valve body.
- I. PE Ball Valves: Comply with ASME B16.40.

1. Body: PE.
2. Ball: PE.
3. Stem: Acetal.
4. Seats and Seals: Nitrile.
5. Ends: Plain or fusible to match piping.
6. CWP Rating: 80 psig.
7. Operating Temperature: Minus 20 to plus 140 deg F.
8. Operator: Nut or flat head for key operation.
9. Include plastic valve extension.
10. Include tamperproof locking feature for valves where indicated on Drawings.

J. Valve Boxes:

1. Cast-iron, two-section box.
2. Top section with cover with "GAS" lettering.
3. Bottom section with base to fit over valve and barrel a minimum of 5 inches in diameter.
4. Adjustable cast-iron extensions of length required for depth of bury.
5. Include tee-handle, steel operating wrench with socket end fitting valve nut or flat head, and with stem of length required to operate valve.

2.6 MOTORIZED GAS VALVES

A. Automatic Gas Valves: Comply with ANSI Z21.21.

1. Body: Brass or aluminum.
2. Seats and Disc: Nitrile rubber.
3. Springs and Valve Trim: Stainless steel.
4. Normally closed.
5. Visual position indicator.
6. Electrical operator for actuation by appliance automatic shutoff device.

B. Electrically Operated Valves: Comply with UL 429.

1. Pilot operated.
2. Body: Brass or aluminum.
3. Seats and Disc: Nitrile rubber.
4. Springs and Valve Trim: Stainless steel.
5. 120-V ac, 60 Hz, Class B, continuous-duty molded coil, and replaceable.
6. NEMA ICS 6, Type 4, coil enclosure.
7. Normally closed.
8. Visual position indicator.

2.7 EARTHQUAKE VALVES

A. Earthquake Valves, Maximum Operating Pressure of 5 psig: Comply with ASCE 25.

1. Listing: Listed and labeled by an NRTL acceptable to authorities having jurisdiction.
2. Maximum Operating Pressure: 5 psig.
3. Cast-aluminum body with nickel-plated chrome steel internal parts.
4. Nitrile-rubber valve washer.
5. Sight windows for visual indication of valve position.
6. Threaded end connections complying with ASME B1.20.1.

7. Wall mounting bracket with bubble level indicator.

2.8 PRESSURE REGULATORS

A. General Requirements:

1. Single stage and suitable for natural gas.
2. Steel jacket and corrosion-resistant components.
3. Elevation compensator.
4. End Connections: Threaded for regulators NPS 2 and smaller; flanged for regulators NPS 2-1/2 and larger.

B. Line Pressure Regulators: Comply with ANSI Z21.80.

1. Body and Diaphragm Case: Cast iron or die-cast aluminum.
2. Springs: Zinc-plated steel; interchangeable.
3. Diaphragm Plate: Zinc-plated steel.
4. Seat Disc: Nitrile rubber resistant to gas impurities, abrasion, and deformation at the valve port.
5. Orifice: Aluminum; interchangeable.
6. Seal Plug: Ultraviolet-stabilized, mineral-filled nylon.
7. Single-port, self-contained regulator with orifice no larger than required at maximum pressure inlet, and no pressure sensing piping external to the regulator.
8. Pressure regulator shall maintain discharge pressure setting downstream, and not exceed 150 percent of design discharge pressure at shutoff.
9. Overpressure Protection Device: Factory mounted on pressure regulator.
10. Atmospheric Vent: Factory- or field-installed, stainless-steel screen in opening if not connected to vent piping.
11. Maximum Inlet Pressure: 5 psig.

C. Appliance Pressure Regulators: Comply with ANSI Z21.18.

1. Body and Diaphragm Case: Die-cast aluminum.
2. Springs: Zinc-plated steel; interchangeable.
3. Diaphragm Plate: Zinc-plated steel.
4. Seat Disc: Nitrile rubber.
5. Seal Plug: Ultraviolet-stabilized, mineral-filled nylon.
6. Factory-Applied Finish: Minimum three-layer polyester and polyurethane paint finish.
7. Regulator may include vent limiting device, instead of vent connection, if approved by authorities having jurisdiction.
8. Maximum Inlet Pressure: 2 psig.

2.9 DIELECTRIC FITTINGS

A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.

B. Dielectric Unions:

1. Description:
 - a. Standard: ASSE 1079.

- b. Pressure Rating: 125 psig minimum at 180 deg F.
 - c. End Connections: Solder-joint copper alloy and threaded ferrous.
- C. Dielectric Flanges:
 - 1. Description:
 - a. Standard: ASSE 1079.
 - b. Factory-fabricated, bolted, companion-flange assembly.
 - c. Pressure Rating: 125 psig minimum at 180 deg F.
 - d. End Connections: Solder-joint copper alloy and threaded ferrous; threaded solder-joint copper alloy and threaded ferrous.
- D. Dielectric-Flange Insulating Kits:
 - 1. Description:
 - a. Nonconducting materials for field assembly of companion flanges.
 - b. Pressure Rating: 150 psig.
 - c. Gasket: Neoprene or phenolic.
 - d. Bolt Sleeves: Phenolic or polyethylene.
 - e. Washers: Phenolic with steel backing washers.

2.10 LABELING AND IDENTIFYING

- A. Detectable Warning Tape: Acid- and alkali-resistant, PE film warning tape manufactured for marking and identifying underground utilities, a minimum of 6 inches wide and 4 mils thick, continuously inscribed with a description of utility, with metallic core encased in a protective jacket for corrosion protection, detectable by metal detector when tape is buried up to 30 inches deep; colored yellow.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine roughing-in for natural-gas piping system to verify actual locations of piping connections before equipment installation.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

- A. Close equipment shutoff valves before turning off natural gas to premises or piping section.
- B. Inspect natural-gas piping according to NFPA 54 to determine that natural-gas utilization devices are turned off in piping section affected.
- C. Comply with NFPA 54 requirements for prevention of accidental ignition.

3.3 OUTDOOR PIPING INSTALLATION

- A. Comply with NFPA 54 for installation and purging of natural-gas piping.
- B. Install underground, natural-gas piping buried at least 36 inches below finished grade. Comply with requirements in Section 31 20 00 "Earth Moving" for excavating, trenching, and backfilling.
 - 1. If natural-gas piping is installed less than 36 inches below finished grade, install it in containment conduit.
- C. Install underground, PE, natural-gas piping according to ASTM D2774.
- D. Steel Piping with Protective Coating:
 - 1. Apply joint cover kits to pipe after joining to cover, seal, and protect joints.
 - 2. Repair damage to PE coating on pipe as recommended in writing by protective coating manufacturer.
 - 3. Replace pipe having damaged PE coating with new pipe.
- E. Copper Tubing with Protective Coating:
 - 1. Apply joint cover kits over tubing to cover, seal, and protect joints.
 - 2. Repair damage to PE coating on pipe as recommended in writing by protective coating manufacturer.
- F. Install fittings for changes in direction and branch connections.
- G. Install pressure gage downstream from each service regulator. Pressure gages are specified in Section 23 05 19 "Meters and Gages for HVAC Piping."

3.4 INDOOR PIPING INSTALLATION

- A. Comply with NFPA 54 for installation and purging of natural-gas piping.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements are used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Arrange for pipe spaces, chases, slots, sleeves, and openings in building structure during progress of construction, to allow for mechanical installations.
- D. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- E. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- F. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

- G. Locate valves for easy access.
- H. Install natural-gas piping at uniform grade of 2 percent down toward drip and sediment traps.
- I. Install piping free of sags and bends.
- J. Install fittings for changes in direction and branch connections.
- K. Verify final equipment locations for roughing-in.
- L. Comply with requirements in Sections specifying gas-fired appliances and equipment for roughing-in requirements.
- M. Drips and Sediment Traps: Install drips at points where condensate may collect, including service-meter outlets. Locate where accessible to permit cleaning and emptying. Do not install where condensate is subject to freezing.
 - 1. Construct drips and sediment traps using tee fitting with bottom outlet plugged or capped. Use nipple a minimum length of 3 pipe diameters, but not less than 3 inches long and same size as connected pipe. Install with space below bottom of drip to remove plug or cap.
- N. Extend relief vent connections for service regulators, line regulators, and overpressure protection devices to outdoors and terminate with weatherproof vent cap.
- O. Conceal pipe installations in walls, pipe spaces, utility spaces, above ceilings, below grade or floors, and in floor channels unless indicated to be exposed to view.
- P. Concealed Location Installations: Except as specified below, install concealed natural-gas piping and piping installed under the building in containment conduit constructed of steel pipe with welded joints as described in Part 2. Install a vent pipe from containment conduit to outdoors and terminate with weatherproof vent cap.
 - 1. Above Accessible Ceilings: Natural-gas piping, fittings, valves, and regulators may be installed in accessible spaces without containment conduit.
 - 2. In Floors: Install natural-gas piping with welded or brazed joints and protective coating in cast-in-place concrete floors. Cover piping to be cast in concrete slabs with minimum of 1-1/2 inches of concrete. Piping may not be in physical contact with other metallic structures such as reinforcing rods or electrically neutral conductors. Do not embed piping in concrete slabs containing quick-set additives or cinder aggregate.
 - 3. In Floor Channels: Install natural-gas piping in floor channels. Channels must have cover and be open to space above cover for ventilation.
 - 4. In Walls or Partitions: Protect tubing installed inside partitions or hollow walls from physical damage using steel striker barriers at rigid supports.
 - a. Exception: Tubing passing through partitions or walls does not require striker barriers.
 - 5. Prohibited Locations:

- a. Do not install natural-gas piping in or through circulating air ducts, clothes or trash chutes, chimneys or gas vents (flues), ventilating ducts, or dumbwaiter or elevator shafts.
 - b. Do not install natural-gas piping in solid walls or partitions.
- Q. Use eccentric reducer fittings to make reductions in pipe sizes. Install fittings with level side down.
- R. Connect branch piping from top or side of horizontal piping.
- S. Install unions in pipes NPS 2 and smaller, adjacent to each valve, at final connection to each piece of equipment. Unions are not required at flanged connections.
- T. Do not use natural-gas piping as grounding electrode.
- U. Install strainer on inlet of each line-pressure regulator and automatic or electrically operated valve.
- V. Install pressure gage downstream from each line regulator. Pressure gages are specified in Section 23 05 19 "Meters and Gages for HVAC Piping."
- W. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 23 05 17 "Sleeves and Sleeve Seals for HVAC Piping."
- X. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 23 05 17 "Sleeves and Sleeve Seals for HVAC Piping."
- Y. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 23 05 18 "Escutcheons for HVAC Piping."

3.5 VALVE INSTALLATION

- A. Install manual gas shutoff valve for each gas appliance ahead of corrugated stainless-steel tubing, aluminum, or copper connector.
- B. Install underground valves with valve boxes.
- C. Install regulators and overpressure protection devices with maintenance access space adequate for servicing and testing.
- D. Install earthquake valves aboveground outside buildings according to listing.
- E. Install anode for metallic valves in underground PE piping.

3.6 PIPING JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs.

- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- C. Threaded Joints:
 - 1. Thread pipe with tapered pipe threads complying with ASME B1.20.1.
 - 2. Cut threads full and clean using sharp dies.
 - 3. Ream threaded pipe ends to remove burrs and restore full inside diameter of pipe.
 - 4. Apply appropriate tape or thread compound to external pipe threads unless dryseal threading is specified.
 - 5. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- D. Welded Joints:
 - 1. Construct joints according to AWS D10.12/D10.12M, using qualified processes and welding operators.
 - 2. Bevel plain ends of steel pipe.
 - 3. Patch factory-applied protective coating as recommended by manufacturer at field welds and where damage to coating occurs during construction.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter.
- F. Flanged Joints: Install gasket material, size, type, and thickness appropriate for natural-gas service. Install gasket concentrically positioned.
- G. Flared Joints: Cut tubing with roll cutting tool. Flare tube end with tool to result in flare dimensions complying with SAE J513. Tighten finger tight, then use wrench. Do not overtighten.
- H. PE Piping Heat-Fusion Joints: Clean and dry joining surfaces by wiping with clean cloth or paper towels. Join according to ASTM D2657.
 - 1. Plain-End Pipe and Fittings: Use butt fusion.
 - 2. Plain-End Pipe and Socket Fittings: Use socket fusion.

3.7 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements for seismic-restraint devices specified in Section 23 05 48 "Vibration and Seismic Controls for HVAC."
- B. Comply with requirements for pipe hangers and supports specified in Section 23 05 29 "Hangers and Supports for HVAC Piping and Equipment."
- C. Install hangers for steel piping, with maximum horizontal spacing and minimum rod diameters, to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

- D. Install hangers for corrugated stainless-steel tubing, with maximum horizontal spacing and minimum rod diameters, to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- E. Support horizontal piping within 12 inches of each fitting.
- F. Support vertical runs of steel piping to comply with MSS-58, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.
- G. Support vertical runs of corrugated stainless-steel tubing to comply with manufacturer's written instructions, locally enforced codes, and authorities having jurisdiction requirements, whichever are most stringent.

3.8 CONNECTIONS

- A. Connect to utility's gas main according to utility's procedures and requirements.
- B. Install natural-gas piping electrically continuous, and bonded to gas appliance equipment grounding conductor of the circuit powering the appliance according to NFPA 70.
- C. Install piping adjacent to appliances to allow service and maintenance of appliances.
- D. Connect piping to appliances using manual gas shutoff valves and unions. Install valve within 72 inches of each gas-fired appliance and equipment. Install union between valve and appliances or equipment.
- E. Sediment Traps: Install tee fitting with capped nipple in bottom to form drip, as close as practical to inlet of each appliance.

3.9 LABELING AND IDENTIFYING

- A. Install detectable warning tape directly above gas piping, 12 inches below finished grade, except 6 inches below subgrade under pavements and slabs.

3.10 PAINTING

- A. Comply with requirements in Section 09 91 13 "Exterior Painting" and Section 09 91 23 "Interior Painting" for painting interior and exterior natural-gas piping.
- B. Paint exposed, exterior metal piping, valves, service regulators, service meters and meter bars, earthquake valves, and piping specialties, except components, with factory-applied paint or protective coating.
 - 1. Alkyd System: MPI EXT 5.1D.
 - a. Prime Coat: Alkyd anticorrosive metal primer.
 - b. Intermediate Coat: Exterior alkyd enamel matching topcoat.
 - c. Topcoat: Exterior alkyd enamel (flat).
 - d. Color: Gray.

- C. Paint exposed, interior metal piping, valves, service regulators, service meters and meter bars, earthquake valves, and piping specialties, except components, with factory-applied paint or protective coating.
 - 1. Latex Over Alkyd Primer System: MPI INT 5.1Q.
 - a. Prime Coat: Alkyd anticorrosive metal primer.
 - b. Intermediate Coat: Interior latex matching topcoat.
 - c. Topcoat: Interior latex (flat).
 - d. Color: Gray.
 - 2. Alkyd System: MPI INT 5.1E.
 - a. Prime Coat: Alkyd anticorrosive metal primer.
 - b. Intermediate Coat: Interior alkyd matching topcoat.
 - c. Topcoat: Interior alkyd (flat).
 - d. Color: Gray.
- D. Damage and Touchup: Repair marred and damaged factory-applied finishes with materials and by procedures to match original factory finish.

3.11 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
 - 1. Test, inspect, and purge natural gas according to NFPA 54 and authorities having jurisdiction.
- C. Natural-gas piping will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

3.12 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain earthquake valves.

3.13 OUTDOOR PIPING SCHEDULE

- A. Underground natural-gas piping shall be the following:
 - 1. PE pipe and fittings joined by heat fusion, or mechanical couplings; service-line risers with tracer wire terminated in an accessible location.
- B. Aboveground natural-gas piping shall be one of the following:
 - 1. Steel pipe with malleable-iron fittings and threaded joints.

2. Steel pipe with wrought-steel fittings and welded joints.
- C. Containment Conduit: Steel pipe with wrought-steel fittings and welded joints. Coat pipe and fittings with protective coating for steel piping.

3.14 INDOOR PIPING SCHEDULE FOR SYSTEM PRESSURES LESS THAN 0.5 PSIG

- A. Aboveground, branch piping NPS 1 and smaller shall be the following:
 1. Steel pipe with malleable-iron fittings and threaded joints.
- B. Aboveground, distribution piping shall be one of the following:
 1. Steel pipe with malleable-iron fittings and threaded joints.
 2. Steel pipe with wrought-steel fittings and welded joints.

3.15 INDOOR PIPING SCHEDULE FOR SYSTEM PRESSURES MORE THAN 0.5 PSIG AND LESS THAN 5 PSIG

- A. Aboveground, branch piping NPS 1 and smaller shall be the following:
 1. Steel pipe with malleable-iron fittings and threaded joints.
- B. Aboveground, distribution piping shall be one of the following:
 1. Steel pipe with malleable-iron fittings and threaded joints.
 2. Steel pipe with steel welding fittings and welded joints.
- C. Underground, below building, piping shall be one of the following:
 1. Steel pipe with malleable-iron fittings and threaded joints.
 2. Steel pipe with wrought-steel fittings and welded joints.

3.16 ABOVEGROUND MANUAL GAS SHUTOFF VALVE SCHEDULE

- A. Valves for pipe sizes NPS 2 and smaller at service meter shall be one of the following:
 1. One-piece, bronze ball valve with bronze trim.
 2. Two-piece, full -port, bronze ball valves with bronze trim.
 3. Bronze plug valve.
- B. Valves for pipe sizes NPS 2-1/2 and larger at service meter shall be the following:
 1. Two-piece, full -port, bronze ball valves with bronze trim.
- C. Distribution piping valves for pipe sizes NPS 2 and smaller shall be the following:
 1. One-piece, bronze ball valve with bronze trim.
 2. Two-piece, full -port, bronze ball valves with bronze trim.
- D. Valves in branch piping for single appliance shall be the following:

1. Two-piece, full -port, bronze ball valves with bronze trim.

END OF SECTION 23 11 23

This page intentionally left blank.

SECTION 23 31 13 - METAL DUCTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes metal ducts for supply, return, outside, and exhaust air-distribution systems in pressure classes from minus 2- to plus 10-inch wg. Metal ducts include the following:
 - 1. Rectangular ducts and fittings.
 - 2. Single-wall, round spiral-seam ducts and formed fittings.
 - 3. Double-wall, round spiral-seam ducts and formed fittings.
 - 4. Duct liner.
- B. Related Sections include the following:
 - 1. Division 23 Section "Duct Accessories" for dampers, sound-control devices, duct-mounting access doors and panels, turning vanes, and flexible ducts.
 - 2. Section 23 05 49 "Mechanical, Plumbing and Fire Protection Systems; Supports, Bracing and Seismic Requirements".
 - 3. Section 23 00 50 "Basic Mechanical Materials and Methods".

1.3 DEFINITIONS

- A. NUSIG: National Uniform Seismic Installation Guidelines.

1.4 SYSTEM DESCRIPTION

- A. Duct system design, as indicated, has been used to select size and type of air-moving and -distribution equipment and other air system components. Changes to layout or configuration of duct system must be specifically approved in writing by Architect. Accompany requests for layout modifications with calculations showing that proposed layout will provide original design results without increasing system total pressure.

1.5 SUBMITTALS

- A. Shop Drawings: CAD-generated and drawn to 1/4 inch equals 1 foot or 1/8 inch equals 1 foot scale. Show fabrication and installation details for metal ducts.
 - 1. Fabrication, assembly, and installation, including plans, elevations, sections, components, and attachments to other work.

2. Duct layout indicating sizes and pressure classes.
 3. Elevations of top and bottom of ducts.
 4. Dimensions of main duct runs from building grid lines.
 5. Fittings.
 6. Reinforcement and spacing.
 7. Seam and joint construction.
 8. Penetrations through fire-rated and other partitions.
 9. Equipment installation based on equipment being used on Project.
 10. Duct accessories, including access doors and panels.
 11. Hangers and supports, including methods for duct and building attachment, vibration isolation, and seismic restraints.
- B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
1. Ceiling suspension assembly members.
 2. Other systems installed in same space as ducts.
 3. Ceiling- and wall-mounting access doors and panels required to provide access to dampers and other operating devices.
 4. Ceiling-mounting items, including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
- C. Welding certificates.
- D. Field quality-control test reports.

1.6 QUALITY ASSURANCE

- A. Welding: Qualify procedures and personnel according to AWS D1.1, "Structural Welding Code--Steel," for hangers and supports AWS D1.2, "Structural Welding Code--Aluminum," for aluminum supporting members and AWS D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.
- B. NFPA Compliance:
1. NFPA 90A, "Installation of Air Conditioning and Ventilating Systems."
 2. NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 SHEET METAL MATERIALS

- A. Comply with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods, unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Lock-forming quality; complying with ASTM A 653/A 653M and having G90 coating designation; ducts shall have mill-phosphatized finish for surfaces exposed to view.
- C. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts.
- D. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.3 DUCT LINER

- A. Fibrous-Glass Liner: Comply with NFPA 90A or NFPA 90B and with NAIMA AH124.
 - 1. Manufacturers:
 - a. CertainTeed Corp.; Insulation Group.
 - b. Johns Manville International, Inc.
 - c. Knauf Fiber Glass GmbH.
 - d. Owens Corning.
 - 2. Materials: ASTM C 1071; surfaces exposed to airstream shall be coated to prevent erosion of glass fibers.
 - a. Thickness: 1 inch.
 - b. Thermal Conductivity (k-Value): 0.26 at 75 deg F mean temperature.
 - c. Fire-Hazard Classification: Maximum flame-spread index of 25 and smoke-developed index of 50 when tested according to ASTM E 84.
 - d. Liner Adhesive: Comply with NFPA 90A or NFPA 90B and with ASTM C 916.
 - e. Mechanical Fasteners: Galvanized steel suitable for adhesive attachment, mechanical attachment, or welding attachment to duct without damaging liner when applied as recommended by manufacturer and without causing leakage in duct.
 - 1) Tensile Strength: Indefinitely sustain a 50-lb- tensile, dead-load test perpendicular to duct wall.
 - 2) Fastener Pin Length: As required for thickness of insulation and without projecting more than 1/8 inch into airstream.
 - 3) Adhesive for Attaching Mechanical Fasteners: Comply with fire-hazard classification of duct liner system.

2.4 SEALANT MATERIALS

- A. Joint and Seam Sealants, General: The term "sealant" is not limited to materials of adhesive or mastic nature but includes tapes and combinations of open-weave fabric strips and mastics.
- B. Joint and Seam Tape: 2 inches wide; glass-fiber-reinforced fabric.
- C. Tape Sealing System: Woven-fiber tape impregnated with gypsum mineral compound and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
- D. Water-Based Joint and Seam Sealant: Flexible, adhesive sealant, resistant to UV light when cured, UL 723 listed, and complying with NFPA requirements for Class 1 ducts.
- E. Solvent-Based Joint and Seam Sealant: One-part, nonsag, solvent-release-curing, polymerized butyl sealant formulated with a minimum of 75 percent solids.
- F. Flanged Joint Mastic: One-part, acid-curing, silicone, elastomeric joint sealant complying with ASTM C 920, Type S, Grade NS, Class 25, Use O.
- G. Flange Gaskets: Butyl rubber or EPDM polymer with polyisobutylene plasticizer.

2.5 HANGERS AND SUPPORTS

- A. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
 - 1. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
 - 2. Exception: Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
- B. Hanger Materials: Galvanized sheet steel or threaded steel rod.
 - 1. Hangers Installed in Corrosive Atmospheres: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
 - 2. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for steel sheet width and thickness and for steel rod diameters.
 - 3. Galvanized-steel straps attached to aluminum ducts shall have contact surfaces painted with zinc-chromate primer.
- C. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- D. Trapeze and Riser Supports: Steel shapes complying with ASTM A 36/A 36M.
 - 1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
 - 2. Supports for Stainless-Steel Ducts: Stainless-steel support materials.
 - 3. Supports for Aluminum Ducts: Aluminum support materials unless materials are electrolytically separated from ducts.

2.6 RECTANGULAR DUCT FABRICATION

- A. Fabricate ducts, elbows, transitions, offsets, branch connections, and other construction according to SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" and complying with requirements for metal thickness, reinforcing types and intervals, tie-rod applications, and joint types and intervals.
 - 1. Lengths: Fabricate rectangular ducts in lengths appropriate to reinforcement and rigidity class required for pressure class.
 - 2. Deflection: Duct systems shall not exceed deflection limits according to SMACNA's "HVAC Duct Construction Standards--Metal and Flexible."
- B. Transverse Joints: Prefabricated slide-on joints and components constructed using manufacturer's guidelines for material thickness, reinforcement size and spacing, and joint reinforcement.
 - 1. Manufacturers:
 - a. Ductmate Industries, Inc.
 - b. Nexus Inc.
 - c. Ward Industries, Inc.
- C. Formed-On Flanges: Construct according to SMACNA's "HVAC Duct Construction Standards--Metal and Flexible," Figure 1-4, using corner, bolt, cleat, and gasket details.
 - 1. Manufacturers:
 - a. Ductmate Industries, Inc.
 - b. Lockformer.
 - 2. Duct Size: Maximum 30 inches wide and up to 2-inch wg pressure class.
 - 3. Longitudinal Seams: Pittsburgh lock sealed with noncuring polymer sealant.
- D. Cross Breaking or Cross Beading: Cross break or cross bead duct sides 19 inches and larger and 0.0359 inch thick or less, with more than 10 sq. ft. of nonbraced panel area unless ducts are lined.

2.7 APPLICATION OF LINER IN RECTANGULAR DUCTS

- A. Adhere a single layer of indicated thickness of duct liner with at least 90 percent adhesive coverage at liner contact surface area. Attaining indicated thickness with multiple layers of duct liner is prohibited.
- B. Apply adhesive to transverse edges of liner facing upstream that do not receive metal nosing.
- C. Butt transverse joints without gaps and coat joint with adhesive.
- D. Fold and compress liner in corners of rectangular ducts or cut and fit to ensure butted-edge overlapping.
- E. Do not apply liner in rectangular ducts with longitudinal joints, except at corners of ducts, unless duct size and standard liner product dimensions make longitudinal joints necessary.

- F. Apply adhesive coating on longitudinal seams in ducts with air velocity of 2500 fpm.
- G. Secure liner with mechanical fasteners 4 inches from corners and at intervals not exceeding 12 inches transversely; at 3 inches from transverse joints and at intervals not exceeding 18 inches longitudinally.
- H. Secure transversely oriented liner edges facing the airstream with metal nosings that have either channel or "Z" profiles or are integrally formed from duct wall. Fabricate edge facings at the following locations:
 - 1. Fan discharges.
 - 2. Intervals of lined duct preceding unlined duct.
 - 3. Upstream edges of transverse joints in ducts where air velocities are greater than 2500 fpm (12.7 m/s) or where indicated.
- I. Terminate inner ducts with buildouts attached to fire-damper sleeves, dampers, turning vane assemblies, or other devices. Fabricated buildouts (metal hat sections) or other buildout means are optional; when used, secure buildouts to duct walls with bolts, screws, rivets, or welds.

2.8 ROUND DUCT AND FITTING FABRICATION

- A. Diameter as applied to flat-oval ducts in this Article is the diameter of a round duct with a circumference equal to the perimeter of a given size of flat-oval duct.
- B. Round, Longitudinal- and Spiral Lock-Seam Ducts: Fabricate supply ducts of galvanized steel according to SMACNA's "HVAC Duct Construction Standards--Metal and Flexible."
- C. Duct Joints:
 - 1. Ducts up to 20 Inches in Diameter: Interior, center-beaded slip coupling, sealed before and after fastening, attached with sheet metal screws.
 - 2. Ducts 21 to 72 Inches in Diameter: Three-piece, gasketed, flanged joint consisting of two internal flanges with sealant and one external closure band with gasket.
 - 3. Ducts Larger Than 72 Inches in Diameter: Companion angle flanged joints per SMACNA "HVAC Duct Construction Standards--Metal and Flexible," Figure 3-2.
 - 4. Round Ducts: Prefabricated connection system consisting of double-lipped, EPDM rubber gasket. Manufacture ducts according to connection system manufacturer's tolerances.
 - a. Manufacturers:
 - 1) Ductmate Industries, Inc.
 - 2) Lindab Inc.
- D. 90-Degree Tees and Laterals and Conical Tees: Fabricate to comply with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible," with metal thicknesses specified for longitudinal-seam straight ducts.
- E. Diverging-Flow Fittings: Fabricate with reduced entrance to branch taps and with no excess material projecting from fitting onto branch tap entrance.

- F. Fabricate elbows using die-formed, gored, pleated, or mitered construction. Bend radius of die-formed, gored, and pleated elbows shall be 1-1/2 times duct diameter. Unless elbow construction type is indicated, fabricate elbows as follows:
1. Mitered-Elbow Radius and Number of Pieces: Welded construction complying with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible," unless otherwise indicated.
 2. Round Mitered Elbows: Welded construction with the following metal thickness for pressure classes from minus 2- to plus 2-inch wg:
 - a. Ducts 3 to 36 Inches in Diameter: 0.034 inch.
 - b. Ducts 37 to 50 Inches in Diameter: 0.040 inch.
 3. Round Mitered Elbows: Welded construction with the following metal thickness for pressure classes from 2- to 10-inch wg:
 - a. Ducts 3 to 26 Inches in Diameter: 0.034 inch.
 - b. Ducts 27 to 50 Inches in Diameter: 0.040 inch.
 4. 90-Degree, 2-Piece, Mitered Elbows: Use only for supply systems or for material-handling Class A or B exhaust systems and only where space restrictions do not permit using radius elbows. Fabricate with single-thickness turning vanes.
 5. Round Elbows 8 Inches and Less in Diameter: Fabricate die-formed elbows for 45- and 90-degree elbows and pleated elbows for 30, 45, 60, and 90 degrees only. Fabricate nonstandard bend-angle configurations or nonstandard diameter elbows with gored construction.
 6. Round Elbows 9 through 14 Inches in Diameter: Fabricate gored or pleated elbows for 30, 45, 60, and 90 degrees unless space restrictions require mitered elbows. Fabricate nonstandard bend-angle configurations or nonstandard diameter elbows with gored construction.
 7. Round Elbows Larger Than 14 Inches in Diameter and All Flat-Oval Elbows: Fabricate gored elbows unless space restrictions require mitered elbows.
 8. Die-Formed Elbows for Sizes through 8 Inches in Diameter and All Pressures 0.040 inch thick with 2-piece welded construction.
 9. Round Gored-Elbow Metal Thickness: Same as non-elbow fittings specified above.
 10. Flat-Oval Elbow Metal Thickness: Same as longitudinal-seam flat-oval duct specified above.
 11. Pleated Elbows for Sizes through 14 Inches in Diameter and Pressures through 10-Inch wg: 0.022 inch.

PART 3 - EXECUTION

3.1 DUCT APPLICATIONS

- A. Static-Pressure Classes: Unless otherwise indicated, construct ducts according to the following:
1. Supply Ducts (before Air Terminal Units): 3-inch wg.
 2. Supply Ducts (after Air Terminal Units): 1-inch wg.
 3. Supply Ducts (in Mechanical Equipment Rooms): 2-inch wg.
 4. Return Ducts (Negative Pressure): 1-inch wg.
 5. Exhaust Ducts (Negative Pressure): 1-inch wg.

B. Liner:

1. Return Air Ducts – Flexible elastomeric, 1-inch thick to be applied in the following locations:
 - a. Discharge of rooftop unit to 6-feet downstream of change in direction.
 - b. Return air boots..
 - c. Return air transfer ducts.

C. All ducts shall be G90 galvanized steel except as follows:

1. Interior (Indoor) Ductwork: G90 galvanized steel.
2. Exterior (Outdoor) Ductwork: Double wall (insulated) with aluminum outer shell and galvanized steel inter shell. Alternate material is non-fibrous, closed cell, outdoor ductwork.

3.2 DUCT INSTALLATION

- A. Construct and install ducts according to SMACNA's "HVAC Duct Construction Standards--Metal and Flexible," unless otherwise indicated.
- B. Install round and flat-oval ducts in lengths not less than 12 feet unless interrupted by fittings.
- C. Install ducts with fewest possible joints.
- D. Install fabricated fittings for changes in directions, size, and shape and for connections.
- E. Install couplings tight to duct wall surface with a minimum of projections into duct. Secure couplings with sheet metal screws. Install screws at intervals of 12 inches, with a minimum of 3 screws in each coupling.
- F. Install ducts, unless otherwise indicated, vertically and horizontally and parallel and perpendicular to building lines; avoid diagonal runs.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- H. Install ducts with a clearance of 1 inch, plus allowance for insulation thickness.
- I. Conceal ducts from view in finished spaces. Do not encase horizontal runs in solid partitions unless specifically indicated.
- J. Coordinate layout with suspended ceiling, fire- and smoke-control dampers, lighting layouts, and similar finished work.
- K. Seal all joints and seams. Apply sealant to male end connectors before insertion, and afterward to cover entire joint and sheet metal screws.
- L. Electrical Equipment Spaces: Route ducts to avoid passing through transformer vaults and electrical equipment spaces and enclosures.

- M. Non-Fire-Rated Partition Penetrations: Where ducts pass through interior partitions and exterior walls and are exposed to view, conceal spaces between construction openings and ducts or duct insulation with sheet metal flanges of same metal thickness as ducts. Overlap openings on 4 sides by at least 1-1/2 inches.
- N. Fire-Rated Partition Penetrations: Where ducts pass through interior partitions and exterior walls, install appropriately rated fire dampers, sleeves, and firestopping sealant. Fire and smoke dampers are specified in Division 23 Section "Duct Accessories." Firestopping materials and installation methods are specified in Division 7 Section "Through-Penetration Firestop Systems."
- O. Install ducts with hangers and braces designed to withstand, without damage to equipment, seismic force required by applicable building codes. Refer to SMACNA's "Seismic Restraint Manual: Guidelines for Mechanical Systems."
- P. Protect duct interiors from the elements and foreign materials until building is enclosed. Follow SMACNA's "Duct Cleanliness for New Construction."
- Q. Paint interiors of metal ducts, that do not have duct liner, for 24 inches upstream of registers and grilles. Apply one coat of flat, black, latex finish coat over a compatible galvanized-steel primer. Paint materials and application requirements are specified in Division 9 painting Sections.

3.3 SEAM AND JOINT SEALING

- A. Seal duct seams and joints according to SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for duct pressure class indicated.
 - 1. For pressure classes lower than 2-inch wg, seal transverse joints.
- B. Seal ducts before external insulation is applied.

3.4 HANGING AND SUPPORTING

- A. Support horizontal ducts within 24 inches of each elbow and within 48 inches of each branch intersection.
- B. Support vertical ducts at maximum intervals of 16 feet and at each floor.
- C. Install upper attachments to structures with an allowable load not exceeding one-fourth of failure (proof-test) load.
- D. Install concrete inserts before placing concrete.
- E. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
 - 1. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.

3.5 CONNECTIONS

- A. Make connections to equipment with flexible connectors according to Division 23 Section "Duct Accessories."
- B. Comply with SMACNA's "HVAC Duct Construction Standards--Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

3.6 FIELD QUALITY CONTROL

- A. Perform the following field tests and inspections according to SMACNA's "HVAC Air Duct Leakage Test Manual" and prepare test reports:
 - 1. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
 - 2. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If pressure classes are not indicated, test entire system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure. Give seven days' advance notice for testing.
 - 3. Maximum Allowable Leakage: Comply with requirements for Leakage Class 3 for round and flat-oval ducts, Leakage Class 12 for rectangular ducts in pressure classes lower than and equal to 2-inch wg (both positive and negative pressures), and Leakage Class 6 for pressure classes from 2- to 10-inch wg.
 - 4. Remake leaking joints and retest until leakage is equal to or less than maximum allowable.
- B. Seal open ends of duct prior to shipment to construction site to maintain duct cleanliness. Maintain seal on duct ends prior to installation.
- C. Required Inspection for Non-fibrous, Closed Cell Ductwork: Arrange for manufacturer's representative to inspect completed installation and provide written report that installation complies with manufacturer's written instructions.
 - 1. Remove and replace duct system where inspection indicates that it does not comply with specified requirements.
 - 2. Perform additional testing and inspecting, at Contractor's expense, to determine compliance of replaced or additional work with specified requirements.

END OF SECTION 23 31 13

SECTION 23 33 00 - AIR DUCT ACCESSORIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Manual volume dampers.
 - 2. Control dampers.
 - 3. Flange connectors.
 - 4. Turning vanes.
 - 5. Duct-mounted access doors.
 - 6. Flexible connectors.
 - 7. Flexible ductwork
 - 8. Duct accessory hardware.
- B. Related Requirements:
 - 1. Section 23 37 23 "HVAC Gravity Ventilators" for roof-mounted ventilator caps.
 - 2. Section 28 46 21.11 "Addressable Fire-Alarm Systems" for duct-mounted fire and smoke detectors.
 - 3. Section 28 46 21.13 "Conventional Fire-Alarm Systems" for duct-mounted fire and smoke detectors.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. For duct silencers, include pressure drop and dynamic insertion loss data. Include breakout noise calculations for high transmission loss casings.
- B. Shop Drawings: For duct accessories. Include plans, elevations, sections, details and attachments to other work.
 - 1. Detail duct accessories fabrication and installation in ducts and other construction. Include dimensions, weights, loads, and required clearances; and method of field assembly into duct systems and other construction. Include the following:
 - a. Special fittings.
 - b. Manual volume damper installations.
 - c. Control-damper installations.

- d. Fire-damper, smoke-damper, combination fire- and smoke-damper, ceiling, and corridor damper installations, including sleeves; and duct-mounted access doors and remote damper operators.
- e. Duct security bars.
- f. Wiring Diagrams: For power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from Installers of the items involved.
- B. Source quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Fusible Links: Furnish quantity equal to 10 percent of amount installed.

PART 2 - PRODUCTS

2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

2.2 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.3 MATERIALS

- A. Galvanized Sheet Steel: Comply with ASTM A653/A653M.
 - 1. Galvanized Coating Designation: G90.
 - 2. Exposed-Surface Finish: Mill phosphatized.
- B. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- C. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

2.4 MANUAL VOLUME DAMPERS

- A. Standard, Steel, Manual Volume Dampers:
 - 1. Standard leakage rating.
 - 2. Suitable for horizontal or vertical applications.
 - 3. Frames:
 - a. Frame: Hat-shaped, 0.094-inch- thick, galvanized sheet steel.
 - b. Mitered and welded corners.
 - c. Flanges for attaching to walls and flangeless frames for installing in ducts.
 - 4. Blades:
 - a. Multiple or single blade.
 - b. Parallel- or opposed-blade design.
 - c. Stiffen damper blades for stability.
 - d. Galvanized -steel, 0.064 inch thick.
 - 5. Blade Axles: Galvanized steel.
 - 6. Bearings:
 - a. Oil-impregnated bronze.
 - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
 - 7. Tie Bars and Brackets: Galvanized steel.
- B. Standard, Aluminum, Manual Volume Dampers:
 - 1. Standard leakage rating.
 - 2. Suitable for horizontal or vertical applications.
 - 3. Frames: Hat-shaped, 0.10-inch- thick, aluminum sheet channels; frames with flanges for attaching to walls and flangeless frames for installing in ducts.
 - 4. Blades:
 - a. Multiple or single blade.
 - b. Parallel- or opposed-blade design.
 - c. Stiffen damper blades for stability.

- d. Roll-Formed Aluminum Blades: 0.10-inch- thick aluminum sheet.
 - e. Extruded-Aluminum Blades: 0.050-inch- thick extruded aluminum.
- 5. Blade Axles: Galvanized steel.
- 6. Bearings:
 - a. Oil-impregnated bronze.
 - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
- 7. Tie Bars and Brackets: Aluminum.
- C. Low-Leakage, Steel, Manual Volume Dampers:
 - 1. Comply with AMCA 500-D testing for damper rating.
 - 2. Low-leakage rating and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
 - 3. Suitable for horizontal or vertical applications.
 - 4. Frames:
 - a. Hat shaped.
 - b. 0.094-inch- thick, galvanized sheet steel.
 - c. Mitered and welded corners.
 - d. Flanges for attaching to walls and flangeless frames for installing in ducts.
 - 5. Blades:
 - a. Multiple or single blade.
 - b. Parallel- or opposed-blade design.
 - c. Stiffen damper blades for stability.
 - d. Galvanized, roll-formed steel, 0.064 inch thick.
 - 6. Blade Axles: Galvanized steel.
 - 7. Bearings:
 - a. Oil-impregnated bronze.
 - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
 - 8. Blade Seals: Neoprene.
 - 9. Jamb Seals: Cambered stainless steel.
 - 10. Tie Bars and Brackets: Galvanized steel.
 - 11. Accessories:
 - a. Include locking device to hold single-blade dampers in a fixed position without vibration.
- D. Low-Leakage, Aluminum, Manual Volume Dampers:
 - 1. Comply with AMCA 500-D testing for damper rating.
 - 2. Low-leakage rating and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
 - 3. Suitable for horizontal or vertical applications.

4. Frames: Hat Angle-shaped, 0.10-inch- thick, aluminum sheet channels; frames with flanges for attaching to walls and flangeless frames for installing in ducts.
5. Blades:
 - a. Multiple or single blade.
 - b. Parallel- or opposed-blade design.
 - c. Roll-Formed Aluminum Blades: 0.10-inch- thick aluminum sheet.
 - d. Extruded-Aluminum Blades: 0.050-inch- thick extruded aluminum.
6. Blade Axles: Galvanized steel.
7. Bearings:
 - a. Oil-impregnated bronze.
 - b. Dampers in ducts with pressure classes of 3-inch wg or less shall have axles full length of damper blades and bearings at both ends of operating shaft.
8. Blade Seals: Neoprene.
9. Jamb Seals: Cambered stainless steel.
10. Tie Bars and Brackets: Galvanized steel.
11. Accessories:
 - a. Include locking device to hold single-blade dampers in a fixed position without vibration.

E. Jackshaft:

1. Size: 0.5-inch diameter.
2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.

F. Damper Hardware:

1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
2. Include center hole to suit damper operating-rod size.
3. Include elevated platform for insulated duct mounting.

2.5 MOTORIZED CONTROL DAMPERS

A. Manufacturers:

1. Arrowunited
2. Tamco
3. Air Balance, Inc.
4. American Warming and Ventilating.
5. Greenheck.
6. McGill AirFlow Corporation.
7. Nailor Industries Inc.
8. Ruskin Company.

- B. General Description: AMCA-rated, parallel-blade design; minimum of 0.08-inch- thick, 4" deep, extruded aluminum frame.
1. Blades: Overlapping, maximum 6" (152.4 mm) deep extruded aluminum (6063-T5) air-foil profiles, symmetrically pivoted.
 2. Secure blades to 1/2-inch- diameter, zinc-plated axles using zinc-plated hardware, with nylon blade bearings, blade-linkage hardware of zinc-plated steel and brass, ends sealed against spring-stainless-steel blade bearings, and thrust bearings at each end of every blade.
 3. Operating Temperature Range: From minus 40 to plus 200 deg F.
 4. Leakage Class: 1A at 1 in. w.g. static pressure differential.
 5. Blade Seals: Extruded EPDM, secured in an integral slot within the aluminum blade extrusions.

2.6 TURNING VANES

- A. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
1. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.
- B. Manufactured Turning Vanes for Nonmetal Ducts: Fabricate curved blades of resin-bonded fiberglass with acrylic polymer coating; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
- C. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 4-3, "Vanes and Vane Runners," and 4-4, "Vane Support in Elbows."
- D. Vane Construction: Single wall.
- E. Vane Construction: Single wall for ducts up to 48 inches wide and double wall for larger dimensions.
- F. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.

2.7 DUCT-MOUNTED ACCESS DOORS

- A. General Description: Fabricate doors airtight and suitable for duct pressure class.
- B. Manufacturers:
- a. American Warming and Ventilating.
 - b. CESCO Products.
 - c. Ductmate Industries, Inc.
 - d. Flexmaster U.S.A., Inc.
 - e. Greenheck.
 - f. McGill AirFlow Corporation.
 - g. Nailor Industries Inc.

- h. Ventfabrics, Inc.
 - i. Ward Industries, Inc.
- C. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors - Round Duct."
 - 1. Door:
 - a. Double wall, rectangular.
 - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
 - c. Vision panel.
 - d. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
 - e. Fabricate doors airtight and suitable for duct pressure class.
 - 2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
 - 3. Number of Hinges and Locks:
 - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
 - b. Access Doors up to 18 Inches Square: Two hinges and two sash locks.
 - c. Access Doors up to 24 by 48 Inches: Three hinges and two compression latches with outside and inside handles.
 - d. Access Doors Larger Than 24 by 48 Inches: Four hinges and two compression latches with outside and inside handles.
- D. Pressure Relief Access Door:
 - 1. Door and Frame Material: Galvanized sheet steel.
 - 2. Door: Single wall with metal thickness applicable for duct pressure class.
 - 3. Operation: Open outward for positive-pressure ducts and inward for negative-pressure ducts.
 - 4. Factory set at 3.0- to 8.0-inch wg.
 - 5. Doors close when pressures are within set-point range.
 - 6. Hinge: Continuous piano.
 - 7. Latches: Cam.
 - 8. Seal around frame attachment to duct and door to frame: Neoprene or foam rubber.
 - 9. Insulation Fill: 1-inch- thick, fibrous-glass or polystyrene-foam board.

2.8 FLEXIBLE CONNECTORS

- A. Manufacturers:
 - 1. Ductmate Industries, Inc.
 - 2. Duro Dyne Corp.
 - 3. Ventfabrics, Inc.
 - 4. Ward Industries, Inc.
- B. Materials: Flame-retardant or noncombustible fabrics.

- C. Coatings and Adhesives: Comply with UL 181, Class 1.
- D. Metal-Edged Connectors: Factory fabricated with a fabric strip 3-1/2 inches wide attached to two strips of 2-3/4-inch- wide, 0.028-inch- thick, galvanized sheet steel or 0.032-inch- thick aluminum sheets. Provide metal compatible with connected ducts.
- E. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
 - 1. Minimum Weight: 26 oz./sq. yd..
 - 2. Tensile Strength: 480 lbf/inch in the warp and 360 lbf/inch in the filling.
 - 3. Service Temperature: Minus 40 to plus 200 deg F.

2.9 FLEXIBLE DUCTS

- A. Manufacturers:
 - 1. Flexmaster U.S.A., Inc.
 - 2. Hart & Cooley, Inc.
 - 3. Thermaflex
- B. Insulated-Duct Connectors: UL 181, Class 1, 2-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene vapor barrier film.
 - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 10 to plus 160 deg F.
- C. Insulated-Duct Connectors: UL 181, Class 1, black polymer film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene vapor barrier film.
 - 1. Pressure Rating: 4-inch wg positive and 0.5-inch wg negative.
 - 2. Maximum Air Velocity: 4000 fpm.
 - 3. Temperature Range: Minus 20 to plus 175 deg F.
- D. Insulated-Duct Connectors: UL 181, Class 1, multiple layers of aluminum laminate supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene vapor barrier film.
 - 1. Pressure Rating: 8-inch wg positive and 3.0-inch wg negative.
 - 2. Maximum Air Velocity: 5000 fpm.
 - 3. Temperature Range: Minus 100 to plus 400 deg F continuous.
- E. Flexible Duct Clamps: Nylon strap, in sizes 3 through 18 inches to suit duct size.

2.10 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.

- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Compliance with ASHRAE/IESNA 90.1-2004 includes Section 6.4.3.3.3 - "Shutoff Damper Controls," restricts the use of backdraft dampers, and requires control dampers for certain applications. Install backdraft dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.
- D. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel. Install at a minimum of two duct widths from branch takeoff.
 - 1. Install steel volume dampers in steel ducts.
 - 2. Install aluminum volume dampers in aluminum ducts.
- E. Set dampers to fully open position before testing, adjusting, and balancing.
- F. Install test holes at fan inlets and outlets and elsewhere as indicated.
- G. Install the following sizes for duct-mounting, rectangular access doors:
 - 1. One-Hand or Inspection Access: 8 by 5 inches.
 - 2. Two-Hand Access: 12 by 6 inches.
 - 3. Head and Hand Access: 18 by 10 inches.
 - 4. Head and Shoulders Access: 21 by 14 inches.
 - 5. Body Access: 25 by 14 inches.
 - 6. Body Plus Ladder Access: 25 by 17 inches.
- H. Install the following sizes for duct-mounting, round access doors:
 - 1. One-Hand or Inspection Access: 8 inches in diameter.
 - 2. Two-Hand Access: 10 inches in diameter.
 - 3. Head and Hand Access: 12 inches in diameter.
 - 4. Head and Shoulders Access: 18 inches in diameter.
 - 5. Body Access: 24 inches in diameter.
- I. Install the following sizes for duct-mounting, pressure relief access doors:

1. One-Hand or Inspection Access: 7 inches in diameter.
 2. Two-Hand Access: 10 inches in diameter.
 3. Head and Hand Access: 13 inches in diameter.
 4. Head and Shoulders Access: 19 inches in diameter.
- J. Label access doors according to Section 23 00 50 "Basic Mechanical Materials and Methods" to indicate the purpose of access door.
- K. Install flexible connectors immediately adjacent to equipment in ducts associated with fans and motorized equipment supported by vibration isolators.
- L. Connect diffusers or light troffer boots to ducts directly or with maximum 60-inch lengths of flexible duct clamped or strapped in place.
- M. Connect flexible ducts to metal ducts with draw bands.
- N. Flexible Duct Installation:
1. Install ducts fully extended.
 2. Do not bend ducts across sharp corners.
 3. Bends of flexible ducting shall not exceed a minimum of one duct diameter.
 4. Avoid contact with metal fixtures, water lines, pipes, or conduits.
 5. Install flexible ducts in a direct line, without sags, twists, or turns.
- O. Supporting Flexible Ducts:
1. Suspend flexible ducts with bands 1-1/2 inches wide or wider and spaced a maximum of 48 inches apart. Maximum centerline sag between supports shall not exceed 1/2 inch per 12 inches.
 2. Install extra supports at bends placed approximately one duct diameter from center line of the bend.
 3. Ducts may rest on ceiling joists or truss supports. Spacing between supports shall not exceed the maximum spacing per manufacturer's written installation instructions.
 4. Vertically installed ducts shall be stabilized by support straps at a maximum of 72 inches o.c.
- P. Install duct test holes where required for testing and balancing purposes.
- 3.2 ADJUSTING
- A. Adjust duct accessories for proper settings.
- B. Final positioning of manual-volume dampers is specified in Division 23 Section "Testing, Adjusting, and Balancing."

3.3 FIELD QUALITY CONTROL

- A. Tests and Inspections:
1. Operate dampers to verify full range of movement.

2. Inspect turning vanes for proper and secure installation.
3. Operate remote damper operators to verify full range of movement of operator and damper.

END OF SECTION 23 33 00

This page intentionally left blank.

SECTION 23 34 23 – HVAC FANS AND POWER VENTILATORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:
 - 1. Square in-line centrifugal fans.
 - 2. Ceiling-mounting ventilators.
- B. Related sections include the following:
 - 1. Section 23 05 48 "Mechanical Systems Vibration Control" for vibration isolation.
 - 2. Section 23 05 49 "Mechanical, Plumbing and Fire Protection Systems; Supports, Bracing and Seismic Requirements".
 - 3. Section 23 00 50 "Basic Mechanical Materials and Methods".

1.3 PERFORMANCE REQUIREMENTS

- A. Project Altitude: Base air ratings on actual site elevations.
- B. Motors shall be sized such that the brake horsepower at design conditions does not exceed 90% of the motor's nameplate rating.
- C. Alternate manufacturer shall meet or exceed the basis of design's fan performance. Engineer reserves the right to reject the selection if the performance curve is unacceptable at the sole judgement of the engineer of record.

1.4 SUBMITTALS

- A. Product Data: Include rated capacities, furnished specialties, and accessories for each type of product indicated and include the following:
 - 1. Construction details, material descriptions, dimensions of individual components and profiles, and finishes for fans.
 - 2. Rated capacities, operating characteristics, and furnished specialties and accessories.
 - 3. Certified fan performance curves with system operating conditions indicated.
 - 4. Certified fan sound-power ratings.
 - 5. Motor ratings and electrical characteristics, plus motor and electrical accessories.
 - 6. Material gages and finishes, including color charts.
 - 7. Dampers, including housings, linkages, and operators.
 - 8. Prefabricated roof curbs.
 - 9. Fan speed controllers.

10. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 11. Wiring Diagrams: Power, signal, and control wiring. Differentiate between manufacturer-installed and field-installed wiring.
 12. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
 13. Vibration Isolation Base Details: Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, and base weights.
- B. Delegated-Design Submittal: For unit hangars and supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
1. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
- C. Seismic Qualification Data: For fans, accessories, and components, from manufacturer.
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- D. Field quality-control reports.
- E. Operations and Maintenance Data: For power ventilators to include in maintenance manuals specified in Division 1.

1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. AMCA Compliance: Products shall comply with performance requirements and shall be licensed to use the AMCA-Certified Ratings Seal.
- C. NEMA Compliance: Motors and electrical accessories shall comply with NEMA standards.
- D. UL Standard: Power ventilators shall comply with UL 705.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Deliver fans as factory-assembled unit, to the extent allowable by shipping limitations, with protective crating and covering.
- B. Disassemble and reassemble units, as required for moving to final location, according to manufacturer's written instructions.

- C. Lift and support units with manufacturer's designated lifting or supporting points.

1.7 COORDINATION

- A. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Division 7 Section "Roof Accessories."

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

- 1. Belts: One sets for each belt-driven unit.

PART 2 - PRODUCTS

2.1 GENERAL REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NFPA Compliance: Comply with NFPA 90A for design, fabrication, and installation of unit components.
- C. ASHRAE Compliance:
 - 1. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."
- D. ASHRAE/IES 90.1 Compliance: Applicable requirements in ASHRAE/IES 90.1, Section 6 - "Heating, Ventilating, and Air-Conditioning."
- E. Delegated Design: Engage a qualified professional engineer, as defined in Section 01 40 00 "Quality Requirements," to design vibration isolation and seismic restraints, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- F. Seismic Performance: HVAC power ventilators shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
 - 2. Component Importance Factor: 1.5.

2.2 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Square In-Line Centrifugal Fans
 - a. Twin City Fan
 - b. Cook, Loren Company.
 - c. Greenheck
 - d. PennBarry
2. Ceiling-Mounting Ventilators:
 - a. Twin City Fan.
 - b. Cook, Loren Company.
 - a. Greenheck
 - b. PennBarry.

2.3 CENTRIFUGAL ROOF VENTILATORS

- A. Description: Belt-driven or direct-driven centrifugal fans consisting of housing, wheel, fan shaft, bearings, motor and disconnect switch, drive assembly, curb base, and accessories. Upblast or downblast as indicated on schedule.
- B. Housing: Removable, spun-aluminum, dome top and outlet baffle ; square, one-piece, aluminum base with venturi inlet cone.
- C. Fan Wheels: Aluminum hub and wheel with backward-inclined blades..
- D. Belt-Driven Drive Assembly: Resiliently mounted to housing, with the following features:
 1. Fan Shaft: Turned, ground, and polished steel; keyed to wheel hub.
 2. Shaft Bearings: Permanently lubricated, permanently sealed, self-aligning ball bearings.
 3. Motor Pulleys: Adjustable pitch for use with motors through 5 hp. Select pulley so pitch adjustment is at the middle of adjustment range at fan design conditions. Provide fixed pitch for use with motors larger than 5 hp.
 4. Fan and motor isolated from exhaust airstream.
 5. Fan and motor isolated from exhaust airstream.
- E. Accessories:
 1. Variable-Speed Controller: Solid-state control to reduce speed from 100 percent to less than 50 percent.
 2. Disconnect Switch: Nonfusible type, with thermal-overload protection mounted inside fan housing, factory wired through an internal aluminum conduit.
 3. Bird Screens: Removable, 1/2-inch mesh, aluminum or brass wire.
 4. Dampers: Counterbalanced, parallel-blade, backdraft dampers mounted in curb base; factory set to close when fan stops.
 5. Motorized Dampers: Parallel-blade dampers mounted in curb base with electric actuator; wired to close when fan stops.
 - 6.
 7. Wall Mount Adapter: Attach wall-mounted fan to wall.
 8. Restaurant Kitchen Exhaust: UL 762 listed for grease-laden air exhaust.
- F. Roof Curbs: Galvanized steel; mitered and welded corners; 1-1/2-inch- thick, rigid, fiberglass insulation adhered to inside walls; and 1-1/2-inch wood nailer. Size as required to suit roof opening and fan base.
 1. Configuration: Self-flashing without a cant strip, with mounting flange.
 2. Overall Height: 12 inches.

3. Sound Curb: Curb with sound-absorbing insulation matrix.
4. Pitch Mounting: Manufacture curb for roof slope.
5. Metal Liner: Galvanized steel.
6. Burglar Bars: 5/8-inch- thick steel bars welded in place to form 6-inch squares.
7. Hinged Subbase: Galvanized steel hinged arrangement permitting service and maintenance.
8. Mounting Pedestal: Galvanized steel with removable access panel.
9. Vented Curb: Unlined with louvered vents in vertical sides.

2.4 CEILING-MOUNTING VENTILATORS

- A. Description: Centrifugal fans designed for installing in ceiling or wall or for concealed in-line applications.
- B. Housing: Steel, lined with acoustical insulation.
- C. Fan Wheel: Centrifugal wheels directly mounted on motor shaft. Fan shrouds, motor, and fan wheel shall be removable for service.
- D. Grille: Plastic, louvered grille with flange on intake and thumbscrew attachment to fan housing.
- E. Electrical Requirements: Junction box for electrical connection on housing and receptacle for motor plug-in.
- F. Accessories:
 1. Variable-Speed Controller: Solid-state control to reduce speed from 100 percent to less than 50 percent.
 2. Manual Starter Switch: Single-pole rocker switch assembly with cover and pilot light.
 3. Time-Delay Switch: Assembly with single-pole rocker switch, timer, and cover plate.
 4. Motion Sensor: Motion detector with adjustable shutoff timer.
 5. Ceiling Radiation Damper: Fire-rated assembly with ceramic blanket, stainless-steel springs, and fusible link.
 6. Filter: Washable aluminum to fit between fan and grille.
 7. Isolation: Rubber-in-shear vibration isolators.
 8. Manufacturer's standard roof jack or wall cap, and transition fittings.

2.5 MOTORS

- A. Refer to Division 23 Section "Motors" for general requirements for factory-installed motors.
- B. Motor Construction: NEMA MG 1, general purpose, continuous duty, Design B.
- C. Where variable-frequency drives are indicated or scheduled, provide fan motor compatible with variable-frequency drive.
- D. Enclosure Type: Open dripproof.

2.6 SOURCE QUALITY CONTROL

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by an NRTL, and marked for intended location and application.

- B. AMCA Certification: Fans shall comply with AMCA 11 and bear the AMCA-Certified Ratings Seal.
- C. Sound-Power Level Ratings: Comply with AMCA 301, "Methods for Calculating Fan Sound Ratings from Laboratory Test Data." Factory test fans according to AMCA 300, "Reverberant Room Method for Sound Testing of Fans." Label fans with the AMCA-Certified Ratings Seal.
- D. Fan Performance Ratings: Establish flow rate, pressure, power, air density, speed of rotation, and efficiency by factory tests and ratings according to AMCA 210, "Laboratory Methods of Testing Fans for Rating."
- E. Operating Limits: Classify according to AMCA 99.
- F. UL Standards: Power ventilators shall comply with UL 705. Power ventilators for use for restaurant kitchen exhaust shall also comply with UL 762.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install fans and power ventilators level and plumb.
- B. Disassemble and reassemble units, as required for moving to the final location, according to manufacturer's written instructions.
- C. Lift and support units with manufacturer's designated lifting or supporting points.
- D. Secure roof-mounting fans to roof curbs with zinc-plated hardware. Refer to Division 7 Section "Roof Accessories" for installation of roof curbs.
- E. Ceiling Units: Suspend units from structure; use steel wire or metal straps.
- F. Support suspended units from structure using threaded steel rods and spring hangers. Vibration-control devices are specified in Division 23 Section "Mechanical Vibration Controls and Seismic Restraints."
 - 1. In seismic zones, restrain support units.
- G. Curb Support, Field Built-Up: Install roof curb on roof structure, level and secure, according to "The NRCA Roofing and Waterproofing Manual," detail "Equipment Support Curb," number "SPF-9" (page 1409) and detail "Equipment Support Curb," number "SPF-9S" (page 1410). Install and secure centrifugal fans on curbs, and coordinate roof penetrations and flashing with roof construction. Secure units to curb support with anchor bolts.
- H. Curb Support, Prefabricated: Rail-type wood support provided by fan manufacturer.
- I. Unit Support: Install centrifugal fans level on structural curbs. Coordinate wall penetrations and flashing with wall construction. Secure units to structural support with anchor bolts.
- J. Isolation Curb Support: Install centrifugal fans on isolation curbs, and install flexible duct connectors and vibration and seismic control devices.

1. Comply with requirements in Section 23 33 00 "Air Duct Accessories" for flexible duct connectors.
 2. Comply with requirements in Section 23 05 48 "Vibration and Seismic Controls for HVAC" for vibration-isolation and seismic-control devices.
- K. Install units with clearances for service and maintenance.
- L. Label units according to requirements specified in Division 23 Section "Mechanical Identification."

3.2 CONNECTIONS

- A. Duct installation and connection requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors. Flexible connectors are specified in Division 23 Section "Duct Accessories."
- B. Install ducts adjacent to power ventilators to allow service and maintenance.
- C. Install piping from scroll drain connection, with trap with seal equal to 1.5 times specified static pressure, to nearest floor drain with pipe sizes matching the drain connection.
- D. Install heat tracing on all drain piping subject to freezing temperature and as indicated on Drawings. Furnish and install heat tracing according to Section 23 05 33 "Heat Tracing for HVAC Piping."
- E. Connect wiring according to Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."
- F. Ground equipment according to Section 26 05 26 "Grounding and Bonding for Electrical Systems."
- G. Install electrical devices furnished by manufacturer, but not factory mounted, according to NFPA 70 and NECA 1.
1. Nameplate shall be laminated acrylic or melamine plastic signs with a black background and engraved white letters at least 1/2 inch high.
- H. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- I. Install control and electrical power wiring to field-mounted control devices.
- J. Connect control wiring according to Section 26 05 23 "Control-Voltage Electrical Power Cables."

3.3 FIELD QUALITY CONTROL

- A. Equipment Startup Checks:
1. Verify that shipping, blocking, and bracing are removed.
 2. Verify that unit is secure on mountings and supporting devices and that connections to ducts and electrical components are complete. Verify that proper thermal-overload protection is installed in motors, starters, and disconnect switches.

3. Verify that cleaning and adjusting are complete.
4. Disconnect fan drive from motor, verify proper motor rotation direction, and verify fan wheel free rotation and smooth bearing operation. Reconnect fan drive system, align and adjust belts, and install belt guards.
5. Verify lubrication for bearings and other moving parts.
6. Verify that manual and automatic volume control and fire and smoke dampers in connected ductwork systems are in fully open position.
7. Disable automatic temperature-control operators.

B. Starting Procedures:

1. Energize motor and adjust fan to indicated rpm.
2. Measure and record motor voltage and amperage.

C. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation. Remove malfunctioning units, replace with new units, and retest.

D. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

E. Shut unit down and reconnect automatic temperature-control operators.

F. Refer to Division 23 Section "Testing, Adjusting, and Balancing" for testing, adjusting, and balancing procedures.

G. Replace fan and motor pulleys as required to achieve design airflow.

H. Repair or replace malfunctioning units. Retest as specified above after repairs or replacements are made.

3.4 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Lubricate bearings.

3.5 CLEANING

- A. On completion of installation, internally clean fans according to manufacturer's written instructions. Remove foreign material and construction debris. Vacuum fan wheel and cabinet.
- B. After completing system installation, including outlet fitting and devices, inspect exposed finish. Remove burrs, dirt, and construction debris and repair damaged finishes.

3.6 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain power ventilators.

1. Train Owner's maintenance personnel on procedures and schedules for starting and stopping, troubleshooting, servicing, and maintaining equipment and schedules.
2. Review data in maintenance manuals. Refer to Division 1 Section "Closeout Procedures."
3. Review data in maintenance manuals. Refer to Division 1 Section "Operation and Maintenance Data."
4. Schedule training with Owner, through Architect, with at least seven days' advance notice.

END OF SECTION 23 34 23

This page intentionally left blank.

SECTION 23 37 13 - DIFFUSERS, REGISTERS, GRILLES, AND LOUVERS

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes ceiling-mounted diffusers, registers, grilles, and louvers.
- B. Related Sections include the following:
 - 1. Section 23 00 00 "Mechanical General Requirements."
 - 2. Section 23 00 50 "Basic Mechanical Materials and Methods."
 - 3. Section 23 33 00 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers.

1.2 SUBMITTALS

- A. Product Data: For each product indicated, include the following:
 - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
 - 2. Diffuser, Register, and Grille Schedule: Indicate Drawing designation, room location, quantity, model number, size, and accessories furnished.
- B. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
 - 1. Ceiling suspension assembly members.
 - 2. Method of attaching hangers to building structure.
 - 3. Size and location of initial access modules for acoustical tile.
 - 4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
 - 5. Duct access panels.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

2.2 GRILLES, REGISTERS AND DIFFUSERS

- A. Provide Grilles, Registers and diffusers as scheduled on the drawings and as manufactured by one of the manufacturers listed below:
 - 1. Manufacturers:

- a. Krueger.
 - b. METALAIRE, Inc.; Metal Industries Inc.
 - c. Price Industries.
 - d. Titus.
 - e. Tuttle & Bailey.
 - f. Nailor
- 2. Material: As scheduled.
- 3. Accessories:
 - a. As scheduled.
 - b. Provide insulated backpans for all air devices located in ceilings that are not return air plenums.
 - c. Provide insulated backpans for all air devices located in ceilings that are on the level immediately below the roof.
- 4. Construction and Performance: Scheduled devices shall be the basis for construction and performance requirements.

2.3 LOUVERS

- A. Provide Louvers as scheduled on the drawings and as manufactured by one of the manufacturer's listed below:
 - 1. Ruskin.
 - 2. Construction Specialties.
 - 3. Greenheck
 - 4. Pottorf
- B. General: Except as otherwise indicated, provide manufacturer's standard storm-proof louvers where shown; of size shape capacity and type indicated; constructed of materials and components as indicated, and as required for complete installation.
- C. Performance: Provide louvers that have maximum free area, and minimum pressure drop for each type as listed in manufacturer's current data, complying with louver schedule.
- D. Substrate compatibility: Provide louvers with frame and sill styles that are compatible with adjacent substrate, and that are specifically manufactured to fit into construction openings with accurate fit and adequate support, for weatherproof installation. Refer to general construction drawings and specifications for types of substrate, which will contain each type of louver.
- E. Materials: Construct of aluminum extrusions, ASTM B 221, Alloy 6063-T52. Weld units or use stainless steel fasteners.
- F. Louver Screens: On inside face of exterior louvers, provide 1/2 square anodized aluminum wire bird screens mounted in removable extruded aluminum frames.
- G. Finish: Louvers shall receive Kynar 500 finish color coating applied following thorough cleaning and pretreatment. Kynar shall be applied to provide 1.2 mils total dry thickness when

baked at 450 deg F for 10 minutes. The finish coating shall meet or exceed AAMA Specifications 605.2.

- H. Colors shall be as selected by the Architect.

2.4 SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas where diffusers, registers, grilles, and louvers are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install diffusers, registers, grilles, and louvers level and plumb, according to manufacturer's written instructions, original design, and referenced standards.
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers.
- D. Seal insulation where it connects to insulated air devices. Seal insulation at ceiling grid and/or frame to prevent unconditioned air from coming in contact with back of air device.

3.3 ADJUSTING

- A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

3.4 CLEANING

- A. After installation of diffusers, registers, grilles, and louvers, inspect exposed finish. Clean exposed surfaces to remove burrs, dirt, and smudges. Replace diffusers, registers, grilles, and louvers that have damaged finishes.

END OF SECTION 23 37 13

This page intentionally left blank.

SECTION 23 37 23 - HVAC GRAVITY VENTILATORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:

- 1. Roof hoods.

1.3 SUBMITTALS

- A. Shop Drawings: For gravity ventilators. Include plans, elevations, sections, details, ventilator attachments to curbs, and curb attachments to roof structure.

- 1. Show weep paths, gaskets, flashing, sealant, and other means of preventing water intrusion.

- B. Samples: For each exposed product and for each color and texture specified.

- C. Coordination Drawings: Roof framing plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:

- 1. Structural members to which roof curbs and ventilators will be attached.
 - 2. Sizes and locations of roof openings.

- D. Seismic Qualification Certificates: For ventilators, accessories, and components, from manufacturer.

- 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

- E. Welding certificates.

1.4 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to the following:

- 1. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum."
 - 2. AWS D1.3, "Structural Welding Code - Sheet Steel."

1.5 COORDINATION

- A. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Aluminum Extrusions: ASTM B 221, Alloy 6063-T5 or T-52.
- B. Aluminum Sheet: ASTM B 209, Alloy 3003 or 5005 with temper as required for forming or as otherwise recommended by metal producer for required finish.
- C. Galvanized-Steel Sheet: ASTM A 653/A 653M, G90 zinc coating, mill phosphatized.

2.2 FABRICATION, GENERAL

- A. Factory or shop fabricate gravity ventilators to minimize field splicing and assembly. Disassemble units to the minimum extent as necessary for shipping and handling. Clearly mark units for reassembly and coordinated installation.
- B. Fabricate frames, including integral bases, to fit in openings of sizes indicated, with allowances made for fabrication and installation tolerances, adjoining material tolerances, and perimeter sealant joints.
- C. Fabricate units with closely fitted joints and exposed connections accurately located and secured.
- D. Fabricate supports, anchorages, and accessories required for complete assembly.
- E. Perform shop welding by AWS-certified procedures and personnel.

2.3 ROOF HOODS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Acme Engineering & Manufacturing Corp.
 - 2. Aerovent; a division of Twin City Fan Companies, Ltd.
 - 3. Carnes Company.
 - 4. Greenheck Fan Corporation.
 - 5. Loren Cook Company.
- B. Factory or shop fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figures 6-6 and 6-7.
- C. Materials: Aluminum sheet, minimum 0.063-inch-thick base and 0.050-inch-thick hood; suitably reinforced.

- D. Roof Curbs: Galvanized-steel sheet; with mitered and welded corners; 1-1/2-inch-thick, rigid fiberglass insulation adhered to inside walls; and 1-1/2-inch wood nailer. Size as required to fit roof opening and ventilator base.
- E. Bird Screening: Aluminum, 1/2-inch-square mesh, 0.063-inch wire.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install gravity ventilators level, plumb, and at indicated alignment with adjacent work.
- B. Install gravity ventilators with clearances for service and maintenance.
- C. Install perimeter reveals and openings of uniform width for sealants and joint fillers, as indicated.
- D. Install concealed gaskets, flashings, joint fillers, and insulation as installation progresses. Comply with Section 07 92 00 "Joint Sealants" for sealants applied during installation.
- E. Label gravity ventilators according to requirements specified in Division 23.
- F. Repair finishes damaged by cutting, welding, soldering, and grinding. Restore finishes so no evidence remains of corrective work. Return items that cannot be refinished in the field to the factory, make required alterations, and refinish entire unit or provide new units.

3.2 CONNECTIONS

- A. Duct installation and connection requirements are specified in Division 23. Drawings indicate general arrangement of ducts and duct accessories.

END OF SECTION

This page intentionally left blank.

SECTION 23 38 13 - KITCHEN HOODS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes Listed Kitchen hoods.

1.3 DEFINITIONS

- A. Listed Hood: A hood, factory fabricated and tested for compliance with UL 507 and UL Subject 300A by a testing agency acceptable to authorities having jurisdiction. Hood shall be certified as compliant with International Mechanical Code and International Fire code.

1.4 ACTION SUBMITTALS

- A. Product Data: For the following:

1. Hoods.
2. Filters/baffles.
3. Fire-suppression systems.
4. Luminaires.

- B. Shop Drawings:

1. Show plan view, elevation view, sections, roughing-in dimensions, service requirements, duct connection sizes, and attachments to other work.
2. Show cooking equipment plan and elevation to confirm minimum code-required overhang.
3. Show control cabinets.
4. Show fire-protection cylinders, piping, actuation devices, and manual control devices.
5. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
6. Include diagrams for power, signal, and control wiring.
7. Piping Diagrams: Detail fire-suppression piping and components and differentiate between manufacturer-installed and field-installed piping. Include roughing-in requirements for drain connections. Show cooking equipment plan and elevation to illustrate fire-suppression nozzle locations.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Grease Filters/Baffles: One complete set(s).

1.6 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D 1.1M, "Structural Welding Code - Steel," for hangers and supports; and AWS D9.1/D9.1M, "Sheet Metal Welding Code," for joint and seam welding.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 HOOD MATERIALS

- A. Stainless-Steel Sheet: 300 series.
 - 1. Minimum Thickness: 18 guage.
 - 2. Finish: Comply with SSINA's "Finishes for Stainless Steel" for recommendations for applying and designating finishes.
 - a. Finish shall be free from tool and die marks and stretch lines and shall have uniform, directionally textured, polished finish indicated, free of cross scratches. Grain shall run with long dimension of each piece.
- B. Sealant: NSF-approved caulk.

2.3 GENERAL HOOD FABRICATION REQUIREMENTS

- A. Welding: Use welding rod of same composition as metal being welded. Use methods that minimize distortion and develop strength and corrosion resistance of base metal. Make ductile welds free of mechanical imperfections such as gas holes, pits, or cracks.
 - 1. Welded Butt Joints: Full-penetration welds for full-joint length. Make joints flat, continuous, and homogenous with sheet metal without relying on straps under seams, filling in with solder, or spot welding.
 - 2. Grind exposed welded joints flush with adjoining material and polish to match adjoining surfaces.
 - 3. Where fasteners are welded to underside of equipment, finish reverse side of weld smooth and flush.
 - 4. Coat concealed stainless-steel welded joints with metallic-based paint to prevent corrosion.
 - 5. After zinc-coated steel is welded, clean welds and abraded areas and apply SSPC-Paint 20, high-zinc-dust-content, galvanizing repair paint to comply with ASTM A780/A780M.
- B. For metal butt joints, comply with SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines."
- C. Where stainless steel is joined to a dissimilar metal, use stainless-steel welding material or fastening devices.

- D. Form metal with break bends that are not flaky, scaly, or cracked in appearance; where breaks mar uniform surface appearance of material, remove marks by grinding, polishing, and finishing.
- E. Sheared Metal Edges: Finish free of burrs, fins, and irregular projections.
- F. In food zones, as defined in NSF, fabricate surfaces free from exposed fasteners.
- G. Cap exposed fastener threads, including those inside cabinets, with stainless-steel lock washers and stainless-steel cap (acorn) nuts.
- H. Fabricate pipe slots on equipment with turned-up edges sized to accommodate service and utility lines and mechanical connections.
- I. Fabricate enclosures, including panels, housings, and skirts, to conceal service lines, operating components, and mechanical and electrical devices including those inside cabinets unless otherwise indicated.
- J. Fabricate seismic restraints according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines," Appendix A, "Seismic Restraint Details."
- K. Fabricate equipment edges and backsplashes according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines."
- L. Fabricate enclosure panels to ceiling and wall as follows:
 - 1. Fabricate panels on all exposed side(s) with same material as hood, and extend from ceiling to top of hood canopy and from canopy to wall.
 - 2. Wall Offset Spacer: Minimum of 3 inches.
 - 3. Wall Shelves and Overshelves: Fabricate according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines," with minimum 0.0625-inch- thick, stainless-steel shelf tops.

2.4 GENERAL REQUIREMENTS

- A. Provide with metal mesh filters.
- B. Provide with two (2) 2200-2700K color LED recessed hood lights. Minimum 50 foot-candles of evenly dispersed lighting on the range below.

2.5 WET-CHEMICAL FIRE-SUPPRESSION SYSTEM

- A. A pre-engineered, fixed pipe, automatic wet chemical (surfactant) fire suppression system for protection of all hazard areas associated with cooking operations, including exhaust hoods, plenums, ductwork, and cooking appliances.
- B. The fire system shall be factory assembled, tested, and shipped as a complete unit.
- C. The following specifications, delivering all capacities scheduled and conforming to the design indicated herein. Alternate layouts or dimensional changes will not be accepted.
- D. Components

1. Exhaust hood fire system components to be factory installed.
 2. Distribution Nozzles
 - a. Nozzles shall be located to protect the exhaust ducts, plenums, and all cooking appliances requiring protection.
 - b. All nozzles shall be equipped with a metal blow off cap. The cap prevents contamination from entering the pipe network and is designed to pop-off upon system discharge, allowing agent to flow to the protected hazard area.
 - c. All nozzles shall incorporate a stamped part number to quickly identify nozzle type.
 3. Distribution System
 - a. The distribution system shall consist of Copper, Schedule 40 black iron, chrome-plated or stainless-steel pipe and fittings. All exposed piping and fittings must be chrome-plated or stainless-steel.
 - b. Fittings shall be minimum class 150. Galvanized fittings shall not be used.
 - c. Flow rate for the hood, when in a fire condition, would be 1.5 gallons per minute per foot of hood.
 - d. Operating pressure for water lines, both hot water and dedicated line, is 30 to 70 psi, depending on the system configuration.
 - e. The maximum static pressure cannot exceed 125 psi; pressure reducing valves can be utilized to meet the correct operating water pressure.
 4. Suppression System
 - a. The system control equipment shall be capable of all functions associated with automatically and manually discharging surfactant from surfactant tank, including automatic shutdown of the heat source or fuel and electrical power to all protected areas upon system discharge.
 - b. For automatic activation, the system will be activated by a Firestat (heat) detector.
 - c. For manual activation, an electrically operated manual release shall be used to actuate the system manually.
 5. Firestat
 - a. Normally Open, Close on Rise 360°F.
 6. Electrical
 - a. Electrical Division to provide shunt trip breakers at main power panel, or disconnects, as designated by the Electrical Engineer; interconnection provided at hood control panel for the signal to shut down all electricity in and under the exhaust hood. Shunt trips/disconnects to accomplish shut off of electricity in the event of fire system activation by others.
 - b. Printed circuit board with microprocessor-based controller that provides all the necessary monitoring, timing, and supervision functions required for the reliable operation of the fire system.
 - c. Independent supervised loops incorporate redundancy and fault detection.
 - d. Real-time cloud-based monitoring connection provided with system by ownership.
 - e. All wiring must be in accordance to NFPA 70 and the Authority Having Jurisdiction (AHJ).
 - f. Electric gas valve provided for equipment below exhaust hood. Coordinate size and installation with Plumbing Division.
 - g. All wiring is to be in accordance with the applicable manufacturer's instructions for the fire alarm control panel, gas shut-off valve, manual reset relay, and contractor supplied shut-off devices.
- E. All fire suppression and control components must be easily accessible by dropping the hood into a service position to allow for service without removing the hood. Latches shall be utilized to hold the hood into place for normal operation. No thumb screws or removable hardware are acceptable.
- F. Hood system shall include a gas shut off device that shall be field connected back to the hood via factory-provided plug and play cables. Prior to fire suppression release, the shut off device

shall be responsible for disabling the range upon detecting a high temperature. Gas disconnect shall include a 3/4" gas valve supplied with plug and play cable and an 115VAC control receptacle.

2.6 REQUIRED OPTIONS

- A. Hood system shall be provided with accessories required for NFPA 101 compliance, including: 500 CFM fan, locked (password protected) appliance disconnect with timed-automatic range deactivation, and manual pull station.
- B. User interface shall be provided to control fan, range, and lights and view system statuses, including faults/alarms. User interface shall be full color 4.3" LCD touch screen. No toggle switches or rheostats shall be acceptable. All factory and configuration settings must be accessed by touchscreen through password-protected entry. For ADA compliance, the user interface shall be shipped loose to be field mounted on a wall near the hood. User interface shall be provided with factory supplied plug and play cable.
- C. The hood system shall be configured with a factory-supplied external fan. Hood shall be top discharge. All factory provided fan options shall include energy efficient electrically commutated motors (ECM) standard.
- D. Enclosure panels to close-off the space above the hood to the ceiling.
- E. Finished top, when no overhead cabinets are enclosing the top of the hood (option for internal fan configuration)
- F. Contacts for connection to fire alarm system.
- G. K-class 6 liter wet chemical fire extinguisher
- H. Manual pull station, with plug and play cable for NFPA 101 compliance

2.7 CONTROLS

- A. Basic hood operation shall be as follows:
 - 1. User interface can be utilized to turn on and off fans, lights, and range disconnect.
 - 2. If configured for NFPA 101 life safety code, password entry will be required to engage disconnect. After range is turned on, count down timer will begin, and upon expiring will disengage the range disconnect.
 - 3. Upon reaching specific set-point, exhaust fan will engage automatically if not already turned on and be forced to a speed based on a temperature range.
 - 4. Upon reaching a second higher temperature set-point, the disconnect will be automatically shut off and a warning will appear on the user interface.
 - 5. Upon reaching a preset temperature, the fire system will engage and discharge wet chemical on top of the range.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for piping systems to verify actual locations of piping connections before equipment installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Coordinate equipment layout and installation with adjacent Work, including luminaires, HVAC equipment, plumbing, and fire-suppression system components.
- B. Install hoods and associated services with clearances and access for maintaining, cleaning, and servicing hoods, filters/baffles, grease extractor, and fire-suppression systems according to manufacturer's written instructions and requirements of authorities having jurisdiction.
- C. Securely anchor and attach items and accessories to walls, floors, or bases with stainless-steel fasteners unless otherwise indicated.
- D. Install hoods to operate free from vibration.
- E. Install seismic restraints according to SMACNA's "Kitchen Ventilation Systems & Food Service Equipment Guidelines," Appendix A, "Seismic Restraint Details."
- F. Install trim strips and similar items requiring fasteners in a bed of sealant. Fasten with stainless-steel fasteners at 48 inches o.c. maximum.
- G. Install sealant in joints between equipment and abutting surfaces with continuous joint backing unless otherwise indicated. Provide airtight, watertight, vermin-proof, sanitary joints.
- H. Install lamps, with maximum recommended wattage, in equipment with integral lighting.
- I. Set initial temperatures, and calibrate sensors.
- J. Set field-adjustable switches.

3.3 CONNECTIONS

- A. Install fire-suppression piping for remote-mounted suppression systems according to NFPA 17A, "Wet Chemical Extinguishing Systems."

3.4 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.

- C. Perform the following tests and inspections with the assistance of a factory-authorized service representative:
 - 1. Test each equipment item for proper operation. Repair or replace equipment that is defective, including units that operate below required capacity or that operate with excessive noise or vibration.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
 - 3. Test water, drain, gas, and liquid-carrying components for leaks. Repair or replace leaking components.
 - 4. Perform hood performance tests required by authorities having jurisdiction.
 - 5. Perform fire-suppression system performance tests required by authorities having jurisdiction.
- D. Commercial-kitchen hoods will be considered defective if they do not pass tests and inspections.
- E. Prepare test and inspection reports.

3.5 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain kitchen hoods.

END OF SECTION 233813

This page intentionally left blank.

SECTION 23 55 23 - LOW INTENSITY RADIANT HEATERS

PART 1 GENERAL

1.1 SUMMARY

- A. Section includes low-intensity, gas-fired, forced-draft radiant heaters.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

- B. Shop Drawings:

1. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
2. Include diagrams for power and control wiring.

1.3 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

1.5 WARRANTY

- A. Manufacturer's Special Warranty: Manufacturer agrees to repair or replace components of radiant heaters that fail in materials or workmanship within specified warranty period.

1. Warranty Period: All warranty periods listed below are from date of Substantial Completion.
 - a. Burner Assembly: Five years.
 - b. Combustion and Emitter Tubes: Five years.
 - c. Heater Controls: One year.

PART 2 PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. UL listed and labeled, with UL label clearly visible on units indicating compliance with ANSI Z83.20/CSA 2.34.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 FORCED-DRAFT HEATERS

- A. Description: Factory-assembled, indoor, overhead-mounted, electrically controlled, low-intensity, infrared radiant heating units using gas combustion. Heater to have all necessary factory-installed wiring and piping required prior to field installation and startup.
- B. Fuel Type: Design burner for natural gas having characteristics same as those of gas available at Project site.
- C. Burner Assembly:
 - 1. Combustion-Air Inlet: Ducted vertical to outdoors through roof with vent caps.
- D. Combustion Chamber: 4-inch- diameter, 12-gage, aluminized steel tubing with high-emissivity, high-temperature, corrosion-resistant external finish.
- E. Emitter Tube: 4-inch- diameter, 12-gage, aluminized steel tubing with high-emissivity, high-temperature, corrosion-resistant external finish.
 - 1. 90-degree-bend emitter steel tubing with high-emissivity, high-temperature, corrosion-resistant external finish.
- F. Reflector: Polished aluminum with end caps. Shape to control radiation from tubing for uniform intensity at floor level with 100 percent cutoff above centerline of tubing. Reflectors or entire heater shall accommodate rotational adjustment from horizontal to a minimum 30-degree tilt from vertical.

2.3 CONTROLS AND SAFETIES

- A. Gas Control Valve: Single-stage, regulated redundant 24-V ac gas valve that contains pilot solenoid valve, electric gas valve, pilot filter, pressure regulator, pilot shutoff, and manual shutoff all in one body.

- B. Failure Safeguards: 100 percent shutoff of gas flow in the event of flame or power failure.
- C. Prepurge of 15 seconds of air control system prior to burner ignition.
- D. Safety lockout of burner after three consecutive ignition failures.
- E. Blocked Vent Safety: Differential pressure switch in burner safety circuit to stop burner operation with high discharge or suction pressure.
- F. Control Panel Interlock: Stops burner if panel is open.
- G. Indicator Lights: "Airflow-on" and "burner-on" indicator lights.
- H. Thermostat: Single-stage, wall-mounted type with 50 to 90 deg F operating range and fan on switch.
 - 1. Control Transformer: Integrally mounted.

PART 3 EXECUTION

3.1 INSTALLATION

- A. Equipment Installation: Install gas-fired, radiant heaters and associated gas features and systems according to NFPA 54.
- B. Suspended Units: Suspend from substrate using chain hanger kits and building attachments.
 - 1. Restrain the unit to resist seismic acceleration. Comply with requirements for seismic-restraint devices specified in Section 23 05 48 "Seismic Restraints for HVAC."
 - 2. Comply with requirements for hangers and supports specified in Section 23 05 29 "Hangers and Supports for HVAC Piping and Equipment."
- C. Maintain manufacturers' recommended clearances for combustibles.
- D. Gas Piping: Comply with Section 22 11 23 "Facility Natural-Gas Piping." Connect gas piping to gas train inlet; provide union with enough clearance for burner removal and service.
 - 1. Gas Connections: Connect gas piping to radiant heaters according to NFPA 54.
- E. Where installing piping adjacent to gas-fired, radiant heaters, allow space for service and maintenance.

F. Vent Connections: Comply with Section 23 31 13 "Metal Ducts". Connections shall be made with rigid ducts meeting manufacturer's requirements.

G. Electrical Connections: Comply with applicable requirements in Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."

1. Install electrical devices furnished with heaters but not specified to be factory mounted.

3.2 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
2. Verify bearing lubrication.
3. Verify proper motor rotation.
4. Test Reports: Prepare a written report to record the following:
 - a. Test procedures used.
 - b. Test results that comply with requirements.
 - c. Test results that do not comply with requirements and corrective action taken to achieve compliance with requirements.

B. Gas-fired, radiant heaters will be considered defective if they do not pass tests and inspections.

C. Prepare test and inspection reports.

3.3 ADJUSTING

A. Adjust initial-temperature set points.

B. Adjust burner and other unit components for optimum heating performance and efficiency.

END OF SECTION 23 55 23

SECTION 23 81 26 - SPLIT-SYSTEM AIR-CONDITIONERS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section includes split-system air-conditioning and heat-pump units consisting of separate evaporator-fan and compressor-condenser components.

1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

1.3 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

1.4 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. ASHRAE Compliance:
 - 1. Fabricate and label refrigeration system to comply with ASHRAE 15, "Safety Standard for Refrigeration Systems."

1.5 WARRANTY

- A. Standard Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of split-system air-conditioning units that fail in materials or workmanship within specified warranty period of at least one year.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Provide by one of the following manufacturers:
 - 1. Mitsubishi
 - 2. Daikin
 - 3. LG
 - 4. Trane

2.2 INDOOR UNITS (5 TONS OR LESS)

A. Wall-Mounted, Evaporator-Fan Components:

1. Cabinet: Enameled steel with removable panels on front and ends in color selected by Architect, and discharge drain pans with drain connection.
2. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins and thermal-expansion valve. Comply with ARI 206/110.
3. Electric Coil: Helical, nickel-chrome, resistance-wire heating elements; with refractory ceramic support bushings, automatic-reset thermal cutout, built-in magnetic contactors, manual-reset thermal cutout, airflow proving device, and one-time fuses in terminal box for overcurrent protection.
4. Fan: Direct drive, centrifugal.
5. Fan Motors:
 - a. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements specified in Section 23 05 13 "Common Motor Requirements for HVAC Equipment."
 - b. Multitapped, multispeed with internal thermal protection and permanent lubrication.
 - c. Enclosure Type: Totally enclosed, fan cooled.
 - d. NEMA Premium (TM) efficient motors as defined in NEMA MG 1.
 - e. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in electrical Sections.
 - f. Mount unit-mounted disconnect switches on exterior of unit.
6. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
7. Condensate Drain Pans:
 - a. Fabricated with two percent slope in at least two planes to collect condensate from cooling coils (including coil piping connections, coil headers, and return bends) and humidifiers, and to direct water toward drain connection.
 - 1) Depth: A minimum of 1 inch deep.
 - b. Double-wall, stainless-steel sheet with space between walls filled with foam insulation and moisture-tight seal.
 - c. Drain Connection: Located at lowest point of pan and sized to prevent overflow. Terminate with threaded nipple on one end of pan.
8. Air Filtration Section:
 - a. General Requirements for Air Filtration Section:
 - 1) Filter-Holding Frames: Arranged for flat or angular orientation, with access doors on both sides of unit. Filters shall be removable from one side or lifted out from access plenum.
 - b. Disposable Panel Filters:

- 1) Factory-fabricated, viscous-coated, flat-panel type.
- 2) Thickness: 1 inch
- 3) MERV according to ASHRAE 52.2: 5 minimum
- 4) Media: Interlaced glass fibers sprayed with nonflammable adhesive.
- 5) Frame: Galvanized steel, with metal grid on outlet side, steel rod grid on inlet side, and hinged; with pull and retaining handles.

2.3 OUTDOOR UNITS (5 TONS OR LESS)

A. Air-Cooled, Compressor-Condenser Components:

1. Casing: Steel, finished with baked enamel in color selected by Architect, with removable panels for access to controls, weep holes for water drainage, and mounting holes in base. Provide brass service valves, fittings, and gage ports on exterior of casing.
2. Compressor: Hermetically sealed with crankcase heater and mounted on vibration isolation device. Compressor motor shall have thermal- and current-sensitive overload devices, start capacitor, relay, and contactor.
 - a. Compressor Type: Scroll.
 - b. Refrigerant: R-410A
 - c. Refrigerant Coil: Copper tube, with mechanically bonded aluminum fins and liquid subcooler. Comply with ARI 206/110.
3. Fan: Aluminum-propeller type, directly connected to motor.
4. Motor: Permanently lubricated, with integral thermal-overload protection.
5. Low Ambient Kit: Permits operation down to 0 deg F
6. Mounting Base: Polyethylene.

2.4 ACCESSORIES

A. Thermostat: Integral unit with the following features:

1. Compressor time delay.
2. 24-hour time control of system stop and start.
3. Liquid-crystal display indicating temperature, set-point temperature, time setting, operating mode, and fan speed.
4. Fan-speed selection including auto setting.
5. Automatic-reset timer to prevent rapid cycling of compressor.

B. Refrigerant Line Kits: Soft-annealed copper suction and liquid lines factory cleaned, dried, pressurized, and sealed; factory-insulated suction line with flared fittings at both ends.

C. Drain Hose: For condensate.

2.5 CAPACITIES AND CHARACTERISTICS

A. Refer to Construction Drawings and Schedules.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install units level and plumb.
- B. Install evaporator-fan components using manufacturer's standard mounting devices securely fastened to building structure.
- C. Install roof-mounted, compressor-condenser components on equipment supports specified in Section 07 72 00 "Roof Accessories." Anchor units to supports with removable, cadmium-plated fasteners.
- D. Equipment Mounting:
 - 1. Install ground-mounted, compressor-condenser components on pre-fabricated equipment base(s) secured to the roof structure.
- E. Install and connect precharged refrigerant tubing to component's quick-connect fittings. Install tubing to allow access to unit.

3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Where piping is installed adjacent to unit, allow space for service and maintenance of unit.

3.3 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- B. Tests and Inspections:
 - 1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
 - 2. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 - 3. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- C. Remove and replace malfunctioning units and retest as specified above.

3.4 DEMONSTRATION

- A. Train the Owner's maintenance personnel to adjust, operate, and maintain units.

END OF SECTION 23 81 26

This page intentionally left blank.

SECTION 23 81 33 - VARIABLE REFRIGERANT SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SYSTEM DESCRIPTION

- A. A variable capacity, heat pump air conditioning variable refrigerant volume type split system. The system shall consist of multiple evaporators using PID control, connected to a single condenser unit or multiple condenser units but not to exceed what is permitted by local code. The condenser shall be a direct expansion (DX), air-cooled heat recovery/heat pump air-conditioning system, variable speed driven compressor multi zone split system, using R-410A refrigerant.
- B. Each system shall be connected to multiple indoor units through a common refrigerant piping network and integrated system controls and communication network. Each indoor unit shall be controlled as a group.

1.3 QUALITY ASSURANCE

- A. The units shall be listed by Electrical Laboratories (ETL) and bear the ETL label.
- B. All wiring shall be in accordance with the National Electrical Code (N.E.C.).
- C. The units shall be manufactured in a facility registered to ISO 9001 and ISO14001 which is a set of standards applying to environmental protection set by the International Standard Organization (ISO).
- D. A full charge of R-410A for the condensing unit only shall be provided in the condensing unit.

1.4 DELIVERY, STORAGE AND HANDLING

- A. All equipment shall be stored protected from weather, extreme temperature, etc. as suggested by the manufacturer. All VRF equipment shall be moved, lifted, etc. as suggested by the manufacturer.

1.5 WARRANTY

- A. Manufacturer's standard form in which manufacturer agrees to repair or replace components of VRF units that fail in materials or workmanship within one year from substantial completion. Compressors shall have a seven year warranty. If, during this period, any part should fail to function properly due to defects in workmanship or material, it shall be replaced or repaired at the discretion of the manufacturer.

1.6 SUBMITTALS

- A. Product Data: Include rated capacities, furnished specialties, and accessories for each model.

- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
1. Wiring Diagrams: Power, signal, and control wiring.
- C. Coordination Drawings: Floor plans, reflected ceiling plans, and other details, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:
1. Suspended ceiling components.
 2. Structural members to which heat pumps will be attached.
 3. Method of attaching hangers to building structure.
 4. Size and location of initial access modules for acoustical tile.
 5. Items penetrating finished ceiling, including the following:
 - a. Lighting fixtures.
 - b. Air outlets and inlets.
 - c. Speakers.
 - d. Sprinklers.
 - e. Access panels.
- D. Delegated-Design Submittals:
1. Include design calculations for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
 2. Include design calculations with corresponding diagram of refrigerant piping and tubing sizing for each system installed.
 3. Include design calculations with corresponding floor plans indicating that refrigerant concentration limits are within allowable limits of ASHRAE 15 and governing codes.
 4. Include calculations showing that system travel distance for refrigerant piping and controls cabling are within horizontal and vertical travel distances set by manufacturer. Provide a comparison table for each system installed.
- E. Seismic Qualification Data: Certificates, for equipment, accessories, and components, from manufacturer.
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- F. Field quality-control test reports.
- G. Operation and Maintenance Data: For water-source heat pumps to include in emergency, operation, and maintenance manuals.
- H. Warranty: Special warranty specified in this Section.

1.7 COORDINATION

- A. Coordinate layout and installation of system and suspension components with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, fire-suppression system components, and partition assemblies.
- B. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.
- C. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Division 07 Section "Roof Accessories."

1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. One set of matched fan belts for each belt-driven fan.
 - 2. One set of filters for each unit.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
 - 1. Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.
 - a. Daikin AC.
 - b. LG
 - c. Mitsubishi Electric
 - d. Trane.

2.2 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional specialist, as defined in Section 01 40 00 "Quality Requirements," to design complete and operational VRF HVAC system(s) complying with requirements indicated.
 - 1. Provide system refrigerant calculations.
 - a. Refrigerant concentration limits shall be within allowable limits of ASHRAE 15 and governing codes.
 - b. Indicate compliance with manufacturer's maximum vertical and horizontal travel distances. Prepare a comparison table for each system showing calculated distances compared to manufacturer's maximum allowed distances.
 - 2. System Refrigerant Piping and Tubing:
 - a. Arrangement: Arrange piping to interconnect indoor units, HRCUs, and outdoor unit(s) in compliance with manufacturer requirements and requirements indicated.

- b. Routing: Conceal piping above ceilings and behind walls to maximum extent possible.
 - c. Sizing: Size piping system, using a software program acceptable to manufacturer, to provide performance requirements indicated. Consider requirements to accommodate future change requirements.
 - 3. System Controls:
 - a. Network arrangement.
 - b. Network interface with other building systems.
 - c. Product selection.
 - d. Sizing.
- B. Service Access:
 - 1. Provide and document service access requirements.
 - 2. Locate equipment, system isolation valves, and other system components that require service and inspection in easily accessible locations. Avoid locations that are difficult to access if possible.
 - 3. Where serviceable components are installed behind walls and above inaccessible ceilings, provide finished assembly with access doors or panels to gain access. Properly size the openings to allow for service, removal, and replacement.
 - 4. If less than full and unrestricted access is provided, locate components within an 18-inch reach of the finished assembly.
 - 5. Where ladder access is required to service elevated components, provide an installation that provides for sufficient access within ladder manufacturer's written instructions for use.
 - 6. Comply with OSHA regulations.
- C. System Design and Installation Requirements:
 - 1. Design and install systems indicated according to manufacturer's recommendations and written instructions.
 - 2. Where manufacturer's requirements differ from requirements indicated, contact Architect for direction. The most stringent requirements should apply unless otherwise directed in writing by Architect.
- D. System Capacity Ratio: The sum of connected capacity of all indoor units shall be within the following range of outdoor-unit rated capacity:
 - 1. Not less than 50 percent.
 - 2. Not more than 120 percent.
 - 3. Range acceptable to manufacturer.
- E. System Turndown: Stable operation down to 20 percent of outdoor-unit capacity.
- F. Seismic Performance: VRF HVAC system(s) shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

1. The term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."
 2. Component Importance Factor: 1.5.
 3. Component Amplification Factor: 2.5
 4. Component Response Modification Factor: 6.0
- G. Thermal Movements: Allow for controlled thermal movements from ambient, surface, and system temperature changes.

H. CEILING CASSETTE INDOOR UNIT WITH GRILLE

1. General:
 - a. The indoor unit shall be a four-way cassette style indoor unit that recesses into the ceiling with a ceiling grille. The indoor unit shall be factory assembled, wired and run tested. Contained within the unit shall be all factory wiring, piping, electronic modulating linear expansion device, control circuit board and fan motor. The unit shall have a self-diagnostic function, 3-minute time delay mechanism, an auto restart function, an emergency operation function and a test run switch. Indoor unit and refrigerant pipes shall be charged with dehydrated air before shipment from the factory. The unit shall be suitable for use in plenums in accordance with UL1995 ed 4.
 - b. The indoor unit shall be completely factory assembled and tested. Included in the unit is factory wiring, piping, electronic proportional expansion valve, control circuit board, fan motor thermal protector, flare connections, condensate drain pan, condensate drain pump, condensate safety shutoff and alarm, self-diagnostics, auto-restart function, 3-minute fused time delay, and test run switch.
 - c. Indoor unit and refrigerant pipes will be charged with dehydrated air prior to shipment from the factory.
 - d. Both refrigerant lines shall be insulated from the outdoor unit.
 - e. The 4-way supply air flow can be field modified to 3-way and 2-way airflow to accommodate various installation configurations including corner installations.
 - f. The cabinet for the 24"x24" indoor unit shall be a compact 22-7/16" wide x 22-7/16" deep so it will fit within a standard 24" square suspended ceiling grid.
2. Construction:
 - a. Three auto-swing positions shall be available to choose, which include standard, draft prevention and ceiling stain prevention.
 - b. Fresh air intake shall be possible by way of direct duct installation to the side of the indoor unit cabinet.
 - c. A branch duct knockout shall exist for branch ducting supply air.
 - d. The cabinet shall be constructed with sound absorbing foamed polystyrene and polyethylene insulation.
 - e. The fan shall be direct-drive turbo fan type with statically and dynamically balanced impeller with high and low fan speeds available.
 - f. The airflow rate shall be available in high and low settings.
 - g. The fan motor shall be thermally protected.
 - h. The return air shall be filtered by means of a washable long-life filter with mildew proof resin.

- i. Coils shall be of the direct expansion type constructed from copper tubes expanded into aluminum fins to form a mechanical bond.
 - j. The coil shall be of a waffle louver fin and high heat exchange, rifled bore tube design to ensure highly efficient performance.
 - k. A condensate pan shall be located under the coil and a pump with a 21 inch lift shall be located below the coil in the condensate pan with a built in safety alarm.
 - l. A thermistor will be located on the liquid and gas line as well as in the return air.
- 3. Electrical:
 - a. A separate power supply will be required of 208/230 volts, 1 phase, 60 hertz. The acceptable voltage range shall be 187 to 253 volts.
 - b. Transmission (control) wiring between the indoor unit and remote controller shall be a maximum distance of 1,640 feet.
- 4. Fan Coil Optional Accessories Required:
 - a. Air filter.
 - b. Room controller with built-in sensor

I. CEILING-CONCEALED DUCTED INDOOR UNIT

- 1. The ceiling-concealed ducted indoor unit shall be factory assembled, wired and run tested. Contained within the unit shall be all factory wiring, piping, electronic modulating linear expansion device, control circuit board and fan motor. The unit shall have a self-diagnostic function, 3-minute time delay mechanism, and an auto restart function. Indoor unit and refrigerant pipes shall be charged with dehydrated air before shipment from the factory. The unit shall be suitable for use in plenums in accordance with UL1995 ed 4.
- 2. Cabinet:
 - a. The unit shall be ceiling-concealed, ducted—with a 2-position, field adjustable return and a fixed horizontal discharge supply.
 - b. The cabinet panel shall have provisions for a field installed filtered outside air intake.
- 3. Refrigerant Coil:
 - a. The indoor coil shall be of nonferrous construction with smooth plate fins on copper tubing. The tubing shall have inner grooves for high efficiency heat exchange. All tube joints shall be brazed with phos-copper or silver alloy
 - b. The coils shall be pressure tested at the factory.
 - c. Coil shall be provided with a sloped drain pan. Units without sloped drain pans which must be installed cockeyed to ensure proper drainage are not allowed.
 - d. The unit shall be provided with an integral condensate lift mechanism able to raise drain water 27 inches above the condensate pan.
- 4. Fan:
 - a. Indoor unit shall feature multiple external static pressure settings ranging from 0.14 to 0.60 in. WG.
 - b. The indoor unit fan shall be an assembly with statically and dynamically balanced direct driven by a single motor with permanently lubricated bearings.

- c. The indoor fan shall consist of three (3) speeds, High, Mid, and Low plus the Auto-Fan function
- 5. Electrical:
 - a. A separate power supply will be required of 208/230 volts, 1 phase, 60 hertz. The acceptable voltage range shall be 187 to 228 volts.
- 6. Filters: Disposable with ASHRAE 52.2 MERV rating of 6 or higher.

J. HEAT RECOVERY OUTDOOR UNIT

- 1. General:
 - a. The condensing unit shall be factory assembled and pre-wired with all necessary electronic and refrigerant controls. The refrigeration circuit of the condensing unit shall consist of scroll compressors, motors, fans, condenser coil, electronic expansion valves, solenoid valves, 4-way valve, distribution headers, capillaries, filters, shut off valves, oil separators, service ports and refrigerant regulator.
 - b. The unit shall incorporate an auto-charging feature to ensure proper refrigerant charge.
 - c. The following safety devices shall be included on the condensing unit; high pressure sensor and switch, low pressure sensor, control circuit fuses, crankcase heaters, fusible plug, overload relay, inverter overload protector, thermal protectors for compressor and fan motors, over current protection for the inverter and anti-recycling timers.
 - d. To ensure the liquid refrigerant does not flash when supplying to the various indoor units, the circuit shall be provided with a sub-cooling feature.
 - e. Oil Return Control Oil: return control is performed in order to avoid insufficient oil supply to the compressor caused by long time low frequency operation. This control is utilized to return the oil flow out to the indoor unit side from the compressor.
- 2. Unit Cabinet:
 - a. The condensing unit shall be completely weatherproof and corrosion resistant. The unit shall be constructed from rust-proofed mild steel panels coated with a baked enamel finish.
- 3. Fan:
 - a. All condensing unit sizes shall consist of minimum two or more propeller type, direct-drive fan motors that have multiple speed operation via a DC (digitally commutating) inverter.
 - b. Night setback control of the fan motor for low noise operation by way of automatically limiting the maximum speed shall be a standard feature. Operation sound level shall be selectable from 3 steps as shown below.
- 4. Condenser Coil:

- a. The condenser coil shall be manufactured from copper tubes expanded into aluminum fins to form a mechanical bond.
 - b. The heat exchanger coil shall be of a waffle louver fin and rifled bore tube design to ensure high efficiency performance.
 - c. The heat exchanger on the condensing units shall be manufactured from Hi-X seamless copper tube with N-shape internal grooves mechanically bonded on to aluminum fins to an e-Pass Design.
 - d. The fins are to be covered with an anti-corrosion acrylic resin and hydrophilic film type E1.
 - e. The pipe plates shall be treated with powdered polyester resin for corrosion prevention. The thickness of the coating must be between 2.0 to 3.0 microns.
5. Compressor:
- a. The inverter scroll compressors shall be variable speed (PVM inverter) controlled which is capable of changing the speed to follow the variations in total cooling and heating load.
 - b. The capacity control range shall be as low as 4%.
 - c. Oil separators shall be standard with the equipment together with an intelligent oil management system.
 - d. The compressor shall be spring mounted to avoid the transmission of vibration.
 - e. All unit sizes shall contain a minimum of 2 compressors. In the event of compressor failure the remaining compressors shall continue to operate and provide heating or cooling as required at a proportionally reduced capacity. The microprocessor and associated controls shall be designed to specifically address this condition.
 - f. Conjoined operation hours of the compressors shall be balanced by means of the Duty Cycling Function, ensuring sequential starting of each module at each start/stop cycle, completion of oil return, completion of defrost or every 8 hours.
6. Safety Devices:
- a. Heat recovery unit shall be equipped with the following safety devices.
 - 1) High pressure safety operation.
 - 2) Low pressure safety operation.
 - 3) Discharge pipe protection control.
 - 4) Inverter protection control.
 - 5) Standard compressor overload protection.
7. Electrical:
- a. The power supply to the condensing unit shall be 208-230 or 460 volts, 3 phase, 60 hertz +/- 10%.
 - b. The control voltage between the indoor and condensing unit shall be 16VDC non-shielded, stranded 2 conductor cable.
 - c. The control wiring shall be a two-wire multiplex transmission system, making it possible to connect multiple indoor units to one condensing unit with one 2-cable wire, thus simplifying the wiring installation.

K. CONTROLS

1. Room Controller for each control zone shall be a LG model PREMTBVC1 or owner approved equivalent by alternate VRF manufacturer.
 - a. Display Features (configurable):
 - 1) The Remote controller shall feature a Backlit LCD Display with contrast adjustment and auto off after 30 seconds.
 - 2) Multiple display modes: Detailed, Standard, and Simple
 - 3) Function button lockout (On/Off, Mode, Fan Speed, Up/Down/Left/Right Arrows)
 - a) Controller Face Plate option to hide unnecessary (locked out) buttons. Face plate and simplified display mode shall enable the user full control of the system with minimum amount of user input.
 - 4) Large 1 1/16" room temperature displayed in Simple display
 - 5) Configure "Off" to be displayed when unit is turned off, and the setpoint can be removed from the display when unit is turned Off
 - 6) Fan speed display, setpoint, room temperature, operational mode are all removable.
 - 7) System Status icons available in large font.
 - 8) The controller shall display temperature setpoint available in one degree increments with a range of 60-90°F (0-32°C)
 - 9) Room temperature (0-176°F/-17-80°C range) available in one degree increment
 - 10) The following is available to display errors and to assist service personnel in troubleshooting:
 - a) A blinking LED will also signal system abnormality/error
 - b) Error codes will be displayed in the event of system abnormality/error.
 - c) Service personnel shall be able to access the following from the room controller:
 - i) Return Air Temperature
 - ii) Liquid Line Temperature
 - iii) Gas Line Temperature
 - iv) Discharge Air Temperature (depending on unit),
 - v) Remote Controller Sensor Temperature
 - vi) Temperature used for Indoor Unit Control
 - b. Operational Adjustments Available (able to be prohibited)
 - 1) On/Off
 - 2) Operation Mode (Cool, Heat, Fan, Dry and Auto)
 - 3) Fan Speed
 - 4) Airflow direction (dependent on indoor unit type).
 - c. Set points and Auto-Changeover
 - 1) The Controller shall support auto-changeover mode for both Heat Pump and Heat Recovery systems allowing the optimal room temperature to be maintained by automatically switching the indoor unit's mode between Cool and Heat according to the room temperature and temperature setpoint.

- 2) The controller shall be able to limit the user adjustable setpoint ranges individually for cooling and heating in the occupied period. The following set point options should be available for every zone:
 - a) Dual Set Points: individual cool and heat setpoints with minimum differential adjustable from 0–7°F
 - b) Single Set Point: single setpoint for heating and cooling.
- 3) Changeover to cooling mode shall occur at cooling setpoint + 1°F (0.5°C)
- 4) Changeover to heating mode shall occur at heating setpoint - 1°F (0.5°C)
- 5) Changeover guard timer shall be configurable to 15, 30, 60, or 90 minutes. The guard timer shall be overridden if either of the following occur:
 - a) Guard timer is ignored by a change of setpoint manually from either the Multi-zone Controller, Remote Controller, or by schedule.
 - b) The Guard timer is ignored if the space temperature change is greater than the configured changeover deadband and the space temperatures reaches the secondary changeover deadband (configurable from 1 – 4°F).
- 6) The controller shall have independent cooling setup and heating setback setpoints in the unoccupied mode
- 7) The Controller shall support an Auto Off Timer for temporarily enabling indoor unit operation during the unoccupied period.
 - a) When the Off Timer is enabled and when the unit is manually turned on at the remote controller
 - b) The controller shall shut off the unit after a set time period configurable in the controller menu with a range of 30-180 minutes.

d. Programmability:

- 1) Clock (12/24 hour) and Day display
- 2) Automatic adjustment for Day Light Savings Time (DST)
- 3) Controller shall support schedule settings with selectable weekly pattern options.
 - a) 7-day / Weekday + Weekend / Weekday + Saturday + Sunday / Everyday
 - b) The schedule shall support unit On/Off
 - c) Independently settable Cooling and/or Heating setpoints when unit is on (occupied)
 - d) Setup (Cooling) and Setback (Heating) setpoints when unit is off (unoccupied)
 - e) Up to 5 operations can be schedulable per day
 - f) Time setting in 1-minute increments

2. Central Control System

- a. The Graphical User Interface (GUI) shall employ browser-like functionality for ease of navigation. It shall include a tree view (similar to Windows Explorer) for quick viewing of, and access to, the hierarchical structure of the database. In addition, menu-pull downs, and toolbars shall employ buttons, commands and navigation to permit the operator to perform tasks with a minimal knowledge of the HVAC Control System and basic computing skills.
- b. Local Workstation Features:

- 1) Shall be a backlit 10.4" LCD display with auto OFF.
- c. Area and Group configuration
- 1) Area contains one (1) or more Area(s) or Group(s)
 - a) A group may be a unit or point that has a network address
 - b) An Area is a tiered group where management points (units, digital input/output, and analog input groups) can be monitored and controlled by global settings. Up to 650 Areas can be created. Area hierarchy can have up to 10 tiered levels (ex. top level: 1st floor West, 2nd level: offices, hallways, 3rd level: Office 101, 102, and 103, etc.). Area configuration shall classify levels of monitoring and control for each management point
 - c) Areas and Groups may be assigned names (ex. Office 101, Lobby, North Hallway, etc.)
- d. Display settings
- 1) The Controller shall display On/Off, Operation Mode, Setpoint, Space Temperature, Louver Position, Fan Speed for each Area or Group. Display information shall be updated every 3 seconds to show the latest status of the indoor unit groups.
 - 2) System status icons shall display On/Off (color coded), Malfunction/Error (color coded), Forced Stop, Setback, Filter, Maintenance, and Screen Lock.
 - 3) The controller shall display the temperature setpoint in one degree increments with a range of 60oF – 90oF, 1oF basis (16oC – 32oC, 0.1oC basis).
 - 4) Display of temperature setpoint information shall be configurable for Fahrenheit or Celsius
 - 5) The Controller shall adjust for daylight savings time (DST) automatically.
 - 6) Display information shall be updated every 3 seconds to show the latest status of the indoor unit groups.
 - 7) Graphic floor plan layouts
 - a) Display site floor plan as the background for visual navigation. Up to 4 status points can be assigned to the indoor unit icon (room name, room temperature, setpoint, and mode)
- e. Scheduling
- 1) The Controller shall display Date (mm/dd/yyyy, yyyy/mm/dd, or dd/mm/yyyy format selectable) and day of the week along with the time of day (12hr or 24hr display selectable).
 - 2) The Controller shall adjust for daylight savings time (DST) automatically.
 - 3) Weekly schedule settings 7 day weekly pattern
 - 4) The schedule shall have the capabilities of being enabled or disabled, and should include minimum 100 independent schedules configurable with up to 20 events settable for each days schedule
 - a) Each scheduled event shall specify time and target Area or Group
 - b) Each scheduled event shall include On/Off, Operation Mode, Occupied Setpoint, Pre-Cool, Pre-Heat, Setback High, Setback Low, Remote Controller On/Off Prohibit, Remote Controller Mode

Prohibit, Remote Controller Setpoint Prohibit, Fan Speed, and Setpoint Range Limit

- c) A timer extension setting should be available to override zones into occupied mode and selectable from 30 to 180 minutes.
- d) Two tiers of setback temperatures should be available for both heating and cooling modes, dependent on occupancy schedule.
- 5) Up to 40 exception days can be scheduled yearly, and set on a set or floating date.

f. Errors

- 1) Error status shall be displayed in the event of system abnormality/error with one of three color coded icons placed over the indoor unit icon or lower task bar.
- 2) Limit errors are based upon preconfigured analog input upper and lower limit settings and are generated when the limits have been met. When limit error is generated a yellow triangle will be placed over the unit icon.
- 3) Communication errors shall be displayed with a blue triangle placed over the indoor unit icon
- 4) Error history shall be available for viewing for up to 500,000 errors/abnormality events

g. Auto-Changeover

- 1) Auto-changeover shall be programmed to allow for the optimal room temperature to be maintained by automatically switching mode between Cool and Heat in accordance with the room temperature and setpoint.
 - a) The setpoint differential should adjustable between 0°F to 13°F. The (Thermal) Differential is the tolerance for the indoor unit's setpoint.
 - b) The operational mode shall change from cooling to heating when the room setpoint is exceeded by 1°F (adjustable).
 - c) The operational mode shall change from heating to cooling when the room temperature drops 1°F (adjustable) below setpoint.
 - d) A guard timer (adjustable 15-60 minutes) should be in place to prevent rapid changing, but is overridden if the room setpoint is changed.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of water-source heat pumps.
- B. Examine roughing-in for piping and electric installations to verify actual locations of piping connections and electrical conduit before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Suspend units from structure with threaded steel rods and minimum 0.25-inch static deflection rubber-in-shear vibration isolators and seismic restraints.
- B. Install wall-mounting thermostats, humidistats, and switch controls in electrical outlet boxes at heights to match lighting controls or as required in Division 23 Section "Instrumentation and Control for HVAC."
- C. Install air-cooled condenser refrigerant condensers on cast-in-place concrete equipment bases. Comply with requirements for equipment bases and foundations.

3.3 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties. Specific connection requirements are as follows:
 - 1. Connect piping to units as recommended by unit manufacturer.
- B. Duct installation requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of ducts. Specific connection requirements are as follows:
 - 1. Connect ducts to units with flexible duct connectors specified in Division 23 Section "Air Duct Accessories."
- C. Install electrical devices furnished by manufacturer but not specified to be factory mounted.
- D. Install piping adjacent to machine to allow service and maintenance.
- E. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- F. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections and to assist in field testing. Report results in writing.
- B. Perform the following field tests and inspections and prepare test reports:
 - 1. After installing units and after electrical circuitry has been energized, test units for compliance with requirements.
 - 2. Inspect for and remove shipping bolts, blocks, and tie-down straps.
 - 3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
 - 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- C. Remove and replace malfunctioning units and retest as specified above.

3.5 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
- B. Complete installation and startup checks according to manufacturer's written instructions and do the following:
 - 1. Inspect for visible damage to unit casing.
 - 2. Inspect for visible damage to compressor, coils, and fans.
 - 3. Inspect internal insulation.
 - 4. Verify that labels are clearly visible.
 - 5. Verify that clearances have been provided for servicing.
 - 6. Verify that controls are connected and operable.
 - 7. Verify that filters are installed.
 - 8. Adjust vibration isolators.
 - 9. Verify bearing lubrication on fan.
 - 10. Inspect fan-wheel rotation for movement in correct direction without vibration and binding.
 - 11. Adjust fan belts to proper alignment and tension.
 - 12. Start unit according to manufacturer's written instructions.
 - 13. Complete startup sheets and attach copy with Contractor's startup report.
 - 14. Inspect and record performance of interlocks and protective devices; verify sequences.
 - 15. Operate unit for an initial period as recommended or required by manufacturer.
 - 16. Verify thermostat calibration.
 - 17. Inspect controls for correct sequencing of heating, refrigeration, and normal and emergency shutdown.
 - 18. Start refrigeration system and measure and record the following:
 - a. Coil leaving-air, dry- and wet-bulb temperatures.
 - b. Coil entering-air, dry- and wet-bulb temperatures.
 - c. Outdoor-air, dry-bulb temperature.
 - d. Outdoor-air-coil, discharge-air, dry-bulb temperature.

3.6 ADJUSTING

- A. Adjust initial temperature set points.
- B. Set field-adjustable switches and circuit-breaker trip ranges as indicated.
- C. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting system to suit actual occupied conditions. Provide up to two visits to Project during other than normal occupancy hours for this purpose.

3.7 CLEANING

- A. Replace filters used during construction prior to air balance or substantial completion.
- B. After completing installation of exposed, factory-finished units, inspect exposed finishes and repair damaged finishes.

3.8 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain the system. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION

This page intentionally left blank.

SECTION 23 82 16 - ELECTRIC-RESISTANCE AIR COILS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes electric resistance air coils.

1.3 SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each air coil.
 - 2. Include rated capacities, operating characteristics, and pressure drops for each air coil.
- B. Shop Drawings: Include diagrams for power, signal, and control wiring.
- C. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which coil location and ceiling-mounted access panels are shown and coordinated with each other.
- D. Field quality-control reports.
- E. Operation and Maintenance Data: For air coils to include in operation and maintenance manuals.

PART 2 - PRODUCTS

2.1 DESCRIPTION

- A. ASHRAE Compliance: Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

2.2 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Indeco.

2. Greenheck.
3. Q Mark.
4. Markel.

2.3 COILS

- A. Testing Agency Listing and Labeling: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Coil Assembly: Comply with UL 1995.
- C. Heating Elements: Coiled resistance wire of 80 percent nickel and 20 percent chromium; surrounded by compacted magnesium-oxide powder in tubular-steel sheath; with spiral-wound, copper-plated, steel fins continuously brazed to sheath.
- D. High-Temperature Coil Protection: Disk-type, automatically reset, thermal-cutout, safety device; serviceable through terminal box without removing heater from duct or casing.
 1. Secondary Protection: Load-carrying, manually reset or manually replaceable, thermal cutouts; factory wired in series with each heater stage.
- E. Frames: Galvanized-steel channel frame, minimum 0.052 inch thick for flanged mounting.
- F. Control Panel: Remote mounted with disconnecting means and overcurrent protection. Include the following controls:
 1. Magnetic contactor.
 2. Mercury contactor.
 3. Toggle switches; one per step.
 4. Step controller.
 5. Time-delay relay.
 6. Pilot lights; one per step.
 7. Airflow proving switch.
- G. See Section 23 09 90 "HVAC Instrumentation and Controls" for thermostat.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine ducts, plenums, and casings to receive air coils for compliance with requirements for installation tolerances and other conditions affecting coil performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install coils level and plumb.

- B. Install coils in metal ducts and casings constructed according to SMACNA's "HVAC Duct Construction Standards, Metal and Flexible."
- C. Clean coils using materials and methods recommended in writing by manufacturers, and clean inside of casings and enclosures to remove dust and debris.

3.3 CONNECTIONS

- A. Ground equipment according to Section 26 05 26 "Grounding and Bonding for Electrical Systems."
- B. Connect wiring according to Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."

3.4 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Operational Test: After electrical circuitry has been energized, operate electric coils to confirm proper unit operation.
 - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- B. Prepare test and inspection reports.

END OF SECTION

This page intentionally left blank.

SECTION 26 00 00 - ELECTRICAL GENERAL REQUIREMENTS AND COMMON WORK RESULTS

PART 1 - GENERAL

1.1 SUMMARY

- A. Drawings and general provisions of Contract, including General and the Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. This Section includes general administrative, material, and procedural requirements for Division 26, 27, and 28 to expand the requirements specified in Division 01.

1.2 GENERAL

- A. Where the word contractor is used in this specification or on the drawings, the term shall apply to a prime contractor or a subcontractor. Where the term "this contractor" is used in this specification, the term shall apply to the electrical contractors as applicable. Words such as "he" and "she" used in this specification are not intended to designate gender.
- B. This Contractor shall refer to the "Instructions to Bidders", General Conditions, Supplementary General Conditions and Special Conditions and Applicable Provisions for bidding requirements and items that effect his work.
- C. Pertinent Federal, State and Local requirements and regulations of OSHA, National Electrical Codes, and NFPA, are hereby made a part of this contract. Use of the term "code" in sections of this specification refers to applicable requirements and regulations of above listed agencies.
- D. It shall be the responsibility of this Contractor to promptly inform the Architects of all deviations in the drawings and specifications from the City, County and State Laws, Ordinances, Regulations or Rulings. This Contractor shall install all work strictly in accordance with all such requirements at no additional cost to Owner.
- E. In the event the specifications or drawings conflict with such laws or ordinances, the conflicting portion of the work affected shall be installed in strict accordance with the laws or ordinances above mentioned and the remainder of the drawings and specifications shall remain in full force.
- F. If the requirements of these specifications or drawings are more stringent than the conflicting laws or ordinances, the requirements of the specifications and drawings shall govern unless amended by the Engineer.

1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct shafts, unheated spaces immediately below the roof, spaces above ceilings, unexcavated spaces, crawl spaces, and tunnels.
- B. Exposed Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms.
- C. Exposed Exterior Installations: Exposed to view outdoors, or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in duct shafts.
- E. Concealed Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants, but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- F. ATS: Acceptance Testing Specifications.
- G. EPDM: Ethylene-propylene-diene terpolymer rubber.
- H. NBR: Acrylonitrile-butadiene rubber.

1.4 REGULATORY REQUIREMENTS

- A. Work and materials shall conform to and be executed, inspected and tested in accordance with the latest edition of applicable Federal, State and local codes and with the other governing rules and regulations of Federal, State, and local governmental agencies.
- B. Specific codes and standards which will apply to this installation are listed in applicable specification sections.
- C. Other codes and standards which will apply to this installation include the current editions of:
 - 1. NFPA 101 - Life Safety Code.
 - 2. Underwriters Laboratories.
- D. Where governing codes indicate the Drawings and Specifications do not comply with the minimum requirements of applicable codes, be responsible for either notifying the Architect/Engineer in writing during the bidding period of the revisions required to meet code requirements, or providing an installation which will comply with the code requirements.
- E. Follow the current issue of NFPA 70 "National Electrical Code" if there are no local codes having jurisdiction. The City of St. Peters has adopted the 202 edition of NFPA 70.

1.5 QUALITY ASSURANCE

- A. Responsibility Prior to Submitting Pricing or Bid Data:
 - 1. Thoroughly review the contract documents and specifications and visit the site prior to issuing bid. Resolve all reported deficiencies with the Engineer prior to awarding any subcontracts, ordering material, or starting any work.
- B. Qualifications:
 - 1. Only products of specified manufacturers, or approved equals as determined by the Engineer, are acceptable.
 - 2. Employ only workmen who are skilled in their trades.
- C. Compliance with Codes, Laws, and Ordinances:
 - 1. Conform to all requirements of the state, city and local codes, laws and ordinances and other regulations having jurisdiction over this installation.
 - 2. If there are any discrepancies between the codes and regulations and these specifications, the Engineer shall determine the method or equipment to be used.
- D. Examination of Drawings and Specifications:
 - 1. The drawings for the indicated work are diagrammatic, intended to convey the scope of the electrical work and to indicate the general arrangements and locations of equipment, wiring devices, etc., and the approximate sizes of equipment. Field verification of dimensions on plans is required. The actual conditions, including heights, lengths and orientation, shall be the basis of the work.
 - 2. The architectural, structural, mechanical and electrical drawings and specifications shall be considered as mutually explanatory and complementary. Any electrical work called for by one and not by the other shall be performed as though required by all. All sections and subsections of the Electrical work shall be governed by and subject to the general and supplementary conditions. Report any discrepancies in or between the drawings and specifications, or between the drawings and actual field conditions to the Engineer in sufficient time to issue an addendum for clarification.
 - 3. Determine the exact locations for equipment and rough-ins, and the exact routing of raceways.
 - 4. Do not scale drawings to determine equipment and system locations.
 - 5. Not all required components are shown on the documents, including junction boxes, pull boxes, conduit fittings, etc. Provide all components required for proper installation of the work.
 - 6. Any item either shown on the drawings or called for in the specifications shall be included in this contract.
 - 7. Determine quantities and quality of material and equipment required from the documents. Provide the more expensive or higher quality amount where discrepancies arise among drawings, schedules or specifications.
 - 8. Inform the Engineer in writing, requesting a clarification at the time of the bidding, if any parts of the drawings or specifications are found not to comply with the codes or regulations. Submit a separate price to make the system comply if there is insufficient time for this procedure.

9. Inform the Engineer in writing requesting a clarification if there is any discrepancy between a manufacturer's recommendation and these specifications.

1.6 PERMITS AND INSPECTIONS

- A. Permits: Obtain and pay for all permits, bonds, licenses, tap-in fees, etc., required by the City, State, or other authority having jurisdiction over the work, as a part of the work of the affected sections.
- B. Inspections: Arrange and pay for all inspections required by the above when they become due as part of the work of the sections affected. Conceal no work until approved by these governing authorities. Coordinate inspection period with Authorities Having Jurisdiction and Engineer.

1.7 SHOP DRAWINGS

- A. This Contractor shall submit electronic PDF of complete shop drawings or manufacturer data sheets, certification and descriptive literature for ALL material and equipment furnished on this project:
- B. Shop drawings, manufacturer data sheets and descriptive literature shall include parts lists, etc.
- C. The Contractor shall review each shop drawing etc. before submitting to the engineer to determine that it is acceptable in terms of the means, methods, techniques, orientation, sequences, operations of construction, safety precautions and programs incidental there to, all of which are the contractor's responsibility.
- D. The engineer shall review each shop drawing, etc. for its conformity with design intent and compliance with information given in the construction documents.
- E. The Contractor shall bring to the engineer's attention any shop drawing, etc. that varies from the contract documents requirements.
- F. The engineers review time for all submittals will be 10 working days.
- G. The Contractor shall pay for the review of all shop drawings, etc. that varies from the requirements of the contract documents.
- H. Shop drawings, etc. submitted for equipment or material which was not specified, included in the specification or drawings by written addendum, or submitted by separate letter with the contractors bid will be returned without review and will not be considered for this project.
- I. At the completion of the project, this Contractor shall give the Owner electronic copies of all shop drawings, data sheets, operating manuals, parts lists, maintenance manuals, etc. submitted with a complete Table of Contents and bookmarked

accordingly. All manuals shall be submitted to the Engineer's Office for review and acceptance prior to transmittal to the Owner.

- J. Failure to Submit: Contractor's failure to provide submittals does not alleviate the responsibility to provide the requirements in the Contract Document as interpreted by the Engineer. Correct noncompliant items.

1.8 MATERIAL AND EQUIPMENT SELECTION

- A. Product Options: The specification of each item of major equipment required for the project may include a list of manufacturers, with one "basis of design" manufacturer, type, and model identified by virtue of their being the first listed manufacturer in the specifications. Where several manufacturers in addition to the "basis of design" manufacturer are listed in the specifications, it shall be understood that the words "or approved equal by" are implied to precede each of the other manufacturer's names.
- B. The manufacturers other than the "basis of design" may be furnished at the contractor's option in lieu of the "basis of design" product, provided that the selected manufacturer's product is equal in all material and functional respects. Additional work required for equipment that is other than the "basis of design", shall be at the expense of the contractor. In addition to submittal requirements that may be specified in this section, submit a line-by-line written verification of the applicable specification section(s) identifying compliance with or variations from the specified features, materials, performance, capacities, weight, size, durability, energy consumption and efficiency, warranty, and visual impact (if exposed to view by other than maintenance persons). The burden of proof of manufacturer/product equality is on the contractor.
- C. Where a product is not scheduled on the drawings and, therefore, where no "basis of design" is indicated, the first listed manufacturer in the specifications shall be deemed as "basis of design"
- D. Products of manufacturers not listed in the Contract Documents are considered Substitutions and are not permitted, except as provided under the General and Supplementary Conditions and Division 1 Specifications. Full compliance with section "Substitutions" below is mandatory for acceptance of products or manufacturers not listed.
- E. Listing of a manufacturer does not imply approval of that manufacturer's standard product or products. Rather, listing of a manufacturer indicates only a general acceptance of that manufacturer's name and reputation. Final approval is subject to full compliance with these Contract Documents.
- F. Model numbers identified on the Drawings notwithstanding, all equipment must comply with the requirements of these Contract Documents. Do not assume that a manufacturer's standard product is acceptable as is. For example, one or more custom modifications, custom colors or finishes, manufacturer's options, and/or accessories may be required to meet the specified requirements.

- G. Where drawings indicate sizes, profiles, connections, and dimensional requirements of material and equipment, these are based on the “basis of design” manufacturer, type and model indicated. In the event that equipment of power, dimensions, capacities, layout, connections, and/or ratings differing from the “basis of design” are selected by the contractor and approved by the Owner’s representative, any necessary adjustments are the contractor’s responsibility. All connecting mechanical and electrical services, circuit breakers, conduit, motors, bases, pipe and duct sizes, pipe and duct layout, and the like shall be adjusted by the contractor to suit the equipment provided. No additional costs will be approved for these changes. Should revisions to the design because of contractor’s selection of manufacturer, type, or model other than the “basis of design” require additional review and/or redesign by an Architect or Engineer, the contractor shall reimburse the Owner for Owner’s added professional fee expenses.
- H. Where two or more materials are listed in the “Part 2 – Products” subsection of any specification section, do not assume that the selection of materials is the contractor’s option. Refer to “Part 3 – Execution” subsection of that same section for an explanation of which specific material(s) shall be used for which specific application(s). For example, Part 2 may list several types and grades of piping, and Part 3 will describe which type and grade of pipe to use for a given application.
- I. Drawing plans, schematics, and diagrams indicate general location and arrangement of systems, and have been coordinated, as much as possible, based on available information and field observations. Deviations to layout that may require additional fittings, and are within 6’-0” of design document layout, shall be at the expense of the contractor. Deviations to layout shall be documented on the coordination drawings. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations.

1.9 SUBSTITUTIONS

- A. Notwithstanding any reference in the specifications to any article, device, product, material, form or type of construction by name, or make, or catalog number, such references shall be interpreted as establishing a standard of quality and shall not be construed as limiting competition; and the Contractor in such cases may, at his option, use any article, device, product, material, fixture, form or type of construction which in the judgment of the Engineer, expressed in writing, is equal to that specified.
- B. Any materials or products other than those specified shall be submitted in writing to the Engineer for approval at least 10 days prior to the submission of bids. Materials and products so approved will be so stated by addendum.
- C. No substitute equipment will be considered unless sufficient data is submitted with the request to allow adequate comparison with the specified equipment.
- D. The Engineer reserves the right to reject any or all substitute equipment, if, in his opinion, said equipment is not of equal quality, capacity or like design. In all cases, the decision of the Engineer shall be final.

- E. This Contractor, at his option, may submit any item of material or equipment in a separate letter listing voluntary alternatives. An additive or deduct price shall be indicated for each voluntary alternate submitted. Sufficient data shall accompany each voluntary alternate submitted to allow adequate comparison with the specified equipment. The Contractor shall pay all costs associated with reviewing proposed substitute material or equipment.
- F. This Contractor shall pay all costs arising from the use of substitute equipment or material. Such costs shall include but shall not be limited to architectural design costs, mechanical, electrical, plumbing, fire protection, civil & structural engineering costs and cost to other trades to accommodate the substitute equipment.

1.10 OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUALS

- A. Upon completion of the job, the installing contractors and major suppliers shall instruct the Owner's representatives in the proper operation and maintenance of the systems installed. The installing Contractors shall submit documentation indicating the date of instruction; names and organization of persons providing and receiving the instructions; systems the instructions covered; and materials received.
- B. Contractor shall also submit electronic pdf operating manuals to the Engineer for review. These manuals shall include the following:
 - 1. Complete set of shop drawings.
 - 2. Copies of all submittals.
 - 3. Parts lists, wiring diagrams, piping diagrams, etc.
 - 4. Manufacturers' operating and maintenance instructions.
 - 5. As-built drawings.
 - 6. Written operating and maintenance instructions for the system. This is a written version of Paragraph "1" above.
 - 7. Copies of warranties.
 - 8. Parts lists for each piece of equipment and name of local supplier.

1.11 OWNERS RECORD SET OF DRAWINGS

- A. During construction, a separate set of plans at the jobsite shall be maintained by the Contractor to keep a record of all changes of locations. See additional requirements in General Conditions and Supplementary Conditions.
- B. Locations of piping, ductwork and other concealed facilities are to be shown by the Contractor if and when they differ from the drawings. Underground piping shall be dimensioned on those drawings.
- C. "As built" drawings are to be submitted to Architect/Engineer for review prior to the time of request for final payment. Submit as-built record drawings in accordance with the General Conditions.

1.12 GUARANTEE AND WARRANTY

- A. This Contractor shall guarantee and warrant all equipment, materials, workmanship, installation, etc., for a period of one year in accordance with the General Conditions unless specified longer in product specification or manufacturers standard. This one-year warranty shall commence on satisfactory completion of final punch list items. Satisfactory completion of the final punch list will be determined by the Engineer. If the Owner accepts a portion(s) of the project earlier than the rest, such as partial beneficial occupancy,

1.13 COORDINATION

- A. Coordinate arrangement, mounting, and support of electrical equipment:
 - 1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
 - 2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
 - 3. To allow right of way for piping and conduit installed at required slope.
 - 4. So connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions and of the working and access space of other equipment.
- B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.
- C. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed.
- D. Coordinate electrical testing of electrical, mechanical, and architectural items, so equipment and systems that are functionally interdependent are tested to demonstrate successful interoperability.

1.14 SEQUENCING AND SCHEDULING

- A. Coordinate electrical equipment installation with other building components.
- B. Arrange for chases, slots, and openings in building structure during progress of construction to allow for electrical installations.
- C. Coordinate the installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- D. Sequence, coordinate, and integrate installations of electrical materials and equipment for efficient flow of the Work. Coordinate installation of large equipment requiring positioning prior to closing in the building.
- E. Coordinate connection of electrical services.

- F. Coordinate requirements for access panels and doors where electrical items requiring access are concealed behind finished surfaces. Access panels and doors are specified in this section.
- G. Coordinate installation of identifying devices after completing covering and painting where devices are applied to surfaces. Install identifying devices prior to installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.
- B. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.
- C. Coordinate sleeve selection and application with selection and application of firestopping.

2.2 SLEEVE SEALS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
 - 1. Manufacturers:
 - a. Advance Products & Systems, Inc.
 - b. Calpico, Inc.
 - c. Metraflex Co.
 - d. Pipeline Seal and Insulator, Inc.
 - 2. Sealing Elements: EPDM or NBR interlocking links shaped to fit surface of cable or conduit. Include type and number required for material and size of raceway or cable.
 - 3. Pressure Plates: Carbon steel or stainless steel. Include two for each sealing element.
 - 4. Connecting Bolts and Nuts: Carbon steel with corrosion-resistant coating or stainless steel of length required to secure pressure plates to sealing elements. Include one for each sealing element.

2.3 CONCRETE BASES

- A. Concrete Forms and Reinforcement Materials: As specified in Division 3 Section "Cast-in-Place Concrete."

- B. Concrete: 3000-psi (20.7-MPa), 28-day compressive strength as specified in Division 3 Section "Cast-in-Place Concrete."

2.4 SOIL MATERIALS

- A. Subbase Material: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, crushed slag, or natural or crushed sand.
- B. Drainage Fill: Washed, evenly graded mixture of crushed stone, or crushed or uncrushed gravel, with 100 percent passing a 1-1/2-inch sieve, and not more than 5 percent passing a No. 4 sieve.
- C. Backfill and Fill Materials: Materials complying with ASTM D2487 soil classification groups GW, GP, GM, SM, SW, and SP; free of clay, rock, or gravel larger than 2 inches in any dimension; debris; waste; frozen materials; and vegetable and other deleterious matter.

PART 3 - EXECUTION

3.1 GENERAL

- A. Contractor shall provide all material, equipment, labor, services, and supplies, required to execute all work shown on the electrical drawings; described in these specifications; or made necessary by the work shown on the drawings and/or described in these specifications.
- B. Contractor shall schedule all work and furnish the required materials in such a manner that the work may progress from start to finish in an expeditious and efficient manner without undue interruption. This Contractor shall also schedule his work to coordinate with the construction staging for this project.
- C. Contractor shall hire the proper trades to accomplish the work described on the drawings or in the specifications.

3.2 COORDINATION WITH OTHER TRADES

- A. Prior to the fabrication or installation of any materials, Contractor shall review the drawings indicating work to be performed by each trade to include mechanical, plumbing, fire protection, and low voltage/controls contractors. If conflicts occur, they shall be brought to the attention of the Engineer for resolution.
- B. If Contractor installs the work without coordinating with the other trades, then, if requested by the Owner, Architect, or Engineer, Contractor shall remove and rework some installed work to resolve a conflict, and such change shall be done at no change in contract price.

- C. The Contractor supplying the equipment shall furnish all motors and components which are part of the equipment.
- D. Control wiring is defined as that wiring which conducts electrical energy at a voltage of less than 100 volts. Interlock wiring is defined as that wiring which performs a control function, but at a voltage of 100 volts or greater. All other wiring shall be considered power wiring.
- E. The Electrical Contractor shall provide power wiring to, and including connection to the equipment. Unless specifically noted otherwise, all interlock wiring shall be provided by the Electrical Contractor. Unless noted otherwise, the control wiring shall be provided by the Contractor furnishing the controlled equipment.
- F. Unless noted otherwise, the Electrical Contractor shall provide all starters, disconnects, switches, push-button stations, etc., except those which are furnished with the equipment as a part of a factory-assembled package. Heater elements for overload relays on magnetic motor starters (except the starters factory pre-wired with equipment) shall be sized, furnished and installed by the Electrical Contractor. Magnetic motor starters for mechanical equipment (except starters factory pre-wired with equipment such as chillers and packaged air conditioners) shall be provided by the Electrical Contractor. Magnetic motor starters will be provided with:
 - 1. Auxiliary contacts as required by the interlocks defined on the drawings or in the specifications.
 - 2. Control Power Transformer - 120 volt secondary, minimum 40 Volt Amps.
- G. Each Contractor furnishing motor-operated equipment shall furnish a list of motor characteristics to the Electrical Contractor so that properly sized heater elements may be provided. The list shall include equipment identification by name and by number, the full load current, locked rotor current, voltage rating, and suggested service factor to compensate for operating duty cycle and ambient temperatures.
- H. Unless specifically noted otherwise, pilot controllers (pressure switches, etc.) shall be furnished and mounted by the Contractor furnishing the controlled equipment.
- I. Unless specifically noted otherwise, control dampers shall be furnished by the Temperature Control Contractor and installed by the Mechanical Contractor.
- J. Electrical Work For Mechanical, Plumbing, and Fire Protection Equipment: Electrical Contractor shall wire all equipment furnished by various contractors in accordance with the following general provisions:
 - 1. Power wiring from panel to motor controllers, relays, etc., and from controller to motor terminals per equipment manufacturer's wiring diagram.
 - 2. Receive, unload, set and align all separately shipped motors. Adjust and align drive and adjust belt tension.
 - 3. Field lubricate all motors prior to initial operation of same.
 - 4. Install individual motor starters specifically called for to be furnished by other Contractors when not a factory pre-wired component.

3.3 PROTECTION OF EQUIPMENT AND WORK

- A. This Contractor shall, at all times, protect and preserve all materials, supplies, equipment, piping, etc., from damage due to weather, corrosion, dirt, vandalism, theft, etc., and shall further provide all enclosures or special protection as indicated by circumstances.
- B. Should any of the materials, equipment, etc., be damaged as a result of his negligence, then this Contractor shall be held responsible for all such damage and costs incurred for repair or replacement.

3.4 CONSTRUCTION STAGING

- A. See schedule in Division 0 and Division 1. This Contractor shall cooperate with and coordinate to plan and schedule the work to satisfy the schedule.

3.5 TEMPORARY POWER AND LIGHTING

- A. Electric power service: Pay electric-power-service use charges and associated metering provisions for electricity used by all entities for construction operations.
- B. Electric service: comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- C. Provide electric power service and distribution system of sufficient size, capacity, and power characteristics required for construction operations.
- D. Lighting: provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
 - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.
- E. Telephone service: provide temporary telephone service in common-use facilities for use by all construction personnel. Install wifi access equipment and one land-based telephone line(s) for each field office.
- F. Electronic communication service: Provide secure wifi wireless connection to internet with provisions for access by architect and owner.

3.6 DEMOLITION

- A. Coordinate the shut-off and disconnection of electrical, fire alarm and communication services with the owner and the utility companies. Coordinate any electrical outages required for service switchovers or connections with the owner a minimum of five working days prior to the interruption. Comply with owner's specific requirements for partial or complete outage requests.

- B. Maintain existing electrical service, electrical distribution, fire alarm and communication equipment in operation until the new electrical service or distribution equipment is energized, tested and accepted.
- C. The intention of the electrical demolition drawings is to disconnect and remove all electrical work made void by the scope of the construction and alteration. Field-verify exact material quantities required to be removed.
- D. The electrical contractor shall remove, cap and/or relocate equipment, outlets, conduit, wire, etc., as shown and specified on drawings and as may become necessary because of existing field conditions. It shall be the responsibility of the electrical contractor to visibly examine all existing walls designated for removal to determine the conduit and the wiring that will require capping and/or removal, whether or not such conditions are indicated on the drawings. The contractor shall be held to having visited the site and considered all existing conditions.
- E. Where the architectural drawings indicate that partitions, walls, ceilings, etc., are to be removed the electrical contractor shall be responsible for removal of all electrical components within those structures including equipment, lighting fixtures, lighting controls, wiring devices, raceways, wiring, electrical systems, etc. See architectural drawings for further detail on demolition scope.
- F. Maintain circuit continuity to all existing fixtures, equipment, outlets, etc., to remain in use whether noted on the plans or not. Field-verify existing items to remain in use. Wiring for existing circuits which must be re-routed or which are partially abandoned, shall be reconnected to service the remaining outlets on the circuit.
- G. Abandoned electrical power distribution equipment, including switchboards, motor controllers, panelboards, lighting fixtures and controls and wiring devices shall be disconnected and removed unless otherwise noted. All supporting equipment for this equipment to be removed, including hangers, supporting rods, ballasts, etc., shall be removed.
- H. Remove all existing electrical work, raceways, and wiring made obsolete by the new work or shown dashed on demolition drawings. Remove back to the source of power unless otherwise noted. While drawings attempt to indicate all such work, total accuracy is not guaranteed. Contractor shall field-verify all areas, including walls and ceilings scheduled for removal, to identify existing electrical items to remain.
- I. Where electrical equipment, conduit, boxes, or supporting hardware are removed, finish the surface to match existing unless otherwise noted. Perform one of the following as applicable
 - 1. For flush devices removed from walls or floors that remain, or for outlets that must remain but with devices removed, install blank covers to match existing covers in the space.
 - 2. Repair all openings created by this work in walls, partitions, ceilings, or floors to match surrounding conditions. Use qualified trades for all finishes. Seal or grout all conduit penetrations through walls.

- J. Replace or reinstall any building elements (ceiling tiles, walls, etc.) Removed to accommodate electrical demolition work. Use qualified trades to match existing conditions.
- K. All removed materials, other than removed materials to be relocated, or stored or turned over to the owner shall become the property of the contractor and shall be removed from the project site in a law abiding manner.
- L. Maintain and restore continuity of all conduits and conductors passing through renovated areas that serve undisturbed areas. Where devices or fixtures are removed, provide junction boxes, extend conduit and wiring, or use other approved methods to ensure circuit continuity.
- M. Remove items indicated, including light fixtures, switches, receptacles, exposed conduit, surface and flush device boxes, device plates, etc. Remove all wiring from existing conduits. Cut back conduit from finished surface and abandon all concealed conduits. Remove conduits above grid type ceilings.
- N. Where buried conduits extending out of a concrete slab become abandoned, cut and grind the conduits off flush with top of slab and plug with non-shrink waterproof grout fill.
- O. All existing conduit, outlets and wire exposed during alterations, that is not serving equipment to remain, shall be removed.
- P. Existing circuits removed during demolition must be marked spare, or identified with new description on circuit directory if reused. Existing active circuits must be verified and accurately labeled on directory. New typed circuit directory must be provided at project completion documenting accurate new circuit conditions which reflect demolition and new work. Spare breakers shall be left in the off position.
- Q. Coordinate electrical demolition with work of other disciplines.

3.7 CLEANING AND CLEANUP

- A. Upon completion of this work, the Contractor shall clean all pipe, ductwork, fixtures, and equipment. Contractor shall leave all work in a finished, clean, and satisfactory working condition.
- B. Each contractor shall be responsible for his own cleanup to a central location designated by the Construction Manager. Contractor shall periodically remove all rubbish, crating, unused material, outfall, and any other debris created by him during the course of the work.

3.8 OWNER TRAINING

- A. Provide Owner training where indicated in the specifications. Video tape training sessions. Save and bookmark to DVD's for future reference.

3.9 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

- A. Coordinate requirements in this Article with Drawings.
- B. Comply with NECA 1.
- C. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.
- D. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange and install components and equipment to provide maximum possible headroom consistent with these requirements.
- E. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.
- F. Right of Way: Give to raceways and piping systems installed at a required slope.
- G. Mounting heights indicated within plans and schedules are dimensioned to the center line of the device, equipment, luminaire, etc. Unless otherwise noted.
- H. Coordinate exact equipment locations with other trades. Equipment locations shown on electrical plans are diagrammatical only and might not be exact.
- I. Install emergency and exit luminaire wiring in a separate raceway from that of any normal power device.
- J. Conceal all conduit in walls, in partitions, and in above ceilings, unless otherwise indicated on the plans or in the specifications. Conduit routed in mechanical rooms, electrical rooms, and storage rooms without ceilings may be routed exposed.
- K. Conceal electrical connections for electric water coolers (ewc) behind water cooler access plate or directly below and centered on wall. Provide a readily accessible GFCI device in circuit breaker panelboard or GFCI when mounted below, prior to installing circuit.
- L. Field coordinate all electrical and telecommunications equipment mounting locations to avoid encroachment of operation and access to equipment from other trades. Coordinate the appropriate mounting location with the affected disciplines when equipment is specified to be mounted onto the surface of another discipline's equipment.
- M. Contractor shall visit job site prior to bidding and verify existing conditions and required work to accomplish construction as depicted in design drawings.
- N. On new work plan, all items shown light are existing to remain. All items shown bold are new/relocated.

- O. Coordinate electrical device installations with final architectural plans and elevations.
- P. All receptacles, switches and junction box covers shall be labeled with panel name and circuit number per owner's standard.
- Q. Provide fire stopping at all conduit penetrations and conduit sleeves through existing floor slabs and fire rated walls to maintain required fire rating. Use ul listed methods and materials or fire-resistance rating of assembly and according to section 07 84 13 "penetration firestopping."
- R. Not all branch circuit conduit and wire is shown on drawings. Only panel names and circuit numbers are shown adjacent to devices. The remaining branch circuit conduit and wires shall be installed according to specifications.
- S. All receptacles within 6 ft of sinks shall be GFI type.
- T. Contractor shall x-ray concrete slabs and walls prior to core drilling to avoid damage to utilities or reinforced steel.
- U. Replace or reinstall all portions of the building (ceiling tiles, walls, etc) removed to accommodate the installation of any electrical device, equipment, etc., using workers qualified in the appropriate trade.
- V. Electrical distribution equipment shall be submitted for approval prior to performing arc flash, short circuit, and coordination studies. Resubmit electrical power distribution equipment for final approval after approval of arc flash, short circuit, and coordination studies.

3.10 SLEEVE INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Electrical penetrations occur when raceways, cables, wireways, cable trays, or busways penetrate concrete slabs, concrete or masonry walls, or fire-rated floor and wall assemblies.
- B. Coordinate sleeve selection and application with selection and application of firestopping.
- C. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.
- D. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
- E. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.
- F. Cut sleeves to length for mounting flush with both surfaces of walls.

- G. Extend sleeves installed in floors 2 inches above finished floor level.
- H. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway or cable unless sleeve seal is to be installed or unless seismic criteria require a different clearance.
- I. Seal space outside of sleeves with grout for penetrations of concrete and masonry and with approved joint compound for gypsum board assemblies.
- J. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint.
- K. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway and cable penetrations. Install sleeves and seal raceway and cable penetration sleeves with firestop materials.
- L. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.
- M. Aboveground, Exterior-Wall Penetrations: Seal penetrations using sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch (25-mm) annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- N. Underground, Exterior-Wall Penetrations: Install cast-iron "wall pipes" for sleeves. Size sleeves to allow for 1-inch annular clear space between raceway or cable and sleeve for installing mechanical sleeve seals.

3.11 SLEEVE-SEAL INSTALLATION

- A. Install to seal underground, exterior wall penetrations.
- B. Use type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.12 FIRESTOPPING

- A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies for all new assemblies and/or to restore original fire-resistance rating of assembly. See Section 7 for requirements.

3.13 UTILITY COMPANY SERVICE

- A. Install equipment according to utility company's written requirements. Provide grounding and empty conduits as required by utility company.

3.14 CONCRETE BASES

- A. Construct concrete bases 4 inches (100 mm), in both directions, than supported unit. Follow supported equipment manufacturer's anchorage recommendations and setting templates for anchor-bolt and tie locations, unless otherwise indicated. Use 3000-psi (20.7-MPa), 28-day compressive-strength concrete and reinforcement as specified in Division 3 Section "Cast-in-Place Concrete."

3.15 EXCAVATION

- A. Slope sides of excavations to comply with local codes and ordinances. Shore and brace as required for stability of excavation.
- B. Shoring and Bracing: Establish requirements for trench shoring and bracing to comply with local codes and authorities. Maintain shoring and bracing in excavations regardless of time period excavations will be open.
 - 1. Remove shoring and bracing when no longer required. Where sheeting is allowed to remain, cut top of sheeting at an elevation of 30 inches below finished grade elevation.
- C. Install sediment and erosion control measures in accordance with local codes and ordinances.
- D. Dewatering: Prevent surface water and subsurface or ground water from flowing into excavations and from flooding project site and surrounding area.
 - 1. Do not allow water to accumulate in excavations. Remove water to prevent softening of bearing materials. Provide and maintain dewatering system components necessary to convey water away from excavations.
 - 2. Establish and maintain temporary drainage ditches and other diversions outside excavation limits to convey surface water to collecting or run-off areas. Do not use trench excavations as temporary drainage ditches.
- E. Material Storage: Stockpile satisfactory excavated materials where directed, until required for backfill or fill. Place, grade, and shape stockpiles for proper drainage.
 - 1. Locate and retain soil materials away from edge of excavations. Do not store within drip-line of trees indicated to remain.
 - 2. Remove and legally dispose of excess excavated materials and materials not acceptable for use as backfill or fill.
- F. Trenching: Excavate trenches for electrical installations as follows:
 - 1. Excavate trenches to the uniform width, sufficiently wide to provide ample working room and a minimum of 6 to 9 inches clearance on both sides of raceways and equipment.

2. Excavate trenches to depth indicated or required.
 3. Limit the length of open trench to that in which installations can be made and the trench backfilled within the same day.
 4. Where rock is encountered, carry excavation below required elevation and backfill with a layer of crushed stone or gravel prior to installation of raceways and equipment. Provide a minimum of 6 inches of stone or gravel cushion between rock bearing surface and electrical installations.
- G. Cold Weather Protection: Protect excavation bottoms against freezing when atmospheric temperature is less than 35 deg F .
- H. Backfilling and Filling: Place soil materials in layers to required subgrade elevations for each area classification listed below, using materials specified in Part 2 of this Section.
1. Under walks and pavements, use a combination of subbase materials and excavated or borrowed materials.
 2. Under building slabs, use drainage fill materials.
 3. Under piping and equipment, use subbase materials where required over rock bearing surface and for correction of unauthorized excavation.
 4. For raceways less than 30 inches below surface of roadways, provide 4-inch-thick concrete base slab support. After installation of raceways, provide a 4-inch thick concrete encasement (sides and top) prior to backfilling and placement of roadway subbase.
 5. Other areas, use excavated or borrowed materials.
- I. Backfill excavations as promptly as work permits, but not until completion of the following:
1. Inspection, testing, approval, and locations of underground utilities have been recorded.
 2. Removal of concrete formwork.
 3. Removal of shoring and bracing, and backfilling of voids.
 4. Removal of trash and debris.
- J. Placement and Compaction: Place backfill and fill materials in layers of not more than 8 inches in loose depth for material compacted by heavy equipment, and not more than 4 inches in loose depth for material compacted by hand-operated tampers.
- K. Before compaction, moisten or aerate each layer as necessary to provide optimum moisture content. Compact each layer to required percentage of maximum dry density or relative dry density for each area classification specified below. Do not place backfill or fill material on surfaces that are muddy, frozen, or contain frost or ice.
- L. Place backfill and fill materials evenly adjacent to structures, piping, and equipment to required elevations. Prevent displacement of raceways and equipment by carrying material uniformly around them to approximately same elevation in each lift.
- M. Compaction: Control soil compaction during construction, providing minimum percentage of density specified for each area classification indicated below.
1. Percentage of Maximum Density Requirements: Compact soil to not less than the following percentages of maximum density for soils which exhibit a

well-defined moisture-density relationship (cohesive soils), determined in accordance with ASTM D 1557 and not less than the following percentages of relative density, determined in accordance with ASTM D 2049, for soils which will not exhibit a well-defined moisture-density relationship (cohesionless soils).

- a. Areas under Structures, Building Slabs and Steps, Pavements: Compact top 12 inches of subgrade and each layer of backfill or fill material to 90 percent maximum density for cohesive material, or 95 percent relative density for cohesionless material.
 - b. Areas Under Walkways: Compact top 6 inches of subgrade and each layer of backfill or fill material to 90 percent maximum density for cohesive material, or 95 percent relative density for cohesionless material.
 - c. Other Areas: Compact top 6 inches of subgrade and each layer of backfill or fill material to 85 percent maximum density for cohesive soils, and 90 percent relative density for cohesionless soils.
2. Moisture Control: Where subgrade or layer of soil material must be moisture conditioned before compaction, uniformly apply water. Apply water in minimum quantity necessary to achieve required moisture content and to prevent water appearing on surface during, or subsequent to, compaction operations.
-
- N. Subsidence: Where subsidence occurs at electrical installation excavations during the period 12 months after Substantial Completion, remove surface treatment (i.e., pavement, lawn, or other finish), add backfill material, compact to specified conditions, and replace surface treatment. Restore appearance, quality, and condition of surface or finish to match adjacent areas.

3.16 FIELD QUALITY CONTROL

- A. Inspect installed sleeve and sleeve-seal installations and associated firestopping for damage and faulty work.

END OF SECTION 26 00 00

SECTION 26 05 19 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

A. Section Includes:

1. Copper building wire.
2. Metal-clad cable, Type MC.
3. Fire-alarm wire and cable – refer to Division 28 31 11
4. Connectors and splices.

B. Related Requirements:

1. Section 26 00 010 "Electrical General Requirements" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. 26 00 11Section 27 13 1300 "Communications Copper Backbone Cabling" for twisted pair cabling used for data circuits.
3. Section 27 15 1300 "Communications Copper Horizontal Cabling" for twisted pair cabling used for data circuits.

1.3 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

PART 2 - PRODUCTS

2.1 COPPER BUILDING WIRE

- A. Description: Flexible, insulated and uninsulated, drawn copper current-carrying conductor with an overall insulation layer or jacket, or both, rated 600 V or less.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Alcan Products Corporation; Alcan Cable Division.
 - 2. American Insulated Wire Corp.; a Leviton Company.
 - 3. General Cable Corporation.
 - 4. Okonite
 - 5. Senator Wire & Cable Company.
 - 6. Southwire Company.
- C. Standards:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
 - 2. RoHS compliant
 - 3. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."
- D. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.
- E. Conductor Insulation:
 - 1. Type TC-ER. Comply with NEMA WC 70/ICEA S-95-658 and UL 1277.
 - 2. Type THHN and Type THWN-2. Comply with UL 83.
 - 3. Type THW and Type THW-2. Comply with NEMA WC-70/ICEA S-95-658 and UL 83.
 - 4. Type UF. Comply with UL 83 and UL 493.
 - 5. Type XHHW-2. Comply with UL 44.

2.2 METAL-CLAD CABLE, TYPE MC

- A. Description: A factory assembly of one or more current-carrying insulated conductors in an overall metallic sheath.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. American Insulated Wire Corp.; a Leviton Company.
 - 2. General Cable Corporation.
 - 3. Okonite
 - 4. Senator Wire & Cable Company.

5. Southwire Company.

C. Standards:

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
2. Comply with UL 1569.
3. RoHS compliant.
4. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."

D. Circuits:

1. Single circuit and multicircuit with color-coded conductors.
2. Power-Limited Fire-Alarm Circuits: Comply with UL 1424.

E. Conductors: Copper, complying with ASTM B3 for bare annealed copper and with ASTM B8 for stranded conductors.

F. Ground Conductor: Insulated.

G. Conductor Insulation:

1. Type TFN/THHN/THWN-2. Comply with UL 83.
2. Type XHHW-2. Comply with UL 44.

H. Armor: Steel or Aluminum, interlocked.

I. Approved use of metal clad cable is limited. Refer to Part 3 of this specification for permitted uses.

2.3 CONNECTORS AND SPLICES

A. Description: Factory-fabricated connectors, splices, and lugs of size, ampacity rating, material, type, and class for application and service indicated; listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.

B. Jacketed Cable Connectors: For steel and aluminum jacketed cables, zinc die-cast with set screws, designed to connect conductors specified in this Section.

C. Lugs: One piece, seamless, designed to terminate conductors specified in this Section.

1. Material: Copper Aluminum.
2. Type: Two hole with standard barrels.
3. Termination: Compression.

PART 3 - EXECUTION

3.1 CONDUCTOR MATERIAL APPLICATIONS

- A. Feeders:
 - 1. Copper; solid or stranded for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- B. Branch Circuits:
 - 1. Copper. Solid or stranded for No. 10 AWG and smaller; stranded for No. 8 AWG and larger.
- C. ASD Output Circuits Cable: Extra-flexible stranded for all sizes.

3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Service Entrance: Type THHN/THWN-2, single conductors in raceway Type XHHW-2, single conductors in raceway.
- B. Exposed Feeders: Type THHN/THWN-2, single conductors in raceway Type XHHW-2, single conductors in raceway.
- C. Feeders Concealed in Ceilings, Walls, Partitions, and Crawlspace: Type THHN/THWN-2, single conductors in raceway.
- D. Exposed Branch Circuits,: Type THHN/THWN-2, single conductors in raceway. .
- E. Exposed Branch Circuits, in Crawlspace: Type THHN/THWN-2, single conductors in raceway. Metal-clad cable, Type MC .
- F. Branch Circuits Concealed in Inaccessible Ceilings, Walls, and Partitions: Type THHN/THWN-2, single conductors in raceway Metal-clad cable, Type MC.
- G. Branch Circuits Concealed in Above Accessible Ceilings: Type THHN/THWN-2, single conductors in raceway. Metal-clad cable, Type MC. Refer to Part 3 METAL CLAD (MC) CABLE INSTALLATION below.
- H. Cord Drops and Portable Appliance Connections: Type SO, hard service cord with stainless steel, wire-mesh, strain relief device at terminations to suit application.
- I. ASD/VFD Output Circuits: Type XHHW-2 in metal conduit Type TC-ER cable with dual tape shield.
- J. METAL CLAD (MC) CABLE INSTALLATION
 - 1. A. Metal clad cables may be utilized for 20A and 15A branch circuit wiring as defined in NFPA 70, Article 330 subject to acceptance by State and Local Codes.

MC cable is not allowed for feeders or feeder circuits to panelboards. Feeder wiring must consist of individual insulated conductors in conduit.

2. Metal clad cable installations shall comply with the requirements stipulated within Article 330 of the National Electrical Code.
3. Provide individual insulated conductors in conduit from branch panelboard to junction box(es) located above the ceiling in the same room as the final device(s) or luminaire(s) being served.
 - a. Metal clad cable is permitted to be extended from this junction box to electrical devices and luminaires in the same room where all other requirements of this specification are met. Horizontal length of metal clad cable extending from the local room junction box to the final in-wall device shall not exceed 50 feet.
 - b. In rooms or spaces with inaccessible ceilings, the aforementioned junction box may be located in the nearest accessible ceiling, corridor preferred.

Metal clad cable is allowed for flexible connection to luminaires in lengths not to exceed 6'-0" and allowed to be daisy chained with no more than two MC cables terminated per luminaire.
4. Metal clad cable is allowed for branch circuits of 20 amperes and less when run from a junction box located above an accessible ceiling, within 8 feet of the partition containing the served wiring device box (or within 6 feet of a lighting fixture). Wiring between the above junction box and the panelboard shall consist of individual conductors in conduit.
5. Metal clad cable runs shall be from a junction box to the final device or luminaire and shall not exceed 50'-0" between connections.

3.3 INSTALLATION, GENERAL

- A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.
- B. Complete raceway installation between conductor and cable termination points in accordance with Division 26 "Conduits for Electrical Systems" prior to pulling conductors and cables.
- C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Section 26 05 29 "Hangers and Supports for Electrical Systems."
- G. Complete cable tray systems installation according to Section 26 05 36 "Cable Trays for Electrical Systems" prior to installing conductors and cables.

3.4 27 05 28 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
 - 1. Use oxide inhibitor in each splice, termination, and taps.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inch of slack.

3.5 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 26 05 53 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

3.6 FIELD QUALITY CONTROL

- A. Tests and Inspections:
 - 1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors for compliance with requirements.
 - 2. Perform each of the following visual and electrical tests:
 - a. Inspect exposed sections of conductor and cable for physical damage and correct connection according to the single-line diagram.
 - b. Test bolted connections for high resistance using one of the following:
 - 1) A low-resistance ohmmeter.
 - 2) Calibrated torque wrench.
 - c. Inspect compression-applied connectors for correct cable match and indentation.
 - d. Inspect for correct identification.
 - e. Inspect cable jacket and condition.
 - f. Insulation-resistance test on each conductor for ground and adjacent conductors. Apply a potential of 500 V(dc) for 300 V rated cable and 1000 V(dc) for 600 V rated cable for a one-minute duration.
 - g. Continuity test on each conductor and cable.
 - h. Uniform resistance of parallel conductors.

- B. Cables will be considered defective if they do not pass tests and inspections.
- C. Prepare test and inspection reports to record the following:
 - 1. Procedures used.
 - 2. Results that comply with requirements.
 - 3. Results that do not comply with requirements, and corrective action taken to achieve compliance with requirements.

END OF SECTION 26 05 19

This page intentionally left blank.

SECTION 26 05 26 - GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Grounding and bonding conductors.
2. Grounding and bonding clamps.
3. Grounding and bonding bushings.
4. Grounding and bonding hubs.
5. Grounding and bonding connectors.
6. Grounding and bonding busbars.
7. Grounding (earthing) electrodes.

B. Related Requirements:

1. Section 26 00 1000 "Electrical General Requirements" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 26 00 110548 "Vibration and Seismic Control for Electrical Systems" for seismic-load, wind-load, acoustical, and other field conditions applicable to Work specified in this Section.
3. Section 26 41 13 "Lightning Protection System" for interconnections between electrical service grounding and lightning protection ground conductors.

1.2 ACTION SUBMITTALS

A. Product Data:

1. For each type of product indicated.

B. Shop Drawings: Plans showing dimensioned locations of grounding features described in "Field Quality Control" Article, including the following:

1. Rod electrodes.
2. Grounding arrangements and connections for separately derived systems.

C. Field Quality-Control Submittals:

1. Field quality-control reports.

1.3 CLOSEOUT SUBMITTALS

PART 2 - PRODUCTS

2.1 GROUNDING AND BONDING CONDUCTORS

A. Equipment Grounding Conductor:

1. General Characteristics: 600 V, THHN/THWN-2, copper wire or cable, green color, in accordance with Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."

B. ASTM - Bare Copper Grounding and Bonding Conductor:

1. Referenced Standards: Complying with one or more of the following:
 - a. Soft or Annealed Copper Wire: ASTM B3
 - b. Concentric-Lay Stranded Copper Conductor: ASTM B8.
 - c. 19-Wire Combination Unilay-Stranded Copper Conductor: ASTM B787/B787M.

2.2 GROUNDING AND BONDING CLAMPS

A. Description: Clamps suitable for attachment of grounding and bonding conductors to grounding electrodes, pipes, tubing, and rebar. Grounding and bonding clamps specified in this article are also suitable for use with communications applications; see Section 27 05 26 "Grounding and Bonding for Communications Systems," for selection and installation guidelines.

B. Source Limitations: Obtain products from single manufacturer.

C. Performance Criteria:

1. Regulatory Requirements:

- a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. Listing Criteria:

- a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
- b. Grounding and Bonding Equipment for Communications: UL CCN KDSH; including UL 467.

D. UL KDER and KDSH - Hex-Fitting-Type Pipe and Rod Grounding and Bonding Clamp:

1. General Characteristics:

- a. Two pieces with zinc-plated bolts.

- b. Clamp Material: Brass Tinned brass.
 - c. Listed for outdoor use.
- E. UL KDER and KDSH - U-Bolt-Type Pipe and Rod Grounding and Bonding Clamp:
 - 1. General Characteristics:
 - a. Clamp Material: Brass Tinned brass.
 - b. Listed for outdoor use.
- F. UL KDER and KDSH - Strap-Type Pipe and Rod Grounding and Bonding Clamp:
 - 1. General Characteristics:
 - a. Clamp Material: Copper Tinned copper.
 - b. Listed for outdoor use.
- G. UL KDER - Beam Grounding and Bonding Clamp:
 - 1. General Characteristics: Mechanical-type, terminal, ground wire access from four directions; with dual, tin-plated or silicon bronze bolts.
- H. UL KDER - Exothermically Welded Connection:
 - 1. General Characteristics: Exothermic-welding kits of types recommended by kit manufacturer for materials being joined and installation conditions.

2.3 GROUNDING AND BONDING BUSHINGS

- A. Description: Bonding bushings connect conduit fittings, tubing fittings, threaded metal conduit, and unthreaded metal conduit to metal boxes and equipment enclosures, and have one or more bonding screws intended to provide electrical continuity between bushing and enclosure. Grounding bushings have provision for connection of bonding or grounding conductor and may or may not also have bonding screws.
- B. Source Limitations: Obtain products from single manufacturer.
- C. Performance Criteria:
 - 1. Regulatory Requirements:
 - a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. Listing Criteria:
 - a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
- D. UL KDER - Bonding Bushing:
 - 1. General Characteristics: Threaded bushing with insulated throat.
- E. UL KDER - Grounding Bushing:

1. General Characteristics: Threaded bushing with insulated throat and mechanical-type wire terminal.

2.4 GROUNDING AND BONDING HUBS

- A. Description: Hubs with certified grounding or bonding locknut.
- B. Source Limitations: Obtain products from single manufacturer.
- C. Performance Criteria:
 1. Regulatory Requirements:
 - a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 2. Listing Criteria:
 - a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
- D. UL KDER - Grounding and Bonding Hub:
 1. General Characteristics: Insulated, gasketed, watertight hub with mechanical-type wire terminal.

2.5 GROUNDING AND BONDING CONNECTORS

- A. Source Limitations: Obtain products from single manufacturer.
- B. Performance Criteria:
 1. Regulatory Requirements:
 - a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 2. Listing Criteria:
 - a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
 - b. Grounding and Bonding Equipment for Communications: UL CCN KDSH; including UL 467.
- C. UL KDER - Pressure-Type Grounding and Bonding Busbar Cable Connector:
 1. General Characteristics: Copper or copper alloy, for compression bonding of one or more conductor directly to copper busbar. Listed for direct burial.
- D. UL KDER - Lay-In Lug Mechanical-Type Grounding and Bonding Busbar Terminal:

1. General Characteristics: Mechanical-type, copper rated for direct burial terminal with set screw.
- E. UL KDER - Crimped Pressure-Type Grounding and Bonding Cable Connector:
1. General Characteristics: Crimp-and-compress connectors that bond to conductor when connector is compressed around conductor.
 - a. Copper, C and H shaped.
- F. UL KDER - Split-Bolt Pressure-Type Grounding and Bonding Cable Connector:
1. General Characteristics: Bolts that surround cable and bond to cable under compression when nut is tightened.
 - a. Copper Tinned copper.

2.6 GROUNDING AND BONDING BUSBARS

- A. Description: Miscellaneous grounding and bonding device that serves as common connection for multiple grounding and bonding conductors.
- B. Source Limitations: Obtain products from single manufacturer.
- C. Performance Criteria:
1. Regulatory Requirements:
 - a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 2. Listing Criteria:
 - a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
- D. UL KDER - Equipment Room Grounding and Bonding Busbar:
1. General Characteristics:
 - a. Bus: Rectangular bar of annealed copper.
 - b. Mounting Stand-Off Insulators: Lexan or PVC.
 - 1) Comply with UL 891 for use in 600 V switchboards, impulse tested at 5000 V.
 2. Options:
 - a. Dimensions: 1/4 by 4 inch length as indicated on Drawings.
 - b. Predrilled Hole Pattern: Suitable for installing specified grounding and bonding connectors.
 - c. Mounting Hardware: Stand-off brackets that provide 2 inch clearance to access rear of bus. Brackets and bolts must be stainless steel.

2.7 GROUNDING (EARTHING) ELECTRODES

- A. Description: Grounding electrodes include rod electrodes, ring electrodes, metal underground water pipes, metal building frames, concrete-encased electrodes, and pipe and plate electrodes.
- B. Source Limitations: Obtain products from single manufacturer.
- C. Performance Criteria:
 - 1. Regulatory Requirements:
 - a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. Listing Criteria:
 - a. Grounding and Bonding Equipment: UL CCN KDER; including UL 467.
- D. UL KDER - Rod Electrode
 - 1. General Characteristics: Copper-clad steel; 3/4 inch by 10 ft

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine facility's grounding electrode system and equipment grounding for compliance with requirements for maximum ground-resistance level and other conditions affecting performance of grounding and bonding of electrical system.
- B. Inspect test results of grounding system measured at point of electrical service equipment connection.
- C. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
- D. Proceed with connection of electrical service equipment only after unsatisfactory conditions have been corrected.

3.2 SELECTION OF BUSBARS

- A. Grounding Bus: Install in electrical equipment rooms, in rooms housing service equipment, and elsewhere as indicated.
 - 1. Install bus horizontally, on insulated spacers 2 inch minimum from wall, 6 inch above finished floor unless otherwise indicated.

2. Where indicated on both sides of doorways, route bus up to top of door frame, across top of doorway, and down; connect to horizontal bus.

3.3 SELECTION OF GROUNDING AND BONDING CONDUCTORS

- A. Conductors: Install solid conductor for 8 AWG and smaller, and stranded conductors for 6 AWG and larger unless otherwise indicated.
- B. Custom-Length Insulated Equipment Bonding Jumpers: 6 AWG, 19-strand, Type THHN.
- C. Bonding Cable: 28 kcmil, 14 strands of 17 AWG conductor, 1/4 inch in diameter.
- D. Bonding Conductor: 4 AWG or 6 AWG, stranded conductor.
- E. Bonding Jumper: Copper tape, braided conductors terminated with copper ferrules; 1-5/8 inch wide and 1/16 inch thick.
- F. Tinned Bonding Jumper: Tinned-copper tape, braided conductors terminated with copper ferrules; 1-5/8 inch wide and 1/16 inch thick.
- G. Underground Grounding Conductors: Install bare copper conductor, 2/0 AWG minimum.
 1. Bury at least 30 inch below grade.
 2. Duct-Bank Grounding Conductor: Bury 12 inch above duct bank when indicated as part of duct-bank installation.

3.4 SELECTION OF CONNECTORS

- A. Conductor Terminations and Connections:
 1. Pipe and Equipment Grounding Conductor Terminations: Bolted connectors.
 2. Underground Connections: Welded connectors except at test wells and as otherwise indicated.
 3. Connections to Structural Steel: Welded connectors.

3.5 INSTALLATION

- A. Comply with manufacturer's published instructions.
- B. Reference Standards:
 1. Ground Bonding Common with Lightning Protection System: Comply with NFPA 780 and UL 96 when interconnecting with lightning protection system. Bond electrical power system ground directly to lightning protection system grounding conductor at closest point to electrical service grounding electrode.

Use bonding conductor sized same as system grounding electrode conductor, and install in conduit.

2. Consult Architect for resolution of conflicting requirements.

C. Special Techniques:

1. Conductors:

- a. Route along shortest and straightest paths possible unless otherwise indicated or required by Code. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage.

2. Connections: Make connections so possibility of galvanic action or electrolysis is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact are galvanically compatible.

- a. Use electroplated or hot-tin-coated materials to ensure high conductivity and to make contact points closer in order of galvanic series.
- b. Make connections with clean, bare metal at points of contact.
- c. Make aluminum-to-steel connections with stainless steel separators and mechanical clamps.
- d. Make aluminum-to-galvanized-steel connections with tin-plated copper jumpers and mechanical clamps.
- e. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.
- f. Bonding Straps and Jumpers: Install in locations accessible for inspection and maintenance except where routed through short lengths of conduit.

- 1) Bonding to Structure: Bond straps directly to basic structure, taking care not to penetrate adjacent parts.
- 2) Bonding to Equipment Mounted on Vibration Isolation Hangers and Supports: Install bonding so vibration is not transmitted to rigidly mounted equipment.
- 3) Use exothermic-welded connectors for outdoor locations; if disconnect-type connection is required, use bolted clamp.

- g. Grounding and Bonding for Piping:

- 1) Metal Water Service Pipe: Install insulated copper grounding conductors, in conduit, from building's main service equipment, or grounding bus, to main metal water service entrances to building. Connect grounding conductors to main metal water service pipes; use bolted clamp connector or bolt lug-type connector to pipe flange by using one of lug bolts of flange. Where dielectric main water fitting is installed, connect grounding conductor on street side of fitting. Bond metal grounding conductor conduit or sleeve to conductor at each end.
- 2) Water Meter Piping: Use braided-type bonding jumpers to electrically bypass water meters. Connect to pipe with bolted connector.

- 3) Bond each aboveground portion of gas piping system downstream from equipment shutoff valve.
- h. Bonding Interior Metal Ducts: Bond metal air ducts to equipment grounding conductors of associated fans, blowers, electric heaters, and air cleaners. Install bonding jumper to bond across flexible duct connections to achieve continuity.
 - i. Grounding for Steel Building Structure: Install driven ground rod at base of each corner column and at intermediate exterior columns at distances not more than 60 ft apart.
- 3. Electrodes:
 - a. Ground Rods: Drive rods until tops are 2 inch below finished floor or final grade unless otherwise indicated.
 - 1) Interconnect ground rods with grounding electrode conductor below grade and as otherwise indicated. Make connections without exposing steel or damaging coating if any.
 - 2) Use exothermic welds for below-grade connections.
 - b. For grounding electrode system, install at least three rods spaced at least one-rod length from each other and located at least same distance from other grounding electrodes, and connect to service grounding electrode conductor.
- 4. Grounding at Service:
 - a. Equipment grounding conductors and grounding electrode conductors must be connected to ground bus. Install main bonding jumper between neutral and ground buses.
- 5. Grounding Separately Derived Systems:
 - a. Generator: Install grounding electrode(s) at generator location. Electrode must be connected to equipment grounding conductor and to frame of generator.
- 6. Grounding Underground Distribution System Components:
 - a. Duct-Bank Grounding Conductor: Bury 12 inch above duct bank when indicated as part of duct-bank installation.
 - b. Comply with IEEE C2 grounding requirements.
 - c. Pad-Mounted Transformers and Switches: Install two ground rods and ring electrode around pad. Ground pad-mounted equipment and noncurrent-carrying metal items associated with substations by connecting them to underground cable and grounding electrodes. Install tinned-copper conductor not less than 2 AWG for ring electrode and for taps to equipment grounding terminals. Bury ring electrode not less than 6 inch from foundation.

7. Equipment Grounding:

- a. Install insulated equipment grounding conductors with all feeders and branch circuits.
- b. Air-Duct Equipment Circuits: Install insulated equipment grounding conductor to duct-mounted electrical devices operating at 120 V and more, including air cleaners, heaters, dampers, humidifiers, and other duct electrical equipment. Bond conductor to each unit and to air duct and connected metallic piping.
- c. Water Heater, Heat-Tracing, and Antifrost Heating Cables: Install separate insulated equipment grounding conductor to each electric water heater and heat-tracing cable. Bond conductor to heater units, piping, connected equipment, and components.
- d. Poles Supporting Outdoor Lighting Fixtures: Install grounding electrode and separate insulated equipment grounding conductor in addition to grounding conductor installed with branch-circuit conductors.

3.6 FIELD QUALITY CONTROL

A. Field tests and inspections must be witnessed by Tenant.

B. Tests and Inspections:

1. After installing grounding system but before permanent electrical circuits have been energized, test for compliance with requirements.
2. Inspect physical and mechanical condition. Verify tightness of accessible, bolted, electrical connections with calibrated torque wrench in accordance with manufacturer's published instructions.
3. Test completed grounding system at each location where maximum ground-resistance level is specified, at service disconnect enclosure grounding terminal, at ground test wells. Make tests at ground rods before conductors are connected.
 - a. Measure ground resistance no fewer than two full days after last trace of precipitation and without soil being moistened by means other than natural drainage or seepage and without chemical treatment or other artificial means of reducing natural ground resistance.
 - b. Perform tests by fall-of-potential method in accordance with IEEE Std 81.
 - c. Excessive Ground Resistance: If resistance to ground exceeds specified values, notify Architect promptly and include recommendations to reduce ground resistance.
4. Prepare dimensioned Drawings locating each test well, ground rod and ground-rod assembly, and other grounding electrodes. Identify each by letter in alphabetical order, and key to record of tests and observations. Include number of rods driven and their depth at each location, and include observations of weather and other phenomena that may affect test results. Describe measures taken to improve test results.

C. Nonconforming Work:

1. Grounding system will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective components and retest.

D. Collect, assemble, and submit test and inspection reports.

1. Report measured ground resistances that exceed the following values:
 - a. Power and Lighting Equipment or System with Capacity of 500 kVA and Less: 10 Ω .
 - b. Pad-Mounted Equipment: 5 Ω .

3.7 PROTECTION

- A. After installation, protect grounding and bonding cables and equipment from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION 26 05 26

This page intentionally left blank.

SECTION 26 05 29 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Support, anchorage, and attachment components.
2. Fabricated metal equipment support assemblies.

B. Related Requirements:

1. Section 26 00 00 "Electrical General Requirements " for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 26 00 11 ACTION SUBMITTALS

A. Shop Drawings: For fabrication and installation details for electrical hangers and support systems.

1. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Engage a qualified structural professional engineer to design hanger and support system.

2.2 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

A. Steel Slotted Support Systems: Preformed steel channels and angles with minimum 13/32 inch diameter holes at a maximum of 8 inch on center in at least one surface.

1. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
2. Material for Channel, Fittings, and Accessories: Galvanized steel.
3. Channel Width: Selected for applicable load criteria.
4. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
5. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.

6. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Aluminum Slotted Support Systems: Extruded-aluminum channels and angles with minimum 13/32 inch diameter holes at a maximum of 8 inch on center in at least one surface.
1. Standard: Comply with MFMA-4 factory-fabricated components for field assembly.
 2. Channel Material: 6063-T5 aluminum alloy.
 3. Fittings and Accessories Material: 5052-H32 aluminum alloy.
 4. Channel Width: Selected for applicable load criteria.
 5. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
 6. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
 7. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- C. Conduit and Cable Support Devices: Steel and malleable-iron hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- D. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for nonarmored electrical conductors or cables in riser conduits. Plugs must have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body must be made of malleable iron.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A36/A36M steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
 3. Concrete Inserts: Steel or malleable-iron, slotted support system units are similar to MSS Type 18 units and comply with MFMA-4 or MSS SP-58.
 4. Clamps for Attachment to Steel Structural Elements: MSS SP-58 units are suitable for attached structural element.
 5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM F3125/F3125M, Grade A325.
 6. Toggle Bolts: All steel springhead type.
 7. Hanger Rods: Threaded steel.

2.3 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.

PART 3 - 05 50 00EXECUTION

3.1 SELECTION

- A. Comply with the following standards for selection and installation of hangers and supports, except where requirements on Drawings or in this Section are stricter:
 - 1. NECA NEIS 101
 - 2. NECA NEIS 102.
 - 3. NECA NEIS 105.
- B. Comply with requirements in Section 07 84 13 "Penetration Firestopping" for firestopping materials and installation for penetrations through fire-rated walls, ceilings, and assemblies.
- C. Comply with requirements for raceways specified in Section 26 05 33.13 "Conduits for Electrical Systems."
- D. Comply with requirements for boxes specified in Section 26 05 33.16 "Boxes and Covers for Electrical Systems."
- E. Provide vibration and seismic controls with hangers and supports in accordance with requirements specified in "Section 26 05 48 "Vibration and Seismic Controls for Electrical Systems."
- F. Maximum Support Spacing and Minimum Hanger Rod Size for Raceways: Space supports for EMT and ERMC as required by NFPA 70. Minimum rod size must be 1/4 inch in diameter.
- G. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
 - 1. Secure raceways and cables to these supports with single-bolt conduit clamps using spring friction action for retention in support channel.
- H. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1inch and smaller raceways serving branch circuits and communication systems above suspended ceilings, and for fastening raceways to trapeze supports.

3.2 INSTALLATION OF SUPPORTS

- A. Comply with NECA NEIS 101 for installation requirements except as specified in this article.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination must be weight of supported components plus 200 lb.
- C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
 - 1. To Wood: Fasten with lag screws or through bolts.
 - 2. To New Concrete: Bolt to concrete inserts.
 - 3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
 - 4. To Existing Concrete: Expansion anchor fasteners.
 - 5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inch thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inch thick.
 - 6. To Steel: Welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts or Beam clamps (MSS SP-58, Type 19, 21, 23, 25, or 27), complying with MSS SP-69 or Spring-tension clamps.
 - 7. To Light Steel: Sheet metal screws.
 - 8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that comply with seismic-restraint strength and anchorage requirements.
- D. Drill holes for expansion anchors in concrete at locations and to depths that avoid the need for reinforcing bars.

3.3 INSTALLATION OF FABRICATED METAL SUPPORTS

- A. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.

3.4 CONCRETE BASES

- A. Construct concrete bases of dimensions indicated, but not less than 4 inch larger in both directions than supported unit, and so anchors will be a minimum of 10 bolt diameters from edge of the base.

- B. Use 3000 psi, 28-day compressive-strength concrete. Concrete materials, reinforcement, and placement requirements are specified in Section 03 30 00 "Cast-in-Place Concrete."
- C. Anchor equipment to concrete base as follows:
 - 1. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 2. Install anchor bolts to elevations required for proper attachment to supported equipment.
 - 3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.

END OF SECTION 26 05 29

This page intentionally left blank.

SECTION 26 05 33.13 - CONDUITS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Type EMT-S duct raceways and elbows.
2. Type ERM-C-S duct raceways, elbows, couplings, and nipples.
3. Type FMC-S and Type FMC-A duct raceways.
4. Type FMT duct raceways.
5. Type LFMC duct raceways.
6. Type LFNC duct raceways.
7. Type PVC duct raceways and fittings.
8. Fittings for conduit, tubing, and cable.
9. Electrically conductive corrosion-resistant compounds for threaded conduit.
10. Solvent cements.

B. Products Installed, but Not Furnished, under This Section:

1. See Section 26 05 53 "Identification for Electrical Systems" for electrical equipment labels.

C. Related Requirements:

1. Section 26 00 1000 "Electrical General Requirements " for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 26 00 1126 05 48 "Vibration and Seismic Controls for Electrical Systems" for seismic-load, and field conditions applicable to Work specified in this Section.

1.2 26 05 19 DEFINITIONS

A. Conduit: A structure containing one or more duct raceways.

B. Duct Raceway: A single enclosed raceway for conductors or cable.

C. Duct Bank: An arrangement of conduit providing one or more continuous duct raceways between two points.

1.3 ACTION SUBMITTALS

A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the

Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

PART 2 - PRODUCTS

2.1 01 60 0001 60 00TYPE EMT-S DUCT RACEWAYS AND ELBOWS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN FJMX; including UL 797.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL FJMX - Steel Electrical Metal Tubing (EMT-S) and Elbows:

1. Material: Steel.
2. Options:
 - a. Exterior Coating: Zinc.
 - b. Interior Coating: Zinc with organic top coating .
 - c. Minimum Trade Size: Metric designator 21 (trade size 3/4).

2.2 26 00 11TYPE ERM-C-S DUCT RACEWAYS, ELBOWS, COUPLINGS, AND NIPPLES

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN DYIX; including UL 6.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

- C. UL DYIX - Galvanized-Steel Electrical Rigid Metal Conduit (ERMC-S-G), Elbows, Couplings, and Nipples:
 - 1. Exterior Coating: Zinc.
 - 2. Options:
 - a. Interior Coating: Zinc.
 - b. Minimum Trade Size: Metric designator 21 (trade size 3/4).

2.3 TYPE FMC-S AND TYPE FMC-A DUCT RACEWAYS

- A. Performance Criteria:
 - 1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. Listing Criteria: UL CCN DXUZ; including UL 1.
- B. Source Quality Control:
 - 1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
 - 2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.
- C. UL DXUZ - Steel Flexible Metal Conduit (FMC-S):
 - 1. Material: Steel.
 - 2. Options:
 - a. Minimum Trade Size: Metric designator 21 (trade size 3/4).
- D. UL DXUZ - Aluminum Flexible Metal Conduit (FMC-A):
 - 1. Options:
 - a. Minimum Trade Size: Metric designator 21 (trade size 3/4).

2.4 TYPE FMT DUCT RACEWAYS

- A. Performance Criteria:
 - 1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. Listing Criteria: UL CCN ILJW; including UL Subject 1652.
- B. Source Quality Control:
 - 1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
 - 2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL ILJW - Steel Flexible Metallic Tubing (FMT):

1. Options:

- a. Minimum Trade Size: Metric designator 21 (trade size 3/4).

2.5 TYPE LFMC DUCT RACEWAYS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN DXHR; including UL 360.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

C. UL DXHR - Steel Liquidtight Flexible Metal Conduit (LFMC-S):

1. Material: Steel.
2. Options:

- a. Minimum Trade Size: Metric designator 21 (trade size 3/4).

2.6 TYPE LFNC DUCT RACEWAYS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN DXOQ; including UL 1660.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

2.7 TYPE PVC DUCT RACEWAYS AND FITTINGS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 2. Listing Criteria: UL CCN DZYR; including UL 651.
- B. Source Quality Control:
1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
 2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.
- C. UL DZYR - Schedule 40 Rigid PVC Conduit (PVC-40) and Fittings:
1. Dimensional Specifications: Schedule 40.
 2. Options:
 - a. Minimum Trade Size: Metric designator 21 (trade size 3/4).
 - b. Markings: For use with maximum 90 deg C wire.
- D. UL DZYR - Schedule 80 Rigid PVC Conduit (PVC-80) and Fittings:
1. Dimensional Specifications: Schedule 80.
 2. Options:
 - a. Minimum Trade Size: Metric designator 21 (trade size 3/4).
 - b. Markings: For use with maximum 90 deg C wire.
- E. UL DZYR - Type A Rigid PVC Concrete-Encased Conduit (PVC-A) and Fittings:
1. Dimensional Specifications: Type A.
 2. Options:
 - a. Minimum Trade Size: Metric designator 21 (trade size 3/4).

2.8 FITTINGS FOR CONDUIT, TUBING, AND CABLE

- A. Performance Criteria:
1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
- B. Source Quality Control:
1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
 2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.
- C. UL FKAV - Fittings for Type EMT Duct Raceways:
1. Listing Criteria: UL CCN FKAV; including UL 514B.
 2. Options:

- a. Material: Steel.
 - b. Coupling Method: Compression coupling or Setscrew coupling. Setscrew couplings with only single screw per conduit are unacceptable.
 - c. Expansion and Deflection Fittings: UL 651 with flexible bonding jumper.
- D. UL ILNR - Fittings for Type FMC Duct Raceways:
 - 1. Listing Criteria: UL CCN ILNR; including UL 514B.
- E. UL DXAS - Fittings for Type LFMC and Type LFNC Duct Raceways:
 - 1. Listing Criteria: UL CCN DXAS; including UL 514B.

2.9 SOLVENT CEMENTS

- A. Performance Criteria:
 - 1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. Listing Criteria: UL CCN DWTT; including UL 514B.
- B. Source Quality Control:
 - 1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
 - 2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.

PART 3 - EXECUTION

3.1 SELECTION OF CONDUITS FOR ELECTRICAL SYSTEMS

- A. Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NFPA 70 for selection of duct raceways. Consult Architect for resolution of conflicting requirements.
- B. Outdoors:
 - 1. Exposed and Subject to Severe Physical Damage: ERM.
 - 2. Exposed and Subject to Physical Damage: ERM.
 - a. Locations less than 2.5 m (8 ft) above finished floor.
 - 3. Exposed and Not Subject to Physical Damage: ERM PVC-80.
 - 4. Concealed Aboveground: EMT.
 - 5. Direct Buried: PVC-40.
 - 6. Concrete Encased Not in Trench: PVC-80.
 - 7. Concrete Encased in Trench: PVC-80.

8. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.

C. Indoors:

1. Hazardous Classified Locations: ERM.
2. Exposed and Subject to Severe Physical Damage: ERM. Locations include the following:
 - a. Loading docks.
 - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
 - c. Mechanical rooms.
 - d. Gymnasiums.
3. Exposed and Subject to Physical Damage: ERM. Locations include the following:
 - a. Locations less than 2.5 m (8 ft) above finished floor.
 - b. Stub-ups to above suspended ceilings.
4. Exposed and Not Subject to Physical Damage: EMT.
5. Concealed in Ceilings and Interior Walls and Partitions: EMT.
6. Damp or Wet Locations: Corrosion-resistant EMT.
7. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.

D. Duct Fittings: Select fittings in accordance with NEMA FB 2.10 guidelines.

1. ERM: Provide threaded-type fittings unless otherwise indicated.

3.2 INSTALLATION OF CONDUITS FOR ELECTRICAL SYSTEMS

A. Comply with manufacturer's published instructions.

B. Reference Standards for Installation: Unless more stringent installation requirements are specified in Contract Documents or manufacturers' published instructions, comply with the following:

1. Type EMT-S: Article 358 of NFPA 70 and NECA NEIS 101.
2. Type ERM-S: Article 344 of NFPA 70 and NECA NEIS 101.
3. Type FMC-S: Article 348 of NFPA 70 and NECA NEIS 101.
4. Type FMC-A: Article 348 of NFPA 70 and NECA NEIS 102.
5. Type FMT: Article 360 of NFPA 70 and NECA NEIS 101.
6. Type LFMC: Article 350 of NFPA 70 and NECA NEIS 101.
7. Type LFNC: Article 342 of NFPA 70 and NECA NEIS 111.
8. Type PVC: Article 356 of NFPA 70 and NECA NEIS 111.
9. Expansion Fittings: NEMA FB 2.40.
10. Consult Architect for resolution of conflicting requirements.

C. Special Installation Techniques:

1. General Requirements for Installation of Duct Raceways:

- a. Complete duct raceway installation before starting conductor installation.
- b. Provide stub-ups through floors with coupling threaded inside for plugs, set flush with finished floor. Plug coupling until conduit is extended above floor to final destination or a minimum of 2 ft above finished floor.
- c. Install no more than equivalent of three 90-degree bends in conduit run except for control wiring conduits, for which no more than equivalent of two 90-degree fewer bends are permitted. Support within 12 inch of changes in direction.
- d. Make bends in duct raceway using large-radius preformed ells except for parallel bends. Field bending must be in accordance with NFPA 70 minimum radii requirements. Provide only equipment specifically designed for material and size involved.
- e. Conceal conduit within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- f. Support conduit within 12 inch of enclosures to which attached.
- g. Install duct sealing fittings at accessible locations in accordance with NFPA 70 and fill them with listed sealing compound. For concealed duct raceways, install fitting in flush steel box with blank cover plate having finish similar to that of adjacent plates or surfaces. Install duct sealing fittings in accordance with NFPA 70.
- h. Install devices to seal duct raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal interior of duct raceways at the following points:
 - 1) Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2) Where an underground service duct raceway enters a building or structure.
 - 3) Conduit extending from interior to exterior of building.
 - 4) Conduit extending into pressurized duct raceway and equipment.
 - 5) Conduit extending into pressurized zones that are automatically controlled to maintain different pressure set points.
 - 6) Where otherwise required by NFPA 70.
- i. Do not install conduits within 2 inch of the bottom side of a metal deck roof.
- j. Keep duct raceways at least 6 inch away from parallel runs of flues and steam or hot-water pipes. Install horizontal duct raceway runs above water and steam piping.
- k. Cut conduit perpendicular to the length. For conduits metric designator 53 (trade size 2) and larger, use roll cutter or a guide to make cut straight and perpendicular to the length. Ream inside of conduit to remove burrs.
- l. Install pull wires in empty duct raceways. Provide polypropylene or monofilament plastic line with not less than 200 lb tensile strength. Leave at least 12 inch of slack at both ends of pull wire. Cap underground duct raceways designated as spare above grade alongside duct raceways in use.
- m. Install duct raceways square to the enclosure and terminate at enclosures without hubs with locknuts on both sides of enclosure wall. Install locknuts hand tight, plus one-quarter turn more.

- 1) Termination fittings with shoulders do not require two locknuts.
- n. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to metric designator 35 (trade size 1-1/4) and insulated throat metal bushings on metric designator 41 (trade size 1-1/2) and larger conduits terminated with locknuts..
2. Type EMT: Do not install EMT duct raceways or fittings in contact with concrete or earth.
3. Types ERM C:
 - a. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound that maintains electrical conductivity to threads of duct raceway and fittings before making up joints. Follow compound manufacturer's published instructions.
4. Types LFMC:
 - a. Provide a maximum of 36 inch of flexible conduit for recessed and semirecessed luminaires, equipment subject to vibration, noise transmission, or movement; and for transformers and motors.
5. Types PVC, HDPE, and EPEC:
 - a. Do not install Type PVC conduit where ambient temperature exceeds 122 deg F. Conductor ratings must be limited to 75 deg C except where installed in a trench outside buildings with concrete encasement, where 90 deg C conductors are permitted.
 - b. Comply with manufacturer's published instructions for solvent welding and fittings.
6. Not Allowed Stub-ups to Above Recessed Ceilings:
 - a. Provide EMT for duct raceways.
 - b. Provide a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.
7. Duct Raceway Terminations at Locations Subject to Moisture or Vibration:
 - a. Provide insulating bushings to protect conductors, including conductors smaller than 4 AWG. Install insulated throat metal grounding bushings on service conduits.
8. Duct Fittings: Install fittings in accordance with NEMA FB 2.10 guidelines.
 - a. EMT: Provide setscrew or compression, steel fittings. Comply with NEMA FB 2.10.
 - b. Flexible Conduit: Provide only fittings listed for use with flexible conduit type. Comply with NEMA FB 2.20.
9. Expansion-Joint Fittings:

- a. Install in runs of aboveground PVC that are located where environmental temperature change may exceed 30 deg F and that have straight-run length that exceeds 25 ft. Install in runs of aboveground ERM and EMT conduit that are located where environmental temperature change may exceed 100 deg F and that have straight-run length that exceeds 100 ft.
 - b. Install type and quantity of fittings that accommodate temperature change listed for the following locations:
 - 1) Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
 - 2) Outdoor Locations Exposed to Direct Sunlight: 155 deg F temperature change.
 - 3) Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
 - 4) Attics: 135 deg F temperature change.
 - c. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.
 - d. Install expansion fittings at locations where conduits cross building or structure expansion joints.
 - e. Install expansion-joint fitting with position, mounting, and piston setting selected in accordance with manufacturer's published instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
- 10. Duct Raceways Penetrating Rooms or Walls with Acoustical Requirements: Seal duct raceway openings on both sides of rooms or walls with acoustically rated putty or firestopping.
 - 11. Identification: Provide labels for conduit assemblies, duct raceways, and associated electrical equipment.
 - a. Provide warning signs.

D. Interfaces with Other Work:

- 1. Coordinate with Section 07 84 13 "Penetration Firestopping" for installation of firestopping at penetrations of fire-rated floor and wall assemblies.
- 2. Coordinate with Section 26 05 29 "Hangers and Supports for Electrical Systems" for installation of conduit hangers and supports.

3.3 PROTECTION

A. Protect coatings, finishes, and cabinets from damage and deterioration.

- 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.

2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 26 05 33

This page intentionally left blank.

SECTION 26 05 33.16 - BOXES AND COVERS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Metallic outlet boxes, device boxes, rings, and covers.
2. Nonmetallic outlet boxes, device boxes, rings, and covers.
3. Junction boxes and pull boxes.
4. Cover plates for device boxes.
5. Hoods for outlet boxes.

B. Products Installed, but Not Furnished, under This Section:

1. See Section 26 05 53 "Identification for Electrical Systems" for electrical equipment labels.

C. Related Requirements:

1. Section 26 00 00 "Electrical General Requirements and Common Work Results" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.

1.2 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

PART 2 - PRODUCTS

2.1 METALLIC OUTLET BOXES, DEVICE BOXES, RINGS, AND COVERS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
2. Listing Criteria: UL CCN QCIT; including UL 514A.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.

C. UL QCIT - Metallic Outlet Boxes and Covers:

1. Description: Box having pryout openings, knockouts, threaded entries, or hubs in either the sides of the back, or both, for entrance of conduit, conduit or cable fittings, or cables, with provisions for mounting outlet box cover, but without provisions for mounting wiring device directly to box.
2. Options:
 - a. Material: Sheet steel.
 - b. Sheet Metal Depth: Minimum 1.5 inch.
 - c. Cast-Metal Depth: Minimum 1.8 inch.
 - d. Paddle Fan Outlet Boxes and Covers: Nonadjustable, designed for attachment of paddle fan weighing up to 70 lb.

D. UL QCIT - Metallic Conduit Bodies:

1. Description: Means for providing access to interior of conduit or tubing system through one or more removable covers at junction or terminal point. In the United States, conduit bodies are listed in accordance with outlet box requirements.

E. UL QCIT - Metallic Device Boxes:

1. Description: Box with provisions for mounting wiring device directly to box.
2. Options:
 - a. Material: Sheet steel.
 - b. Sheet Metal Depth: minimum 1.5 inch.
 - c. Cast-Metal Depth: minimum 1.8 inch.

F. UL QCIT - Metallic Extension Rings:

1. Description: Ring intended to extend sides of outlet box or device box to increase box depth, volume, or both.

2.2 NONMETALLIC OUTLET BOXES, DEVICE BOXES, RINGS, AND COVERS

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.

2. Listing Criteria: UL CCN QCMZ; including UL 514C.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.

C. UL QCMZ - Nonmetallic Outlet Boxes and Covers:

1. Description: Box having pryout openings, knockouts, threaded entries, or hubs in either the sides or the back, or both, for entrance of conduit, conduit or cable fittings, or cables, with provisions for mounting outlet box cover, but without provisions for mounting wiring device directly to box.

D. UL QCMZ - Nonmetallic Conduit Bodies:

1. Description: Means for providing access to interior of conduit or tubing system through one or more removable covers at junction or terminal point. In the United States, conduit bodies are listed in accordance with outlet box requirements.

E. UL QCMZ - Nonmetallic Device Boxes:

1. Description: Box with provisions for mounting wiring device directly to box.

F. UL QCMZ - Nonmetallic Extension Rings:

1. Description: Ring intended to extend sides of outlet box or device box to increase box depth, volume, or both.

2.3 JUNCTION BOXES AND PULL BOXES

A. Performance Criteria:

1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
2. Listing Criteria: UL CCN BGUZ; including UL 50 and UL 50E.

B. Source Quality Control:

1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.

C. UL BGUZ - Indoor Sheet Metal Junction and Pull Boxes:

1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
2. Options:
 - a. Degree of Protection: Type 1.

- D. UL BGUZ - Indoor Cast-Metal Junction and Pull Boxes:
 - 1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
 - 2. Options:
 - a. Degree of Protection: Type 1.
- E. UL BGUZ - Outdoor Sheet Metal Junction and Pull Boxes:
 - 1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
 - 2. Options:
 - a. Degree of Protection: Type 3R.
- F. UL BGUZ - Outdoor Cast-Metal Junction and Pull Boxes:
 - 1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
 - 2. Options:
 - a. Degree of Protection: Type 3R.
- G. UL BGUZ - Outdoor Polymeric Junction and Pull Boxes:
 - 1. Description: Box with a blank cover that serves the purpose of joining different runs of raceway or cable.
 - 2. Options:
 - a. Degree of Protection: Type 3R.

2.4 COVER PLATES FOR DEVICES BOXES

- A. Performance Criteria:
 - 1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
 - 2. Listing Criteria: UL CCN QCIT or UL CCN QCMZ; including UL 514D.
 - 3. Wallplate-Securing Screws: Metal with head color to match wallplate finish.
- B. Source Quality Control:
 - 1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
- C. UL QCIT or QCMZ - Metallic Cover Plates for Device Boxes:
 - 1. Options:

- a. Damp and Wet Locations: Listed, labeled, and marked for location and use. Provide gaskets and accessories necessary for compliance with listing.
 - b. Wallplate Material: 0.04 inch thick steel with chrome-plated finish.
- D. UL QCIT or QCMZ - Nonmetallic Cover Plates for Device Boxes:
 - 1. Options:
 - a. Damp and Wet Locations: Listed, labeled, and marked for location and use. Provide gaskets and accessories necessary for compliance with listing.
 - b. Wallplate Material: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device.
 - c. Color: As indicated on architectural Drawings.
- E. UL QCIT or QCMZ - Illuminating Cover Plates for Device Boxes:
 - 1. Options:
 - a. Damp and Wet Locations: Listed, labeled, and marked for location and use. Provide gaskets and accessories necessary for compliance with listing.
 - b. Wallplate Material: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device.
 - c. Color: As indicated on architectural Drawings.

2.5 HOODS FOR OUTLET BOXES

- A. Performance Criteria:
 - 1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70 and marked for intended location and use.
 - 2. Listing Criteria:
 - a. UL CCN QCIT or UL CCN QCMZ; including UL 514D.
 - b. Receptacle, Hood, Cover Plate, Gaskets, and Seals: UL 498 Supplement SA when mated with box or enclosure complying with UL 514A, UL 514C, or UL 50E.
 - 3. Mounts to box using fasteners different from wiring device.
- B. Source Quality Control:
 - 1. Product Data: Prepare and submit catalog cuts, brochures, and performance data illustrating size, physical appearance, and other characteristics of product.
 - 2. Manufacturer's Published Instructions: Prepare and submit installation, testing, and operating instructions for product.
- C. UL QCIT or QCMZ - Retractable or Reattachable Hoods for Outlet Boxes:
 - 1. Options:
 - a. Provides clear, weatherproof, "while-in-use" cover.
- D. UL QCIT or QCMZ - Extra-Duty, While-in-Use Hoods for Outlet Boxes:

1. Additional Characteristics: Marked "Extra-Duty" in accordance with UL 514D.
2. Options:
 - a. Provides clear, weatherproof, "while-in-use" cover.
 - b. Manufacturer may combine nonmetallic device box with hood as extra-duty rated assembly.

PART 3 - EXECUTION

3.1 PREPARATION

A. Shop Drawings: Prepare and submit the following:

1. Shop Drawings for Floor Boxes: Show that floor boxes are located to avoid interferences and are structurally allowable. Indicate floor thickness where boxes are embedded in concrete floors and underfloor clearances where boxes are installed in raised floors.

3.2 SELECTION OF BOXES AND COVERS FOR ELECTRICAL SYSTEMS

A. Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NFPA 70 for selection of boxes and enclosures. Consult Architect for resolution of conflicting requirements.

B. Degree of Protection:

1. Outdoors:

- a. unless otherwise indicated.
- b. Locations Exposed to Hosedown:.
- c. Locations Subject to Potential Flooding: Type 6P.
- d. Locations Aboveground Where Mechanism Must Operate When Ice Covered: Type 3S.
- e. Locations in-Ground or Exposed to Corrosive Agents: Type 4X.
- f. Locations in-Ground or Exposed to Corrosive Agents Where Mechanism Must Operate When Ice Covered: Type 3SX.

2. Indoors:

- a. Type 1 unless otherwise indicated.
- b. Surface Mounted in Kitchens and Other Locations Exposed to Oil or Coolants: Type 12.
- c. Flush Mounted in Kitchens and Other Locations Exposed to Oil or Coolants: Type 12.

C. Exposed Boxes Installed Less Than 2.5 m (8 ft) Above Floor:

1. Provide cast-metal boxes.

2. Provide exposed cover. Flat covers with angled mounting slots or knockouts are prohibited.

3.3 INSTALLATION OF BOXES AND COVERS FOR ELECTRICAL SYSTEMS

- A. Comply with manufacturer's published instructions.
- B. Reference Standards for Installation: Unless more stringent installation requirements are specified in Contract Documents or manufacturers' published instructions, comply with the following:
 1. Outlet, Device, Pull, and Junction Boxes: Article 314 of NFPA 70.
 2. Consult Architect for resolution of conflicting requirements.
- C. Special Installation Techniques:
 1. Provide boxes in wiring and raceway systems wherever required for pulling of wires, making connections, and mounting of devices or fixtures.
 2. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
 3. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box, whether installed indoors or outdoors.
 4. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
 5. Locate boxes so that cover or plate will not span different building finishes.
 6. Support boxes in recessed ceilings independent of ceiling tiles and ceiling grid.
 7. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for purpose.
 8. Fasten junction and pull boxes to, or support from, building structure. Do not support boxes by conduits.
 9. Set metal floor boxes level and flush with finished floor surface.
 10. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.
 11. Do not install aluminum boxes, enclosures, or fittings in contact with concrete or earth.
 12. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to ensure a continuous ground path.
 13. Boxes and Enclosures in Areas or Walls with Acoustical Requirements:
 - a. Seal openings and knockouts in back and sides of boxes and enclosures with acoustically rated putty.
 - b. Provide gaskets for wallplates and covers.
 14. Identification: Provide labels for boxes and associated electrical equipment.

- a. Identify field-installed conductors, interconnecting wiring, and components.
- b. Provide warning signs.
- c. Label each box with engraved metal or laminated-plastic nameplate.

3.4 26 05 7326 05 73CLEANING

- A. Remove construction dust and debris from boxes before installing wallplates, covers, and hoods.

3.5 PROTECTION

- A. After installation, protect boxes from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION 26 05 33.16

SECTION 26 05 48 - VIBRATION AND SEISMIC CONTROLS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following:

- 1. Isolation pads.
- 2. Spring isolators.
- 3. Restrained spring isolators.
- 4. Channel support systems.
- 5. Restraint cables.
- 6. Hanger rod stiffeners.
- 7. Anchorage bushings and washers.

- B. Related Sections include the following:

- 1. Division 26 Section "Hangers And Supports For Electrical Systems" for commonly used electrical supports and installation requirements.

- C. Delegated Design

- 1. Provide a complete, code-compliant vibration and seismic support system under a delegated design approach. Work shall include all engineering, design, installation labor, materials, equipment, permits, fees, and transportation necessary to furnish, install, test, and certify a fully operational system.

- D. Performance Requirements

- 1. The Contract Documents establish minimum material standards, system features, and performance requirements.. Based on the specified performance and indicated equipment, the Contractor and Vendor shall be solely responsible for the complete design, coordination, and provision of all components and wiring necessary to deliver a fully functional and compliant support system.

- E. Scope of Work

- 1. Work includes, but is not limited to, the following:
 - a. Complete system design, engineering, and coordination with the Architect and other trades, including testing and final acceptance by the Owner, Authority Having Jurisdiction (AHJ), and applicable certification agencies.
 - b. Preparation and submission for plan review and approval.
 - c. Furnishing and installation of all system components and devices.
 - d. Preparation and submission of installation details, wiring diagrams, shop drawings, and product data.
 - e. Provision of all labor and materials required for a complete and operational sys-

tem, whether specifically indicated or reasonably inferred.

- f. Preparation and submission of record (as-built) documents.
- g. Obtaining all required permits, inspections, and payment of associated fees.
- h. System identification and provision of written operation and maintenance instructions.
- i. Coordination with existing conditions and the work of other trades.
- j. Furnishing and installation of special supports required for work under this Section but provided in coordination with other Sections.

1.3 DEFINITIONS

- A. The IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.
- C. OSHPD: Office of Statewide Health Planning and Development for the State of California.

1.4 PERFORMANCE REQUIREMENTS

- A. Seismic-Restraint Loading:
 - 1. Site Class as Defined in the IBC: D.
 - 2. Assigned Seismic Use Group or Building Category as Defined in the IBC: IV
 - a. Component Importance Factor: 1.0.
 - b. Component Response Modification Factor: 1.5.
 - c. Component Amplification Factor: 1.0.
 - 3. Design Spectral Response Acceleration at Short Periods (0.2 Second): $S_s=0.458$, $S_1=0.161$
 - 4. Design Spectral Response Acceleration at 1.0-Second Period: $S_{DS}=0.438$, $S_{D1}=0.244$

1.5 SUBMITTALS

- A. Product Data: For the following:
 - 1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
 - 2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of seismic-restraint component used.
 - a. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an agency acceptable to authorities having jurisdiction.
 - b. Annotate to indicate application of each product submitted and compliance with requirements.
 - 3. Restrained-Isolation Devices: Include ratings for horizontal, vertical, and combined loads.
- B. Delegated-Design Submittal: For seismic-restraint details to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

C.

1. Design Calculations: Calculate static and dynamic loading due to equipment weight and operation, seismic forces required to select vibration isolators and seismic restraints.
 - a. Coordinate design calculations with wind-load calculations required for equipment mounted outdoors. Comply with requirements in other Division 26 Sections for equipment mounted outdoors.
 2. Indicate materials and dimensions and identify hardware, including attachment and anchorage devices.
 3. Field-fabricated supports.
 4. Seismic-Restraint Details:
 - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads.
 - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events
 - c. Preapproval and Evaluation Documentation: By an agency acceptable to authorities having jurisdiction, showing maximum ratings of restraint items and the basis for approval (tests or calculations).
- D. Coordination Drawings: Show coordination of seismic bracing for electrical components with other systems and equipment in the vicinity, including other supports and seismic restraints.
- E. Welding certificates.
- F. Qualification Data: For professional engineer.
- G. Field quality-control test reports.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
- B. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- C. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Seismic-restraint devices shall have horizontal and vertical load testing and analysis and shall bear anchorage preapproval OPA number from OSHPD, preapproval by ICC-ES, or preapproval by another agency acceptable to authorities having jurisdiction, showing maximum seismic-restraint ratings. Ratings based on independent testing are preferred to ratings based on calculations. If preapproved ratings are not available, submittals based on independent testing are preferred. Calculations (including combining shear and tensile loads) to support seismic-restraint designs must be signed and sealed by a qualified professional engineer.
- E. Comply with NFPA 70.

PART 2 - PRODUCTS

2.1 VIBRATION ISOLATORS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Ace Mountings Co., Inc.
 - 2. Amber/Booth Company, Inc.
 - 3. California Dynamics Corporation.
 - 4. Isolation Technology, Inc.
 - 5. Kinetics Noise Control.
 - 6. Mason Industries.
 - 7. Vibration Eliminator Co., Inc.
 - 8. Vibration Isolation.
 - 9. Vibration Mountings & Controls, Inc.
- B. Pads: Arrange in single or multiple layers of sufficient stiffness for uniform loading over pad area, molded with a nonslip pattern and galvanized-steel baseplates, and factory cut to sizes that match requirements of supported equipment.
 - 1. Resilient Material: Oil- and water-resistant neoprene.

2.2 SEISMIC-RESTRAINT DEVICES

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Amber/Booth Company, Inc.
 - 2. California Dynamics Corporation.
 - 3. Cooper B-Line, Inc.; a division of Cooper Industries.
 - 4. Hilti Inc.
 - 5. Loos & Co.; Seismic Earthquake Division.
 - 6. Mason Industries.
 - 7. TOLCO Incorporated; a brand of NIBCO INC.
 - 8. Unistrut; Tyco International, Ltd.
- B. General Requirements for Restraint Components: Rated strengths, features, and application requirements shall be as defined in reports by an agency acceptable to authorities having jurisdiction.
 - 1. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they will be subjected.
- C. Channel Support System: MFMA-3, shop- or field-fabricated support assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; and rated in tension, compression, and torsion forces.
- D. Restraint Cables: ASTM A 603 galvanized steel cables with end connections made of steel assemblies with thimbles, brackets, swivels, and bolts designed for restraining cable service; and with a minimum of two clamping bolts for cable engagement.

- E. Hanger Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod. Do not weld stiffeners to rods.
- F. Bushings for Floor-Mounted Equipment Anchor: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchors and studs.
- G. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices.
- H. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.
- I. Mechanical Anchor: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchors with strength required for anchor and as tested according to ASTM E 488. Minimum length of eight times diameter.
- J. Adhesive Anchor: Drilled-in and capsule anchor system containing polyvinyl or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

2.3 FACTORY FINISHES

- A. Finish: Manufacturer's standard prime-coat finish ready for field painting.
- B. Finish: Manufacturer's standard paint applied to factory-assembled and -tested equipment before shipping.
 - 1. Powder coating on springs and housings.
 - 2. All hardware shall be galvanized. Hot-dip galvanize metal components for exterior use.
 - 3. Baked enamel or powder coat for metal components on isolators for interior use.
 - 4. Color-code or otherwise mark vibration isolation and seismic-control devices to indicate capacity range.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and equipment to receive seismic-control devices for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 APPLICATIONS

- A. Multiple Raceways or Cables: Secure raceways and cables to trapeze member with clamps approved for application by an agency acceptable to authorities having jurisdiction.

- B. Hanger Rod Stiffeners: Install hanger rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Select sizes of components so strength will be adequate to carry present and future static and seismic loads within specified loading limits.

3.3 SEISMIC-RESTRAINT DEVICE INSTALLATION

- A. Equipment and Hanger Restraints:
 - 1. Install restrained isolators on electrical equipment.
 - 2. Install resilient, bolt-isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
 - 3. Install seismic-restraint devices using methods approved by an agency acceptable to authorities having jurisdiction providing required submittals for component.
- B. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- C. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- D. Drilled-in Anchors:
 - 1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify the structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
 - 2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
 - 3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
 - 4. Adhesive Anchors: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
 - 5. Set anchors to manufacturer's recommended torque, using a torque wrench.
 - 6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Install flexible connections in runs of raceways, cables, wireways, cable trays, and busways where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where they terminate with connection to equipment that is anchored to a different structural element from the one supporting them as they approach equipment.

3.5 FIELD QUALITY CONTROL

A. Perform tests and inspections.

B. Tests and Inspections:

1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
5. Test to 90 percent of rated proof load of device.
6. Retain first three subparagraphs below if vibration isolators are required for Project.
7. Measure isolator restraint clearance.
8. Measure isolator deflection.
9. Verify snubber minimum clearances.
10. If a device fails test, modify all installations of same type and retest until satisfactory results are achieved.

C. Remove and replace malfunctioning units and retest as specified above.

D. Prepare test and inspection reports.

3.6 ADJUSTING

A. Adjust isolators after isolated equipment is at operating weight.

B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.

C. Adjust active height of spring isolators.

D. Adjust restraints to permit free movement of equipment within normal mode of operation.

END OF SECTION 26 05 48

This page intentionally left blank.

SECTION 26 05 53 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Identification for raceways.
 - 2. Identification of power and control cables.
 - 3. Identification for conductors.
 - 4. Underground-line warning tape.
 - 5. Warning labels and signs.
 - 6. Instruction signs.
 - 7. Equipment identification labels.
 - 8. Miscellaneous identification products.

1.3 SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

1.4 QUALITY ASSURANCE

- A. Comply with ANSI A13.1
- B. Comply with NFPA 70.
- C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.
- D. Comply with ANSI Z535.4 for safety signs and labels.
- E. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.

1.5 COORDINATION

- A. Coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual; and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.
- B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- C. Coordinate installation of identifying devices with location of access panels and doors.
- D. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 - PRODUCTS

2.1 POWER AND CONTROL CABLE IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each raceway and cable size.
- B. Self-Adhesive Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound adhesive tape for securing ends of legend label.

2.2 CONDUCTOR IDENTIFICATION MATERIALS

- A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils thick by 1 to 2 inches wide.
- B. Self-Adhesive Vinyl Labels: Preprinted, flexible label laminated with a clear, weather- and chemical-resistant coating and matching wraparound adhesive tape for securing ends of legend label.
- C. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.

2.3 UNDERGROUND-LINE WARNING TAPE

- A. Tape:
 - 1. Recommended by manufacturer for the method of installation and suitable to identify and locate underground electrical and communications utility lines.
 - 2. Printing on tape shall be permanent and shall not be damaged by burial operations.
 - 3. Tape material and ink shall be chemically inert, and not subject to degrading when exposed to acids, alkalis, and other destructive substances commonly found in soils.

- B. Color and Printing:
 - 1. Comply with ANSI Z535.1 through ANSI Z535.5.
 - 2. Inscriptions for Red-Colored Tapes: ELECTRIC LINE, HIGH VOLTAGE
 - 3. Inscriptions for Orange-Colored Tapes: TELEPHONE CABLE, CATV CABLE, COMMUNICATIONS CABLE, OPTICAL FIBER CABLE,

2.4 WARNING LABELS AND SIGNS

- A. Comply with NFPA 70 and 29 CFR 1910.145.
- B. Self-Adhesive Warning Labels: Factory-printed, multicolor, pressure-sensitive adhesive labels, configured for display on front cover, door, or other access to equipment unless otherwise indicated.
- C. Baked-Enamel Warning Signs:
 - 1. Preprinted aluminum signs, punched or drilled for fasteners, with colors, legend, and size required for application.
 - 2. 1/4-inch grommets in corners for mounting.
 - 3. Nominal size, 7 by 10 inches.
- D. Warning label and sign shall include, but are not limited to, the following legends:
 - 1. Multiple Power Source Warning: "DANGER - ELECTRICAL SHOCK HAZARD - EQUIPMENT HAS MULTIPLE POWER SOURCES."
 - 2. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR 36 INCHES."

2.5 INSTRUCTION SIGNS

- A. Engraved, laminated acrylic or melamine plastic, minimum 1/16 inch thick for signs up to 20 sq. inches and 1/8 inch thick for larger sizes.
 - 1. Engraved legend with black letters on white face.
 - 2. Punched or drilled for mechanical fasteners.
 - 3. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.
- B. Adhesive Film Label: Machine printed, in black, by thermal transfer or equivalent process. Minimum letter height shall be 3/8 inch.
- C. Adhesive Film Label with Clear Protective Overlay: Machine printed, in black, by thermal transfer or equivalent process. Minimum letter height shall be 3/8 inch. Overlay shall provide a weatherproof and UV-resistant seal for label.

2.6 EQUIPMENT IDENTIFICATION LABELS

- A. Engraved, Laminated Acrylic or Melamine Label: Punched or drilled for screw mounting. White letters on a dark-gray background. Minimum letter height shall be 3/8 inch.

2.7 CABLE TIES

- A. General-Purpose Cable Ties: Fungus inert, self extinguishing, one piece, self locking, Type 6/6 nylon.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
 - 3. Temperature Range: Minus 40 to plus 185 deg F.
 - 4. Color: Black except where used for color-coding.
- B. UV-Stabilized Cable Ties: Fungus inert, designed for continuous exposure to exterior sunlight, self extinguishing, one piece, self locking, Type 6/6 nylon.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 12,000 psi.
 - 3. Temperature Range: Minus 40 to plus 185 deg F.
 - 4. Color: Black.
- C. Plenum-Rated Cable Ties: Self extinguishing, UV stabilized, one piece, self locking.
 - 1. Minimum Width: 3/16 inch.
 - 2. Tensile Strength at 73 deg F, According to ASTM D 638: 7000 psi.
 - 3. UL 94 Flame Rating: 94V-0.
 - 4. Temperature Range: Minus 50 to plus 284 deg F.
 - 5. Color: Black.

2.8 MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Paint: Comply with requirements in Division 09 painting Sections for paint materials and application requirements. Select paint system applicable for surface material and location (exterior or interior).
- B. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Verify identity of each item before installing identification products.
- B. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.
- C. Apply identification devices to surfaces that require finish after completing finish work.
- D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.
- E. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.

- F. System Identification Color-Coding Bands for Raceways and Cables: Each color-coding band shall completely encircle cable or conduit. Place adjacent bands of two-color markings in contact, side by side. Locate bands at changes in direction, at penetrations of walls and floors, at 50-foot maximum intervals in straight runs, and at 25-foot maximum intervals in congested areas.
- G. Cable Ties: For attaching tags. Use general-purpose type, except as listed below:
 - 1. Outdoors: UV-stabilized nylon.
 - 2. In Spaces Handling Environmental Air: Plenum rated.
- H. Underground-Line Warning Tape: During backfilling of trenches install continuous underground-line warning tape directly above line at 6 to 8 inches below finished grade. Use multiple tapes where width of multiple lines installed in a common trench exceeds 16 inches overall.
- I. Painted Identification: Comply with requirements in Division 09 painting Sections for surface preparation and paint application.

3.2 IDENTIFICATION SCHEDULE

- A. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with the wiring system legend and system voltage and circuit
- B. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
 - 1. Color-Coding for Phase: Use colors listed below.
 - a. Color shall be factory applied or field applied for sizes larger than No. 8 AWG
 - b. Colors for 208/120-V Circuits:
 - 1) Phase A: Black.
 - 2) Phase B: Red.
 - 3) Phase C: Blue.
 - c. Field-Applied, Color-Coding Conductor Tape: Apply in half-lapped turns for a minimum distance of 6 inches from terminal points and in boxes where splices or taps are made. Apply last two turns of tape with no tension to prevent possible unwinding. Locate bands to avoid obscuring factory cable markings.
- C. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.
 - 1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
 - 2. Use system of marker tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
 - 3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual.

- D. Locations of Underground Lines: Identify with underground-line warning tape for power, lighting, communication, and control wiring and optical fiber cable.
 - 1. Limit use of underground-line warning tape to direct-buried cables.
 - 2. Install underground-line warning tape for both direct-buried cables and cables in raceway.
- E. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting:
 - 1. Comply with 29 CFR 1910.145.
 - 2. Identify system voltage with black letters on an orange background.
 - 3. Apply to exterior of door, cover, or other access.
 - 4. For equipment with multiple power or control sources, apply to door or cover of equipment including, but not limited to, the following:
 - a. Power transfer switches.
 - b. Controls with external control power connections.
- F. Operating Instruction Signs: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.
- G. Emergency Operating Instruction Signs: Install instruction signs with white legend on a red background with minimum 3/8-inch- high letters for emergency instructions.
- H. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and the Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.
 - 1. Labeling Instructions:
 - a. Indoor Equipment: Self-adhesive, engraved, laminated acrylic or melamine label. Unless otherwise indicated, provide a single line of text with 1/2-inch- high letters on 1-1/2-inch- high label; where two lines of text are required, use labels 2 inches high.
 - b. Outdoor Equipment: Engraved, laminated acrylic or melamine label. Stenciled legend 4 inches high.
 - c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
 - d. Unless provided with self-adhesive means of attachment, fasten labels with appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.
 - 2. Electrical service shall be provided with identification labels in accordance with NFPA 70 Article 230 including available sources of power and locations and service short circuit availability.
 - 3. Equipment to Be Labeled:
 - a. Panelboards: Typewritten directory of circuits in the location provided by panelboard manufacturer. Panelboard identification shall be engraved, laminated acrylic or melamine label.
 - b. Enclosures and electrical cabinets.
 - c. Access doors and panels for concealed electrical items.
 - d. Emergency system boxes and enclosures.

- e. Enclosed switches.
- f. Enclosed circuit breakers.
- g. Enclosed controllers.
- h. Variable-speed controllers.
- i. Push-button stations.
- j. Power transfer equipment.
- k. Contactors.
- l. Remote-controlled switches, dimmer modules, and control devices.
- m. Power-generating units.
- n. Monitoring and control equipment.
- o. UPS equipment.

END OF SECTION 26 05 53

This page intentionally left blank.

SECTION 26 05 73 - OVERCURRENT PROTECTIVE DEVICE ARC-FLASH STUDY
PART - 1 GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes computer-based, fault-current analysis and report, overcurrent protective device coordination study and arc flash hazard analysis and report.
 - 1. Electrical service fault current calculation labeling shall be provided based upon the results as required in NFPA 70 Article 110.24.
 - 2. Protective devices shall be set based on results of the protective device coordination study.
 - 3. Arc flash labeling shall be provided based upon results of arc flash analysis Study per the requirements set forth in the current issue of NFPA 70E-Standard for Electrical Safety in the Workplace. The arc flash hazard analysis shall be performed according to the IEEE Standard 1584-2018, the IEE Guide for Performing Arc-Flash Calculations.
- B. Perform study starting at each metered service from the local utility. Obtain necessary information from the local utility. Verify Utility's overcurrent protection.
- C. The scope of the studies shall include the entire electrical system proposed within the contract documents.
- D. Contractor shall engage the services of a professional engineer to perform the power system studies.

1.3 DEFINITIONS

- A. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.
- B. One-Line Diagram: A diagram which shows, by means of single lines and graphic symbols, the course of an electric circuit or system of circuits and the component devices or parts used therein.
- C. Protective Device: A device that senses when an abnormal current flow exists and then removes the affected portion from the system.
- D. SCCR: Short-circuit current rating.
- E. Service: The conductors and equipment for delivering electric energy from the serving utility to the wiring system of the premises served.

1.4 ACTION SUBMITTALS

- A. Product Certificates: For coordination-study, fault-current-study, and arc flash hazard calculation computer software programs, certifying compliance with IEEE 399.

B. Qualification Data: For coordination-study specialist:

1. The power system studies shall be performed based upon the contract documents and shall include the specific equipment, settings and performance to be provided and estimated conductor lengths.

C. First Submittal: A Short Circuit, Arc Flash and Coordination Analysis shall be submitted at the same time as the electrical equipment shop drawings are submitted. Approval of shop drawings will not be provided until study has been submitted.

D. Second Submittal: A Power System Study Report shall be resubmitted, if required, no later than four (4) weeks after the short circuit, arc flash and coordination analysis and shop drawings have been reviewed.

1. Documentation shall be provided in electronic report format. Individual studies shall be separated with identification labels.

a. The report shall include the following sections:

- i. Executive Summary including Introduction, Scope of Work and Results/Recommendations.
- ii. Short-Circuit Methodology Analysis Results and Recommendations.
 - 1) Fault current calculations shall be provided for both utility fault current contributions and on-site standby-power generation fault current contributions. Calculation input data shall be provided including fault current contributions. Fault current calculations shall be submitted in both report form and plotted one-line diagrams.
- iii. Short Circuit Device and Bus Evaluation Tables.
- iv. Protective Device Coordination Methodology Analysis Results and Recommendations.
- v. Protective Device Settings Table.
- vi. Time-Current Coordination Graphs and Recommendations.
- vii. Arc Flash Hazard Methodology Analysis Results and Recommendations.
 - 1) This section shall include the details of the incident energy and flash protection boundary calculations, along with Arc Flash boundary distances, working distances, Incident Energy levels. The arc flash calculation results should consider and evaluate all possible power source scenarios (utility power source, emergency power source, etc.) and alternate temporary circuit breaker settings (maintenance mode).
- viii. Arc Flash Labeling.
 - 1) This section shall include descriptive information as well as typical label images for the types of labels to be provided.
- ix. Computer Generated One-Line Diagram of the Electrical System.

- 1) The One-Line diagram must clearly identify individual equipment buses, bus numbers used in the short-circuit analysis, cable and bus connections between the equipment, calculated maximum short-circuit current at each bus location, device numbers used in the time-current coordination analysis and other information pertinent to the computer analysis.
2. Power system study project model and results shall be submitted on electronic media for use by the Owner. Electrical model information shall include complete coordination files including all device curves. (If using the SKM PowerTools program, Project - Backup shall be used to provide all project electrical model information.)
3. Calculations and analysis shall include the stamp or seal and signature of the preparing Registered Professional Electrical Engineer and shall be reviewed and approved by the Engineer of Record.

1.5 QUALITY ASSURANCE

- A. Studies shall use computer programs that are distributed nationally and are in wide use. Software algorithms shall comply with requirements of standards and guides specified in this Section. Manual calculations are unacceptable.
- B. Arc-Flash Study Software Developer Qualifications: An entity that owns and markets computer software used for studies, having performed successful studies of similar magnitude on electrical distribution systems using similar devices.
 1. The computer program shall be developed under the charge of a licensed professional engineer who holds IEEE Computer Society's Certified Software Development Professional certification.
- C. Arc-Flash Study Specialist Qualifications: Professional engineer in charge of performing the study, analyzing the arc flash, and documenting recommendations, licensed in the state where Project is located. All elements of the study shall be performed under the direct supervision and control of this professional engineer.
- D. Provide products and installation methods specified in this section that comply with the following Standards:
 1. Comply with IEEE 242 for short-circuit currents and coordination time intervals.
 2. Comply with IEEE 399 for general study procedures.
 3. Comply with IEEE 1584 and NFPA70E-most recent version for arc flash hazard analysis.

PART - 2 PRODUCTS

2.1 COMPUTER SOFTWARE DEVELOPERS

- A. Software Developers:
 1. SKM Systems Analysis, Inc. Power Tools for Windows (PTW)
 2. Easy Power
- B. Comply with IEEE 1584 and NFPA 70E.

- C. Analytical features of device coordination study computer software program shall have the capability to calculate "mandatory," "very desirable," and "desirable" features as listed in IEEE 399.

2.2 COMPUTER SOFTWARE PROGRAM REQUIREMENTS

- A. Comply with IEEE 399.
- B. Analytical features of fault-current-study computer software program shall include "mandatory," "very desirable" and "desirable" features as listed in IEEE 399.
- C. Computer software program shall be capable of plotting and diagramming time-current-characteristic curves as part of its output. Computer software program shall report device settings and ratings of all overcurrent protective devices and shall demonstrate selective coordination by computer-generated, time-current coordination plots.
- D. Analysis shall include software capable of calculating arc flash hazard and preparing arc flash hazard labels.

2.3 SHORT-CIRCUIT STUDY REPORT CONTENT

- A. Executive summary.
- B. Study descriptions, purpose, basis and scope.
- C. One-line diagram, showing the following:
 - 1. Protective device designations and ampere ratings.
 - 2. Cable size and lengths.
 - 3. Transformer kilovolt ampere (kVA) and voltage ratings.
 - 4. Motor and generator designations and kVA ratings.
 - 5. Switchgear, switchboard, motor-control center and panelboard designations.
- D. Study Input Data: As described in "Power System Data" Article.
- E. Short-Circuit Study Output:
 - 1. Interrupting Duty Report: Three-phase and unbalanced fault calculations, showing the following for each overcurrent device location:
 - a. Voltage.
 - b. Calculated symmetrical fault-current magnitude and angle.
 - c. Fault-point X/R ratio.
 - d. No AC Decrement (NACD) ratio.
 - e. Equivalent impedance.
- F. Incident Energy and Flash Protection Boundary Calculations:
 - 1. Arcing fault magnitude.
 - 2. Protective device clearing time.
 - 3. Duration of arc.
 - 4. Arc-flash boundary.
 - 5. Working distance.

6. Incident energy.
7. Hazard risk category.
8. Recommendations for arc-flash energy reduction.

G. Fault study input data, case descriptions, and fault-current calculations including a definition of terms and guide for interpretation of the computer printout.

2.4 ARC-FLASH WARNING LABELS

- A. Comply with requirements in Section 26 05 53 "Identification for Electrical Systems." Produce a 3.5-by-5-inch thermal transfer label of high-adhesion polyester for each work location included in the analysis.
- B. The label shall have an orange header with the wording, "WARNING, ARC-FLASH HAZARD," and shall include the following information taken directly from the arc-flash hazard analysis:
 1. Location designation.
 2. Nominal voltage.
 3. Flash protection boundary.
 4. Hazard risk category.
 5. Incident energy.
 6. Working distance.
 7. Engineering report number, revision number, and issue date.
- C. Labels shall be machine printed, with no field-applied markings.

PART - 3 EXECUTION

3.1 EXAMINATION

- A. Examine Project overcurrent protective device submittals for compliance with electrical distribution system coordination requirements and other conditions affecting performance. Devices to be coordinated are indicated on Drawings, in the Specifications, by the Owner, and as required by the applicable edition of the National Electrical Code NFPA 70.
- B. Proceed with coordination study only after relevant equipment submittals have been assembled. Overcurrent protective devices that have not been submitted and approved prior to coordination study may not be used in study.
- C. The short circuit, overcurrent protective device coordination analysis and fault hazard calculations shall be based upon a complete electrical model of the electrical system from the utility service through the entire building's electrical distribution system, including branch circuit and lighting panelboards, engine-generator sets, individual motor control devices, motor disconnect switches and distribution panelboards.

3.2 POWER SYSTEM DATA

- A. Gather and tabulate the following input data to support coordination study:
 1. Product Data for overcurrent protective devices specified in other Division 26 Sections and involved in overcurrent protective device coordination studies. Use equipment designation tags that are consistent with electrical distribution system diagrams, overcurrent protective device submittals, input and output data and recommended device settings.
 2. Impedance of utility service entrance.

3. Electrical Distribution System Diagram: In hard-copy and electronic-copy formats, showing the following:
 - a. Circuit-breaker and fuse-current ratings and types.
 - b. Relays and associated power and current transformer ratings and ratios.
 - c. Transformer kilovolt amperes, primary and secondary voltages, connection type, impedance and X/R ratios.
 - d. Generator kilovolt amperes, size, voltage and source impedance.
 - e. Cables: Indicate conduit material, sizes of conductors, conductor material, insulation and length.
 - f. Motor horsepower and code letter designation according to NEMA MG 1.
4. Data sheets to supplement electrical distribution system diagram, cross-referenced with tag numbers on diagram showing the following:
 - a. Special load considerations, including starting inrush currents and frequent starting and stopping.
 - b. Transformer characteristics, including primary protective device, magnetic inrush current and overload capability.
 - c. Motor full-load current, locked rotor current, service factor, starting time, type of start and thermal-damage curve.
 - d. Generator thermal-damage curve.
 - e. Ratings, types and settings of utility company's overcurrent protective devices.
 - f. Special overcurrent protective device settings or types stipulated by utility company.
 - g. Time-current-characteristic curves of devices indicated to be coordinated.
 - h. Manufacturer, frame size, interrupting rating in amperes rms symmetrical, ampere or current sensor rating, long-time adjustment range, short-time adjustment range and instantaneous adjustment range for circuit breakers.
 - i. Manufacturer and type, ampere-tap adjustment range, time-delay adjustment range, instantaneous attachment adjustment range and current transformer ratio for overcurrent relays.
 - j. Panelboard ampacity and interrupting rating in amperes rms symmetrical.

3.3 SHORT-CIRCUIT CURRENT STUDY

- A. Calculate the maximum available short-circuit current in Amperes (RMS, Symmetrical) from the utility service to and including circuit-breaker positions of the electrical power distribution system shown on the drawings.
- B. Transformer design impedances shall be used when test impedances are not available.
- C. Variable Frequency Drives (VFD's) and Uninterruptable Power Supply (UPS') shall be modeled with bypass "on" as a worst-case scenario.
- D. The calculation shall be for a current immediately after initiation and for a three-phase bolted short circuit at the main bus of all switchboards, distribution panelboards, branch panelboards, motor controllers (including variable frequency drives) and disconnect switches
- E. Study electrical distribution system from normal and alternate power sources (engine-generators and UPS) throughout electrical distribution system for Project. Include studies of system-switching configurations and alternate operations that could result in maximum fault conditions.
- F. Calculate momentary and interrupting duties on the basis of maximum available fault current.

G. Calculations to verify interrupting ratings of overcurrent protective devices shall comply with the latest edition of the following:

1. IEEE 241 – IEEE Recommended Practice for Electric Power Systems in Commercial Buildings
2. IEEE 242 – IEEE Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems

H. Study Report:

1. Input Data: The study shall include input circuit data including electric utility system characteristics, source impedance data, conductor lengths, number of conductors per phase, conductor impedance values, insulation types, transformer impedances and X/R ratios, motor contributions and other circuit information as related to the short-circuit calculations.
2. One-Line Diagram: Documentation shall be made in one-line diagram form showing the magnitude and location of each calculated fault. A summary of the fault currents available shall also be submitted.
3. Calculations: Provide tabulated form of calculated quantities including short-circuit currents, X/R ratios, equipment short-circuit interrupting or withstand current ratings and notes regarding adequacy or inadequacy of the equipment ratings.
4. Show calculated X/R ratios and equipment interrupting rating (1/2-cycle) fault currents on electrical distribution system diagram.
5. Provide a comprehensive discussion section evaluating the adequacy or inadequacy of the equipment and include recommendations as appropriate for improvements to the system.
6. Contractor shall notify the Engineer in writing of any circuit protective devices improperly rated for the calculated available fault current.

3.4 OVERCURRENT PROTECTIVE DEVICE COORDINATION STUDY

A. Perform coordination study using approved computer software program. The analysis shall include comparing time/current curves of primary protective devices, service and distribution transformers, main service overcurrent protective devices, distribution panelboard, panelboards and branch feeder devices.

1. Where applicable, the analysis shall include the standby and emergency power system components, including the standby power source fault currents and overcurrent device operations.
2. Terminate device characteristics curves at a point reflecting maximum symmetrical or asymmetrical fault current to which the device is exposed.
3. The protective device settings shall address the need to minimize arc flash hazards while maintaining proper coordination.

B. Comply with recommendations for fault currents and time intervals dictated within the latest edition of the following:

1. IEEE 241 – IEEE Recommended Practice for Electric Power Systems in Commercial Buildings
2. IEEE 242 – IEEE Recommended Practice for Protection and Coordination of Industrial and Commercial Power Systems

C. Transformer Primary Overcurrent Protective Devices:

1. Device shall not operate in response to the following:

- a. Inrush current when first energized.
 - b. Self-cooled, full-load current or forced-air-cooled, full-load current, whichever is specified for that transformer.
 - c. Permissible transformer overloads according to IEEE C57.96 if required by unusual loading or emergency conditions.
- 2. Device settings shall protect transformers according to IEEE C57.12.00, for fault currents.
- D. Conductor Protection: Protect cables against damage from fault currents according to ICEA P 32-382, ICEA P-45-482 and conductor melting curves in IEEE 242. Demonstrate that equipment withstands the maximum short-circuit current for a time equivalent to the tripping time of the primary relay protection or total clearing time of the fuse. To determine temperatures that damage insulation, use curves from cable manufacturers or from listed standards indicating conductor size and short-circuit current.
- E. Selective Coordination Analysis
 - 1. Provide a complete selective coordination analysis, comparing time/current curves of the protective devices to be installed to assure complete selectivity between main and downstream devices for code-required branches and branches identified specifically on the one-line diagram.
 - 2. Provide settings of protective devices to assure complete selectivity between devices as indicated below and as required by Code while providing proper protection.
- F. Coordination-Study Report: Prepare a written report indicating the following results of coordination study:
 - 1. One-Line Diagram: Provide a one-line diagram which clearly identifies individual equipment buses, bus numbers, protective device identification numbers and the maximum available short-circuit current at each bus when known.
 - 2. Tabular Format of Settings Selected for Overcurrent Protective Devices: Provide a separate tabular printout containing the type and recommended settings of all adjustable overcurrent protective device parameters, the equipment designation where the device is located, and the device number corresponding to the device on the system one-line diagram.
 - 3. Coordination Curves: Prepare log-log scale graphs using time-current curves to determine settings of series connected overcurrent protective devices to achieve selective coordination. Graphically illustrate that adequate time separation exists between devices installed in series, including power utility company's upstream devices. Prepare separate sets of curves for the switching schemes and for emergency periods where the power source is local generation. Identify the device associated with each curve by device identification tag, manufacturer type, function and, if applicable, tap, time delay and instantaneous settings recommended. In addition, include the following information on the time-current curve graphs, where applicable:
 - a. Electric utility's overcurrent protective device.
 - i. Medium voltage equipment overcurrent relays.
 - ii. Medium and low voltage fuses including manufacturer's minimum melt, total clearing, tolerance and damage bands.
 - b. Low voltage equipment circuit breaker trip devices, including manufacturer's tolerance bands.
 - c. Transformer full-load current, magnetizing inrush current, and ANSI through-fault protection curves.
 - d. Ground fault protective devices.

- e. Pertinent motor starting characteristics and motor damage points.
 - f. Generator short-circuit decrement curve and generator damage point.
 - g. The largest feeder circuit breaker or fuse in each panelboard.
- 4. Include time current curves for both the phase and ground fault settings for each overcurrent protective device including device set points.
 - 5. Completed data sheets for setting of overcurrent protective devices.
- G. The Contractor shall notify the Engineer in writing of any significant deficiencies in protection and/or coordination, along with recommendations for improvements.

3.5 ARC FLASH HAZARD ANALYSIS

- A. Arc flash hazard analysis shall be performed according to the IEEE 1584 equations that are presented in NFPA70E-2024, Annex D after completion of settings for all overcurrent protective devices in the electrical model and calculation of the maximum available fault currents at each bus.
- B. Arc flash hazard analysis shall calculate the flash boundary and incident energy at all significant locations in the electrical distribution system (switchboards, switchgear, motor-control centers, panelboards, busway and splitters) where work could be performed on energized parts.
- C. Safe working distances shall be based on IEEE 1584. The calculated arc flash protection boundary shall be determined using those working distances.
- D. The fault calculations and resulting arc flash hazard calculation results shall be compared for multiple scenarios to determine the greatest incident energy for each equipment location. Calculations shall be performed at both maximum and minimum fault currents, and for scenarios where system is operating based upon utility or standby power sources.
 - 1. A minimum calculation shall assume the utility contribution is at a minimum and will assume a minimum motor contribution (all motors off).
 - 2. A maximum calculation will assume a maximum contribution from the utility and will assume the maximum amount of motors to be operating.
 - 3. A minimum calculation shall assume that the engine-generator set is operating and serving the system with all motors off.
- E. When appropriate, the short circuit calculations and the clearing times of the phase overcurrent devices shall be retrieved from the short-circuit and coordination study model. Ground overcurrent relays should not be taken into consideration when determining the clearing time when performing incident energy calculations.
- F. The incident energy calculations shall consider the accumulation of energy over time when performing arc flash calculations on buses with multiple sources. Iterative calculations shall take into account the changing current contributions, as the sources are interrupted or decremented with time. Fault contribution from motors and generators should be decremented as follows:
 - 1. Fault contribution from induction motors should not be considered beyond 3 to 5 cycles.
 - 2. Fault contribution from synchronous motors and generators should be decayed to match the actual decrement of each as closely as possible (e.g., contributions from permanent magnet generators will typically decay from 10 per unit to 3 per unit after 10 cycles).
- G. For each equipment location with a separately enclosed main device (where there is adequate separation between the line side terminals of the main protective device and the work location),

calculations for incident energy and flash protection boundary shall include both the line and load side of the main breaker.

- H. When performing incident energy calculations on the line side of a main breaker (as required per the above), the line side and load side contributions must be included in the fault calculation.
- I. Coordination should be checked among all devices within the branch containing the immediate protective device upstream of the calculation location, and the calculation should utilize the fastest device to compute the incident energy for the corresponding location.
- J. Arc flash calculations shall be based on actual overcurrent protective device clearing time. Maximum clearing time will be capped at 2 seconds based on IEEE 1584-2002.
- K. Where it is not physically possible to move outside the flash protection boundary in less than 2 seconds during an arc flash event, a maximum clearing time based on the specific location shall be utilized.
- L. Create and install NFPA 70E compliant labels describing the arc flash hazard level at all switchboards, panelboards, disconnect switches and other locations in the electrical distribution system where work could be performed on energized parts.
 - 1. The label shall include worst-case incident energy calculated in the analysis and the hazard category or appropriate personal protective equipment (PPE) required to perform maintenance on the system when energized, the available short circuit current at the equipment, the study report number and the date the calculations were performed. Labels shall be waterproof vinyl or laminated, with a self-adhesive backing.
 - 2. Provide labels on the front of each individual section of floor standing and wall mounted equipment.
 - 3. Install labels on the front of each individual section of floor standing and wall mounted equipment.
- M. A list of all hazard categories and the corresponding PPE requirements shall be posted in the main electric room, engineering office or other location. The list shall be plastic laminate or typewritten and housed in a plastic frame.
- N. Contractor shall submit the following:
 - 1. Results of the Arc-Flash Hazard Analysis in tabular form, Include device or bus name, bolted fault and arcing fault current levels, flash protection boundary distances, working distances, personal-protective equipment classes and Arc Flash Incident Energy Levels. Report shall clearly indicate which analysis scenario yielded the worst-case result.
 - 2. Report incident energy values based on recommended device settings for equipment within the scope of the study.
 - 3. Recommendations to reduce Arc Flash Incident Energy Levels and enhance worker safety, where applicable.

3.6 LABELING

- A. Apply one arc-flash label for each switchboard, engine-generator set, distribution panelboard, lighting and appliance panelboard, enclosed circuit breaker, portable generator docking station, and disconnect switch.

3.7 ADJUSTMENTS

- A. Manufacturer's authorized representative or Contractor shall set all adjustable protective devices to values indicated in the approved coordination study.
- B. The Contractor shall make minor modifications to equipment as required to accomplish conformance with short circuit and protective device coordination studies.
- C. The Short Circuit Study, Coordination Study and Arc Flash Hazard Analysis shall be reviewed and updated to reflect any changes and corrections to conductor length within one week of the final electrical walk through for punch list.

3.8 APPLICATION OF WARNING LABELS

- A. Install the arc-fault warning labels under the direct supervision and control of the Arc Flash Study Specialist.

3.9 DEMONSTRATION

- A. Provide two hours of Owner training relating to arc flash hazard risks and labeling.

END OF SECTION 26 05 73

This page intentionally left blank.

SECTION 26 09 23 - LIGHTING CONTROL DEVICES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Time switches.
 - 2. Photoelectric switches.
 - 3. Indoor occupancy and vacancy sensors.
 - 4. Switchbox-mounted occupancy sensors.
 - 5. Lighting contactors.
 - 6. Emergency shunt relays.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings:
 - 1. Interconnection diagrams showing field-installed wiring.
 - 2. Include diagrams for power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.
- B. Sample Warranty: For manufacturer's warranties.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For each type of lighting control device to include in operation and maintenance manuals.

1.6 WARRANTY

- A. Manufacturer's Warranty: Manufacturer and Installer agree to repair or replace lighting control devices that fail(s) in materials or workmanship within specified warranty period.
 - 1. Failures include, but are not limited to, the following:

- a. Faulty operation of lighting control software.
 - b. Faulty operation of lighting control devices.
- 2. Warranty Period: Two year(s) from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 TIME SWITCHES

- A. Electronic Time Switches: Solid state, programmable, with alphanumeric display; complying with UL 917.
 - 1. Listed and labeled as defined in NFPA 70 and marked for intended location and application.
 - 2. Automatic daylight savings time changeover.
 - 3. Battery Backup: Not less than seven days reserve, to maintain schedules and time clock.

2.2 OUTDOOR PHOTOELECTRIC SWITCHES

- A. Description: Solid state, with dry contacts rated for 1800 VA inductive, to operate connected relay, contactor coils, or microprocessor input; complying with UL 773A, and compatible with ballasts and LED lamps.
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Light-Level Monitoring Range: 1.5 to 10 fc, with an adjustment for turn-on and turn-off levels within that range, and a directional lens in front of the photocell to prevent fixed light sources from causing turn-off.
 - 3. Time Delay: Fifteen-second minimum, to prevent false operation.
 - 4. Surge Protection: Metal-oxide varistor.
 - 5. Mounting: Twist lock complies with NEMA C136.10, with base-and-stem mounting or stem-and-swivel mounting accessories as required to direct sensor to the north sky exposure.
 - 6. Failure Mode: Luminaire stays ON.

2.3 INDOOR OCCUPANCY AND VACANCY SENSORS

- A. General Requirements for Sensors:
 - 1. Solid-state indoor occupancy/vacancy sensors. (Field Selectable)
 - 2. Dual technology. Unless noted on drawings.
 - 3. Power pack.
 - 4. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 5. Operation:
 - a. Occupancy Sensor: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.

- b. Vacancy Sensor: Unless otherwise indicated, lights are manually turned on and sensor turns lights off when the room is unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
 - c. Combination Sensor: Unless otherwise indicated, sensor shall be programmed to turn lights on when coverage area is occupied and turn them off when unoccupied, or to turn off lights that have been manually turned on; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
 - 6. Power Pack: Dry contacts rated for 20-A LED load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Sensor has 24-V dc, 150-mA, Class 2 power source, as defined by NFPA 70.
 - 7. Mounting:
 - a. Sensor: Suitable for mounting in any position on a standard outlet box.
 - b. Relay: Externally mounted through a 1/2-inch knockout in a standard electrical enclosure.
 - c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.
 - 8. Bypass Switch: Override the "on" function in case of sensor failure.
 - 9. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc; turn lights off when selected lighting level is present.
- B. PIR Type: detect occupants in coverage area by their heat and movement.
- 1. Detector Sensitivity: Detect occurrences of 6-inch- minimum movement of any portion of a human body that presents a target of not less than 36 sq. in..
 - 2. Detection Coverage (Room, Ceiling Mounted): Detect occupancy anywhere in a circular area of 1000 sq. ft. when mounted on a 96-inch- high ceiling.
 - 3. Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 square feet when mounted 48 inches above finished floor.
- C. Ultrasonic Type: detect occupants in coverage area through pattern changes of reflected ultrasonic energy.
- 1. Detector Sensitivity: Detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
 - 2. Detection Coverage (Small Room): Detect occupancy anywhere within a circular area of 600 sq. ft. when mounted on a 96-inch- high ceiling.
 - 3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch- high ceiling.
 - 4. Detection Coverage (Large Room): Detect occupancy anywhere within a circular area of 2000 sq. ft. when mounted on a 96-inch- high ceiling.
 - 5. Detection Coverage (Corridor): Detect occupancy anywhere within 90 feet when mounted on a 10-foot- high ceiling in a corridor not wider than 14 feet.
 - 6. Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 square feet when mounted 48 inches above finished floor.
- D. Dual-Technology Type: detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of technologies that control on-off functions is selectable in the field by operating controls on unit.
- 1. Sensitivity Adjustment: Separate for each sensing technology.

2. Detector Sensitivity: Detect occurrences of 6-inch- minimum movement of any portion of a human body that presents a target of not less than 36 sq. in., and detect a person of average size and weight moving not less than 12 inches in either a horizontal or a vertical manner at an approximate speed of 12 inches/s.
3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. when mounted on a 96-inch- high ceiling.
4. Detection Coverage (Room, Wall Mounted): Detect occupancy anywhere within a 180-degree pattern centered on the sensor over an area of 1000 square feet when mounted 48 inches above finished floor.

2.4 SWITCHBOX-MOUNTED OCCUPANCY SENSORS

- A. General Requirements for Sensors: Automatic-wall-switch occupancy sensor with manual on-off switch, suitable for mounting in a single gang switchbox using hardwired connection.
 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 2. Occupancy Sensor Operation: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn lights off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
 3. Operating Ambient Conditions: Dry interior conditions, 32 to 120 deg F.
 4. Switch Rating: Not less than 800-VA LED load at 120 V, or LED load at 277 V.
- B. Wall-Switch Sensor:
 1. Standard Range: 180-degree field of view, field adjustable from 180 to 40 degrees; with a minimum coverage area of 900 sq. ft..
 2. Sensing Technology: Dual technology - PIR and ultrasonic.
 3. Capable of controlling load in three-way application.
 4. Voltage: Dual voltage - 120 and 277 V.
 5. Concealed, field-adjustable, "off" time-delay selector at up to 30 minutes.

2.5 LIGHTING CONTACTORS

- A. Description: Electrically operated and mechanically held, combination-type lighting contactors complying with NEMA ICS 2 and UL 508.
 1. Current Rating for Switching: Listing or rating consistent with type of load served, including tungsten filament, inductive, and high-inrush ballast (ballast with 15 percent or less THD of normal load current).
 2. Fault Current Withstand Rating: Equal to or exceeding the available fault current at the point of installation.
 3. Enclosure: Comply with NEMA 250.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine lighting control devices before installation. Reject lighting control devices that are wet, moisture damaged, or mold damaged.

- B. Examine walls and ceilings for suitable conditions where lighting control devices will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 SENSOR INSTALLATION

- A. Comply with NECA 1.
- B. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression systems, and partition assemblies.
- C. Install and aim sensors in locations to achieve not less than 90-percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.

3.3 CONTACTOR INSTALLATION

- A. Comply with NECA 1.
- B. Mount electrically held lighting contactors with elastomeric isolator pads to eliminate structure-borne vibration unless contactors are installed in an enclosure with factory-installed vibration isolators.

3.4 WIRING INSTALLATION

- A. Comply with NECA 1.
- B. Wiring Method: Comply with Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size is 1/2 inch.
- C. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and nonpower-limited conductors according to conductor manufacturer's written instructions.
- D. Size conductors according to lighting control device manufacturer's written instructions unless otherwise indicated.
- E. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.

3.5 IDENTIFICATION

- A. Identify components and power and control wiring according to Section 26 05 53 "Identification for Electrical Systems."
 - 1. Identify controlled circuits in lighting contactors.
 - 2. Identify circuits or luminaires controlled by photoelectric and occupancy sensors at each sensor.

- B. Label time switches and contactors with a unique designation.

3.6 FIELD QUALITY CONTROL

- A. Lighting control devices will be considered defective if they do not pass tests and inspections.
- B. Prepare test and inspection reports.

3.7 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months from date of Substantial Completion, provide on-site assistance in adjusting lighting control devices to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.
 - 1. For occupancy and motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.
 - 2. Align high-bay occupancy sensors using manufacturer's laser aiming tool.

3.8 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain lighting control devices.

END OF SECTION 26 09 23

SECTION 26 24 16 - PANELBOARDS

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Power panelboards.
2. Lighting and appliance branch-circuit panelboards.
3. Disconnecting and overcurrent protective devices.

B. Related Requirements:

1. Section 26 00 00 "Electrical General Requirements and Common Work Results" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 26 05 48 "Vibration and Seismic Controls for Electrical Systems" for seismic-load, wind-load, acoustical, and other field conditions applicable to Work specified in this Section.

1.2 DEFINITIONS

- A. GFEP: Ground-fault equipment protection.
- B. MCCB: Molded-case circuit breaker.
- C. VPR: Voltage protection rating.

1.3 ACTION SUBMITTALS

A. Product Data:

1. Power panelboards.
2. Lighting and appliance branch-circuit panelboards.
3. Disconnecting and overcurrent protective devices.
4. Include materials, switching and overcurrent protective devices, SPDs, accessories, and components indicated.
5. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, and finishes.

B. Shop Drawings: For each panelboard and related equipment.

1. Include dimensioned plans, elevations, sections, and details.
2. Show tabulations of installed devices with nameplates, conductor termination sizes, equipment features, and ratings.

3. Detail enclosure types including mounting and anchorage, environmental protection, knockouts, corner treatments, covers and doors, gaskets, hinges, and locks.
4. Detail bus configuration, current, and voltage ratings.
5. Short-circuit current rating of panelboards and overcurrent protective devices.
6. Include evidence of listing, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for SPD as installed in panelboard.
7. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
8. Include wiring diagrams for power, signal, and control wiring.
9. Key interlock scheme drawing and sequence of operations, if applicable.
10. Include time-current coordination curves for each type and rating of overcurrent protective device included in panelboards. Include selectable ranges for each type of overcurrent protective device. Include Internet link for electronic access to downloadable PDF of coordination curves.

1.4 CLOSEOUT SUBMITTALS

- A. Warranty documentation.

1.5 DELIVERY, STORAGE, AND HANDLING

- A. Remove loose packing and flammable materials from inside panelboards; install temporary electric heating (250 W per panelboard) to prevent condensation.
- B. Handle and prepare panelboards for installation in accordance with NECA 407.

1.6 WARRANTY

- A. Warranty: Installer warrants that fabricated and installed panelboards perform in accordance with specified requirements and agrees to repair or replace components or products that fail to perform as specified within extended-warranty period.
 1. Warranty Period: Two years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 PANELBOARDS COMMON REQUIREMENTS

- A. Fabricate and test panelboards in accordance with IEEE 344 to withstand seismic forces defined in Section 26 05 48 "Vibration and Seismic Controls for Electrical Systems."
- B. Product Selection for Restricted Space: Drawings indicate maximum dimensions for panelboards including clearances between panelboards and adjacent surfaces and other items. Comply with indicated maximum dimensions.

- C. Electrical Components, Devices, and Accessories: Listed and labeled in accordance with NFPA 70, by qualified electrical testing agency recognized by authorities having jurisdiction, and marked for intended location and application.
- D. Comply with NEMA PB 1.
- E. Comply with NFPA 70.
- F. Manufacturers:
 - 1. Eaton
 - 2. Square D (Schneider Electric)
 - 3. ABB
- G. Enclosures: Flush or Surface-mounted as shown on drawings, dead-front cabinets.
 - 1. Rated for environmental conditions at installed location.
 - a. Indoor Dry and Clean Locations: UL 50E, Type 1.
 - b. Outdoor Locations: UL 50E, Type 3R.
 - c. Kitchen Wash-Down Areas: UL 50E, Type 4X, stainless steel.
 - d. Other Wet or Damp Indoor Locations: UL 50E,.
 - e. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: UL 50E, Type 12.
 - 2. Height: 7 feet 7 feet maximum.
 - 3. Front: Secured to box with concealed trim clamps. For surface-mounted fronts, match box dimensions; for flush-mounted fronts, overlap box. Trims must cover live parts and may have no exposed hardware. Front hinged standard door within center of trim cover.
 - 4. Finishes:
 - a. Panels and Trim: Steel, factory finished immediately after cleaning and pretreating with manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
 - b. Back Boxes: Galvanized steel
- H. Incoming Mains:
 - 1. Location: Convertible between top and bottom. Contractor to coordinate and verify top or bottom entry per field conditions.
 - 2. Main Breaker: Main lug interiors up to 400 A must be field convertible to main breaker.
- I. Phase, Neutral, and Ground Buses:
 - 1. Material: Hard-drawn copper, 98 percent conductivity.
 - a. Plating must run entire length of bus.
 - b. Bus must be fully rated for entire length.

2. Interiors must be factory assembled into unit. Replacing switching and protective devices may not disturb adjacent units or require removing main bus connectors.
3. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment grounding conductors; bonded to box.
4. Full-Sized Neutral: Equipped with full-capacity bonding strap for service entrance applications. Mount electrically isolated from enclosure.
5. Do not mount neutral bus in gutter.

J. Conductor Connectors: Suitable for use with conductor material and sizes.

1. Material: Hard-drawn copper, 98 percent conductivity.
2. Terminations must allow use of 75 deg C rated conductors without derating.
3. Size: Lugs suitable for indicated conductor sizes, with additional gutter space, if required, for larger conductors.
4. Main and Neutral Lugs: Mechanical type, with lug on neutral bar for each pole in panelboard.
5. Ground Lugs and Bus-Configured Terminators: Mechanical type, with lug on bar for each pole in panelboard.
6. Feed-Through Lugs: Mechanical type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.
7. Subfeed (Double) Lugs: Mechanical type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.

K. Quality-Control Label: Panelboards or load centers must be labeled, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for use as service equipment with one or more main service disconnecting and overcurrent protective devices. Panelboards or load centers must have meter enclosures, wiring, connections, and other provisions for utility metering. Coordinate with utility company for exact requirements.

L. Panelboard Short-Circuit Current Rating:

1. Fully rated to interrupt symmetrical short-circuit current available at terminals. Assembly listed, by qualified electrical testing laboratory recognized by authorities having jurisdiction, for 100 percent interrupting capacity.
 - a. Panelboards and overcurrent protective devices rated 240 V or less must have short-circuit ratings as shown on Drawings, but not less than 10, 000 A(rms) symmetrical.
 - b. Panelboards and overcurrent protective devices rated above 240 V and less than 600 V must have short-circuit ratings as shown on Drawings, but not less than 14, 000 A(rms) symmetrical.

M. Surge Suppression: Factory installed as integral part of indicated panelboards, complying with UL 1449 SPD Type 2.

2.2 POWER (DISTRIBUTION) PANELBOARDS

- A. Listing Criteria: NEMA PB 1, distribution type.
- B. Doors: Secured with vault-type latch with tumbler lock; keyed alike.
 - 1. For doors more than 36 inch high, provide two latches, keyed alike.
- C. Mains: Circuit breaker or Lugs only as specified on drawings.
- D. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes 125 A and Smaller: Bolt-on circuit breakers.
- E. Branch Overcurrent Protective Devices for Circuit-Breaker Frame Sizes Larger Than 125 A: Bolt-on circuit breakers.

2.3 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

- A. Listing Criteria: NEMA PB 1, lighting and appliance branch-circuit type.
- B. Mains: Circuit breaker or lugs only as specified on drawings
- C. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.
- D. Doors: Door-in-door construction with concealed hinges; secured with flush latch with tumbler lock; keyed alike. Outer door must permit full access to panel interior. Inner door must permit access to breaker operating handles and labeling, but current carrying terminals and bus must remain concealed.

2.4 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

- A. MCCB: Comply with UL 489, with interrupting capacity to meet available fault currents. Refer to drawings for designation of devices with adjustable LSI settings.
 - 1. Thermal-Magnetic Circuit Breakers:
 - a. Inverse time-current element for low-level overloads.
 - b. Instantaneous magnetic trip element for short circuits.
 - c. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
 - 2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
 - 3. Electronic Trip Circuit Breakers:
 - a. RMS sensing.
 - b. Field-replaceable rating plug or electronic trip.
 - c. Digital display of settings, trip targets, and indicated metering displays.

- d. Multi-button keypad to access programmable functions and monitored data.
- e. Ten-event, trip-history log. Each trip event must be recorded with type, phase, and magnitude of fault that caused trip.
- f. Integral test jack for connection to portable test set or laptop computer.
- g. Field-Adjustable Settings:
 - 1) Instantaneous trip.
 - 2) Long- and short-time pickup levels.
 - 3) Long and short time adjustments.
 - 4) Ground-fault pickup level, time delay, and I squared T response.
- 4. GFCI Circuit Breakers: Single- and double-pole configurations with Class A ground-fault protection (6 mA trip).
- 5. GFEP Circuit Breakers: Class B ground-fault protection (30 mA trip).
- 6. Arc-Fault Circuit Interrupter Circuit Breakers: Comply with UL 1699; 120/240 V, single-pole configuration.
- 7. Subfeed Circuit Breakers: Vertically mounted.
- 8. 100% Rated: Where indicated on drawings provide circuit breaker and panelboard rated for continuous operation at 100 percent of the rating.
- 9. MCCB Features and Accessories:
 - a. Standard frame sizes, trip ratings, and number of poles.
 - b. Breaker handle indicates tripped status.
 - c. UL listed for reverse connection without restrictive line or load ratings.
 - d. Lugs: Mechanical style, suitable for number, size, trip ratings, and conductor materials.
 - e. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and HID lighting circuits.
 - f. Ground-Fault Protection: Integrally mounted relay and trip unit with adjustable pickup and time-delay settings, push-to-test feature, and ground-fault indicator.
 - g. Shunt Trip: 120 V trip coil energized from separate circuit, set to trip at 55 percent of rated voltage or as otherwise noted on drawings
 - h. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Verify actual conditions with field measurements prior to ordering panelboards to verify that equipment fits in allocated space in, and comply with, minimum required clearances specified in NFPA 70.
- B. Receive, inspect, handle, and store panelboards in accordance with NECA 407 and NEMA PB 1.1.

- C. Examine panelboards before installation. Reject panelboards that are damaged, rusted, or have been subjected to water saturation.
- D. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of the Work.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with manufacturer's published instructions.
- B. Reference Standards:
 - 1. Panelboards: Unless more stringent requirements are specified in Contract Documents or manufacturers' published instructions, comply with NECA 407 and NEMA PB 1.1.
 - 2. Consult Architect for resolution of conflicting requirements.
- C. Special Techniques:
 - 1. Equipment Mounting:
 - a. Install panelboards on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in Section 03 30 00 "Cast-in-Place Concrete."
 - b. Attach panelboard to vertical finished or structural surface behind panelboard.
 - c. For damp, wet, or dirty locations, mount surface-mounted panelboards to steel slotted supports 1-1/4 inch in depth. Orient steel slotted supports vertically.
 - d. Comply with requirements for seismic control devices specified in Section 26 05 48.01 "Vibration and Seismic Controls for Electrical Systems."
 - 2. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from panelboards.
 - 3. Mount top of trim 7.5 ft above finished floor unless otherwise indicated.
 - 4. Mount panelboard cabinet plumb and rigid without distortion of box.
 - 5. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.
 - 6. Install overcurrent protective devices and controllers not already factory installed.
 - a. Set field-adjustable, circuit-breaker trip ranges.
 - b. Tighten bolted connections and circuit breaker connections using calibrated torque wrench or torque screwdriver in accordance with manufacturer's published instructions.

7. Make grounding connections and bond neutral for services and separately derived systems to ground. Make connections to grounding electrodes, separate grounds for isolated ground bars, and connections to separate ground bars.
8. Install filler plates in unused spaces.
9. Stub four 1 inch empty conduits from panelboard into accessible ceiling space or space designated to be ceiling space in future.
10. Arrange conductors in gutters into groups and bundle and wrap with wire ties.

D. Interfaces with Other Work:

1. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

3.3 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; install warning signs complying with requirements in Section 26 05 53 "Identification for Electrical Systems."
- B. Panelboard Nameplates: Label each panelboard with nameplate complying with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."
- C. Device Nameplates: Label each branch circuit device in power panelboards with nameplate complying with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."
- D. Install warning signs complying with requirements in Section 26 05 53 "Identification for Electrical Systems" identifying source of remote circuit.
- E. Panelboard Label: Manufacturer's name and trademark, voltage, amperage, number of phases, and number of poles must be located on interior of panelboard door.
- F. Breaker Labels: Faceplate must list current rating, UL and IEC certification standards, and AIC rating.
- G. Circuit Directory:
 1. Provide typed directory card inside panelboard door, mounted in transparent card holder.
 - a. Circuit directory must identify specific purpose with detail sufficient to distinguish it from other circuits.
 2. Provide computer-generated circuit directory mounted inside panelboard door with transparent plastic protective cover.

- a. Circuit directory must identify specific purpose with detail sufficient to distinguish it from other circuits.

3.4 FIELD QUALITY CONTROL

A. Acceptance Testing Preparation:

1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
2. Test continuity of each circuit.

B. Tests and Inspections:

1. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.

C. Nonconforming Work:

1. Panelboards will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective units and retest.

D. Collect, assemble, and submit test and inspection reports, including certified report that identifies panelboards included and that describes scanning results, with comparisons of two scans. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 ADJUSTING

A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.

B. Set field-adjustable circuit-breaker trip ranges as specified in Section 26 07 53 "Power Systems Studies."

3.6 PROTECTION

A. Temporary Heating: Prior to energizing panelboards, apply temporary heat to maintain temperature in accordance with manufacturer's published instructions.

END OF SECTION 26 24 16

This page intentionally left blank.

SECTION 26 27 26 - WIRING DEVICES

PART 1 - GENERAL

1.1 SUMMARY

A. Section Includes:

1. Heavy duty switches, dimmer switches, and fan-speed controller switches.
2. Specification grade single straight-blade receptacles.
3. Specification grade duplex straight-blade receptacles.
4. Special-purpose power outlet assemblies (cord reels).
5. Connectors, cords, and plugs.

B. Related Requirements:

1. Section 26 00 00 "Electrical General Requirements" for additional abbreviations, definitions, submittals, qualifications, testing agencies, and other Project requirements applicable to Work specified in this Section.
2. Section 26 09 23 "Lighting Control Devices" for occupancy sensors, timers, control-voltage switches, and control-voltage dimmers.

1.2 DEFINITIONS

- A. Commercial/Industrial-Use Cord Reel: A cord reel subject to severe use in factories, commercial garages, construction sites, and similar locations requiring a harder service-type cord.
- B. UL 1472 Type I Dimmer: Dimmer in which air-gap switch is used to energize preset lighting levels.

1.3 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

1.4 WARRANTY FOR CORD REELS

- A. Special Installer Extended Warranty: Installer warrants that fabricated and installed cord-reel power outlet assemblies perform in accordance with specified requirements and agrees to repair or replace assemblies that fail to perform as specified within extended warranty period.
 - 1. Extended Warranty Period: Two years from date of Substantial Completion; full coverage for labor, materials, and equipment.
- B. Special Manufacturer Extended Warranty: Manufacturer warrants that components of cord-reel power outlet assemblies perform in accordance with specified requirements and agrees to provide repair or replacement of components that fail to perform as specified within extended warranty period.
 - 1. Initial Extended Warranty Period: Five years from date of Substantial Completion; full coverage for labor, materials, and equipment.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Cooper Wiring Devices; a division of Cooper Industries, Inc. (Cooper).
- B. Hubbell Incorporated; Wiring Device-Kellems (Hubbell).
- C. Leviton Mfg. Company Inc. (Leviton).
- D. Pass & Seymour/Legrand; Wiring Devices & Accessories (Pass & Seymour).

2.2 SPECIFICATION-GRADE SINGLE STRAIGHT-BLADE RECEPTACLES

- A. Single Straight-Blade Receptacle:
 - 1. Regulatory Requirements:
 - a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. General Characteristics:
 - a. Reference Standards: UL CCN RTRT and UL 498.
 - 3. Options:
 - a. Device Color: White.
 - b. Configuration:
 - 1) Specification grade NEMA 5-20R.
 - 2) Specification grade smooth face, NEMA 5-20R.

4. Accessories:

- a. Cover Plate: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device; from same manufacturer as wiring device.
 - 1) Coverplates in the following areas shall be high-impact thermoplastic as indicated above: Bunk Rooms, Bunk Corridor, Lockers, Office, Restrooms, and associated spaces.
 - 2) Coverplates in the following areas shall be 304/430 stainless steel: Apparatus Bays, Laundry, Mechanical/Electrical, Fitness, Extractor Shelter and Gear Room.
- b. Securing Screws for Cover Plate: Metal with head color matching wallplate finish.

2.3 SPECIFICATION-GRADE DUPLEX STRAIGHT-BLADE RECEPTACLES

A. Duplex Straight-Blade Receptacle:

1. Regulatory Requirements:

- a. Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.

2. General Characteristics:

- a. Reference Standards: UL CCN RTRT and UL 498.

3. Options:

- a. Device Color: White.
- b. Configuration:
 - 1) Specification Grade, NEMA 5-20R.
 - 2) Specification Grade, smooth face NEMA 5-20R.

4. Accessories:

- a. Cover Plate: 0.060 inch thick, high-impact thermoplastic (nylon) with smooth finish and color matching wiring device; from same manufacturer as wiring device.
 - 1) Coverplates in the following areas shall be high-impact thermoplastic as indicated above: Bunk Rooms, Bunk Corridor, Lockers, Office, Restrooms, and associated spaces.
 - 2) Coverplates in the following areas shall be 304/430 stainless steel: Apparatus Bays, Laundry, Mechanical/Electrical, Fitness, Extractor Shelter and Gear Room.
- b. Securing Screws for Cover Plate: Metal with head color matching wallplate finish.

2.4 SPECIAL-PURPOSE POWER OUTLET ASSEMBLIES

- A. Spring-Driven Commercial/Industrial-Use Cord Reel, No. 12 AWG Conductors Insert drawing designation:
 - 1. Regulatory Requirements: Listed and labeled in accordance with NFPA 70, by qualified electrical testing laboratory recognized by authorities having jurisdiction, and marked for intended location and application.
 - 2. General Characteristics:
 - a. Reference Standards: UL CCN SBCV and UL 355.
 - b. Spring take-up retraction mechanism.
 - 3. Options:
 - a. Electrical Rating with Cable: 600 V, 20 A.
 - b. Color: Yellow.
 - c. Enclosure Degree of Protection: Type 4X.
 - d. Ball stop.
 - e. Pivot base.
 - f. Spool Capacity:
 - 1) No. 12 AWG, two wires and equipment ground, 50 ft.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Receptacles:
 - 1. Verify that receptacles to be procured and installed for Owner-furnished equipment are compatible with mating attachment plugs on equipment.
- B. Cord Reels:
 - 1. Examine roughing-in for cord reel mounting and power connections to verify actual locations of mounts and power connections before cord reel installation.
 - 2. Examine walls, floors, and ceilings for suitable conditions where cord reel will be installed.
 - 3. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION OF SWITCHES

- A. Comply with manufacturer's instructions.
- B. Reference Standards:
 - 1. Unless more stringent requirements are specified in Contract Documents or manufacturers' instructions, comply with installation instructions in NECA NEIS 130.

2. Mounting Heights: Unless otherwise indicated in Contract Documents, comply with mounting heights recommended in NECA NEIS 1.
3. Consult Architect for resolution of conflicting requirements.

3.3 INSTALLATION OF STRAIGHT-BLADE RECEPTACLES

- A. Comply with manufacturer's instructions.
- B. Reference Standards:
 1. Unless more stringent requirements are specified in Contract Documents or manufacturers' instructions, comply with installation instructions in NECA NEIS 130.
 2. Mounting Heights: Unless otherwise indicated in Contract Documents, comply with mounting heights recommended in NECA NEIS 1.
 3. Consult Architect for resolution of conflicting requirements.
- C. Identification:
 1. Identify cover or cover plate for device with panelboard identification and circuit number in accordance with Section 26 05 53 "Identification for Electrical Systems."
 - a. Mark cover or cover plate using hot, stamped, or engraved machine printing with black-filled lettering, and provide durable wire markers or tags inside device box or outlet box.
- D. Interfaces with Other Work:
 1. Do not install Type 3 SPD, including surge-protected relocatable taps and power strips, on branch circuit downstream of GFCI device.

3.4 INSTALLATION OF LOCKING RECEPTACLES

- A. Comply with manufacturer's instructions.
- B. Reference Standards:
 1. Unless more stringent requirements are specified in Contract Documents or manufacturers' instructions, comply with installation instructions in NECA NEIS 130.
 2. Mounting Heights: Unless otherwise indicated in Contract Documents, comply with mounting heights recommended in NECA NEIS 1.
 3. Receptacle Orientation: Unless otherwise indicated in Contract Documents, orient receptacle to match configuration diagram in NEMA WD 6.
 4. Consult Architect for resolution of conflicting requirements.
- C. Identification:

1. Identify cover or cover plate for device with panelboard identification and circuit number in accordance with Section 26 05 53 "Identification for Electrical Systems."
 - a. Mark cover or cover plate using hot, stamped, or engraved machine printing with black-filled lettering, and provide durable wire markers or tags inside device box or outlet box.

3.5 FIELD QUALITY CONTROL OF SWITCHES

A. Tests and Inspections:

1. Perform tests and inspections in accordance with manufacturers' instructions.

B. Nonconforming Work:

1. Unit will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

3.6 FIELD QUALITY CONTROL OF RECEPTACLES

A. Tests and Inspections:

1. Insert and remove test plug to verify that device is securely mounted.
2. Verify polarity of hot and neutral pins.
3. Measure line voltage.

B. Nonconforming Work:

1. Device will be considered defective if it does not pass tests and inspections.
2. Remove and replace defective units and retest.

3.7 FIELD QUALITY CONTROL OF CORD REELS AND FITTINGS

A. Tests and Inspections:

1. Perform tests and inspections indicated in manufacturer's instructions.

B. Nonconforming Work:

1. Components and assemblies will be considered defective if they do not pass tests and inspections.
2. Remove and replace defective units and retest.

C. Assemble and submit test and inspection reports.

3.8 SYSTEM STARTUP FOR SWITCHES

A. Perform startup service.

1. Complete installation and startup checks for momentary switches, dimmer switches, and fan-speed controller switches in accordance with manufacturer's instructions.

3.9 PROTECTION

A. Devices:

1. Schedule and sequence installation to minimize risk of contamination of wires and cables, devices, device boxes, outlet boxes, covers, and cover plates by plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other materials.
2. After installation, protect wires and cables, devices, device boxes, outlet boxes, covers, and cover plates from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

B. Cord Reels and Fittings:

1. After installation, protect cord reels and fittings from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

C. Connectors, Cords, and Plugs:

1. After installation, protect connectors, cords, and plugs from construction activities. Remove and replace items that are contaminated, defaced, damaged, or otherwise caused to be unfit for use prior to acceptance by Owner.

END OF SECTION 26 27 26

This page intentionally left blank.

SECTION 26 28 13

FUSES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Cartridge fuses rated 600-V ac and less for use in control circuits, enclosed switches, and enclosed controllers.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material, dimensions, descriptions of individual components, and finishes for spare-fuse cabinets. Include the following for each fuse type indicated:
 - 1. Ambient Temperature Adjustment Information: If ratings of fuses have been adjusted to accommodate ambient temperatures, provide list of fuses with adjusted ratings.
 - a. For each fuse having adjusted ratings, include location of fuse, original fuse rating, local ambient temperature, and adjusted fuse rating.
 - b. Provide manufacturer's technical data on which ambient temperature adjustment calculations are based.
 - 2. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
 - 3. Current-limitation curves for fuses with current-limiting characteristics.
 - 4. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit on translucent log-log graph paper.
 - 5. Coordination charts and tables and related data.
 - 6. Fuse sizes for elevator feeders and elevator disconnect switches.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For fuses to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. Ambient temperature adjustment information.
 - 2. Current-limitation curves for fuses with current-limiting characteristics.

3. Time-current coordination curves (average melt) and current-limitation curves (instantaneous peak let-through current) for each type and rating of fuse. Submit on translucent log-log graph paper.
4. Coordination charts and tables and related data.

1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 1. Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than two of each size and type.

1.6 QUALITY ASSURANCE

- A. Source Limitations: Obtain fuses, for use within a specific product or circuit, from single source from single manufacturer.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Comply with NEMA FU 1 for cartridge fuses.
- D. Comply with NFPA 70.
- E. Comply with UL 248-11 for plug fuses.

1.7 PROJECT CONDITIONS

- A. Where ambient temperature to which fuses are directly exposed is less than 40 deg F or more than 100 deg F, apply manufacturer's ambient temperature adjustment factors to fuse ratings.

1.8 COORDINATION

- A. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size and with system short-circuit current levels.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 1. Cooper Bussmann, Inc.

2. Edison Fuse, Inc.
3. Ferraz Shawmut, Inc.
4. Littelfuse, Inc.

2.2 CARTRIDGE FUSES

- A. Characteristics: NEMA FU 1, nonrenewable cartridge fuses with voltage ratings consistent with circuit voltages.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine fuses before installation. Reject fuses that are moisture damaged or physically damaged.
- B. Examine holders to receive fuses for compliance with installation tolerances and other conditions affecting performance, such as rejection features.
- C. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.
- D. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 FUSE APPLICATIONS

- A. Cartridge Fuses:
 1. Service Entrance: Class RK1, fast acting.
 2. Feeders: Class RK1, fast acting.
 3. Motor Branch Circuits: Class RK1, time delay.
 4. Other Branch Circuits: Class RK1, time delay.
 5. Control Circuits: Class CC, fast acting.

3.3 INSTALLATION

- A. Install fuses in fusible devices. Arrange fuses so rating information is readable without removing fuse.

3.4 IDENTIFICATION

- A. Install labels complying with requirements for identification specified in Division 26 Section "Identification for Electrical Systems" and indicating fuse replacement

information on inside door of each fused switch and adjacent to each fuse block, socket, and holder.

END OF SECTION 26 28 13

SECTION 26 28 16 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Fusible switches.
 - 2. Nonfusible switches.
 - 3. Shunt trip switches.
 - 4. Enclosed circuit breakers.
 - 5. Enclosures.

1.3 DEFINITIONS

- A. NC: Normally closed.
- B. NO: Normally open.
- C. SPDT: Single pole, double throw.

1.4 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Enclosed switches and circuit breakers shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

1.5 SUBMITTALS

- A. Product Data: For each type of enclosed switch, circuit breaker, accessory, and component indicated. Include dimensioned elevations, sections, weights, and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.
 - 1. Enclosure types and details for types other than NEMA 250, Type 1.
 - 2. Current and voltage ratings.
 - 3. Short-circuit current ratings (interrupting and withstand, as appropriate).
 - 4. Include evidence of NRTL listing for series rating of installed devices.

5. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices, accessories, and auxiliary components.
 6. Include time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device.
- B. Shop Drawings: For enclosed switches and circuit breakers. Include plans, elevations, sections, details, and attachments to other work.
1. Wiring Diagrams: For power, signal, and control wiring.
- C. Qualification Data: For qualified testing agency.
- D. Seismic Qualification Certificates: For enclosed switches and circuit breakers, accessories, and components, from manufacturer.
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- E. Field quality-control reports.
1. Test procedures used.
 2. Test results that comply with requirements.
 3. Results of failed tests and corrective action taken to achieve test results that comply with requirements.
- F. Manufacturer's field service report.
- G. Operation and Maintenance Data: For enclosed switches and circuit breakers to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
1. Manufacturer's written instructions for testing and adjusting enclosed switches and circuit breakers.
 2. Time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device.

1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Member company of NETA or an NRTL.
1. Testing Agency's Field Supervisor: Currently certified by NETA to supervise on-site testing.
- B. Source Limitations: Obtain enclosed switches and circuit breakers, overcurrent protective devices, components, and accessories, within same product category, from single source from single manufacturer.

- C. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches and circuit breakers, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- E. Comply with NFPA 70.

1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
 - 1. Ambient Temperature: Not less than minus 22 deg F and not exceeding 104 deg F.
 - 2. Altitude: Not exceeding 6600 feet.

1.8 COORDINATION

- A. Coordinate layout and installation of switches, circuit breakers, and components with equipment served and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

PART 2 - PRODUCTS

2.1 FUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
 - 2. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
 - 3. Siemens Energy & Automation, Inc.
 - 4. Square D; a brand of Schneider Electric.
- B. Type HD, Heavy Duty, Single Throw, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, with clips or bolt pads to accommodate fuses, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

2.2 NONFUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
 - 2. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
 - 3. Siemens Energy & Automation, Inc.
 - 4. Square D; a brand of Schneider Electric.

- B. Type HD, Heavy Duty, Single Throw, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.

2.3 SHUNT TRIP SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following
 - 1. Cooper Bussmann, Inc.
 - 2. Mersen, Inc.
 - 3. Littelfuse, Inc.
- B. General Requirements: Comply with ASME A17.1, UL 50, and UL 98, with 200-kA interrupting and short-circuit current rating when fitted with Class J fuses.
- C. Switches: Three-pole, horsepower rated, with integral shunt trip mechanism and Class J fuse block; lockable handle with capability to accept three padlocks; interlocked with cover in closed position.
- D. Control Circuit: 120-V ac; obtained from integral control power transformer, with primary and secondary fuses with a control power transformer of enough capacity to operate shunt trip, connected pilot, and indicating and control devices.
- E. Accessories:
 - 1. Oiltight key switch for key-to-test function.
 - 2. Oiltight ON pilot light.
 - 3. Isolated neutral lug; 100 percent rating.
 - 4. Mechanically interlocked auxiliary contacts that change state when switch is opened and closed.
 - 5. Form C alarm contacts that change state when switch is tripped.

2.4 CIRCUIT BREAKERS

- A. Molded Case Circuit Breaker: Comply with UL 489, with interrupting capacity to meet available fault currents.
 - 1. Electronic Trip Circuit Breakers:
 - a. RMS sensing.
 - b. Field-replaceable rating plug or electronic trip.
 - c. Digital display of settings, trip targets, and indicated metering displays.
 - d. Multi-button keypad to access programmable functions and monitored data.
 - e. Ten-event, trip-history log. Each trip event must be recorded with type, phase, and magnitude of fault that caused trip.
 - f. Integral test jack for connection to portable test set or laptop computer.
 - g. Field-Adjustable Settings:
 - 1) Instantaneous trip.
 - 2) Long- and short-time pickup levels.
 - 3) Long and short time adjustments.
 - 4) Ground-fault pickup level, time delay, and I squared T response.

2. Service Entrance Rated:
 - a. Provide UL 869A compliant equipment where indicated. Provide factory-installed service entrance label and removable main bonding jumper.

2.5 ENCLOSURES

- A. Enclosed Switches and Circuit Breakers: NEMA AB 1, NEMA KS 1, NEMA 250, and UL 50, to comply with environmental conditions at installed location.
 1. Indoor, Dry and Clean Locations: NEMA 250, Type 1.
 2. Outdoor Locations: NEMA 250, Type 3R.
 3. Indoor Locations Subject to Dust, Falling Dirt, and Dripping Noncorrosive Liquids: NEMA 250, Type 12.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Install individual wall-mounted switches and circuit breakers with tops at uniform height unless otherwise indicated.
- B. Comply with mounting and anchoring requirements specified in Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
- C. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.
- D. Install fuses in fusible devices.
- E. Comply with NECA 1.

3.3 IDENTIFICATION

- A. Comply with requirements in Division 26 Section "Identification for Electrical Systems."
 1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
 2. Label each enclosure with engraved metal or laminated-plastic nameplate.

3.4 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.
- B. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- C. Acceptance Testing Preparation:
 - 1. Test insulation resistance for each enclosed switch and circuit breaker, component, connecting supply, feeder, and control circuit.
 - 2. Test continuity of each circuit.
- D. Tests and Inspections:
 - 1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
 - 2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
 - 3. Perform the following infrared scan tests and inspections and prepare reports:
 - a. Initial Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each enclosed switch and circuit breaker. Remove front panels so joints and connections are accessible to portable scanner.
 - b. Instruments and Equipment: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - 4. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.
- E. Enclosed switches and circuit breakers will be considered defective if they do not pass tests and inspections.
- F. Prepare test and inspection reports, including a certified report that identifies enclosed switches and circuit breakers and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.5 ADJUSTING

- A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.
- B. Electronic trip circuit breakers shall be adjusted to the settings provided in the accepted Power System Study provided as part of the specification section 26 05 73 Study.

END OF SECTION 26 28 16

SECTION 26 32 13 ENGINE GENERATORS

PART 1 - GENERAL

1.1 WORK INCLUDES

- A. General:
 - 1. Provide the following:
 - a. Generator Set with Enclosure, EPO, and Auxiliaries.
 - b. Remote Annunciator.

1.2 SUMMARY

- A. This section includes packaged natural gas-engine generator sets with the following features and accessories:
 - 1. Battery charger.
 - 2. Engine-generator set.
 - 3. Muffler.
 - 4. Exhaust piping external to set.
 - 5. Outdoor sound attenuating enclosure.
 - 6. Remote stop switch.
 - 7. Starting battery.

1.3 DEFINITIONS

- A. Operational Bandwidth: The total variation from the lowest to highest value of a parameter over the range of conditions indicated, expressed as a percentage of the nominal value of the parameter.
- B. Steady-State Voltage Modulation: The uniform cyclical variation of voltage within the operational bandwidth, expressed in Hertz or cycles per second.

1.4 SUBMITTALS

- A. Product Data: Include the following:
 - 1. Data on features, components, accessories ratings, and performance.
 - 2. Thermal damage curve for generator.
 - 3. Time-current characteristic curves for generator protective device.
- B. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 1. Dimensioned outline plan and elevation drawings of engine-generator set and other components specified.

2. Vibration Isolation Base Details: Signed and sealed by a qualified professional engineer. Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include base weights.
 3. Wiring Diagrams: Power, signal, and control wiring.
- C. Welding certificates.
- D. Manufacturer Seismic Qualification Certification: Submit certification that engine-generator set, batteries, battery racks, accessories, and components will withstand seismic forces defined in Division 16 Section "Seismic Controls for Electrical Work." Include the following:
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - a. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- E. Qualification Data: For manufacturer.
- F. Certified summary of prototype-unit test report.
- G. Certified Test Reports: For components and accessories that are equivalent, but not identical, to those tested on prototype unit.
- H. Certified Summary of Performance Tests: Demonstrate compliance with specified requirement to meet performance criteria for sensitive loads.
- I. Test Reports:
1. Report of factory test on units to be shipped for this Project, showing evidence of compliance with specified requirements.
 2. Report of sound generation.
 3. Report of exhaust emissions showing compliance with applicable regulations.
 4. Field quality-control test reports.
- J. Certification of Torsional Vibration Compatibility: Comply with NFPA 110.
- K. Operation and Maintenance Data: For packaged engine generators to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 1 Section "Closeout Procedures Operation and Maintenance Data," include the following:
1. List of tools and replacement items recommended to be stored at the Project for ready access. Include part and drawing numbers, current unit prices, and source of supply.
- L. Warranty: Special warranty specified in this Section.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
 - 1. Maintenance Proximity: Not more than four hours' normal travel time from Installer's place of business to Project site.
 - 2. Engineering Responsibility: Preparation of data for vibration isolators and seismic restraints of engine skid mounts, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
- B. Manufacturer Qualifications: A qualified manufacturer. Maintain, within 200 miles of Project site, a service center capable of providing training, parts, and emergency maintenance repairs.
- C. Source Limitations: Obtain packaged generator sets and auxiliary components through one source from a single manufacturer.
- D. Product Options: Drawings indicate size, profiles, and dimensional requirements of packaged generator sets and are based on the specific system indicated. Refer to Division 1 Section "Product Requirements."
- E. Welding: Qualify procedures and personnel according to ASME Boiler and Pressure Vessel Code: Section IX for welding exhaust-system piping.
- F. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- G. Comply with NFPA 37.
- H. Comply with NFPA 70.
- I. Comply with NFPA 110 for a Level 1 Emergency System.
- J. Engine Exhaust Emissions: Comply with applicable state and local government requirements.
- K. Noise Emission: Comply with applicable state and local government requirements for maximum noise level at adjacent property boundaries due to sound emitted by generator set including engine, engine exhaust, engine cooling-air intake and discharge, and other components of installation. Refer to City of St. Peters MO Ordinance Ttl II Article X1 Section 210.390 for specific limitations.

1.6 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases.

1.7 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of packaged engine generators and associated auxiliary components that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: One year from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Caterpillar; Engine Div.
 - 2. Onan/Cummins
 - 3. Generac

2.2 ENGINE-GENERATOR SET

- A. Packaged engine-generator set shall be a coordinated assembly of compatible components.
- B. Power Output Ratings: Nominal ratings as indicated, with capacity as required to operate as a unit as evidenced by records of prototype testing.
- C. Output Connections: Per Drawings..
- D. Safety Standard: Comply with ASME B15.1.
- E. Nameplates: Each major system component shall be equipped with a nameplate to identify manufacturer's name and address, and model and serial number of component.
- F. Fabricate engine-generator-set mounting frame and attachment of components to resist generator-set movement during a seismic event.
- G. Mounting Frame: Adequate strength and rigidity to maintain alignment of mounted components without depending on concrete foundation. Mounting frame shall be free from sharp edges and corners and shall have lifting attachments arranged for lifting with slings without damaging components.
 - 1. Rigging Diagram: Inscribed on metal plate permanently attached to mounting frame to indicate location and lifting capacity of each lifting attachment and generator-set center of gravity.

2.3 GENERATOR-SET PERFORMANCE

- A. Steady-State Voltage Operational Bandwidth: 4 percent of rated output voltage from no load to full load.

- B. Steady-State Voltage Modulation Frequency: Less than 1 Hz.
- C. Transient Voltage Performance: Not more than 20 percent variation for 50 percent step-load increase or decrease. Voltage shall recover and remain within the steady-state operating band within three seconds.
- D. Steady-State Frequency Operational Bandwidth: 0.5 percent of rated frequency from no load to full load.
- E. Steady-State Frequency Stability: When system is operating at any constant load within the rated load, there shall be no random speed variations outside the steady-state operational band and no hunting or surging of speed.
- F. Transient Frequency Performance: Less than 5 percent variation for a 50 percent step-load increase or decrease. Frequency shall recover and remain within the steady-state operating band within five seconds.
- G. Output Waveform: At no load, harmonic content measured line to line or line to neutral shall not exceed 5 percent total and 3 percent for single harmonics. The telephone influence factor, determined according to NEMA MG 1, shall not exceed 50 percent.
- H. Sustained Short-Circuit Current: For a single-phase, bolted short circuit at system output terminals, the system shall supply a minimum of 250 percent of rated full-load current for not less than 10 seconds and then clear the fault automatically, without damage to generator system components.
- I. Start Time: Generator shall start and pick up load within 10 seconds of loss of normal power.

2.4 SERVICE CONDITIONS

- A. Environmental Conditions: Engine-generator system shall withstand the following environmental conditions without mechanical or electrical damage or degradation of performance capability:
 - 1. Ambient Temperature: Minus 15 to plus 40 deg C.
 - 2. Relative Humidity: 0 to 95 percent.
 - 3. Altitude: Sea level to 1000 feet.

2.5 ENGINE

- A. Fuel: Natural Gas.
- B. Rated Engine Speed: 1800 rpm.
- C. Lubrication System: The following items are mounted on engine or skid:
 - 1. Filter and Strainer: Rated to remove 90 percent of particles 5 micrometers and smaller while passing full flow.
 - 2. Thermostatic Control Valve: Control flow in system to maintain optimum oil temperature. Unit shall be capable of full flow and is designed to be fail-safe.

- 3. Crankcase Drain: Arranged for complete gravity drainage to an easily removable container with no disassembly and without use of pumps, siphons, special tools, or appliances.
- D. Engine Fuel System (Natural Gas):
 - 1. Primary and secondary fuel shutoff.
 - 2. Flexible fuel line – NPT connection
- E. Coolant Jacket Heater: Electric-immersion type, factory installed in coolant jacket system. Comply with NFPA 110 requirements for Level 1 equipment for heater capacity.
- F. Governor: Adjustable isochronous, with speed sensing.

2.6 ENGINE COOLING SYSTEM

- A. Description: Closed loop, liquid cooled, with radiator factory mounted on engine-generator-set mounting frame and integral engine-driven coolant pump.
- B. Radiator: Rated for specified coolant.
- C. Coolant: Solution of 50 percent ethylene-glycol-based antifreeze and 50 percent water, with anticorrosion additives as recommended by engine manufacturer.
- D. Expansion Tank: Constructed of welded steel plate and rated to withstand maximum closed-loop coolant system pressure for engine used. Equip with gage glass and petcock.
- E. Temperature Control: Self-contained, thermostatic-control valve modulates coolant flow automatically to maintain optimum constant coolant temperature as recommended by engine manufacturer.
- F. Coolant Hose: Flexible assembly with inside surface of nonporous rubber and outer covering of aging-, ultraviolet-, and abrasion-resistant fabric.
 - 1. Rating: 50-psig maximum working pressure with coolant at 180 deg F, and noncollapsible under vacuum.
 - 2. End Fittings: Flanges or steel pipe nipples with clamps to suit piping and equipment connections.

2.7 FUEL SUPPLY SYSTEM

- A. Comply with NFPA 30 and NFPA 54.

2.8 ENGINE EXHAUST SYSTEM

- A. Muffler: Critical type, sized as recommended by engine manufacturer; sound level measured at a distance of 10 feet from exhaust discharge shall be 71 dBA or less.

- B. Condensate Drain for Muffler: Schedule 40, black steel pipe connected to muffler drain outlet through a petcock.
- C. Connection from Engine to Exhaust System: Flexible section of corrugated stainless-steel pipe.
- D. Connection from Exhaust Pipe to Muffler: Stainless-steel expansion joint with liner.
- E. Muffler shall be internal to weatherproof housing.

2.9 COMBUSTION-AIR INTAKE

- A. Description: Heavy-duty, engine-mounted air cleaner with replaceable dry-filter element and "blocked filter" indicator.

2.10 STARTING SYSTEM

- A. Description: 24 -V electric, with negative ground and including the following items:
 1. Components: Sized so they will not be damaged during a full engine-cranking cycle with ambient temperature at maximum specified in "Environmental Conditions" Paragraph in "Service Conditions" Article.
 2. Cranking Motor: Heavy-duty unit that automatically engages and releases from engine flywheel without binding.
 3. Battery: Adequate capacity within ambient temperature range specified in "Environmental Conditions" Paragraph in "Service Conditions" Article to provide specified cranking cycle at least three times without recharging.
 4. Battery Cable: Size as recommended by engine manufacturer for cable length indicated. Include required interconnecting conductors and connection accessories.
 5. Battery Compartment: Factory fabricated of metal with acid-resistant finish and thermal insulation. Thermostatically controlled heater shall be arranged to maintain battery above 10 deg C regardless of external ambient temperature within range specified in "Environmental Conditions" Paragraph in "Service Conditions" Article. Include accessories required to support and fasten batteries in place.
 6. Battery-Charging Alternator: Factory mounted on engine with solid-state voltage regulation and 35-A minimum continuous rating.
 7. Battery Charger: Current-limiting, automatic-equalizing and float-charging type. Unit shall comply with UL 1236 and include the following features:
 - a. Operation: Equalizing-charging rate of 10 A shall be initiated automatically after battery has lost charge until an adjustable equalizing voltage is achieved at battery terminals. Unit shall then be automatically switched to a lower float-charging mode and shall continue to operate in that mode until battery is discharged again.
 - b. Automatic Temperature Compensation: Adjust float and equalize voltages for variations in ambient temperature from minus 40 deg C to plus 60 deg C to prevent overcharging at high temperatures and undercharging at low temperatures.

- c. Automatic Voltage Regulation: Maintain constant output voltage regardless of input voltage variations up to plus or minus 10 percent.
- d. Ammeter and Voltmeter: Flush mounted in door. Meters shall indicate charging rates.
- e. Safety Functions: Sense abnormally low battery voltage and close contacts providing low battery voltage indication on control and monitoring panel. Sense high battery voltage and loss of ac input or dc output of battery charger. Either condition shall close contacts that provide a battery-charger malfunction indication at system control and monitoring panel.
- f. Enclosure and Mounting: NEMA 250, Type 1, wall-mounted cabinet.

2.11 CONTROL AND MONITORING

- A. Functional Description: When mode-selector switch on the control and monitoring panel is in the automatic position, remote-control contacts in one or more separate automatic transfer switches initiate starting and stopping of the generator set. When mode-selector switch is switched to the on position, the generator set starts. The off position of the same switch initiates generator-set shutdown. When generator set is running, specified system or equipment failures or derangements automatically shut down the generator set and initiate alarms. Operation of a remote emergency-stop switch also shuts down the generator set.
- B. Functional Description: Switching on-off switch on the generator control panel to the on position starts the generator set. The off position of the same switch initiates generator-set shutdown. When generator set is running, specified system or equipment failures or derangements automatically shut down the generator set and initiate alarms. Operation of a remote emergency-stop switch also shuts down the generator set.
- C. Configuration: Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common control and monitoring panel mounted on the generator set. Mounting method shall isolate the control panel from generator-set vibration.
- D. Indicating and Protective Devices and Controls:
 - 1. AC voltmeter.
 - 2. AC ammeter.
 - 3. AC frequency meter.
 - 4. DC voltmeter (alternator battery charging).
 - 5. Engine-coolant temperature gage.
 - 6. Engine lubricating-oil pressure gage.
 - 7. Running-time meter.
 - 8. Ammeter-voltmeter, phase-selector switch(es).
 - 9. Generator-voltage adjusting rheostat.
 - 10. Start-stop switch.
 - 11. Overspeed shutdown device.
 - 12. Coolant high-temperature shutdown device.
 - 13. Coolant low-level shutdown device.
 - 14. Oil low-pressure shutdown device.

15. Generator overload.

- E. Supporting Items: Include sensors, transducers, terminals, relays, and other devices and include wiring required to support specified items. Locate sensors and other supporting items on engine or generator, unless otherwise indicated.
- F. Connection to Data Link: A separate terminal block, factory wired to Form C dry contacts, for each alarm and status indication is reserved for connections for data-link transmission of indications to remote data terminals.
- G. Common Remote Audible Alarm: Comply with NFPA 110 requirements for Level 1 systems. Include necessary contacts and terminals in control and monitoring panel.

2.12 GENERATOR OVERCURRENT AND FAULT PROTECTION

- A. Generator Circuit Breaker: Molded-case, thermal-magnetic type; 80 percent rated; complying with NEMA AB 1 and UL 489.
 - 1. Tripping Characteristic: Designed specifically for generator protection.
 - 2. Trip Rating: Matched to generator rating.
 - 3. Mounting: Adjacent to or integrated with control and monitoring panel.
- B. Generator Protector: Microprocessor-based unit that continuously monitors current level in each phase of generator output, integrates generator heating effect over time, and predicts when thermal damage of the alternator will occur. When signaled by the protector or other generator-set protective devices, a shunt-trip device in the generator disconnect switch shall open the switch to disconnect the generator from the load circuits. Protector shall perform the following functions:
 - 1. Initiates a generator overload alarm when the generator has operated at an overload equivalent to 110 percent of full-rated load for 60 seconds. Indication for this alarm is integrated with other generator-set malfunction alarms.
 - 2. Under single phase fault conditions, regulates the generator to 300 percent of rated full-load current for up to 10 seconds.
 - 3. As the overcurrent heating effect on the generator approaches the thermal damage point of the unit, the protector switches the excitation system off, opens the generator disconnect device, and shuts down the generator set.
 - 4. Senses clearing of a fault by other overcurrent devices and controls recovery of rated voltage to avoid overshoot.

2.13 GENERATOR, EXCITER, AND VOLTAGE REGULATOR

- A. Comply with NEMA MG 1 and specified performance requirements.
- B. Drive: Generator shaft shall be directly connected to engine shaft. Exciter shall be rotated integrally with generator rotor.
- C. Electrical Insulation: Class H or Class F.
- D. Stator-Winding Leads: Brought out to terminal box to permit future reconnection for other voltages if required.

- E. Construction shall prevent mechanical, electrical, and thermal damage due to vibration, overspeed up to 125 percent of rating, and heat during operation at 110 percent of rated capacity.
- F. Excitation shall use no slip or collector rings, or brushes, and shall be arranged to sustain generator output under short-circuit conditions as specified.
- G. Enclosure: Dripproof.
- H. Instrument Transformers: Mounted within generator enclosure.
- I. Voltage Regulator: Solid-state type, separate from exciter, providing performance as specified.
 - 1. Adjusting rheostat on control and monitoring panel shall provide plus or minus 5 percent adjustment of output-voltage operating band.
- J. Strip Heater: Thermostatically controlled unit arranged to maintain stator windings above dew point.
- K. Windings: Two-thirds pitch stator winding and fully linked amortisseur winding.
- L. Subtransient Reactance: 12 percent, maximum.

2.14 OUTDOOR GENERATOR-SET ENCLOSURE

- A. Description: Vandal-resistant, weatherproof steel housing, wind resistant up to 100 mph. Multiple panels shall be lockable and provide adequate access to components requiring maintenance. Panels shall be removable by one person without tools. Instruments and control shall be mounted within enclosure. Sound attenuation shall be provided to limit the noise to comply with the local noise ordinance. Maximum sound output shall be 71 dB at ten feet from the enclosure.
- B. Description: Prefabricated or preengineered enclosure with the following features:
 - 1. Construction: Galvanized-steel, metal-clad, integral structural-steel-framed building erected on concrete foundation.
 - 2. Structural Design and Anchorage: Wind resistant up to 100 mph.
 - 3. Space Heater: Thermostatically controlled and sized to prevent condensation.
 - 4. Louvers: Equipped with bird screen and filter arranged to permit air circulation when engine is not running while excluding exterior dust, birds, and rodents.
 - 5. Hinged Doors: With padlocking provisions.
 - 6. Ventilation: Louvers equipped with bird screen and filter arranged to permit air circulation while excluding exterior dust, birds, and rodents.
 - 7. Thermal Insulation: Manufacturer's standard materials and thickness selected in coordination with space heater to maintain winter interior temperature within operating limits required by engine-generator-set components.
 - 8. Muffler Location: Within enclosure.
- C. Engine Cooling Airflow through Enclosure: Maintain temperature rise of system components within required limits when unit operates at 110 percent of rated load for 2 hours with ambient temperature at top of range specified in system service conditions.

1. Louvers: Fixed-engine cooling-air inlet and discharge. Storm-proof and drainable louvers prevent entry of rain and snow.
2. Automatic Dampers: At engine cooling-air inlet and discharge. Dampers shall be closed to reduce enclosure heat loss in cold weather when unit is not operating.

2.15 FINISHES

- A. Indoor and Outdoor Enclosures and Components: Manufacturer's standard enamel over corrosion-resistant pretreatment and compatible standard primer.

2.16 SOURCE QUALITY CONTROL

- A. Prototype Testing: Factory test engine-generator set using same engine model, constructed of identical or equivalent components and equipped with identical or equivalent accessories.
 1. Tests: Comply with NFPA 110, Level 1 energy converters in Paragraphs 3.2.1, 3.2.1.1, and 3.2.1.2.
 2. Generator Tests: Comply with IEEE 115.
 3. Components and Accessories: Items furnished with installed unit that are not identical to those on tested prototype shall have been factory tested to demonstrate compatibility and reliability.
- B. Project-Specific Equipment Tests: Before shipment, factory test engine-generator set and other system components and accessories manufactured specifically for this Project. Perform tests at rated load and power factor. Include the following tests:
 1. Full load run.
 2. Maximum power.
 3. Voltage regulation.
 4. Transient and steady-state governing.
 5. Single-step load pickup.
 6. Safety shutdown.
- C. Report factory test results within 10 days of completion of test.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas, equipment bases, and conditions, with Installer present, for compliance with requirements for installation and other conditions affecting packaged engine-generator performance.
- B. Examine roughing-in of piping systems and electrical connections. Verify actual locations of connections before packaged engine-generator installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 CONCRETE BASES

- A. Coordinate size and location of concrete bases. Verify structural requirements with structural engineer.

3.3 INSTALLATION

- A. Comply with packaged engine-generator manufacturers' written installation and alignment instructions and with NFPA 110.
- B. Install packaged engine generators level on concrete base.
- C. Install packaged engine generator to provide access, without removing connections or accessories, for periodic maintenance.
- D. Electrical Wiring: Install electrical devices furnished by equipment manufacturers but not specified to be factory mounted.

3.4 CONNECTIONS

- A. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- B. Connect wiring according to Division 26 Section "Low Voltage Electrical Power Conductors and Cables."
- C. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

3.5 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections, and to assist in field testing. Report results in writing.
- B. Perform the following field tests and inspections and prepare test reports:
 - 1. Perform each electrical test and visual and mechanical inspection stated in NETA ATS, Sections 7.15.2.1 and 7.22.1 (except for vibration baseline test). Certify compliance with test parameters.
 - 2. Perform tests recommended by manufacturer.
 - 3. NFPA 110 Acceptance Tests: Perform tests required by NFPA 110 that are additional to those specified here including, but not limited to, the following:
 - a. Single-step full-load pickup test.
 - 4. Battery Tests: Equalize charging of battery cells according to manufacturer's written instructions. Record individual cell voltages.

- a. Measure charging voltage and voltages between available battery terminals for full-charging and float-charging conditions. Check electrolyte level and specific gravity under both conditions.
 - b. Test for contact integrity of all connectors. Perform an integrity load test and a capacity load test for the battery.
 - c. Verify acceptance of charge for each element of the battery after discharge.
 - d. Verify that measurements are within manufacturer's specifications.
 - 5. Battery-Charger Tests: Verify specified rates of charge for both equalizing and float-charging conditions.
 - 6. System Integrity Tests: Methodically verify proper installation, connection, and integrity of each element of engine-generator system before and during system operation. Check for air, exhaust, and fluid leaks.
 - 7. Exhaust-System Back-Pressure Test: Use a manometer with a scale exceeding 40-inch wg. Connect to exhaust line close to engine exhaust manifold. Verify that back pressure at full-rated load is within manufacturer's written allowable limits for the engine.
 - 8. Voltage and Frequency Transient Stability Tests: Use recording oscilloscope to measure voltage and frequency transients for 50 and 100 percent step-load increases and decreases, and verify that performance is as specified.
 - 9. Harmonic-Content Tests: Measure harmonic content of output voltage under 25 percent and at 100 percent of rated linear load. Verify that harmonic content is within specified limits.
- C. Coordinate tests with tests for transfer switches and run them concurrently.
- D. Test instruments shall have been calibrated within the last 12 months, traceable to standards of the National Institute for Standards and Technology, and adequate for making positive observation of test results. Make calibration records available for examination on request.
- E. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
- F. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
- G. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- H. Remove and replace malfunctioning units and retest as specified above.
- I. Retest: Correct deficiencies identified by tests and observations and retest until specified requirements are met.
- J. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation resistances, time delays, and other values and observations. Attach a label or tag to each tested component indicating satisfactory completion of tests.

3.6 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
- B. Inspect field-assembled components and equipment installation, including piping and electrical connections. Report results in writing.
- C. Complete installation and startup checks according to manufacturer's written instructions.

3.7 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain packaged engine generators.
 - 1. Coordinate this training with that for transfer switches.

END OF SECTION 26 32 13

SECTION 26 33 16

FLOOR BOXES

PART 1 - GENERAL

1.1 CONDITIONS AND REQUIREMENTS

- A. The General Conditions, Supplementary Conditions, and Division 01 – General Requirements apply.

1.2 SECTION INCLUDES

- A. Floor boxes.

1.3 RELATED SECTIONS

- A. Section 07 84 13.16 - Penetration Firestopping Devices.
- B. Division 26 - Electrical: Electrical systems and components.

1.4 SUBMITTALS

- A. Submit under provisions of Section 0 Administrative Requirements.
- B. Product Data: Submit for electrical floor boxes.

1.5 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Firms regularly engaged in manufacture of electrical floor boxes and fittings of the types and sizes required, whose products have been in satisfactory use in similar service for not less than 10 years. Provide electrical floor boxes and fittings produced by a manufacturer listed in this section.
- B. Electrical Boxes and Fittings: Comply with requirements of applicable local codes, NEC, UL, ETL, and NEMA Standards pertaining to boxes and fittings. Listed and labeled in accordance with NFPA 70, Section 300-21.

1.6 DELIVERY, STORAGE AND HANDLING

- A. Deliver electrical floor boxes in factory labeled packages.
- B. Store and handle in strict compliance with manufacturer's written instructions and recommendations.
- C. Protect from damage due to weather, excessive temperature, and construction operations.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Basis-of-Design Product: The design for electrical floor boxes and fittings is based on Evolution Series Floor Boxes.
- B. Substitutions will be considered under provisions of Section 01 25 00.

2.2 FLOOR BOXES

- A. Classification and Use: Floor boxes shall have been examined and tested by Underwriters Laboratories Inc. to meet UL514A and/or UL514C and Canadian Standard C22.2, No. 18.1-04 and 18.2-06 and bear the U.S. and Canadian UL Listing Mark. Floor

boxes shall also have been tested by Underwriters Laboratories Inc. and classified for fire resistance and bear the U.S. and Canadian UL Classification Mark. Devices shall be classified for use in 2-hour rated, unprotected reinforced concrete floors and 2-hour rated floors employing unprotected steel floor units and concrete toppings (D900 Series Designs) or concrete floors with suspended ceilings (fire resistive designs with suspended ceilings should have provisions for accessibility in the ceiling below the floor boxes). Floor boxes shall also conform to the standards set in Section 300-21 of the National Electrical Code. Floor boxes shall meet UL scrub water requirements, but are not suitable for wet or damp locations, or other areas subject to saturation with water or other liquids such as commercial kitchens. Floor boxes shall also have been evaluated by UL to meet the applicable U.S. and Canadian safety standards for scrub water exclusion when used on tile, bare concrete, terrazzo, wood, and carpet covered floors. Floor boxes shall be suitable for use in air handling spaces in accordance with Section 300-22 (C) of the National Electrical Code.

- B. Floor Boxes, General: Boxes shall be compatible with complete line of Ortronics® workstation connectivity outlets and modular inserts.
 - 1. Floor boxes provide the interface between power, communication and audio/video (A/V) cabling in on-grade concrete floors. Boxes shall provide recessed device outlets that will not obstruct the floor area. Refer to Drawings for size and types.
 - 2. Floor boxes shall permit all wiring to be completed at floor level. The FC models shall be used as defined by the UL Fire Resistance Directory at a minimum spacing of two feet on center.
- C. Model EFB45S-OG Floor Boxes: Manufactured from stamped steel approved for use in above grade and on-grade floor applications. Boxes shall have the ability to accept a component (EFB45-CTR) that will allow the box to be installed in polished concrete or terrazzo floors. Boxes shall be painted with a fusion-bonded epoxy designed for use on metal reinforcement bar and related accessories before encapsulation in concrete, and be approved for use on-grade floors. Boxes shall be 12 1/16" L 9 3/16" W x 5 15/16" H. Provide boxes with four (4) independent wiring compartments that allow for up to four (4) duplex receptacles, communication and/or audio/video services. Box shall have the ability to expand to five (5) independent wiring compartments by changing out the mounting brackets module. Boxes shall have removable and relocatable dividers to permit custom configuration of compartments as well as permit feed to adjacent compartments. Each of the two (2) outer compartments shall have a minimum wiring capacity of 28-in³. Each of the two (2) center compartments shall have a minimum wiring capacity of 34-in³. Each of the four (4) compartments shall have a minimum depth of 3-1/2" behind the plate. Provide boxes with removable compartments to facilitate installation. The compartments shall be removable from the top of the floor box. Provide boxes with two (2) cable guides to organize and maintain the cables egress out of the box. The box shall contain the following number of knockouts: six (6) 1-inch trade size, three (3) 1-1/4-inch trade size, and two (2) 2-inch trade size. Boxes shall be fully adjustable, accommodating a maximum 2-inch pre-concrete pour and a maximum 1/2" post-concrete pour adjustment. The box shall be able to accept standard size single gang (2-3/4" x 4-1/2"), double gang (2-3/4" x 4-1/2"), and triple gang (6-3/8" x 4-1/2") wall plates. Include mounting brackets with the boxes that will accommodate 20 amp straight blade receptacles. Boxes shall also accommodate Ortronics® workstation connectivity and modular adapters, a variety of audio/video devices from most manufacturers, and other open system devices.

- 2.3 Evolution EFB45BT Series Covers: Manufactured of die-cast aluminum. Activation covers shall be available in surface mount and flush versions. Provide covers with two (2) gaskets (one (1) for carpet and one (1) for tile) to go under the trim flange to maintain scrub watertightness. Covers shall be 13-7/8" x 9-15/16" x 3/16". Covers shall be available with a carpet recess area or a solid lid. Covers shall also be available with tamper-resistant protection. Secure the cover to the flange and enable cover to rotate greater than 180 degrees to reduce trip hazards and provide maximum amount of working space. Provide covers with spring-loaded self-closing slide egress doors to reduce egress opening when cables are exiting and reduce trip hazards. Each of the two (2) egress openings shall have a minimum of 2-in², or a minimum of 4-in² per cover assembly. Cover finish shall be durable satin nickel.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine conditions under which boxes and fittings are to be installed. Notify the Architect/Engineer in writing of conditions detrimental to proper completion of the work. Do not proceed with work until unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Strictly comply with manufacturer's installation instructions and recommendations. Coordinate installation with adjacent work to ensure proper clearances and to prevent electrical hazards.

3.3 CLEANING AND PROTECTION

- A. Clean exposed surfaces using non-abrasive materials and methods recommended by manufacturer.
- B. Protect boxes until acceptance.

END OF SECTION

This page intentionally left blank.

SECTION 26 36 00

TRANSFER SWITCHES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes transfer switches rated 600 V and less, including the following:
 - 1. Automatic transfer switches with bypass isolation, front-accessible only.
 - 2. Limiting Conditions: ATS shall fit within the allowable equipment space with required clearances.

1.3 SUBMITTALS

- A. Product Data: For each type of product indicated. Include rated capacities, weights, operating characteristics, furnished specialties, and accessories.
- B. Shop Drawings: Dimensioned plans, elevations, sections, and details showing minimum clearances, conductor entry provisions, gutter space, installed features and devices, and material lists for each switch specified.
 - 1. Single-Line Diagram: Show connections between transfer switch, bypass/isolation switch, power sources, and load; and show interlocking provisions for each combined transfer switch and bypass/isolation switch.
- C. Manufacturer Seismic Qualification Certification: Submit certification that transfer switches accessories, and components will withstand seismic forces defined in Division 26 Section "Vibration and Seismic Controls for Electrical Systems." Include the following:
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - a. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
 - b. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.

3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- D. Qualification Data: For manufacturer.
- E. Field quality-control test reports.
- F. Operation and Maintenance Data: For each type of product to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 1. Features and operating sequences, both automatic and manual.
 2. List of all factory settings of relays; provide relay-setting and calibration instructions, including software, where applicable.

1.4 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Maintain a service center capable of providing training, parts, and emergency maintenance repairs within a response period of less than eight hours from time of notification.
- B. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a member company of the InterNational Electrical Testing Association or is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association or the National Institute for Certification in Engineering Technologies to supervise on-site testing specified in Part 3.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- D. Comply with NEMA ICS 1.
- E. Comply with NFPA 70.
- F. Comply with NFPA 110.
- G. Comply with UL 1008 unless requirements of these Specifications are stricter.

1.5 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Contactor Transfer Switches:
 - a. Caterpillar; Engine Div.
 - b. Emerson; ASCO Power Technologies, LP.
 - c. Eaton.
 - d. GE Zenith Controls.
 - e. Kohler Power Systems; Generator Division.
 - f. Onan/Cummins Power Generation; Industrial Business Group.
 - g. Russelectric, Inc.

2.2 GENERAL TRANSFER-SWITCH PRODUCT REQUIREMENTS

- A. Indicated Current Ratings: Apply as defined in UL 1008 for continuous loading and total system transfer, including tungsten filament lamp loads not exceeding 30 percent of switch ampere rating, unless otherwise indicated.
- B. Tested Fault-Current Closing and Withstand Ratings: Adequate for duty imposed by protective devices at installation locations in Project under the fault conditions indicated, based on testing according to UL 1008.
 - 1. Where transfer switch includes internal fault-current protection, rating of switch and trip unit combination shall exceed indicated fault-current value at installation location.
- C. Solid-State Controls: Repetitive accuracy of all settings shall be plus or minus 2 percent or better over an operating temperature range of minus 20 to plus 70 deg C.
- D. Resistance to Damage by Voltage Transients: Components shall meet or exceed voltage-surge withstand capability requirements when tested according to IEEE C62.41. Components shall meet or exceed voltage-impulse withstand test of NEMA ICS 1.
- E. Electrical Operation: Accomplish by a nonfused, momentarily energized solenoid or electric-motor-operated mechanism, mechanically and electrically interlocked in both directions.
- F. Switch Characteristics: Designed for continuous-duty repetitive transfer of full-rated current between active power sources.
 - 1. Limitation: Switches using molded-case switches or circuit breakers or insulated-case circuit-breaker components are not acceptable.
 - 2. Switch Action: Double throw; mechanically held in both directions.
 - 3. Contacts: Silver composition or silver alloy for load-current switching. Conventional automatic transfer-switch units, rated 225 A and higher, shall have separate arcing contacts.

- G. Neutral Terminal: Solid and fully rated, unless otherwise indicated.
- H. Annunciation, Control, and Programming Interface Components: Devices at transfer switches for communicating with remote programming devices, annunciators, or annunciator and control panels shall have communication capability matched with remote device.
- I. Factory Wiring: Train and bundle factory wiring and label, consistent with Shop Drawings, either by color-code or by numbered or lettered wire and cable tape markers at terminations. Color-coding and wire and cable tape markers are specified in Division 26 Section "Identification for Electrical Systems."
 - 1. Designated Terminals: Pressure type, suitable for types and sizes of field wiring indicated.
 - 2. Power-Terminal Arrangement and Field-Wiring Space: Suitable for top, side, or bottom entrance of feeder conductors as indicated.
 - 3. Control Wiring: Equipped with lugs suitable for connection to terminal strips.
- J. Enclosures: General-purpose NEMA 250, Type 1, complying with NEMA ICS 6 and UL 508, unless otherwise indicated.

2.3 AUTOMATIC TRANSFER SWITCHES

- A. Comply with Level 1 equipment according to NFPA 110.
- B. Switching Arrangement: Double-throw type, incapable of pauses or intermediate position stops during normal functioning, unless otherwise indicated.
- C. The ATS shall be a 4-pole unit with a switched neutral. Neutral shall be make-before-break.
- D. Manual Switch Operation: Under load, with door closed and with either or both sources energized. Transfer time is same as for electrical operation. Control circuit automatically disconnects from electrical operator during manual operation.
- E. Transfer Switches Based on Molded-Case-Switch Components: Comply with NEMA AB 1, UL 489, and UL 869A.
- F. In-Phase Monitor: Factory-wired, internal relay controls transfer so it occurs only when the two sources are synchronized in phase. Relay compares phase relationship and frequency difference between normal and emergency sources and initiates transfer when both sources are within 15 electrical degrees, and only if transfer can be completed within 60 electrical degrees. Transfer is initiated only if both sources are within 2 Hz of nominal frequency and 70 percent or more of nominal voltage.
- G. Automatic Transfer-Switch Features:
 - 1. Undervoltage Sensing for Each Phase of Normal Source: Sense low phase-to-ground voltage on each phase. Pickup voltage shall be adjustable from 85 to 100 percent of nominal, and dropout voltage is adjustable from 75 to 98 percent of pickup value. Factory set for pickup at 90 percent and dropout at 85 percent.

2. Adjustable Time Delay: For override of normal-source voltage sensing to delay transfer and engine start signals. Adjustable from zero to six seconds, and factory set for one second.
3. Voltage/Frequency Lockout Relay: Prevent premature transfer to generator. Pickup voltage shall be adjustable from 85 to 100 percent of nominal. Factory set for pickup at 90 percent. Pickup frequency shall be adjustable from 90 to 100 percent of nominal. Factory set for pickup at 95 percent.
4. Time Delay for Retransfer to Normal Source: Adjustable from 0 to 30 minutes, and factory set for 10 minutes to automatically defeat delay on loss of voltage or sustained undervoltage of emergency source, provided normal supply has been restored.
5. Test Switch: Simulate normal-source failure.
6. Switch-Position Pilot Lights: Indicate source to which load is connected. Connect switch showing switch in emergency position to elevator control panel.
7. Source-Available Indicating Lights: Supervise sources via transfer-switch normal- and emergency-source sensing circuits.
 - a. Normal Power Supervision: Green light with nameplate engraved "Normal Source Available."
 - b. Emergency Power Supervision: Red light with nameplate engraved "Emergency Source Available."
8. Unassigned Auxiliary Contacts: Two normally open, single-pole, double-throw contacts for each switch position, rated 10 A at 240-V ac.
9. Transfer Override Switch: Overrides automatic retransfer control so automatic transfer switch will remain connected to emergency power source regardless of condition of normal source. Pilot light indicates override status.
10. Engine Starting Contacts: One isolated and normally closed, and one isolated and normally open; rated 10 A at 32-V dc minimum.
11. Engine Shutdown Contacts: Instantaneous; shall initiate shutdown sequence at remote engine-generator controls after retransfer of load to normal source.
12. Engine Shutdown Contacts: Time delay adjustable from zero to five minutes, and factory set for five minutes. Contacts shall initiate shutdown at remote engine-generator controls after retransfer of load to normal source.
13. Engine-Generator Exerciser: Solid-state, programmable-time switch starts engine generator and transfers load to it from normal source for a preset time, then retransfers and shuts down engine after a preset cool-down period. Initiates exercise cycle at preset intervals adjustable from 7 to 30 days. Running periods are adjustable from 10 to 30 minutes. Factory settings are for 7-day exercise cycle, 20-minute running period, and 5-minute cool-down period. Exerciser features include the following:
 - a. Exerciser Transfer Selector Switch: Permits selection of exercise with and without load transfer.
 - b. Push-button programming control with digital display of settings.
 - c. Integral battery operation of time switch when normal control power is not available.

2.4 TRANSFER SWITCH ACCESSORIES

- A. Bypass/Isolation Switches
 1. General Requirements

- a. Source Limitations: Provide bypass/isolation switches manufactured by the same manufacturer as the associated automatic transfer switch (ATS).
 - b. Standards Compliance: Equipment shall comply with requirements for Level 1 systems in accordance with NFPA 110.
- 2. Description: Provide a manually operated bypass/isolation switch arranged to permit selection and direct connection of either power source to the load while fully isolating the transfer switch from both the load and all power sources. Each combined ATS and bypass/isolation switch assembly shall include the following features:
 - a. Provision for locking the bypass/isolation switch in the isolation position, allowing complete electrical testing of the transfer switch while isolated. Interlocks shall prevent transfer switch operation, except during testing or maintenance, when isolated.
 - b. Means to supply power to the transfer switch control circuit for testing and maintenance purposes while isolated.
 - c. Drawout Arrangement: Transfer switch shall be provided in a drawout configuration to allow physical separation from live parts and safe accessibility for testing and maintenance. Transfer switch and bypass/isolation switch shall be housed in separate isolated compartments.
- 3. Transition Type: Provide open-transition (break-before-make) operation during transfer between power sources.
- 4. Ratings: Current, voltage, closing, and short-circuit withstand ratings of the bypass/isolation switch shall be equal to or greater than those of the associated transfer switch, with matching phase configuration and number of poles.
 - a. Contact temperature rise of bypass/isolation switch contacts shall not exceed that of the associated automatic transfer switch when carrying rated load.
- 5. Manual Operation: Equipment shall be designed such that load bypass and transfer switch isolation can be accomplished by a single operator in no more than two operations within 15 seconds. Operating handles shall be externally accessible.
- 6. Automatic and Nonautomatic Control: Where specified, the automatic transfer switch controller shall also control the bypass/isolation switch.
- 7. Identification: Provide manufacturer's standard engraved nameplates, control labels, and instruction signage clearly indicating operating procedures.
- 8. Maintainability: Equipment shall be designed to permit removal of major components from the front without disturbing adjacent components or main power conductors.
- 9. Interconnection: Interconnect bypass/isolation switches and automatic transfer switches using factory-installed copper bus bars, plated at all connection points and braced to withstand the available short-circuit current.

2.5 SOURCE QUALITY CONTROL

- A. Factory test and inspect components, assembled switches, and associated equipment. Ensure proper operation. Check transfer time and voltage, frequency, and time-delay settings for compliance with specified requirements. Perform dielectric strength test complying with NEMA ICS 1.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Design each fastener and support to carry load indicated by seismic requirements and according to seismic-restraint details. See Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
- B. Floor-Mounting Switch: Anchor to floor by bolting.
 - 1. Concrete Bases: 4 inches high, reinforced, with chamfered edges. Extend base no more than 4 inches in all directions beyond the maximum dimensions of switch, unless otherwise indicated or unless required for seismic support. Construct concrete bases according to Division 26 Sections "Hangers and Supports for Electrical Systems" and "Vibration and Seismic Controls for Electrical Systems."
- C. Wall-Mounting Switch: Refer to Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
- D. Identify components according to Division 26 Section "Identification for Electrical Systems."
- E. Set field-adjustable intervals and delays, relays, and engine exerciser clock.

3.2 CONNECTIONS

- A. Wiring to Remote Components: Match type and number of cables and conductors to control and communication requirements of transfer switches and generator as recommended by manufacturer. Increase raceway sizes at no additional cost to Owner if necessary to accommodate required wiring.
- B. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- C. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.3 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections. Report results in writing.
- B. Perform tests and inspections and prepare test reports.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installation, including connections, and to assist in testing.
 - 2. After installing equipment and after electrical circuitry has been energized, test for compliance with requirements.

3. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
 4. Measure insulation resistance phase-to-phase and phase-to-ground with insulation-resistance tester. Include external annunciation and control circuits. Use test voltages and procedure recommended by manufacturer. Comply with manufacturer's specified minimum resistance.
 - a. Check for electrical continuity of circuits and for short circuits.
 - b. Inspect for physical damage, proper installation and connection, and integrity of barriers, covers, and safety features.
 - c. Verify that manual transfer warnings are properly placed.
 - d. Perform manual transfer operation.
 5. After energizing circuits, demonstrate interlocking sequence and operational function for each switch at least three times.
 - a. Simulate power failures of normal source to automatic transfer switches and of emergency source with normal source available.
 - b. Simulate loss of phase-to-ground voltage for each phase of normal source.
 - c. Verify time-delay settings.
 - d. Verify pickup and dropout voltages by data readout or inspection of control settings.
 - e. Test bypass/isolation unit functional modes and related automatic transfer-switch operations.
 - f. Perform contact-resistance test across main contacts and correct values exceeding 500 microhms and values for 1 pole deviating by more than 50 percent from other poles.
 - g. Verify proper sequence and correct timing of automatic engine starting, transfer time delay, retransfer time delay on restoration of normal power, and engine cool-down and shutdown.
 6. Ground-Fault Tests: Coordinate with testing of ground-fault protective devices for power delivery from both sources.
 - a. Verify grounding connections and locations and ratings of sensors.
- C. Coordinate tests with tests of generator and run them concurrently.
- D. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation and contact resistances and time delays. Attach a label or tag to each tested component indicating satisfactory completion of tests.
- E. Remove and replace malfunctioning units and retest as specified above.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain transfer switches and related equipment as specified below. Refer to Division 01 Section "Demonstration and Training."
- B. Coordinate this training with that for engine-generator equipment.

END OF SECTION 26 36 00

SECTION 26 41 13

LIGHTNING PROTECTION FOR STRUCTURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes lightning protection for structures and building site components.
- B. Delegated Design
 - 1. Provide a complete, code-compliant lightning protection system under a delegated design approach. Work shall include all engineering, design, installation labor, materials, equipment, permits, fees, and transportation necessary to furnish, install, test, and certify a fully operational system.
- C. Lightning Protection System Description
 - 1. Provide a lightning protection system for the indicated structure, including, but not limited to, air terminals at roofs and roof-mounted mechanical equipment; protection of parapets and penthouse roofs; bonding of the structural system and other metal objects; grounding electrodes; and all required interconnecting conductors.
 - 2. Use Class I materials for structures not exceeding 75 feet in height above grade, and Class II materials for structures exceeding 75 feet in height above grade.
- D. Performance Requirements
 - 1. The Contract Documents establish minimum material standards, system features, and performance requirements. They do not depict every air terminal, conductor, or connection required for a complete installation. Based on the specified performance and indicated equipment, the Contractor and Vendor shall be solely responsible for the complete design, coordination, and provision of all components and wiring necessary to deliver a fully functional and compliant system.
- E. Scope of Work
 - 1. Work includes, but is not limited to, the following:
 - a. Complete system design, engineering, and coordination with the Architect and other trades, including testing and final acceptance by the Owner, Authority Having Jurisdiction (AHJ), and applicable certification agencies.
 - b. Semi-concealed, conventional lightning protection system for standard structures.

- c. Preparation and submission for plan review and approval.
- d. Furnishing and installation of all system components and devices.
- e. Installation of all conductors, wiring, and terminations.
- f. Coordination with Section 26 05 29, "Grounding and Bonding for Electrical Systems."
- g. Preparation and submission of installation details, wiring diagrams, shop drawings, and product data.
- h. Provision of all labor and materials required for a complete and operational system, whether specifically indicated or reasonably inferred.
- i. Preparation and submission of record (as-built) documents.
- j. Obtaining all required permits, inspections, and payment of associated fees.
- k. System identification and provision of written operation and maintenance instructions.
- l. Coordination with existing conditions and the work of other trades.
- m. Furnishing and installation of special supports required for work under this Section but provided in coordination with other Sections.

1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: For air terminals and mounting accessories.
 - 1. Layout of the lightning protection system, along with details of the components to be used in the installation.
 - 2. Include indications for use of raceway, data on how concealment requirements will be met, and calculations required by NFPA 780 for bonding of grounded and isolated metal bodies.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer and manufacturer. Include data on listing or certification by UL.
- B. Certification, signed by Contractor, that roof adhesive is approved by manufacturer of roofing material.
- C. Field quality-control reports.
- D. Comply with recommendations in NFPA 780, Annex D, "Inspection and Maintenance of Lightning Protection Systems," for maintenance of the lightning protection system.
- E. Other Informational Submittals: Plans showing dimensioned as-built locations of grounding features, including the following:
 - 1. Ground rods.
 - 2. Ground conductors.

1.5 QUALITY ASSURANCE

- A. Designer and Installer Qualifications: Certified by UL as a Master Installer/Designer, trained and approved for installation of units required for this Project.
- B. System Certificate:
 - 1. UL Master Label.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 780, "Definitions" Article.

1.6 COORDINATION

- A. Coordinate installation of lightning protection with installation of other building systems and components, including electrical wiring, supporting structures and building materials, metal bodies requiring bonding to lightning protection components, and building finishes.
- B. Coordinate installation of air terminals attached to roof systems with roofing manufacturer and Installer.
- C. Flashings of through-roof assemblies shall comply with roofing manufacturers' specifications.

PART 2 - PRODUCTS

2.1 LIGHTNING PROTECTION SYSTEM COMPONENTS

- A. Comply with UL 96 and NFPA 780.
- B. Roof-Mounted Air Terminals: NFPA 780, Class I, copper unless otherwise indicated.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. East Coast Lightning Equipment Inc.
 - b. ERICO International Corporation.
 - c. Harger.
 - d. Heary Bros. Lightning Protection Co. Inc.
 - e. Independent Protection Co.
 - f. Preferred Lightning Protection.
 - g. Robbins Lightning, Inc.
 - h. Thompson Lightning Protection, Inc.
 - 2. Air Terminals More than 24 Inches Long: With brace attached to the terminal at not less than half the height of the terminal.
 - 3. Single-Membrane, Roof-Mounted Air Terminals: Designed specifically for single-membrane roof system materials. Comply with requirements in Division 07 roofing Sections.

- C. Main and Bonding Conductors: Copper.
- D. Ground Rods: Copper-clad steel; 3/4 inch in diameter by 10 feet long.
- E. Heavy-Duty, Stack-Mounted, Lightning Protection Components: Solid copper.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install lightning protection components and systems according to UL 96A and NFPA 780.
- B. Install conductors with direct paths from air terminals to ground connections. Avoid sharp bends.
- C. Conceal the following conductors:
 - 1. System conductors.
 - 2. Down conductors.
 - 3. Interior conductors.
 - 4. Conductors within normal view of exterior locations at grade within 200 feet of building.
- D. Cable Connections: Use crimped or bolted connections for all conductor splices and connections between conductors and other components. Use exothermic-welded connections in underground portions of the system.
 - 1. Exception: In single-ply membrane roofing, exothermic-welded connections may be used only below the roof level.
- E. Air Terminals on Single-Ply Membrane Roofing: Comply with roofing membrane and adhesive manufacturer's written instructions.
- F. Bond extremities of vertical metal bodies exceeding 60 feet in length to lightning protection components.

3.2 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Division 26 Section "Electrical General Requirements and Common Work Results."

3.3 CORROSION PROTECTION

- A. Do not combine materials that can form an electrolytic couple that will accelerate corrosion in the presence of moisture unless moisture is permanently excluded from junction of such materials.

- B. Use conductors with protective coatings where conditions cause deterioration or corrosion of conductors.

3.4 FIELD QUALITY CONTROL

- A. Notify Architect at least 48 hours in advance of inspection before concealing lightning protection components.
- B. UL Inspection: Meet requirements to obtain a UL Master Label for system.

END OF SECTION 26 41 13

This page intentionally left blank.

SECTION 26 43 13 - SURGE PROTECTION FOR LOW-VOLTAGE ELECTRICAL POWER CIRCUITS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section includes field-mounted SPDs for low-voltage (120 to 600 V) power distribution and control equipment.
- B. Related Requirements:
 - 1. Section 26 24 16 "Panelboards" for factory-installed SPDs.

1.3 DEFINITIONS

- A. Inominal: Nominal discharge current.
- B. MCOV: Maximum continuous operating voltage.
- C. Mode(s), also Modes of Protection: The pair of electrical connections where the VPR applies.
- D. MOV: Metal-oxide varistor; an electronic component with a significant non-ohmic current-voltage characteristic.
- E. OCPD: Overcurrent protective device.
- F. SCCR: Short-circuit current rating.
- G. SPD: Surge protective device.
- H. VPR: Voltage protection rating.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

2. Copy of UL Category Code VZCA certification, as a minimum, listing the tested values for VPRs, Inominal ratings, MCOVs, type designations, OCPD requirements, model numbers, system voltages, and modes of protection.

1.5 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.
- B. Sample Warranty: For manufacturer's special warranty.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For SPDs to include in maintenance manuals.

1.7 WARRANTY

- A. Manufacturer's Warranty: Manufacturer agrees to replace or replace SPDs that fail in materials or workmanship within specified warranty period.
- B. Warranty Period: Ten years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 GENERAL SPD REQUIREMENTS

- A. SPD with Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.
- C. Comply with UL 1449.
- D. MCOV of the SPD shall be the nominal system voltage.

2.2 SERVICE ENTRANCE AND TRANSFER SWITCH SUPPRESSOR

- A. Manufacturer:
 1. Current Technology, Inc.
 2. Leviton Manufacturing Co., Inc.
 3. Surge Suppression, LLC
- B. SPDs: Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 1449, Type 2
 1. SPDs with the following features and accessories:

- C. Integral disconnect switch.
- D. Internal thermal protection that disconnects the SPD before damaging internal suppressor components.
 - 1. Indicator light display for protection status.
 - 2. Surge counter.
- E. Comply with UL 1283.
- F. Peak Surge Current Rating: The minimum single-pulse surge current withstand rating per phase shall not be less than 200 kA. The peak surge current rating shall be the arithmetic sum of the ratings of the individual MOVs in a given mode.
- G. Protection modes and UL 1449 VPR for grounded wye circuits with 208Y/120 V, three-phase, four-wire circuits shall not exceed the following:
 - 1. Line to Neutral: 700 V for 208Y/120 V.
 - 2. Line to Ground: 1200 V for 208Y/120 V.
 - 3. Neutral to Ground: 700 V for 208Y/120 V.
 - 4. Line to Line: 1000 V for 208Y/120 V.
- H. Protection modes and UL 1449 VPR for 240/120 V, single-phase, three-wire circuits shall not exceed the following:
 - 1. Line to Neutral: 700 V.
 - 2. Line to Ground: 700 V.
 - 3. Neutral to Ground: 700 V
 - 4. Line to Line: 1000 V.
- I. SCCR: Equal or exceed 100 kA.
- J. Inominal Rating: 20 kA.

2.3 PANELBOARD SUPPRESSORS

- A. Current Technology, Inc.
- B. Leviton Manufacturing Co., Inc.
- C. Surge Suppression, LLC
- D. SPDs: Comply with UL 1449, Type 2.
 - 1. Include LED indicator lights for power and protection status.
- E. Internal thermal protection that disconnects the SPD before damaging internal suppressor components.
 - 1. Include Form-C contacts rated at 5 A and 250-V ac, one normally open and one normally closed, for remote monitoring of protection status.

- F. Peak Surge Current Rating: The minimum single-pulse surge current withstand rating per phase shall not be less than 100 kA. The peak surge current rating shall be the arithmetic sum of the ratings of the individual MOVs in a given mode.
- G. Comply with UL 1283.
- H. Protection modes and UL 1449 VPR for grounded wye circuits with 208Y/120 V, three-phase, four-wire circuits shall not exceed the following:
 - 1. Line to Neutral: 700 V for 208Y/120 V.
 - 2. Line to Ground: 700 V for 208Y/120 V.
 - 3. Neutral to Ground: 700 V for 208Y/120 V.
 - 4. Line to Line: 1200 V for 208Y/120 V.

2.4 ENCLOSURES

- A. Indoor Enclosures: NEMA 250, Type 1.

2.5 CONDUCTORS AND CABLES

- A. Power Wiring: Same size as SPD leads, complying with Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Comply with NECA 1.
- B. Install an OCPD or disconnect as required to comply with the UL listing of the SPD.
- C. Install SPDs with conductors between suppressor and points of attachment as short and straight as possible, and adjust circuit-breaker positions to achieve shortest and straightest leads. Do not splice and extend SPD leads unless specifically permitted by manufacturer. Do not exceed manufacturer's recommended lead length. Do not bond neutral and ground.
- D. Use crimped connectors and splices only. Wire nuts are unacceptable.
- E. Wiring:
 - 1. Power Wiring: Comply with wiring methods in Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."
 - 2. Controls: Comply with wiring methods in Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables."

3.2 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections with the assistance of a factory-authorized service representative.
 - 1. Compare equipment nameplate data for compliance with Drawings and Specifications.
 - 2. Inspect anchorage, alignment, grounding, and clearances.
 - 3. Verify that electrical wiring installation complies with manufacturer's written installation requirements.
- B. An SPD will be considered defective if it does not pass tests and inspections.
- C. Prepare test and inspection reports.

3.3 STARTUP SERVICE

- A. Complete startup checks according to manufacturer's written instructions.
- B. Do not perform insulation-resistance tests of the distribution wiring equipment with SPDs installed. Disconnect SPDs before conducting insulation-resistance tests and reconnect them immediately after the testing is over.
- C. Energize SPDs after power system has been energized, stabilized, and tested.

END OF SECTION 26 43 13

This page intentionally left blank.

SECTION 26 51 19 - LED INTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Downlight.
 - 2. Linear industrial.
 - 3. Recessed, linear.
 - 4. Strip light.
 - 5. Surface mount, linear.
 - 6. Suspended, linear.
 - 7. Materials.
 - 8. Luminaire support.
- B. Related Requirements:
 - 1. Section 26 09 23 "Lighting Control Devices" for automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors.

1.3 DEFINITIONS

- A. CCT: Correlated color temperature.
- B. CRI: Color Rendering Index.
- C. Fixture: See "Luminaire."
- D. IP: International Protection or Ingress Protection Rating.
- E. LED: Light-emitting diode.
- F. Lumen: Measured output of lamp and luminaire, or both.
- G. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. Arrange in order of luminaire designation.
 - 2. Include data on features, accessories, and finishes.
 - 3. Include physical description and dimensions of luminaires.
 - 4. Include emergency lighting units, including batteries and chargers.
 - 5. Include life, output (lumens, CCT, and CRI), and energy-efficiency data.
 - 6. Photometric data and adjustment factors based on laboratory tests, complying with IES "Lighting Measurements Testing and Calculation Guides" for each luminaire type. The adjustment factors shall be for lamps and accessories identical to those indicated for the luminaire as applied in this Project IES LM-79.
 - a. Manufacturers' Certified Data: Photometric data certified by manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products.
- B. Product Designations: For luminaires and lamps. Use same designations indicated on Drawings.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For luminaires and lighting systems to include in operation and maintenance manuals.
 - 1. Provide a list of all lamp types used on Project; use ANSI and manufacturers' codes.

1.6 QUALITY ASSURANCE

- A. Luminaire Photometric Data Testing Laboratory Qualifications:
 - 1. Luminaire manufacturer's laboratory that is accredited under the NVLAP for Energy Efficient Lighting Products.
- B. Provide luminaires from a single manufacturer for each luminaire type.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering before shipping.

1.8 WARRANTY

- A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.

- B. Warranty Period: Five year(s) from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Seismic Performance:

1. Luminaires shall withstand the effects of earthquake motions determined in accordance with local codes and Section "26 05 48 Vibration and Seismic Controls for Electrical Systems".
2. General Lighting: The term "withstand" means "the luminaire will remain in place without separation of any parts when subjected to the seismic forces specified."
3. Emergency and Life Safety Lighting: The term "withstand" means "the luminaire will remain in place without separation of any parts when subjected to the seismic forces specified and the luminaire will be fully operational during and after the seismic event."

B. Ambient Temperature: 5 to 104 deg F.

1. Relative Humidity: Zero to 95 percent.

C. Altitude: Sea level to 1000 feet.

2.2 LUMINAIRE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Factory-Applied Labels: Comply with UL 1598. Include recommended lamps. Locate labels where they will be readily visible to service personnel, but not seen from normal viewing angles when lamps are in place.

1. Label shall include the following lamp characteristics:

- a. "USE ONLY" and include specific lamp type.
- b. Lamp diameter, shape, size, wattage, and coating.
- c. CCT and CRI.

C. Recessed luminaires shall comply with NEMA LE 4.

2.3 DOWNLIGHT.

A. Manufacturers: Per Light Fixture Schedule on drawings.

B. Nominal Operating Voltage: Per Light Fixture Schedule on drawings.

- C. Lamp:
 - 1. Minimum allowable efficacy of 80 lm/W.
 - 2. CRI of minimum 80. CCT per Light Fixture Schedule on drawings.
 - 3. Rated lamp life of 35,000 hours to L70.
 - 4. Dimmable from 100 percent to zero percent of maximum light output.
 - 5. Internal driver.
 - 6. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.
- D. Housings:
 - 1. Extruded-aluminum housing and heat sink.
 - 2. Integral junction box with conduit fittings.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- F. Diffusers and Globes:
 - 1. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
 - 2. Glass: Annealed crystal glass unless otherwise indicated.
 - 3. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.
- G. Standards:
 - 1. ENERGY STAR certified.
 - 2. RoHS compliant.
 - 3. UL Listing: Listed for damp location.
 - 4. Recessed luminaires shall comply with NEMA LE 4.

2.4 RECESSED, LINEAR.

- A. Manufacturers: Per Light Fixture Schedule on drawings.
- B. Nominal Operating Voltage: Per Light Fixture Schedule on drawings.
- C. Lamp:
 - 1. Minimum allowable efficacy of 80 lm/W.
 - 2. CRI of minimum 80. CCT per Light Fixture Schedule on drawings.
 - 3. Rated lamp life of 35,000 hours to L70.
 - 4. Dimmable from 100 percent to zero percent of maximum light output.
- D. Internal driver.
- E. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.
- F. Housings:
 - 1. Extruded-aluminum housing and heat sink.

2. With integral mounting provisions.

G. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

H. Diffusers and Globes:

1. Per Light Fixture Schedule on drawings. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
2. Glass: Annealed crystal glass unless otherwise indicated.
3. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

I. Standards:

1. ENERGY STAR certified.
2. RoHS compliant.
3. UL Listing: Listed for damp location.
4. NEMA LE 4.

2.5 STRIP LIGHT.

A. Manufacturers: Per Light Fixture Schedule on drawings.

B. Nominal Operating Voltage: Per Light Fixture Schedule on drawings.

C. Lamp:

1. Minimum allowable efficacy of 80 lm/W.
2. CRI of minimum 80. CCT per Light Fixture Schedule on drawings.
3. Rated lamp life of 35,000 hours to L70.
4. Dimmable from 100 percent to zero percent of maximum light output.
5. Internal driver.
6. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

D. Housings:

1. Extruded-aluminum housing and heat sink.
2. With integral mounting provisions.

E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping of luminaire without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

F. Diffusers and Globes:

1. Per Light Fixture Schedule on drawings. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
2. Glass: Annealed crystal glass unless otherwise indicated.
3. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

G. Standards:

1. ENERGY STAR certified.
2. RoHS compliant.
3. UL Listing: Listed for damp location.

2.6 SURFACE MOUNT, LINEAR.

A. Manufacturers: Per Light Fixture Schedule on drawings.

B. Nominal Operating Voltage: Per Light Fixture Schedule on drawings.

C. Lamp:

1. Minimum allowable efficacy of 80 lm/W.
2. CRI of minimum 80. CCT per Light Fixture Schedule on drawings.
3. Rated lamp life of 35,000 hours to L70.
4. Dimmable from 100 percent to zero percent of maximum light output.
5. Internal driver. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

D. Housings:

1. Extruded-aluminum housing and heat sink.
2. With integral mounting provisions.

E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

F. Diffusers and Globes:

1. Per Light Fixture Schedule on drawings. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
2. Glass: Annealed crystal glass unless otherwise indicated.
3. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.

G. Standards:

1. ENERGY STAR certified.
2. RoHS compliant.
3. UL Listing: Listed for damp location.

2.7 SUSPENDED, LINEAR

- A. Manufacturers: Per Light Fixture Schedule on drawings.
- B. Nominal Operating Voltage: Per Light Fixture Schedule on drawings.
- C. Lamp:
 - 1. Minimum allowable efficacy of 80 lm/W.
 - 2. CRI of minimum 80. CCT per Light Fixture Schedule on drawings.
 - 3. Rated lamp life of 35,000 hours to L70.
 - 4. Dimmable from 100 percent to zero percent of maximum light output.
 - 5. Internal driver. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.
- D. Housings:
 - 1. Extruded-aluminum housing and heat sink.
 - 2. With integral mounting provisions.
- E. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Components are designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- F. Diffusers and Globes:
 - 1. Per Light Fixture Schedule on drawings. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
 - 2. Glass: Annealed crystal glass unless otherwise indicated.
 - 3. Lens Thickness: At least 0.125-inch minimum unless otherwise indicated.
- G. Standards:
 - 1. ENERGY STAR certified.
 - 2. RoHS compliant.
 - 3. UL Listing: Listed for damp location.

2.8 MATERIALS

- A. Metal Parts:
 - 1. Free of burrs and sharp corners and edges.
 - 2. Sheet metal components shall be steel unless otherwise indicated.
 - 3. Form and support to prevent warping and sagging.
- B. Steel:
 - 1. ASTM A36/A36M for carbon structural steel.
 - 2. ASTM A568/A568M for sheet steel.

- C. Stainless Steel:
 - 1. Manufacturer's standard grade.
 - 2. Manufacturer's standard type, ASTM A240/240M.
- D. Galvanized Steel: ASTM A653/A653M.
- E. Aluminum: ASTM B209.

2.9 METAL FINISHES

- A. Variations in finishes are unacceptable in the same piece. Variations in finishes of adjoining components are acceptable if they are within the range of approved Samples and if they can be and are assembled or installed to minimize contrast.

2.10 LUMINAIRE SUPPORT

- A. Comply with requirements in Section 26 05 29 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch steel tubing with swivel ball fittings and ceiling canopy. Finish same as luminaire.
- C. Wires: ASTM A641/A641M, Class 3, soft temper, zinc-coated steel, 12 gage.
- D. Rod Hangers: 1/4"-inch minimum diameter, cadmium-plated, threaded steel rod.
- E. Hook Hangers: Integrated assembly matched to luminaire, line voltage, and equipment with threaded attachment, cord, and locking-type plug.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before luminaire installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with NECA 1.

- B. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.
- C. Install lamps in each luminaire.
- D. Supports:
 - 1. Sized and rated for luminaire weight.
 - 2. Able to maintain luminaire position after cleaning and relamping.
 - 3. Provide support for luminaire without causing deflection of ceiling or wall.
 - 4. Luminaire-mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire weight and a vertical force of 400 percent of luminaire weight.
- E. Flush-Mounted Luminaires:
 - 1. Secured to outlet box.
 - 2. Attached to ceiling structural members at four points equally spaced around circumference of luminaire.
 - 3. Trim ring flush with finished surface.
- F. Wall-Mounted Luminaires:
 - 1. Attached to structural members in walls.
 - 2. Do not attach luminaires directly to gypsum board.
- G. Suspended Luminaires:
 - 1. Ceiling Mount:
 - a. Two 5/32-inch- diameter aircraft cable supports adjustable to 10 feet in length.
 - b. Pendant mount and Four-point pendant mount with 5/32-inch- diameter aircraft cable supports adjustable to 10 feet in length.
 - 2. Pendants and Rods: Where longer than 48 inches, brace to limit swinging.
 - 3. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
 - 4. Continuous Rows of Luminaires: Use tubing or stem for wiring at one point and tubing or rod or wire support for suspension for each unit length of luminaire chassis, including one at each end.
 - 5. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.
- H. Ceiling-Grid-Mounted Luminaires:
 - 1. Secure to any required outlet box.

2. Use approved devices and support components to connect luminaire to ceiling grid and building structure in a minimum of four locations, spaced near corners of luminaire.
- I. Comply with requirements in Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables" for wiring connections.

3.3 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."

3.4 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
 2. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
- B. Luminaire will be considered defective if it does not pass operation tests and inspections.
- C. Prepare test and inspection reports.

3.5 STARTUP SERVICE

- A. Comply with requirements for startup specified in Section 26 09 23 "Lighting Control Devices".

END OF SECTION 26 51 19

SECTION 26 56 00

EXTERIOR LIGHTING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Exterior luminaires with lamps and ballasts.
 - 2. Luminaire-mounted photoelectric relays.
 - 3. Poles and accessories.
- B. Related Sections:
 - 1. Division 26 Section "Interior Lighting" for exterior luminaires normally mounted on exterior surfaces of buildings.

1.3 DEFINITIONS

- A. CCT: Correlated color temperature.
- B. CRI: Color-rendering index.
- C. HID: High-intensity discharge.
- D. LER: Luminaire efficacy rating.
- E. Luminaire: Complete lighting fixture, including ballast housing if provided.
- F. Pole: Luminaire support structure, including tower used for large area illumination.
- G. Standard: Same definition as "Pole" above.

1.4 STRUCTURAL ANALYSIS CRITERIA FOR POLE SELECTION

- A. Dead Load: Weight of luminaire and its horizontal and vertical supports, lowering devices, and supporting structure, applied as stated in AASHTO LTS-4-M.
- B. Live Load: Single load of 500 lbf, distributed as stated in AASHTO LTS-4-M.

- C. Ice Load: Load of 3 lbf/sq. ft., applied as stated in AASHTO LTS-4-M Ice Load Map.
- D. Wind Load: Pressure of wind on pole and luminaire and banners and banner arms, calculated and applied as stated in AASHTO LTS-4-M.
 - 1. Basic wind speed for calculating wind load for poles 50 feet high or less is 100 mph
 - a. Wind Importance Factor: 1.0
 - b. Minimum Design Life: 25 years
 - c. Velocity Conversion Factors: 1.0

1.5 SUBMITTALS

- A. Product Data: For each luminaire, pole, and support component, arranged in order of lighting unit designation. Include data on features, accessories, finishes, and the following:
 - 1. Physical description of luminaire, including materials, dimensions, effective projected area, and verification of indicated parameters.
 - 2. Details of attaching luminaires and accessories.
 - 3. Details of installation and construction.
 - 4. Luminaire materials.
 - 5. Photometric data based on laboratory tests of each luminaire type, complete with indicated lamps, ballasts, and accessories.
 - a. Testing Agency Certified Data: For indicated luminaires, photometric data shall be certified by a qualified independent testing agency. Photometric data for remaining luminaires shall be certified by manufacturer.
 - b. Manufacturer Certified Data: Photometric data shall be certified by manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products.
 - 6. Photoelectric relays.
 - 7. Ballasts, including energy-efficiency data.
 - 8. Lamps, including life, output, CCT, CRI, lumens, and energy-efficiency data.
 - 9. Materials, dimensions, and finishes of poles.
 - 10. Means of attaching luminaires to supports, and indication that attachment is suitable for components involved.
 - 11. Anchor bolts for poles.
 - 12. Manufactured pole foundations.
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
 - 1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 2. Anchor-bolt templates keyed to specific poles and certified by manufacturer.
 - 3. Design calculations, certified by a qualified professional engineer, indicating strength of screw foundations and soil conditions on which they are based.
 - 4. Wiring Diagrams: For power, signal, and control wiring.
- C. Pole and Support Component Certificates: Signed by manufacturers of poles, certifying that products are designed for indicated load requirements in AASHTO LTS-

4-M and that load imposed by luminaire and attachments has been included in design. The certification shall be based on design calculations by a professional engineer.

- D. Qualification Data: For qualified agencies providing photometric data for lighting fixtures.
- E. Field quality-control reports.
- F. Operation and Maintenance Data: For luminaires and poles to include in emergency, operation, and maintenance manuals.
- G. Warranty: Sample of special warranty.

1.6 QUALITY ASSURANCE

- A. Luminaire Photometric Data Testing Laboratory Qualifications: Provided by manufacturers' laboratories that are accredited under the National Volunteer Laboratory Accreditation Program for Energy Efficient Lighting Products.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Comply with IEEE C2, "National Electrical Safety Code."
- D. Comply with NFPA 70.

1.7 DELIVERY, STORAGE, AND HANDLING

- A. Package aluminum poles for shipping according to ASTM B 660.
- B. Store poles on decay-resistant-treated skids at least 12 inches above grade and vegetation. Support poles to prevent distortion and arrange to provide free air circulation.
- C. Retain factory-applied pole wrappings on metal poles until right before pole installation. For poles with nonmetallic finishes, handle with web fabric straps.

1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace products that fail in materials or workmanship; that corrode; or that fade, stain, perforate, erode, or chalk due to effects of weather or solar radiation within specified warranty period. Manufacturer may exclude lightning damage, hail damage, vandalism, abuse, or unauthorized repairs or alterations from special warranty coverage.
 - 1. Warranty Period for Luminaires: One year from date of Substantial Completion.
 - 2. Warranty Period for Metal Corrosion: One year from date of Substantial Completion.

3. Warranty Period for Color Retention: One year from date of Substantial Completion.
4. Warranty Period for Poles: Repair or replace lighting poles and standards that fail in finish, materials, and workmanship within manufacturer's standard warranty period.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Products: Subject to compliance with requirements, provide product indicated on Drawings

2.2 GENERAL REQUIREMENTS FOR LUMINAIRES

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NRTL Compliance: Luminaires shall be listed and labeled for indicated class and division of hazard by an NRTL.
- C. FM Global Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM Global.
- D. UL Compliance: Comply with UL 1598
- E. Lamps dimmable from 100 percent to 0 percent of maximum light output.
- F. Internal driver.
- G. Source Limitations: Obtain luminaires from single source from a single manufacturer.
- H. Source Limitations: For luminaires, obtain each color, grade, finish, type, and variety of luminaire from single source with resources to provide products of consistent quality in appearance and physical properties.

2.3 GENERAL REQUIREMENTS FOR POLES AND SUPPORT COMPONENTS

- A. Structural Characteristics: Comply with AASHTO LTS-4-M.
 1. Wind-Load Strength of Poles: Adequate at indicated heights above grade without failure, permanent deflection, or whipping in steady winds of speed indicated in "Structural Analysis Criteria for Pole Selection" Article.
 2. Strength Analysis: For each pole, multiply the actual equivalent projected area of luminaires and brackets by a factor of 1.1 to obtain the equivalent projected area to be used in pole selection strength analysis.

- B. Luminaire Attachment Provisions: Comply with luminaire manufacturers' mounting requirements. Use stainless-steel fasteners and mounting bolts unless otherwise indicated.
- C. Mountings, Fasteners, and Appurtenances: Corrosion-resistant items compatible with support components.
 - 1. Materials: Shall not cause galvanic action at contact points.
 - 2. Anchor Bolts, Leveling Nuts, Bolt Caps, and Washers: Hot-dip galvanized after fabrication unless otherwise indicated.
 - 3. Anchor-Bolt Template: Plywood or steel.
- D. Handhole: Oval-shaped, with minimum clear opening of 2-1/2 by 5 inches, with cover secured by stainless-steel captive screws.
- E. Concrete Pole Foundations: Cast in place, with anchor bolts to match pole-base flange. Concrete, reinforcement, and formwork are specified in Division 03 Section "Cast-in-Place Concrete."
- F. Breakaway Supports: Frangible breakaway supports, tested by an independent testing agency acceptable to authorities having jurisdiction, according to AASHTO LTS-4-M.

2.4 STEEL POLES

- A. Poles: Comply with ASTM A 500, Grade B, carbon steel with a minimum yield of 46,000 psig; one-piece construction up to 40 feet in height with access handhole in pole wall.
- B. Pole-Top Tenons: Fabricated to support luminaire or luminaires and brackets indicated, and securely fastened to pole top.
- C. Grounding and Bonding Lugs: Welded 1/2-inch threaded lug, complying with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems," listed for attaching grounding and bonding conductors of type and size listed in that Section, and accessible through handhole.
- D. Cable Support Grip: Wire-mesh type with rotating attachment eye, sized for diameter of cable and rated for a minimum load equal to weight of supported cable times a 5.0 safety factor.
- E. Prime-Coat Finish: Manufacturer's standard prime-coat finish ready for field painting.
- F. Galvanized Finish: After fabrication, hot-dip galvanize complying with ASTM A 123/A 123M.
- G. Factory-Painted Finish: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
 - 1. Surface Preparation: Clean surfaces to comply with SSPC-SP 1, "Solvent Cleaning," to remove dirt, oil, grease, and other contaminants that could impair paint bond. Grind welds and polish surfaces to a smooth, even finish. Remove

- mill scale and rust, if present, from uncoated steel, complying with SSPC-SP 5/NACE No. 1, "White Metal Blast Cleaning," or with SSPC-SP 8, "Pickling."
2. Interior Surfaces of Pole: One coat of bituminous paint, or otherwise treat for equal corrosion protection.
 3. Exterior Surfaces: Manufacturer's standard finish consisting of one or more coats of primer and two finish coats of high-gloss, high-build polyurethane enamel.
 - a. Color: As per drawings/architect

2.5 ALUMINUM POLES

- A. Poles: Seamless, extruded structural tube complying with ASTM B 429/B 429M, Alloy 6063-T6 with access handhole in pole wall.
- B. Poles: ASTM B 209, 5052-H34 marine sheet alloy with access handhole in pole wall.
 1. Shape: Per drawings.
 2. Mounting Provisions: Butt flange for bolted mounting on foundation or breakaway support.
- C. Pole-Top Tenons: Fabricated to support luminaire or luminaires and brackets indicated, and securely fastened to pole top.
- D. Grounding and Bonding Lugs: Welded 1/2-inch threaded lug, complying with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems," listed for attaching grounding and bonding conductors of type and size listed in that Section, and accessible through handhole.
- E. Prime-Coat Finish: Manufacturer's standard prime-coat finish ready for field painting.
- F. Aluminum Finish: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
 - a. Color: Per drawings.

PART 3 - EXECUTION

3.1 LUMINAIRE INSTALLATION

- A. Install lamps in each luminaire.
- B. Fasten luminaire to indicated structural supports.
 1. Use fastening methods and materials selected to resist seismic forces defined for the application and approved by manufacturer.
- C. Adjust luminaires that require field adjustment or aiming. Include adjustment of photoelectric device to prevent false operation of relay by artificial light sources, favoring a north orientation.

3.2 POLE INSTALLATION

- A. Alignment: Align pole foundations and poles for optimum directional alignment of luminaires and their mounting provisions on the pole.
- B. Concrete Pole Foundations: Set anchor bolts according to anchor-bolt templates furnished by pole manufacturer. Concrete materials, installation, and finishing requirements are specified in Division 03 Section "Cast-in-Place Concrete."
- C. Foundation-Mounted Poles: Mount pole with leveling nuts, and tighten top nuts to torque level recommended by pole manufacturer.
 - 1. Use anchor bolts and nuts selected to resist seismic forces defined for the application and approved by manufacturer.
 - 2. Grout void between pole base and foundation. Use nonshrink or expanding concrete grout firmly packed to fill space.
 - 3. Install base covers unless otherwise indicated.
 - 4. Use a short piece of 1/2-inch- diameter pipe to make a drain hole through grout. Arrange to drain condensation from interior of pole.
- D. Raise and set poles using web fabric slings (not chain or cable).

3.3 BOLLARD LUMINAIRE INSTALLATION

- A. Align units for optimum directional alignment of light distribution.
- B. Install on concrete base. Cast conduit into base, and shape base to match shape of bollard base. Finish by troweling and rubbing smooth. Concrete materials, installation, and finishing are specified in Division 03 Section "Cast-in-Place Concrete."

3.4 INSTALLATION OF INDIVIDUAL GROUND-MOUNTING LUMINAIRES

- A. Install on concrete base with top 4 inches above finished grade or surface at luminaire location. Cast conduit into base, and finish by troweling and rubbing smooth. Concrete materials, installation, and finishing are specified in Division 03 Section "Cast-in-Place Concrete."

3.5 CORROSION PREVENTION

- A. Aluminum: Do not use in contact with earth or concrete. When in direct contact with a dissimilar metal, protect aluminum by insulating fittings or treatment.
- B. Steel Conduits: Comply with Division 26 Section "Raceway and Boxes for Electrical Systems." In concrete foundations, wrap conduit with 0.010-inch- thick, pipe-wrapping plastic tape applied with a 50 percent overlap.

3.6 GROUNDING

- A. Ground nonmetallic poles and support structures according to Division 26 Section "Grounding and Bonding for Electrical Systems."
 - 1. Install grounding electrode for each pole.
 - 2. Install grounding conductor and conductor protector.
 - 3. Ground metallic components of pole accessories and foundations.

3.7 FIELD QUALITY CONTROL

- A. Inspect each installed fixture for damage. Replace damaged fixtures and components.
- B. Illumination Observations: Verify normal operation of lighting units after installing luminaires and energizing circuits with normal power source.
 - 1. Verify operation of photoelectric controls.
- C. Prepare a written report of tests, inspections, observations, and verifications indicating and interpreting results. If adjustments are made to lighting system, retest to demonstrate compliance with standards.

END OF SECTION 26 56 00

SECTION 27 05 28 - PATHWAYS FOR COMMUNICATIONS SYSTEMS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal conduits and fittings.
 - 2. Nonmetallic conduits and fittings.
 - 3. Optical-fiber-cable pathways and fittings.
 - 4. Metal wireways and auxiliary gutters.
 - 5. Boxes, enclosures, and cabinets.
 - 6. Handholes and boxes for exterior underground cabling.
- B. Related Requirements:
 - 1. Division 26 Section "Underground Ducts and Raceways for Electrical Systems" for exterior ductbanks, manholes, and underground utility construction.
 - 2. Division 26 Section "Raceways and Boxes for Electrical Systems" for conduits, wireways, surface raceways, boxes, enclosures, cabinets, handholes, and faceplate adapters serving electrical systems.
 - 3. Division 28 Section "Pathways for Electronic Safety and Security" for conduits, surface pathways, innerduct, boxes, and faceplate adapters serving electronic safety and security.

1.3 DEFINITIONS

- A. GRC: Galvanized rigid steel conduit.

1.4 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

PART 2 - PRODUCTS

2.1 METAL CONDUITS AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Allied Tube & Conduit; a Tyco International Ltd. Co.
 - 2. O-Z/Gedney; a brand of EGS Electrical Group.
 - 3. Southwire Company.
 - 4. Thomas & Betts Corporation.
 - 5. Western Tube and Conduit Corporation.
 - 6. Wheatland Tube Company; a division of John Maneely Company.
- B. General Requirements for Metal Conduits and Fittings:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Comply with TIA-569-B.
- C. GRC: Comply with ANSI C80.1 and UL 6.
- D. EMT: Comply with ANSI C80.3 and UL 797.
- E. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
 - 1. Conduit Fittings for Hazardous (Classified) Locations: Comply with UL 886 and NFPA 70.
 - 2. Fittings for EMT:
 - a. Material: Steel.
 - b. Type: Setscrew.
 - 3. Expansion Fittings: PVC or steel to match conduit type, complying with UL-467, rated for environmental conditions where installed, and including flexible external bonding jumper.
- F. Joint Compound for GRC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.2 NONMETALLIC CONDUITS AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Allied Tube & Conduit; a Tyco International Ltd. Co.
 - 2. O-Z/Gedney; a brand of EGS Electrical Group.
 - 3. Southwire Company.
 - 4. Thomas & Betts Corporation.
 - 5. Western Tube and Conduit Corporation.
 - 6. Wheatland Tube Company; a division of John Maneely Company.

- B. General Requirements for Nonmetallic Conduits and Fittings:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Comply with TIA-569-B.
- C. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- D. Fittings for RNC: Comply with NEMA TC 3; match to conduit or tubing type and material.
- E. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- F. Solvent cements and adhesive primers shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.3 OPTICAL-FIBER-CABLE PATHWAYS AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Alpha Wire Company.
 - 2. Arnco Corporation.
 - 3. Endot Industries Inc.
 - 4. IPEX.
 - 5. Lamson & Sessions; Carlon Electrical Products.
- B. Description: Comply with UL 2024; flexible-type pathway, approved for general-use installation unless otherwise indicated.
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Comply with TIA-569-B.

2.4 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Manufacturers: Subject to compliance with requirements, [available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Cooper B-Line, Inc.
 - 2. Hoffman; a Pentair company.
 - 3. Mono-Systems, Inc.
 - 4. Square D; a brand of Schneider Electric.
- B. Description: Sheet metal, complying with UL 870 and NEMA 250, Type 1 and Type 3R unless otherwise indicated, and sized according to NFPA 70.

1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 2. Comply with TIA-569-B.
- C. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- D. Wireway Covers: Screw-cover type unless otherwise indicated.
- E. Finish: Manufacturer's standard enamel finish.

2.5 BOXES, ENCLOSURES, AND CABINETS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Cooper Technologies Company; Cooper Crouse-Hinds.
 2. EGS/Appleton Electric.
 3. Erickson Electrical Equipment Company.
 4. Hoffman; a Pentair company.
 5. Hubbell Incorporated; Killark Division.
 6. O-Z/Gedney; a brand of EGS Electrical Group.
 7. RACO; a Hubbell company.
 8. Thomas & Betts Corporation.
 9. Wiremold / Legrand.
- B. General Requirements for Boxes, Enclosures, and Cabinets:
1. Comply with TIA-569-B.
 2. Boxes, enclosures and cabinets installed in wet locations shall be listed for use in wet locations.
- C. Sheet-Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- D. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, ferrous alloy, Type FD, with gasketed cover.
- E. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- F. Nonmetallic Floor Boxes: Nonadjustable, round or rectangular.
1. Listing and Labeling: Nonmetallic floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- G. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- H. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, galvanized, cast iron with gasketed cover.

- I. Device Box Dimensions: 4 inches square by 2-1/8 inches deep.
- J. Gangable boxes are allowed.
- K. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 and Type 3R with continuous-hinge cover with flush latch unless otherwise indicated.
 - 1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
 - 2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- L. Cabinets:
 - 1. NEMA 250, Type 1 and Type 3R, galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
 - 2. Hinged door in front cover with flush latch and concealed hinge.
 - 3. Key latch to match panelboards.
 - 4. Metal barriers to separate wiring of different systems and voltage.
 - 5. Accessory feet where required for freestanding equipment.
 - 6. Nonmetallic cabinets shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.6 HANDHOLES AND BOXES FOR EXTERIOR UNDERGROUND CABLING

- A. General Requirements for Handholes and Boxes:
 - 1. Boxes and handholes for use in underground systems shall be designed and identified as defined in NFPA 70, for intended location and application.
 - 2. Boxes installed in wet areas shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 3. Comply with TIA-569-B.
- B. Polymer-Concrete Handholes and Boxes with Polymer-Concrete Cover: Molded of sand and aggregate, bound together with polymer resin, and reinforced with steel, fiberglass, or a combination of the two.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Armorcast Products Company.
 - b. Carson Industries LLC.
 - c. CDR Systems Corporation; Hubbell Power Systems.
 - d. NewBasis.
 - e. Oldcastle Precast, Inc.; Christy Concrete Products.
 - f. Synertech Moulded Products; a division of Oldcastle Precast, Inc.
 - 2. Standard: Comply with SCTE 77.
 - 3. Configuration: Designed for flush burial with closed bottom unless otherwise indicated.
 - 4. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure and handhole location.
 - 5. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
 - 6. Cover Legend: Molded lettering, "COMMUNICATIONS."

7. Conduit Entrance Provisions: Conduit-terminating fittings shall mate with entering ducts for secure, fixed installation in enclosure wall.
8. Handholes 12 Inches Wide by 24 Inches Long and Larger: Have inserts for cable racks and pulling-in irons installed before concrete is poured.

2.7 SOURCE QUALITY CONTROL FOR UNDERGROUND ENCLOSURES

- A. Handhole and Pull-Box Prototype Test: Test prototypes of handholes and boxes for compliance with SCTE 77. Strength tests shall be for specified tier ratings of products supplied.
 1. Tests of materials shall be performed by an independent testing agency.
 2. Strength tests of complete boxes and covers shall be by either an independent testing agency or manufacturer. A qualified registered professional engineer shall certify tests by manufacturer.
 3. Testing machine pressure gages shall have current calibration certification complying with ISO 9000 and ISO 10012, and traceable to NIST standards.

PART 3 - EXECUTION

3.1 PATHWAY APPLICATION

- A. Outdoors: Apply pathway products as specified below unless otherwise indicated:
 1. Exposed Conduit: GRC, IMC,.
 2. Concealed Conduit, Aboveground: GRC or EMT.
 3. Underground Conduit: RNC, Type EPC-40-PVC, concrete encased.
 4. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.
- B. Indoors: Apply pathway products as specified below unless otherwise indicated:
 1. Exposed, Not Subject to Physical Damage: EMT.
 2. Exposed, Not Subject to Severe Physical Damage: EMT.
 3. Exposed and Subject to Severe Physical Damage: GRC. Pathway locations include the following:
 - a. Loading dock.
 - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
 - c. Mechanical rooms.
 4. Concealed in Ceilings and Interior Walls and Partitions: EMT.
 5. Damp or Wet Locations: GRC.
 6. Pathways for Optical-Fiber or Communications Cable in Spaces Used for Environmental Air: EMT.
 7. Pathways for Optical-Fiber or Communications-Cable Risers in Vertical Shafts: EMT.
 8. Pathways for Concealed General-Purpose Distribution of Optical-Fiber or Communications Cable: EMT.
 9. Boxes and Enclosures: NEMA 250 Type 1, except use NEMA 250 Type 4 stainless steel in institutional and commercial kitchens and damp or wet locations.

- C. Minimum Pathway Size: 1-inch trade size. Minimum size for optical-fiber cables is 1 inch.
- D. Pathway Fittings: Compatible with pathways and suitable for use and location.
 - 1. Rigid Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
 - 2. EMT: Use setscrew fittings. Comply with NEMA FB 2.10.
- E. Do not install aluminum conduits, boxes, or fittings in contact with concrete or earth.
- F. Install surface pathways only where indicated on Drawings.
- G. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F.

3.2 INSTALLATION

- A. Comply with NECA 1, NECA 101, and TIA-569-B for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum pathways. Comply with NFPA 70 limitations for types of pathways allowed in specific occupancies and number of floors.
- B. Keep pathways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal pathway runs above water and steam piping.
- C. Complete pathway installation before starting conductor installation.
- D. Comply with requirements in Division 26 Section "Hangers and Supports for Electrical Systems" for hangers and supports.
- E. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- F. Install no more than the equivalent of two 90-degree bends in any pathway run. Support within 12 inches of changes in direction. Utilize long radius ells for all optical-fiber cables.
- G. Conceal conduit and EMT within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- H. Support conduit within 12 inches of enclosures to which attached.
- I. Pathways Embedded in Slabs:
 - 1. Do not install conduit in slab.
- J. Stub-ups to Above Recessed Ceilings:
 - 1. Use EMT or RMC for pathways.
 - 2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.

- K. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of pathway and fittings before making up joints. Follow compound manufacturer's written instructions.
- L. Coat field-cut threads on PVC-coated pathway with a corrosion-preventing conductive compound prior to assembly.
- M. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install insulated bushings on conduits terminated with locknuts.
- N. Install pathways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- O. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.
- P. Cut conduit perpendicular to the length. For conduits of 2-inch trade size and larger, use roll cutter or a guide to ensure cut is straight and perpendicular to the length.
- Q. Install pull wires in empty pathways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground pathways designated as spare above grade alongside pathways in use.
- R. Pathways for Optical-Fiber and Communications Cable: Install pathways, metal and nonmetallic, rigid and flexible, as follows:
 - 1. 1-Inch Trade Size and Larger: Install pathways in maximum lengths of 75 feet.
 - 2. Install with a maximum of two 90-degree bends or equivalent for each length of pathway unless Drawings show stricter requirements. Separate lengths with pull or junction boxes or terminations at distribution frames or cabinets where necessary to comply with these requirements.
- S. Install pathway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed pathways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install pathway sealing fittings according to NFPA 70.
- T. Install devices to seal pathway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all pathways at the following points:
 - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2. Where an underground service pathway enters a building or structure.
 - 3. Where otherwise required by NFPA 70.
- U. Comply with manufacturer's written instructions for solvent welding PVC conduit and fittings.
- V. Expansion-Joint Fittings:

1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F, and that has straight-run length that exceeds 25 feet. Install in each run of aboveground RMC and EMT conduit that is located where environmental temperature change may exceed 100 deg F and that has straight-run length that exceeds 100 feet.
 2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
 - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
 - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F temperature change.
 - c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
 - d. Attics: 135 deg F temperature change.
 3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.
 4. Install expansion fittings at all locations where conduits cross building or structure expansion joints.
 5. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
- W. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
- X. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surface to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.
- Y. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
- Z. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- AA. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.

3.3 INSTALLATION OF UNDERGROUND CONDUIT

- A. Direct-Buried Conduit:

1. Excavate trench bottom to provide firm and uniform support for conduit. Prepare trench bottom as specified in Division 31 Section "Earth Moving" for pipe less than 6 inches in nominal diameter.
2. Install backfill as specified in Division 31 Section "Earth Moving."
3. After installing conduit, backfill and compact. Start at tie-in point, and work toward end of conduit run, leaving conduit at end of run free to move with expansion and contraction as temperature changes during this process. Firmly hand tamp backfill around conduit to provide maximum supporting strength. After placing controlled backfill to within 12 inches of finished grade, make final conduit connection at end of run and complete backfilling with normal compaction as specified in Division 31 Section "Earth Moving."
4. Install manufactured duct elbows for stub-ups at poles and equipment and at building entrances through floor unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.
5. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through floor.
 - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches of concrete for a minimum of 12 inches on each side of the coupling.
 - b. For stub-ups at equipment mounted on outdoor concrete bases and where conduits penetrate building foundations, extend steel conduit horizontally a minimum of 60 inches from edge of foundation or equipment base. Install insulated grounding bushings on terminations at equipment.
6. Warning Planks: Bury warning planks approximately 12 inches above direct-buried conduits, but a minimum of 6 inches below grade. Align planks along centerline of conduit.
7. Underground Warning Tape: Comply with requirements in Division 26 Section "Identification for Electrical Systems."

3.4 INSTALLATION OF UNDERGROUND HANDHOLES AND BOXES

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting conduits to minimize bends and deflections required for proper entrances.
- B. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch sieve to No. 4 sieve and compacted to same density as adjacent undisturbed earth.
- C. Elevation: In paved areas, set so cover surface will be flush with finished grade. Set covers of other enclosures 1 inch above finished grade.
- D. Install handholes with bottom below frost line, below grade.
- E. Install removable hardware, including pulling eyes, cable stanchions, cable arms, and insulators, as required for installation and support of cables and conductors and as indicated. Select arm lengths to be long enough to provide spare space for future cables, but short enough to preserve adequate working clearances in enclosure.

- F. Field cut openings for conduits according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.

3.5 FIRESTOPPING

- A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Division 07 Section "Penetration Firestopping."
- B. Install Hubbell EZ Pass at all wall penetrations with multiple cable penetrations not installed in raceway.

3.6 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage or deterioration.
 - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
 - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 27 05 28

This page intentionally left blank.

SECTION 27 05 44

SLEEVES AND SLEEVE SEALS FOR COMMUNICATIONS PATHWAYS AND CABLING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Sleeves for pathway and cable penetration of non-fire-rated construction walls and floors.
 - 2. Sleeve-seal systems.
 - 3. Sleeve-seal fittings.
 - 4. Grout.
 - 5. Silicone sealants.
- B. Related Requirements:
 - 1. Division 07 Section "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

1.3 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

PART 2 - PRODUCTS

2.1 SLEEVES

- A. Wall Sleeves:
 - 1. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, plain ends.
 - 2. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies: Galvanized-steel sheet; 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint, with tabs for screw-fastening the sleeve to the board.
- C. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.
- D. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.
- E. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.
- F. Sleeves for Rectangular Openings:
 - 1. Material: Galvanized-steel sheet.
 - 2. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches and with no side larger than 16 inches, thickness shall be 0.052 inch.
 - b. For sleeve cross-section rectangle perimeter 50 inches or more and one or more sides larger than 16 inches, thickness shall be 0.138 inch.

2.2 SLEEVE-SEAL SYSTEMS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and pathway or cable.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Advance Products & Systems, Inc.
 - b. CALPICO, Inc.
 - c. Metraflex Company (The).
 - d. Pipeline Seal and Insulator, Inc.
 - e. Proco Products, Inc.
 - 2. Sealing Elements: EPDM rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Stainless steel.
 - 4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

2.3 SLEEVE-SEAL FITTINGS

- A. Description: Manufactured plastic, sleeve-type, waterstop assembly made for embedding in concrete slab or wall. Unit shall have plastic or rubber waterstop collar with center opening to match piping OD.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Presealed Systems.

2.4 GROUT

- A. Description: Nonshrink; recommended for interior and exterior sealing openings in non-fire-rated walls or floors.
- B. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

2.5 SILICONE SEALANTS

- A. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below.
 - 1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces that are not fire rated.
 - 2. Sealant shall have VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 3. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- B. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION FOR NON-FIRE-RATED ELECTRICAL PENETRATIONS

- A. Comply with NECA 1.
- B. Comply with NEMA VE 2 for cable tray and cable penetrations.

- C. Sleeves for Conduits Penetrating Above-Grade Non-Fire-Rated Concrete and Masonry-Unit Floors and Walls:
 - 1. Interior Penetrations of Non-Fire-Rated Walls and Floors:
 - a. Seal annular space between sleeve and pathway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
 - b. Seal space outside of sleeves with mortar or grout. Pack sealing material solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect material while curing.
 - 2. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
 - 3. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and pathway or cable unless sleeve seal is to be installed or unless seismic criteria require different clearance.
 - 4. Install sleeves for wall penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of walls. Cut sleeves to length for mounting flush with both surfaces of walls. Deburr after cutting.
 - 5. Install sleeves for floor penetrations. Extend sleeves installed in floors 2 inches above finished floor level. Install sleeves during erection of floors.
- D. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies:
 - 1. Use circular metal sleeves unless penetration arrangement requires rectangular sleeved opening.
 - 2. Seal space outside of sleeves with approved joint compound for gypsum board assemblies.
- E. Roof-Penetration Sleeves: Seal penetration of individual pathways and cables with flexible boot-type flashing units applied in coordination with roofing work.
- F. Aboveground, Exterior-Wall Penetrations: Seal penetrations using cast-iron pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- G. Underground, Exterior-Wall and Floor Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch annular clear space between pathway or cable and sleeve for installing sleeve-seal system.

3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at pathway entries into building.
- B. Install type and number of sealing elements recommended by manufacturer for pathway or cable material and size. Position pathway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pathway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.3 SLEEVE-SEAL-FITTING INSTALLATION

- A. Install sleeve-seal fittings in new walls and slabs as they are constructed.
- B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position waterstop flange to be centered in concrete slab or wall.
- C. Secure nailing flanges to concrete forms.
- D. Using grout, seal the space around outside of sleeve-seal fittings.

END OF SECTION 27 05 44

This page intentionally left blank.

SECTION 27 11 00

COMMUNICATIONS EQUIPMENT ROOM FITTINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Backboards.
 - 2. Grounding.
- B. Related Requirements:
 - 1. Division 27 Section "Communications Backbone Cabling" for voice and data cabling associated with system panels and devices.
 - 2. Division 27 Section "Communications Horizontal Cabling" for voice and data cabling associated with system panels and devices.
 - 3. Division 28 Section "Conductors and Cables for Electronic Safety and Security" for voice and data cabling associated with system panels and devices.

1.3 DEFINITIONS

- A. BICSI: Building Industry Consulting Service International.
- B. LAN: Local area network.
- C. RCDD: Registered Communications Distribution Designer.

1.4 ACTION SUBMITTALS

- A. Shop Drawings: For communications equipment room fittings. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Grounding: Indicate location of grounding bus bar and its mounting detail showing standoff insulators and wall mounting brackets.

1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified layout technician, installation supervisor, and field inspector.
- B. Seismic Qualification Certificates: For equipment frames from manufacturer.

1.6 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
 - 1. Layout Responsibility: Preparation of Shop Drawings shall be under the direct supervision of Commercial Installer, Level 2.
 - 2. Installation Supervision: Installation shall be under the direct supervision of Level 2 Installer, who shall be present at all times when Work of this Section is performed at Project site.
 - 3. Field Inspector: Currently registered by BICSI as Commercial Installer, Level 2 to perform the on-site inspection.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Equipment frames shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
 - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."

2.2 BACKBOARDS

- A. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches.

2.3 GROUNDING

- A. Comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems." for grounding conductors and connectors.
- B. Telecommunications Main Bus Bar:
 - 1. Connectors: Mechanical type, cast silicon bronze, solderless compression-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.
 - 2. Ground Bus Bar: Copper, minimum 1/4 inch thick by 4 inches wide by 24 inch long with 9/32-inch holes spaced 1-1/8 inches apart.
 - 3. Stand-Off Insulators: Comply with UL 891 for use in switchboards, 600 V. Lexan or PVC, impulse tested at 5000 V.
- C. Comply with J-STD-607-A.

2.4 LABELING

- A. Comply with TIA/EIA-606-A and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

PART 3 - EXECUTION

3.1 ENTRANCE FACILITIES

- A. Contact telecommunications service provider and arrange for installation of demarcation point, protected entrance terminals, and a housing when so directed by service provider.
- B. Comply with requirements in Division 27 Section "Pathways for Communications Systems" for materials and installation requirements for underground pathways.

3.2 INSTALLATION

- A. Comply with NECA 1.
- B. Comply with BICSI TDMM for layout and installation of communications equipment rooms.
- C. Bundle, lace, and train conductors and cables to terminal points without exceeding manufacturer's limitations on bending radii. Install lacing bars and distribution spools.
- D. Coordinate layout and installation of communications equipment with Owner's telecommunications and LAN equipment and service suppliers. Coordinate service entrance arrangement with local exchange carrier.
 - 1. Meet jointly with telecommunications and LAN equipment suppliers, local exchange carrier representatives, and Owner to exchange information and agree on details of equipment arrangements and installation interfaces.
 - 2. Record agreements reached in meetings and distribute them to other participants.
 - 3. Adjust arrangements and locations of distribution frames, cross-connects, and patch panels in equipment rooms to accommodate and optimize arrangement and space requirements of telephone switch and LAN equipment.
 - 4. Adjust arrangements and locations of equipment with distribution frames, cross-connects, and patch panels of cabling systems of other communications, electronic safety and security, and related systems that share space in the equipment room.
- E. Coordinate location of power raceways and receptacles with locations of communications equipment requiring electrical power to operate.

3.3 SLEEVE AND SLEEVE SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Division 27 Section "Sleeves and Sleeve Seals for Communications Pathways and Cabling."

3.4 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping."
- B. Comply with TIA-569-B, Annex A, "Firestopping."
- C. Comply with BICSI TDMM, "Firestopping Systems" Article.

3.5 GROUNDING

- A. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. Comply with J-STD-607-A.
- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch clearance behind the grounding bus bar. Connect grounding bus bar with a minimum No. 4 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.
- D. Bond metallic equipment to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.
 - 1. Bond the shield of shielded cable to the grounding bus bar in communications rooms and spaces.

3.6 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements in Division 26 Section "Identification for Electrical Systems."
- B. Comply with requirements in Division 09 Section "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- C. Paint and label colors for equipment identification shall comply with TIA/EIA-606-A for Class 3 level of administration.
- D. Labels shall be preprinted or computer-printed type.

END OF SECTION 27 11 00

SECTION 27 13 00

COMMUNICATIONS BACKBONE CABLING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Pathways.
 - 2. UTP cable.
 - 3. Cable connecting hardware, patch panels, and cross-connects.
 - 4. Cabling identification products.

1.3 DEFINITIONS

- A. BICSI: Building Industry Consulting Service International.
- B. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.
- C. EMI: Electromagnetic interference.
- D. IDC: Insulation displacement connector.
- E. LAN: Local area network.
- F. RCDD: Registered Communications Distribution Designer.
- G. UTP: Unshielded twisted pair.

1.4 BACKBONE CABLING DESCRIPTION

- A. Backbone cabling system shall provide interconnections between communications equipment rooms, main terminal space, and entrance facilities in the telecommunications cabling system structure. Cabling system consists of backbone cables, intermediate and main cross-connects, mechanical terminations, and patch cords or jumpers used for backbone-to-backbone cross-connection.

- B. Backbone cabling cross-connects may be located in communications equipment rooms or at entrance facilities. Bridged taps and splitters shall not be used as part of backbone cabling.

1.5 PERFORMANCE REQUIREMENTS

- A. General Performance: Backbone cabling system shall comply with transmission standards in TIA/EIA-568-B.1, when tested according to test procedures of this standard.

1.6 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
 - 1. For cable, include the following installation data for each type used:
 - a. Nominal OD.
 - b. Minimum bending radius.
 - c. Maximum pulling tension.
- B. Shop Drawings:
 - 1. System Labeling Schedules: Electronic copy of labeling schedules, in software and format selected by Owner.
 - 2. Cabling administration drawings and printouts.

1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Patch-Panel Units: One of each type.
 - 2. Connecting Blocks: One of each type.

1.8 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
 - 1. Layout Responsibility: Preparation of Shop Drawings, Cabling Administration Drawings, and field testing program development by an RCDD.
 - 2. Installation Supervision: Installation shall be under the direct supervision of Level 2 Installer, who shall be present at all times when Work of this Section is performed at Project site.
 - 3. Testing Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
- B. Testing Agency Qualifications: An NRTL.
 - 1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.

- C. Surface-Burning Characteristics: As determined by testing identical products according to ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 450 or less.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- E. Telecommunications Pathways and Spaces: Comply with TIA/EIA-569-A.
- F. Grounding: Comply with ANSI-J-STD-607-A.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
 - 1. Test each pair of UTP cable for open and short circuits.

1.10 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.11 COORDINATION

- A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers.

1.12 SOFTWARE SERVICE AGREEMENT

- A. Technical Support: Beginning with Substantial Completion, provide software support for two years.
- B. Upgrade Service: Update software to latest version at Project completion. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software shall include operating system. Upgrade shall include new or revised licenses for use of software.
 - 1. Provide 30 days' notice to Owner to allow scheduling and access to system and to allow Owner to upgrade computer equipment if necessary.

PART 2 - PRODUCTS

2.1 PATHWAYS

- A. General Requirements: Comply with TIA/EIA-569-A.
- B. Cable Support: NRTL labeled for support of Category 6 cabling, designed to prevent degradation of cable performance and pinch points that could damage cable.
 - 1. Support brackets with cable tie slots for fastening cable ties to brackets.
 - 2. Lacing bars, spools, J-hooks, and D-rings.
 - 3. Straps and other devices.
- C. Conduit and Boxes: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems." Flexible metal conduit shall not be used.
 - 1. Outlet boxes shall be no smaller than 2 inches wide, 3 inches high, and 2-1/2 inches deep.

2.2 UTP CABLE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Belden CDT Inc.; Electronics Division.
 - 2. Berk-Tek; a Nexans company.
 - 3. CommScope, Inc.
 - 4. Draka USA.
 - 5. Genesis Cable Products; Honeywell International, Inc.
 - 6. KRONE Incorporated.
 - 7. Mohawk; a division of Belden CDT.
 - 8. Nordex/CDT; a subsidiary of Cable Design Technologies.
 - 9. Superior Essex Inc.
 - 10. SYSTIMAX Solutions; a CommScope Inc. brand.
 - 11. 3M.
 - 12. Tyco Electronics/AMP Netconnect; Tyco International Ltd.
- B. Description: 100-ohm, 100-pair UTP, formed into 25-pair binder groups covered with a gray thermoplastic jacket.
 - 1. Comply with ICEA S-90-661 for mechanical properties.
 - 2. Comply with TIA/EIA-568-B.1 for performance specifications.
 - 3. Comply with TIA/EIA-568-B.2, [Category 5e] [Category 6].
 - 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
 - a. Communications, General Purpose: Type CM or CMG.
 - b. Communications, Plenum Rated: Type CMP, complying with NFPA 262.
 - c. Communications, Riser Rated: Type CMR, complying with UL 1666.
 - d. Communications, Limited Purpose: Type CMX.
 - e. Multipurpose: Type MP or MPG.
 - f. Multipurpose, Plenum Rated: Type MPP, complying with NFPA 262.
 - g. Multipurpose, Riser Rated: Type MPR, complying with UL 1666.

2.3 UTP CABLE HARDWARE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. American Technology Systems Industries, Inc.
 - 2. Dynacom Corporation.
 - 3. Hubbell Premise Wiring.
 - 4. KRONE Incorporated.
 - 5. Leviton Voice & Data Division.
 - 6. Molex Premise Networks; a division of Molex, Inc.
 - 7. Nordex/CDT; a subsidiary of Cable Design Technologies.
 - 8. Panduit Corp.
 - 9. Siemon Co. (The).
 - 10. Tyco Electronics/AMP Netconnect; Tyco International Ltd.
- B. General Requirements for Cable Connecting Hardware: Comply with TIA/EIA-568-B.2, IDC type, with modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of same category or higher.
- C. Connecting Blocks: [110-style IDC for Category 5e] [110-style IDC for Category 6] [66-style IDC for Category 5e]. Provide blocks for the number of cables terminated on the block, plus 25 percent spare. Integral with connector bodies, including plugs and jacks where indicated.
- D. Cross-Connect: Modular array of connecting blocks arranged to terminate building cables and permit interconnection between cables.
 - 1. Number of Terminals per Field: One for each conductor in assigned cables.
- E. Patch Panel: Modular panels housing multiple-numbered jack units with IDC-type connectors at each jack for permanent termination of pair groups of installed cables.
 - 1. Number of Jacks per Field: One for each four-pair UTP cable indicated.
- F. Jacks and Jack Assemblies: Modular, color-coded, eight-position modular receptacle units with integral IDC-type terminals.
- G. Patch Cords: Factory-made, 4-pair cables in 36-inch lengths; terminated with 8-position modular plug at each end.
 - 1. Patch cords shall have bend-relief-compliant boots and color-coded icons to ensure Category 6 performance. Patch cords shall have latch guards to protect against snagging.
 - 2. Patch cords shall have color-coded boots for circuit identification.

2.4 GROUNDING

- A. Comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems." for grounding conductors and connectors.
- B. Comply with ANSI-J-STD-607-A.

2.5 IDENTIFICATION PRODUCTS

- A. Comply with TIA/EIA-606-A and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

2.6 SOURCE QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate cables.
- B. Factory test cables on reels according to TIA/EIA-568-B.1.
- C. Factory test UTP cables according to TIA/EIA-568-B.2.
- D. Cable will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 ENTRANCE FACILITIES

- A. Coordinate backbone cabling with the protectors and demarcation point provided by communications service provider.

3.2 WIRING METHODS

- A. Wiring Method: Install cables in raceways except within consoles, cabinets, desks, and counters. Conceal raceway and cables except in unfinished spaces.
 - 1. Install plenum cable, including plenum ceilings.
 - 2. Comply with requirements for raceways and boxes specified in Division 26 Section "Raceway and Boxes for Electrical Systems."
- B. Wiring Method: Conceal conductors and cables in accessible ceilings, walls, and floors where possible.
- C. Wiring within Enclosures: Bundle, lace, and train cables within enclosures. Connect to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.

3.3 INSTALLATION OF PATHWAYS

- A. Comply with requirements for demarcation point, pathways, cabinets, and racks specified in Division 27 Section "Communications Equipment Room Fittings." Drawings indicate general arrangement of pathways and fittings.
- B. Comply with TIA/EIA-569-A for pull-box sizing and length of conduit and number of bends between pull points.

- C. Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems" for installation of conduits and wireways.
- D. Install manufactured conduit sweeps and long-radius elbows whenever possible.
- E. Pathway Installation in Communications Equipment Rooms:
 - 1. Position conduit ends adjacent to a corner on backboard where a single piece of plywood is installed, or in the corner of room where multiple sheets of plywood are installed around perimeter walls of room.
 - 2. Secure conduits to backboard when entering room from overhead.
 - 3. Extend conduits 3 inches above finished floor.
 - 4. Install metal conduits with grounding bushings and connect with grounding conductor to grounding system.

3.4 INSTALLATION OF CABLES

- A. Comply with NECA 1.
- B. General Requirements for Cabling:
 - 1. Comply with TIA/EIA-568-B.1.
 - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
 - 3. Install 110-style IDC termination hardware unless otherwise indicated.
 - 4. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
 - 5. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
 - 6. Install lacing bars to restrain cables, to prevent straining connections, and to prevent bending cables to smaller radii than minimums recommended by manufacturer.
 - 7. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Use lacing bars and distribution spools.
 - 8. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
 - 9. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
 - 10. In the communications equipment room, install a 10-foot- long service loop on each end of cable.
 - 11. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
- C. UTP Cable Installation:
 - 1. Comply with TIA/EIA-568-B.2.
 - 2. Do not untwist UTP cables more than 1/2 inch from the point of termination to maintain cable geometry.

- D. Open-Cable Installation:
 - 1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
 - 2. Suspend UTP cable not in a wireway or pathway, a minimum of 8 inches above ceilings by cable supports not more than 60 inches apart.
 - 3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.
- E. Group connecting hardware for cables into separate logical fields.
- F. Separation from EMI Sources:
 - 1. Comply with BICSI TDMM and TIA/EIA-569-A recommendations for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.
 - 2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.
 - 3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
 - 4. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
 - 5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.

3.5 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping."
- B. Comply with TIA/EIA-569-A, Annex A, "Firestopping."
- C. Comply with BICSI TDMM, "Firestopping Systems" Article.

3.6 GROUNDING

- A. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. Comply with ANSI-J-STD-607-A.

- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch clearance behind the grounding bus bar. Connect grounding bus bar with a minimum No. 4 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.
- D. Bond metallic equipment to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.

3.7 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
 - 1. Administration Class: 2.
 - 2. Color-code cross-connect fields and apply colors to voice and data service backboards, connections, covers, and labels.
- B. Comply with requirements in Division 09 Section "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- C. Paint and label colors for equipment identification shall comply with TIA/EIA-606-A for Class 2 level of administration.
- D. Comply with requirements in Division 27 Section "Communications Horizontal Cabling" for cable and asset management software.
- E. Cable Schedule: Install in a prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish an electronic copy of final comprehensive schedules for Project.
- F. Cabling Administration Drawings: Show building floor plans with cabling administration-point labeling. Identify labeling convention and show labels for telecommunications closets, backbone pathways and cables, entrance pathways and cables, terminal hardware and positions, horizontal cables, work areas and workstation terminal positions, grounding buses and pathways, and equipment grounding conductors.
- G. Cable and Wire Identification:
 - 1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
 - 2. Each wire connected to building-mounted devices is not required to be numbered at device if color of wire is consistent with associated wire connected and numbered within panel or cabinet.
 - 3. Exposed Cables and Cables: Label each cable at intervals not exceeding 15 feet.
 - 4. Label each terminal strip and screw terminal in each cabinet, rack, or panel.
 - a. Individually number wiring conductors connected to terminal strips and identify each cable or wiring group being extended from a panel or cabinet

to a building-mounted device with name and number of particular device as shown.

- b. Label each unit and field within distribution racks and frames.
- 5. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.
- H. Labels shall be preprinted or computer-printed type with printing area and font color that contrasts with cable jacket color but still complies with requirements in TIA/EIA 606-A, for the following:
 - 1. Cables use flexible vinyl or polyester that flexes as cables are bent.

3.8 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
 - 1. Visually inspect UTP jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA/EIA-568-B.1.
 - 2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
 - 3. Test UTP copper cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.
 - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
- C. Data for each measurement shall be documented. Data for submittals shall be printed in a summary report that is formatted similar to Table 10.1 in BICSI TDMM, or transferred from the instrument to the computer, saved as text files, and printed and submitted.
- D. Remove and replace cabling where test results indicate that they do not comply with specified requirements.
- E. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

END OF SECTION 27 13 00

SECTION 27 15 00 - COMMUNICATIONS HORIZONTAL CABLING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. UTP cabling.
 - 2. Multiuser telecommunications outlet assemblies.
 - 3. Cable connecting hardware, patch panels, and cross-connects.
 - 4. Telecommunications outlet/connectors.
 - 5. Cabling system identification products.
 - 6. Cable management system.

1.3 DEFINITIONS

- A. BICSI: Building Industry Consulting Service International.
- B. Consolidation Point: A location for interconnection between horizontal cables extending from building pathways and horizontal cables extending into furniture pathways.
- C. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.
- D. EMI: Electromagnetic interference.
- E. IDC: Insulation displacement connector.
- F. LAN: Local area network.
- G. MUTOA: Multiuser telecommunications outlet assembly, a grouping in one location of several telecommunications outlet/connectors.
- H. Outlet/Connectors: A connecting device in the work area on which horizontal cable or outlet cable terminates.
- I. RCDD: Registered Communications Distribution Designer.
- J. UTP: Unshielded twisted pair.

1.4 ADMINISTRATIVE REQUIREMENTS

- A. Coordinate layout and installation of telecommunications cabling with Owner's telecommunications and LAN equipment and service suppliers.
- B. Coordinate telecommunications outlet/connector locations with location of power receptacles at each work area.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
 - 1. For cable, include the following installation data for each type used:
 - a. Nominal OD.
 - b. Minimum bending radius.
 - c. Maximum pulling tension.
- B. Shop Drawings:
 - 1. System Labeling Schedules: Electronic copy of labeling schedules, in software and format selected by Owner.
 - 2. System Labeling Schedules: Electronic copy of labeling schedules that are part of the cabling and asset identification system of the software.
 - 3. Cabling administration drawings and printouts.
 - 4. Wiring diagrams to show typical wiring schematics, including the following:
 - a. Cross-connects.
 - b. Patch panels.
 - c. Patch cords.
 - 5. Cross-connects and patch panels. Detail mounting assemblies, and show elevations and physical relationship between the installed components.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer, qualified layout technician, installation supervisor, and field inspector.
- B. Source quality-control reports.
- C. Field quality-control reports.

1.7 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For splices and connectors to include in maintenance manuals.
- B. Software and Firmware Operational Documentation:
 - 1. Software operating and upgrade manuals.
 - 2. Program Software Backup: On magnetic media or compact disk, complete with data files.
 - 3. Device address list.

4. Printout of software application and graphic screens.

1.8 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
 1. Layout Responsibility: Preparation of Shop Drawings, Cabling Administration Drawings, and field testing program development by an RCDD.
 2. Installation Supervision: Installation shall be under the direct supervision of Registered Technician, who shall be present at all times when Work of this Section is performed at Project site.
 3. Testing Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
- B. Testing Agency Qualifications: An NRTL.
 1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
 1. Test each pair of UTP cable for open and short circuits.

PART 2 - PRODUCTS

2.1 HORIZONTAL CABLING DESCRIPTION

- A. Horizontal cable and its connecting hardware provide the means of transporting signals between the telecommunications outlet/connector and the horizontal cross-connect located in the communications equipment room. This cabling and its connecting hardware are called a "permanent link," a term that is used in the testing protocols.
 1. Horizontal cabling shall contain no more than one transition point or consolidation point between the horizontal cross-connect and the telecommunications outlet/connector.
 2. Bridged taps and splices shall not be installed in the horizontal cabling.
- B. The maximum allowable horizontal cable length is 295 feet. This maximum allowable length does not include an allowance for the length of 16 feet to the workstation equipment or in the horizontal cross-connect.

2.2 PERFORMANCE REQUIREMENTS

- A. General Performance: Horizontal cabling system shall comply with transmission standards in TIA/EIA-568-B.1 when tested according to test procedures of this standard.

- B. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 50 or less.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. Grounding: Comply with J-STD-607-A.

2.3 UTP CABLE

- A. Manufacturers: Subject to compliance with requirements, provide products by the following unless noted otherwise on drawings:
 - 1. Comscope
 - 2. General Cable
 - 3. Optical Cable
 - 4. Mohawk.
 - 5. Belden
- B. Description: 100-ohm, four-pair UTP, formed into 25-pair, binder groups covered with a blue thermoplastic jacket.
 - 1. Comply with ICEA S-90-661 for mechanical properties.
 - 2. Comply with TIA/EIA-568-B.1 for performance specifications.
 - 3. Comply with TIA/EIA-568-B.2, Category 6. Belden DataTwist 600e
 - 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
 - a. Communications, Plenum Rated: Type CMP, complying with NFPA 262.

2.4 UTP CABLE HARDWARE

- A. General Requirements for Cable Connecting Hardware: Comply with TIA/EIA-568-B.2, IDC type, with modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of same category or higher.
- B. Cross-Connect: Modular array of connecting blocks arranged to terminate building cables and permit interconnection between cables.
- C. Patch Panel: Modular panels housing multiple-numbered jack units with IDC-type connectors at each jack for permanent termination of pair groups of installed cables.
- D. Jacks and Jack Assemblies: Modular, color-coded, eight-position modular receptacle units with integral IDC-type terminals.
- E. Patch Cords: Factory-made, four-pair cables in 36-inch lengths; terminated with eight-position modular plug at each end.

1. Patch cords shall have bend-relief-compliant boots and color-coded icons to ensure Category 6 performance. Patch cords shall have latch guards to protect against snagging.
2. Patch cords shall have color-coded boots for circuit identification.

2.5 CONSOLIDATION POINTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 1. Belden CDT Networking Division/NORDX.
 2. Chatsworth Products, Inc.
- B. Description: Consolidation points shall comply with requirements for cable connecting hardware.
 1. Mounting: Recessed.
 2. NRTL listed as complying with UL 50 and UL 1863.
 3. When installed in plenums used for environmental air, NRTL listed as complying with UL 2043.

2.6 TELECOMMUNICATIONS OUTLET/CONNECTORS

- A. Jacks: 100-ohm, balanced, twisted-pair connector; four-pair, eight-position modular. Comply with TIA/EIA-568-B.1.
- B. Workstation Outlets: Four-port-connector assemblies mounted in single faceplate.
 1. Plastic Faceplate: High-impact plastic. Coordinate color with Section 26 27 26 "Wiring Devices."
 2. For use with snap-in jacks accommodating any combination of UTP work area cords.
 - a. Flush mounting jacks, positioning the cord at a 45-degree angle.
 3. Legend: Factory labeled by silk-screening or engraving.
 4. Legend: Machine printed, in the field, using adhesive-tape label.
 5. Legend: Snap-in, clear-label covers and machine-printed paper inserts.

2.7 GROUNDING

- A. Comply with requirements in Section 26 70 526 "Grounding and Bonding for Electrical Systems" for grounding conductors and connectors.
- B. Comply with J-STD-607-A.

2.8 IDENTIFICATION PRODUCTS

- A. Comply with TIA/EIA-606-A and UL 969 for labeling materials, including label stocks, laminating adhesives, and inks used by label printers.
- B. Comply with requirements in Section 26 05 53 "Identification for Electrical Systems."

2.9 SOURCE QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate cables.
- B. Factory test UTP cables on reels according to TIA/EIA-568-B.1.
- C. Factory test UTP cables according to TIA/EIA-568-B.2.
- D. Factory test multimode optical fiber cables according to TIA-526-14-A and TIA/EIA-568-B.3.
- E. Cable will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 ENTRANCE FACILITIES

- A. Coordinate backbone cabling with the protectors and demarcation point provided by communications service provider.

3.2 WIRING METHODS

- A. Install cables in pathways except within consoles, cabinets, desks, and counters and except in accessible ceiling spaces and in gypsum board partitions where unenclosed wiring method may be used. Conceal pathways and cables except in unfinished spaces.
 - 1. Install plenum cable in all spaces, including plenum ceilings.
 - 2. Comply with requirements in Section 27 05 28 "Pathways for Communications Systems."
- B. Conceal conductors and cables in accessible ceilings, walls, and floors where possible.
- C. Wiring within Enclosures:
 - 1. Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii.
 - 2. Install lacing bars and distribution spools.
 - 3. Install conductors parallel with or at right angles to sides and back of enclosure.

3.3 INSTALLATION OF CABLES

- A. Comply with NECA 1.
- B. General Requirements for Cabling:
 - 1. Comply with TIA/EIA-568-B.1.
 - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."

3. Consolidation points may be used only for making a direct connection to telecommunications outlet/connectors:
 - a. Do not use consolidation point as a cross-connect point, as a patch connection, or for direct connection to workstation equipment.
 - b. Locate consolidation points for UTP at least 49 feet from communications equipment room.
 4. Terminate conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
 5. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
 6. Install lacing bars to restrain cables, to prevent straining connections, and to prevent bending cables to smaller radii than minimums recommended by manufacturer.
 7. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Install lacing bars and distribution spools.
 8. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
 9. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
 10. In the communications equipment room, install a 10-foot- long service loop on each end of cable.
 11. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
- C. UTP Cable Installation:
1. Comply with TIA/EIA-568-B.2.
 2. Do not untwist UTP cables more than 1/2 inch from the point of termination to maintain cable geometry.
- D. Open-Cable Installation:
1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
 2. Suspend UTP cable not in a wireway or pathway a minimum of 8 inches above ceilings by cable supports not more than 60 inches apart.
 3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.
- E. Group connecting hardware for cables into separate logical fields.
- F. Separation from EMI Sources:
1. Comply with BICSI TDMM and TIA-569-B for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.
 2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:

- a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.
- 3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
- 4. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
- 5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.

3.4 FIRESTOPPING

- A. Comply with requirements in Section 07 84 13 "Penetration Firestopping."
- B. Comply with TIA-569-B, Annex A, "Firestopping."
- C. Comply with BICSI TDMM, "Firestopping Systems" Article.

3.5 GROUNDING

- A. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. Comply with J-STD-607-A.
- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch clearance behind the grounding bus bar. Bond metallic equipment to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.

3.6 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."
- B. Using cable management system software specified in Part 2, develop Cabling Administration Drawings for system identification, testing, and management. Use unique, alphanumeric designation for each cable and label cable, jacks, connectors,

and terminals to which it connects with same designation. At completion, cable and asset management software shall reflect as-built conditions.

- C. Comply with requirements in Section 09 91 23 "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- D. Paint and label colors for equipment identification shall comply with TIA/EIA-606-A
- E. Cable Schedule: Post in prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish an electronic copy of final comprehensive schedules for Project.
- F. Cable and Wire Identification:
 - 1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
 - 2. Each wire connected to building-mounted devices is not required to be numbered at device if color of wire is consistent with associated wire connected and numbered within panel or cabinet.
 - 3. Exposed Cables and Cables in Cable Trays and Wire Troughs: Label each cable at intervals not exceeding 15 feet.
 - 4. Label each terminal strip and screw terminal in each cabinet, rack, or panel.
 - a. Individually number wiring conductors connected to terminal strips, and identify each cable or wiring group being extended from a panel or cabinet to a building-mounted device shall be identified with name and number of particular device as shown.
 - b. Label each unit and field within distribution racks and frames.
 - 5. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.
- G. Labels shall be preprinted or computer-printed type with printing area and font color that contrasts with cable jacket color but still complies with requirements in TIA/EIA-606-A.
 - 1. Cables use flexible vinyl or polyester that flex as cables are bent.

3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- C. Perform the following tests and inspections:
 - 1. Visually inspect UTP and optical fiber cable jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA/EIA-568-B.1.

2. Visually confirm Category 6, marking of outlets, cover plates, outlet/connectors, and patch panels.
3. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
4. Test UTP backbone copper cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.
 - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
5. Optical Fiber Cable Tests:
 - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.1. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
 - b. Link End-to-End Attenuation Tests:
 - 1) Horizontal and multimode backbone link measurements: Test at 850 or 1300 nm in 1 direction according to TIA-526-14-A, Method B, One Reference Jumper.
 - 2) Attenuation test results for backbone links shall be less than 2.0 dB. Attenuation test results shall be less than that calculated according to equation in TIA/EIA-568-B.1.
6. UTP Performance Tests:
 - a. Test for each outlet and MUTOA. Perform the following tests according to TIA/EIA-568-B.1 and TIA/EIA-568-B.2:
 - 1) Wire map.
 - 2) Length (physical vs. electrical, and length requirements).
 - 3) Insertion loss.
 - 4) Near-end crosstalk (NEXT) loss.
 - 5) Power sum near-end crosstalk (PSNEXT) loss.
 - 6) Equal-level far-end crosstalk (ELFEXT).
 - 7) Power sum equal-level far-end crosstalk (PSELFEXT).
 - 8) Return loss.
 - 9) Propagation delay.
 - 10) Delay skew.
7. Final Verification Tests: Perform verification tests for UTP and optical fiber systems after the complete communications cabling and workstation outlet/connectors are installed.
 - a. Voice Tests: These tests assume that dial tone service has been installed. Connect to the network interface device at the demarcation point. Go off-hook and listen and receive a dial tone. If a test number is available, make and receive a local, long distance, and digital subscription line telephone call.
 - b. Data Tests: These tests assume the Information Technology Staff has a network installed and is available to assist with testing. Connect to the network interface device at the demarcation point. Log onto the network to ensure proper connection to the network.

- D. Document data for each measurement. Data for submittals shall be printed in a summary report that is formatted similar to Table 10.1 in BICSI TDMM, or transferred from the instrument to the computer, saved as text files, and printed and submitted.
- E. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

3.8 SOFTWARE SERVICE AGREEMENT

- A. Technical Support: Beginning with Substantial Completion, provide software support for two years.
- B. Upgrade Service: Update software to latest version at Project completion. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software shall include operating system. Upgrade shall include new or revised licenses for use of software.
 - 1. Provide 30 days' notice to Owner to allow scheduling and access to system and to allow Owner to upgrade computer equipment if necessary.

3.9 DEMONSTRATION

- A. Train Owner's maintenance personnel in cable-plant management operations, including changing signal pathways for different workstations, rerouting signals in failed cables, and keeping records of cabling assignments and revisions when extending wiring to establish new workstation outlets

END OF SECTION 27 15 00

This page intentionally left blank.

SECTION 28 05 13

CONDUCTORS AND CABLES FOR ELECTRONIC SAFETY AND SECURITY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. UTP cabling.
 - 2. Low-voltage control cabling.
 - 3. Control-circuit conductors.
 - 4. Identification products.

1.3 DEFINITIONS

- A. BICSI: Building Industry Consulting Service International.
- B. EMI: Electromagnetic interference.
- C. IDC: Insulation displacement connector.
- D. Low Voltage: As defined in NFPA 70 for circuits and equipment operating at less than 50 V or for remote-control and signaling power-limited circuits.
- E. Open Cabling: Passing telecommunications cabling through open space (e.g., between the studs of a wall cavity).
- F. RCDD: Registered Communications Distribution Designer.

1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified layout technician, installation supervisor, and field inspector.
- B. Source quality-control reports.
- C. Field quality-control reports.

1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An NRTL.
 - 1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
 - 1. Test each pair of UTP cable for open and short circuits.

1.7 FIELD CONDITIONS

- A. Do not install conductors and cables that are wet, moisture damaged, or mold damaged.
 - 1. Indications that wire and cables are wet or moisture damaged include, but are not limited to, discoloration and sagging of factory packing materials.
- B. Environmental Limitations: Do not deliver or install UTP and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

- A. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
 - 1. Flame-Spread Index: 25 or less.
 - 2. Smoke-Developed Index: 450 or less.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 BACKBOARDS

- A. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches. Comply with requirements for plywood backing panels in Division 06 Section "Rough Carpentry."

2.3 UTP CABLE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. ADC.
 2. AMP Netconnect; a brand of Tyco Electronics Corporation.
 3. Belden Inc.
 4. Berk-Tek; a Nexans company.
 5. CommScope, Inc.
 6. Draka Cableteq USA.
 7. Genesis Cable Products; Honeywell International, Inc.
 8. Mohawk; a division of Belden Networking, Inc.
 9. Superior Essex Inc.
 10. SYSTIMAX Solutions; a CommScope, Inc. brand.
 11. 3M; Communication Markets Division.
- B. Description: 100-ohm, four-pair UTP, covered with a blue thermoplastic jacket.
1. Comply with ICEA S-90-661 for mechanical properties.
 2. Comply with TIA/EIA-568-B.1 for performance specifications.
 3. Comply with TIA/EIA-568-B.2 Category 6.
 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
 - a. Communications, Plenum Rated: Type CMP, complying with NFPA 262.
 - b. Multipurpose, Plenum Rated: Type MPP, complying with NFPA 262.

2.4 UTP CABLE HARDWARE

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. ADC.
 2. American Technology Systems Industries, Inc.
 3. AMP Netconnect; a brand of Tyco Electronics Corporation.
 4. Belden Inc.
 5. Dynacom Inc.
 6. Hubbell Incorporated; Hubbell Premise Wiring.
 7. Leviton Commercial Networks Division.
 8. Molex Premise Networks; a division of Molex, Inc.
 9. Panduit Corp.
 10. Siemon.
- B. UTP Cable Connecting Hardware: IDC type, using modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of the same category or higher.

2.5 LOW-VOLTAGE CONTROL CABLE

- A. Plenum-Rated, Paired Cable: NFPA 70, Type CMP.
 - 1. One pair, twisted, No. 16 AWG, stranded (19x29) tinned copper conductors.
 - 2. PVC insulation.
 - 3. Unshielded.
 - 4. PVC jacket.
 - 5. Flame Resistance: Comply with NFPA 262.
- B. Access Control Door Cable: 18/4, shielded, plenum rated cable.

2.6 CONTROL-CIRCUIT CONDUCTORS

- A. Class 1 Control Circuits: Stranded copper, Type THHN-THWN, complying with UL 83, in raceway.
- B. Class 2 Control Circuits: Stranded copper, Type THHN-THWN, complying with UL 83, in raceway.
- C. Class 3 Remote-Control and Signal Circuits: Stranded copper, Type TW or TF, complying with UL 83.

2.7 IDENTIFICATION PRODUCTS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Brady Worldwide, Inc.
 - 2. HellermannTyton North America.
 - 3. Kroy LLC.
 - 4. Panduit Corp.
- B. Comply with UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.
- C. Comply with requirements in Division 26 Section "Identification for Electrical Systems."

2.8 SOURCE QUALITY CONTROL

- A. Factory test UTP and optical fiber cables on reels according to TIA/EIA-568-B.1.
- B. Factory test UTP cables according to TIA/EIA-568-B.2.
- C. Factory sweep test coaxial cables at frequencies from 5 MHz to 1 GHz. Sweep test shall test the frequency response, or attenuation over frequency, of a cable by

generating a voltage whose frequency is varied through the specified frequency range and graphing the results.

- D. Cable will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

PART 3 - EXECUTION

3.1 INSTALLATION OF HANGERS AND SUPPORTS

- A. Comply with requirements in Division 26 Section "Hangers and Supports for Electrical Systems" for installation of supports for cables.

3.2 WIRING METHOD

- A. Install wiring in metal pathways and wireways.
 - 1. Minimum conduit size shall be 1 inch. Control and data transmission wiring shall not share conduit with other building wiring systems.
 - 2. Comply with requirements in Division 28 Section "Pathways for Electronic Safety and Security."
 - 3. Comply with requirements in Division 26 Section "Cable Trays for Electrical Systems."
- B. Install cable, concealed in accessible ceilings, walls, and floors when possible.
- C. Wiring within Enclosures:
 - 1. Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii.
 - 2. Install lacing bars and distribution spools.
 - 3. Separate power-limited and non-power-limited conductors as recommended in writing by manufacturer.
 - 4. Install conductors parallel with or at right angles to sides and back of enclosure.
 - 5. Connect conductors that are terminated, spliced, or interrupted in any enclosure associated with intrusion system to terminal blocks.
 - 6. Mark each terminal according to system's wiring diagrams.
 - 7. Make all connections with approved crimp-on terminal spade lugs, pressure-type terminal blocks, or plug connectors.

3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Comply with NECA 1.
- B. Conductors: Size according to system manufacturer's written instructions unless otherwise indicated.

- C. General Requirements for Cabling:
1. Comply with TIA/EIA-568-B.1.
 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
 3. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, and cross-connect and patch panels.
 4. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
 5. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Install lacing bars and distribution spools.
 6. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
 7. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps shall not be used for heating.
 8. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
- D. UTP Cable Installation: Install using techniques, practices, and methods that are consistent with Category 6 rating of components and that ensure Category 6 performance of completed and linked signal paths, end to end.
1. Comply with TIA/EIA-568-B.2.
 2. Install 110-style IDC termination hardware unless otherwise indicated.
 3. Do not untwist UTP cables more than 1/2 inch from the point of termination to maintain cable geometry.
- E. Open-Cable Installation:
1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
 2. Suspend copper cable not in a wireway or pathway a minimum of 8 inches above ceilings by cable supports not more than 60 inches apart.
 3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.
- F. Separation from EMI Sources:
1. Comply with BICSI TDMM and TIA-569-B recommendations for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.
 2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.

3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
4. Separation between cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
 - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
 - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
 - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
5. Separation between Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.

3.4 POWER AND CONTROL-CIRCUIT CONDUCTORS

- A. 120-V Power Wiring: Install according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables" unless otherwise indicated.
- B. Minimum Conductor Sizes:
 1. Class 1 remote-control and signal circuits, No. 14 AWG.
 2. Class 2 low-energy, remote-control and signal circuits, No. 16 AWG.
 3. Class 3 low-energy, remote-control, alarm and signal circuits, No. 12 AWG.

3.5 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping."
- B. Comply with TIA-569-B, "Firestopping" Annex A.
- C. Comply with BICSI TDMM, "Firestopping Systems" Article.

3.6 GROUNDING

- A. For communications wiring, comply with J-STD-607-A and with BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. For low-voltage wiring and cabling, comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems."

3.7 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."

3.8 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
 - 1. Visually inspect UTP cable jacket materials for NRTL certification markings. Inspect cabling terminations to confirm color-coding for pin assignments, and inspect cabling connections to confirm compliance with TIA/EIA-568-B.1.
 - 2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
 - 3. Test UTP cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross connection.
 - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-B.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
- B. Document data for each measurement. Print data for submittals in a summary report that is formatted using Table 10.1 in BICSI TDMM as a guide, or transfer the data from the instrument to the computer, save as text files, print, and submit.
- C. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- D. Prepare test and inspection reports.

END OF SECTION 28 05 13

SECTION 28 05 28

PATHWAYS FOR ELECTRONIC SAFETY AND SECURITY

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Metal conduits, tubing, and fittings.
 - 2. Nonmetallic conduits, tubing, and fittings.
 - 3. Optical-fiber-cable pathways and fittings.
 - 4. Metal wireways and auxiliary gutters.
 - 5. Nonmetallic wireways and auxiliary gutters.
 - 6. Boxes, enclosures, and cabinets.
- B. Related Requirements:
 - 1. Division 26 Section "Underground Ducts and Raceways for Electrical Systems" for exterior ductbanks, manholes, and underground utility construction.
 - 2. Division 26 Section "Raceways and Boxes for Electrical Systems" for conduits, wireways, surface raceways, boxes, enclosures, cabinets, handholes, and faceplate adapters serving electrical systems.
 - 3. Division 27 Section "Pathways for Communications Systems" for conduits, surface pathways, innerduct, boxes, and faceplate adapters serving communications systems.

1.3 DEFINITIONS

- A. GRC: Galvanized rigid steel conduit.

1.4 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination

and conformance of the Work, regardless of whether submittals are required or reviewed.

- B. Product Data: For surface pathways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.

PART 2 - PRODUCTS

2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. Allied Tube & Conduit; a Tyco International Ltd. Co.
 - 2. Alpha Wire Company.
 - 3. Anamet Electrical, Inc.
 - 4. Electri-Flex Company.
 - 5. O-Z/Gedney; a brand of EGS Electrical Group.
 - 6. Republic Conduit.
 - 7. Southwire Company.
 - 8. Thomas & Betts Corporation.
 - 9. Western Tube and Conduit Corporation.
 - 10. Wheatland Tube Company; a division of John Maneely Company.
- B. General Requirements for Metal Conduits and Fittings:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Comply with TIA-569-B.
- C. GRC: Comply with ANSI C80.1 and UL 6.
- D. EMT: Comply with ANSI C80.3 and UL 797.
- E. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- F. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
 - 1. Conduit Fittings for Hazardous (Classified) Locations: Comply with UL 886 and NFPA 70.
 - 2. Fittings for EMT:
 - a. Material: Steel.
 - b. Type: Setscrew.
 - 3. Expansion Fittings: PVC or steel to match conduit type, complying with UL 467, rated for environmental conditions where installed, and including flexible external bonding jumper.
 - 4. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch, with overlapping sleeves protecting threaded joints.

- G. Joint Compound for GRC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

2.2 NONMETALLIC CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - 1. AFC Cable Systems, Inc.
 - 2. Allied Tube & Conduit; a Tyco International Ltd. Co.
 - 3. Anamet Electrical, Inc.
 - 4. Arnco Corporation.
 - 5. CANTEX Inc.
 - 6. CertainTeed Corp.
 - 7. Condux International, Inc.
 - 8. Electri-Flex Company.
 - 9. Kraloy.
 - 10. Lamson & Sessions; Carlon Electrical Products.
 - 11. Niedax-Kleinhuis USA, Inc.
 - 12. RACO; a Hubbell Company.
 - 13. Thomas & Betts Corporation.
- B. General Requirements for Nonmetallic Conduits and Fittings:
 - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
 - 2. Comply with TIA-569-B.
- C. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- D. Rigid HDPE: Comply with UL 651A.
- E. Fittings for RNC: Comply with NEMA TC 3; match to conduit or tubing type and material.
- F. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- G. Solvent cements and adhesive primers shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

2.3 BOXES, ENCLOSURES, AND CABINETS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Adalet.
 2. Cooper Technologies Company; Cooper Crouse-Hinds.
 3. EGS/Appleton Electric.
 4. Erickson Electrical Equipment Company.
 5. Hoffman; a Pentair company.
 6. Hubbell Incorporated; Killark Division.
 7. Lamson & Sessions; Carlon Electrical Products.
 8. Milbank Manufacturing Co.
 9. Molex, Woodhead Brand
 10. Mono-Systems, Inc.
 11. O-Z/Gedney; a brand of EGS Electrical Group.
 12. RACO; a Hubbell Company.
 13. Robroy Industries.
 14. Spring City Electrical Manufacturing Company.
 15. Stahlin Non-Metallic Enclosures; a division of Robroy Industries.
 16. Thomas & Betts Corporation.
 17. Wiremold / Legrand.
- B. General Requirements for Boxes, Enclosures, and Cabinets:
1. Comply with TIA-569-B.
 2. Boxes, enclosures and cabinets installed in wet locations shall be listed for use in wet locations.
- C. Sheet-Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- D. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, ferrous alloy, Type FD, with gasketed cover.
- E. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- F. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- G. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, galvanized, cast iron with gasketed cover.
- H. Device Box Dimensions: 4-inches square by 2-1/8 inches deep
- I. Gangable boxes are allowed
- J. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 with continuous-hinge cover with flush latch unless otherwise indicated.
1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
 2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.

- K. Cabinets:
1. NEMA 250, Type 1, galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
 2. Hinged door in front cover with flush latch and concealed hinge.
 3. Key latch to match panelboards.
 4. Metal barriers to separate wiring of different systems and voltage.
 5. Accessory feet where required for freestanding equipment.
 6. Nonmetallic cabinets shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

PART 3 - EXECUTION

3.1 PATHWAY APPLICATION

- A. Outdoors: Apply pathway products as specified below unless otherwise indicated:
1. Exposed Conduit: GRC.
 2. Concealed Conduit, Aboveground: GRC.
 3. Underground Conduit: RNC, Type EPC-40-PVC.
 4. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
 5. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.
- B. Indoors: Apply pathway products as specified below unless otherwise indicated:
1. Exposed, Not Subject to Physical Damage: EMT.
 2. Exposed, Not Subject to Severe Physical Damage: EMT.
 3. Exposed and Subject to Severe Physical Damage: GRC. Pathway locations include the following:
 - a. Apparatus Bay.
 - b. Mechanical rooms.
 4. Concealed in Ceilings and Interior Walls and Partitions: EMT.
 5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric-Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
 6. Damp or Wet Locations: GRC.
 7. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel in institutional and commercial kitchens and damp or wet locations.
- C. Minimum Pathway Size: 1-inch trade size.
- D. Pathway Fittings: Compatible with pathways and suitable for use and location.
1. Rigid Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
 2. EMT: Use setscrew, steel fittings. Comply with NEMA FB 2.10.
 3. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.
- E. Do not install aluminum conduits, boxes, or fittings in contact with concrete or earth.

- F. Install surface pathways only where indicated on Drawings.
- G. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F

3.2 INSTALLATION

- A. Comply with NECA 1, NECA 101, and TIA-569-B for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum pathways. Comply with NFPA 70 limitations for types of pathways allowed in specific occupancies and number of floors.
- B. Keep pathways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal pathway runs above water and steam piping.
- C. Complete pathway installation before starting conductor installation.
- D. Comply with requirements in Division 26 Section "Hangers and Supports for Electrical Systems" for hangers and supports.
- E. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- F. Install no more than the equivalent of three 90-degree bends in any conduit run except for communications wiring conduits for which only two 90-degree bends are allowed. Support within 12 inches of changes in direction.
- G. Conceal conduit and EMT within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- H. Support conduit within 12 inches of enclosures to which attached.
- I. Stub-ups to Above Recessed Ceilings:
 - 1. Use EMT or RMC for pathways.
 - 2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.
- J. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of pathway and fittings before making up joints. Follow compound manufacturer's written instructions.
- K. Coat field-cut threads on PVC-coated pathway with a corrosion-preventing conductive compound prior to assembly.
- L. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install insulated bushings on conduits terminated with locknuts.
- M. Install pathways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.

- N. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to conduit assembly to assure a continuous ground path.
- O. Cut conduit perpendicular to the length. For conduits of 2-inch trade size and larger, use roll cutter or a guide to ensure cut is straight and perpendicular to the length.
- P. Install pull wires in empty pathways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire. Cap underground pathways designated as spare above grade alongside pathways in use.
- Q. Install pathway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed pathways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install pathway sealing fittings according to NFPA 70.
- R. Install devices to seal pathway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all pathways at the following points:
 - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
 - 2. Where an underground service pathway enters a building or structure.
 - 3. Where otherwise required by NFPA 70.
- S. Comply with manufacturer's written instructions for solvent welding PVC conduit and fittings.
- T. Expansion-Joint Fittings:
 - 1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F, and that has straight-run length that exceeds 25 feet. Install in each run of aboveground RMC and EMT conduit that is located where environmental temperature change may exceed 100 deg F and that has straight-run length that exceeds 100 feet.
 - 2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
 - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F temperature change.
 - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F temperature change.
 - c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F temperature change.
 - d. Attics: 135 deg F temperature change.
 - 3. Install fitting(s) that provide expansion and contraction for at least 0.00041 inch per foot of length of straight run per deg F of temperature change for PVC conduits. Install fitting(s) that provide expansion and contraction for at least 0.000078 inch per foot of length of straight run per deg F of temperature change for metal conduits.
 - 4. Install expansion fittings at all locations where conduits cross building or structure expansion joints.

- 5. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
 - U. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to center of box unless otherwise indicated.
 - V. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surface to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.
 - W. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
 - X. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
 - Y. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.
- 3.3 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRONIC SAFETY AND SECURITY PENETRATIONS
- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Division 28 Section "Sleeves and Sleeve Seals for Electronic Safety and Security Pathways and Cabling."
- 3.4 FIRESTOPPING
- A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Division 07 Section "Penetration Firestopping."
- 3.5 PROTECTION
- A. Protect coatings, finishes, and cabinets from damage and deterioration.
 - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
 - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

END OF SECTION 28 05 28

SECTION 28 05 44

SLEEVES AND SLEEVE SEALS FOR ELECTRONIC SAFETY AND SECURITY PATHWAYS AND CABLING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Sleeves for pathway and cable penetration of non-fire-rated construction walls and floors.
 - 2. Sleeve-seal systems.
 - 3. Sleeve-seal fittings.
 - 4. Grout.
 - 5. Silicone sealants.
- B. Related Requirements:
 - 1. Division 07 Section "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

1.3 ACTION SUBMITTALS

- A. Submittals are not required for this Section unless specifically requested in writing by the Engineer. Submittals submitted without such written request will not be reviewed or acted upon and shall not be deemed approved. The absence of a submittal requirements shall not be construed as authorization for substitutions, deviations, omissions, or departures from the Contract Documents, nor shall it relieve the Contractor of the responsibility for full compliance with the Contract Documents. The Contractor remains solely responsible for the accuracy, completeness, coordination and conformance of the Work, regardless of whether submittals are required or reviewed.

PART 2 - PRODUCTS

2.1 SLEEVES

- A. Wall Sleeves:
 - 1. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, plain ends.
 - 2. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies: Galvanized-steel sheet; 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint, with tabs for screw-fastening the sleeve to the board.
- C. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.
- D. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.
- E. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.
- F. Sleeves for Rectangular Openings:
 - 1. Material: Galvanized-steel sheet.
 - 2. Minimum Metal Thickness:
 - a. For sleeve cross-section rectangle perimeter less than 50 inches and with no side larger than 16 inches, thickness shall be 0.052 inch.
 - b. For sleeve cross-section rectangle perimeter 50 inches or more and one or more sides larger than 16 inches, thickness shall be 0.138 inch.

2.2 SLEEVE-SEAL SYSTEMS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and pathway or cable.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Advance Products & Systems, Inc.
 - b. CALPICO, Inc.
 - c. Metraflex Company (The).
 - d. Pipeline Seal and Insulator, Inc.
 - e. Proco Products, Inc.
 - 2. Sealing Elements: EPDM rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
 - 3. Pressure Plates: Stainless steel.
 - 4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

2.3 SLEEVE-SEAL FITTINGS

- A. Description: Manufactured plastic, sleeve-type, waterstop assembly made for embedding in concrete slab or wall. Unit shall have plastic or rubber waterstop collar with center opening to match piping OD.
 - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
 - a. Presealed Systems.

2.4 GROUT

- A. Description: Nonshrink; recommended for interior and exterior sealing openings in non-fire-rated walls or floors..
- B. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

2.5 SILICONE SEALANTS

- A. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below.
 - 1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces that are not fire rated.
 - 2. Sealant shall have VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
 - 3. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- B. Silicone Foams: Multicomponent, silicone-based, liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.

PART 3 - EXECUTION

3.1 SLEEVE INSTALLATION FOR NON-FIRE-RATED ELECTRICAL PENETRATIONS

- A. Comply with NECA 1.
- B. Comply with NEMA VE 2 for cable tray and cable penetrations.

- C. Sleeves for Conduits Penetrating Above-Grade Non-Fire-Rated Concrete and Masonry-Unit Floors and Walls:
 - 1. Interior Penetrations of Non-Fire-Rated Walls and Floors:
 - a. Seal annular space between sleeve and pathway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Division 07 Section "Joint Sealants."
 - b. Seal space outside of sleeves with mortar or grout. Pack sealing material solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect material while curing.
 - 2. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
 - 3. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and pathway or cable unless sleeve seal is to be installed or unless seismic criteria require different clearance.
 - 4. Install sleeves for wall penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of walls. Cut sleeves to length for mounting flush with both surfaces of walls. Deburr after cutting.
 - 5. Install sleeves for floor penetrations. Extend sleeves installed in floors 2 inches above finished floor level. Install sleeves during erection of floors.
- D. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies:
 - 1. Use circular metal sleeves unless penetration arrangement requires rectangular sleeved opening.
 - 2. Seal space outside of sleeves with approved joint compound for gypsum board assemblies.
- E. Roof-Penetration Sleeves: Seal penetration of individual pathways and cables with flexible boot-type flashing units applied in coordination with roofing work.
- F. Aboveground, Exterior-Wall Penetrations: Seal penetrations using cast-iron pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch annular clear space between pipe and sleeve for installing mechanical sleeve seals.
- G. Underground, Exterior-Wall and Floor Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch annular clear space between pathway or cable and sleeve for installing sleeve-seal system.

3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at pathway entries into building.
- B. Install type and number of sealing elements recommended by manufacturer for pathway or cable material and size. Position pathway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between pathway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.

3.3 SLEEVE-SEAL-FITTING INSTALLATION

- A. Install sleeve-seal fittings in new walls and slabs as they are constructed.
- B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position waterstop flange to be centered in concrete slab or wall.
- C. Secure nailing flanges to concrete forms.
- D. Using grout, seal the space around outside of sleeve-seal fittings.

END OF SECTION 28 05 44

This page intentionally left blank.

SECTION 28 31 11 - DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Fire-alarm control unit.
 - 2. Manual fire-alarm boxes.
 - 3. System smoke detectors.
 - 4. Notification appliances.
 - 5. Device guards.
 - 6. Remote annunciator.
 - 7. Addressable interface device.
 - 8. Digital alarm communicator transmitter.
- B. Delegated Design
 - 1. Provide a complete, code-compliant fire alarm system under a delegated design approach. Work shall include all engineering, design, installation labor, materials, equipment, permits, fees, and transportation necessary to furnish, install, test, and certify a fully operational system.
 - 2. Fire alarm system documents shall be prepared, reviewed and sealed by a registered professional engineer in the State of Missouri.
- C. Fire Alarm System Description
 - 1. Provide a complete fire alarm initiation, notification and communication system for the indicated structure.
- D. Performance Requirements
 - 1. The Contract Documents establish minimum material standards, system features, and performance requirements. They do not depict every component, conductor, or connection required for a complete installation. Based on the specified performance and indicated equipment, the Contractor and Vendor shall be solely responsible for the complete design, coordination, and provision of all components and wiring necessary to deliver a fully functional and compliant system.
- E. Scope of Work
 - 1. Work includes, but is not limited to, the following:

- a. Complete system design, engineering, and coordination with the Architect and other trades, including testing and final acceptance by the Owner, Authority Having Jurisdiction (AHJ), and applicable certification agencies.
- b. Preparation and submission for plan review and approval.
- c. Furnishing and installation of all system components and devices.
- d. Installation of all conductors, wiring, and terminations.
- e. Coordination with Section 26 05 29, "Grounding and Bonding for Electrical Systems."
- f. Preparation and submission of installation details, wiring diagrams, shop drawings, and product data.
- g. Provision of all labor and materials required for a complete and operational system, whether specifically indicated or reasonably inferred.
- h. Preparation and submission of record (as-built) documents.
- i. Obtaining all required permits, inspections, and payment of associated fees.
- j. System identification and provision of written operation and maintenance instructions.
- k. Coordination with existing conditions and the work of other trades.
- l. Furnishing and installation of special supports required for work under this Section but provided in coordination with other Sections.

1.3 DEFINITIONS

- A. EMT: Electrical Metallic Tubing.
- B. FACP: Fire Alarm Control Panel.
- C. HLI: High Level Interface.
- D. NICET: National Institute for Certification in Engineering Technologies.
- E. PC: Personal computer.
- F. VESDA: Very Early Smoke-Detection Apparatus.

1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product, including furnished options and accessories.
 - 1. Include construction details, material descriptions, dimensions, profiles, and finishes.
 - 2. Include rated capacities, operating characteristics, and electrical characteristics.
- B. Shop Drawings: For fire-alarm system.
 - 1. Comply with recommendations and requirements in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
 - 2. Include plans, elevations, sections, details, and attachments to other work.
 - 3. Include details of equipment assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and locations.

Indicate conductor sizes, indicate termination locations and requirements, and distinguish between factory and field wiring.

4. Detail assembly and support requirements.
5. Include voltage drop calculations for notification-appliance circuits.
6. Include battery-size calculations.
7. Include input/output matrix.
8. Include statement from manufacturer that all equipment and components have been tested as a system and meet all requirements in this Specification and in NFPA 72.
9. Include performance parameters and installation details for each detector.
10. Verify that each duct detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
11. Provide program report showing that air-sampling detector pipe layout balances pneumatically within the airflow range of the air-sampling detector.
12. Include plans, sections, and elevations of heating, ventilating, and air-conditioning ducts, drawn to scale; coordinate location of duct smoke detectors and access to them.
 - a. Show critical dimensions that relate to placement and support of sampling tubes, detector housing, and remote status and alarm indicators.
 - b. Show field wiring required for HVAC unit shutdown on alarm.
 - c. Show field wiring and equipment required for HVAC unit shutdown on alarm and override by firefighters' control system.
 - d. Show field wiring and equipment required for HVAC unit shutdown on alarm and override by firefighters' smoke-evacuation system.
 - e. Locate detectors according to manufacturer's written recommendations.
 - f. Show air-sampling detector pipe routing.

C. General Submittal Requirements:

1. Submittals shall be approved by authorities having jurisdiction prior to submitting them to Architect.

D. Delegated-Design Submittal: For notification appliances and smoke and heat detectors, in addition to submittals listed above, indicate compliance with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. Drawings showing the location of each notification appliance and smoke and heat detector, ratings of each, and installation details as needed to comply with listing conditions of the device.
2. Design Calculations: Calculate requirements for selecting the spacing and sensitivity of detection, complying with NFPA 72. Calculate spacing and intensities for strobe signals and sound-pressure levels for audible appliances.
3. Indicate audible appliances required to produce square wave signal per NFPA 72.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Seismic Qualification Certificates: For fire-alarm control unit, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

C. Field quality-control reports.

1.6 Sample Warranty: For special warranty.

1.7 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals.

1. In addition to items specified in Section 01 78 23 "Operation and Maintenance Data," include the following:
 - a. Comply with the "Records" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - b. Provide "Fire Alarm and Emergency Communications System Record of Completion Documents" according to the "Completion Documents" Article in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
 - c. Complete wiring diagrams showing connections between all devices and equipment. Each conductor shall be numbered at every junction point with indication of origination and termination points.
 - d. Riser diagram.
 - e. Device addresses.
 - f. Air-sampling system sample port locations and modeling program report showing layout meets performance criteria.
 - g. Record copy of site-specific software.
 - h. Provide "Inspection and Testing Form" according to the "Inspection, Testing and Maintenance" chapter in NFPA 72, and include the following:
 - 1) Equipment tested.
 - 2) Frequency of testing of installed components.
 - 3) Frequency of inspection of installed components.
 - 4) Requirements and recommendations related to results of maintenance.
 - 5) Manufacturer's user training manuals.
 - i. Manufacturer's required maintenance related to system warranty requirements.
 - j. Abbreviated operating instructions for mounting at fire-alarm control unit and each annunciator unit.

B. Software and Firmware Operational Documentation:

1. Software operating and upgrade manuals.
2. Program Software Backup: On magnetic media or compact disk, complete with data files.
3. Device address list.
4. Printout of software application and graphic screens.

1.8 QUALITY ASSURANCE

- A. Installer Qualifications: Personnel shall be trained and certified by manufacturer for installation of units required for this Project.
- B. The fire alarm equipment supplier shall have a NICET level 4 certified individual on staff responsible for overseeing the technical design and engineering functions related to the fire alarm system. The NICET level 4-certificate number must be submitted to the engineer with shop drawing submittals.
- C. The fire alarm equipment supplier shall have on staff NICET level 2 technicians supervising the final connections and programming of the system.
- D. NFPA Certification: Obtain certification according to NFPA 72 by a UL-listed alarm company.

1.9 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace fire-alarm system equipment and components that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Extent: All equipment and components not covered in the Maintenance Service Agreement.
 - 2. Warranty Period: One years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 SYSTEM DESCRIPTION

- A. Noncoded, UL-certified addressable system, with multiplexed signal transmission and horn/strobe evacuation.
- B. Automatic sensitivity control of certain smoke detectors.
- C. All components provided shall be listed for use with the selected system.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.2 SYSTEMS OPERATIONAL DESCRIPTION

- A. Fire-alarm signal initiation shall be by one or more of the following devices:
 - 1. Manual stations.
 - 2. Smoke detectors.
 - 3. Heat detectors.
 - 4. Duct smoke detectors.
 - 5. Waterflow switch.

6. Kitchen hood.
 7. Kitchen suppression pull station.
- B. Fire-alarm signal shall initiate the following actions:
1. Continuously operate alarm notification appliances
 2. Identify alarm and specific initiating device at fire-alarm control unit and remote annunciators.
 3. Transmit an alarm signal to the remote alarm receiving station.
- C. System trouble signal initiation shall be by one or more of the following devices and actions:
1. Open circuits, shorts, and grounds in designated circuits.
 2. Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
 3. Loss of communication with any addressable sensor, input module, relay, control module, remote annunciator, printer interface, or Ethernet module.
 4. Loss of primary power at fire-alarm control unit.
 5. Ground or a single break in internal circuits of fire-alarm control unit.
 6. Abnormal ac voltage at fire-alarm control unit.
 7. Break in standby battery circuitry.
 8. Failure of battery charging.
 9. Abnormal position of any switch at fire-alarm control unit or annunciator.

2.3 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Fire-alarm control unit and raceways shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event]."

2.4 FIRE-ALARM CONTROL UNIT

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Gamewell - FCI by Honeywell.
 2. Notifier.
 3. Siemens Industry, Inc.; Fire Safety Division.
- B. General Requirements for Fire-Alarm Control Unit:
1. The FACP catalog number is based on a Notifier panel. Equivalent systems as manufactured by Honeywell and Simplex meeting requirements of specification will be acceptable upon approval by engineer. The panel shall communicate with and control the following types of equipment used to make up the system: detectors and other system controlled devices. System capacity shall be minimum 198 points. See drawings for total number of point required system shall have capacity for 20% expansion. The panel shall be UL Listed as a Fire Alarm Control Panel per UL 864 and NFPA 72

2. Field-programmable, microprocessor-based, modular, power-limited design with electronic modules, complying with UL 864.
 - a. System software and programs shall be held in nonvolatile flash, electrically erasable, programmable, read-only memory, retaining the information through failure of primary and secondary power supplies.
 - b. Include a real-time clock for time annotation of events on the event recorder and printer.
 - c. Provide communication between the FACP and remote circuit interface panels, annunciators, and displays.
 - d. The FACP shall be listed for connection to a central-station signaling system service.
 - e. Provide nonvolatile memory for system database, logic, and operating system and event history. The system shall require no manual input to initialize in the event of a complete power down condition. The FACP shall provide a minimum 500-event history log.
 3. Addressable Initiation Device Circuits: The FACP shall indicate which communication zones have been silenced and shall provide selective silencing of alarm notification appliance by building communication zone.
- C. Smoke-Alarm Verification:
1. Initiate audible and visible indication of an "alarm-verification" signal at fire-alarm control unit.
 2. Activate an approved "alarm-verification" sequence at fire-alarm control unit and detector.
 3. Sound general alarm if the alarm is verified.
 4. Cancel fire-alarm control unit indication and system reset if the alarm is not verified.
- D. Notification-Appliance Circuit:
1. Audible appliances shall sound in a three-pulse temporal pattern, as defined in NFPA 72.
 2. Visual alarm appliances shall flash in synchronization where multiple appliances are in the same field of view, as defined in NFPA 72.
- E. Fire-alarm signal shall initiate the following actions:
1. Continuously operate alarm notification appliances
 2. Identify alarm and specific initiating device at fire-alarm control
 3. Transmit an alarm signal to the remote alarm receiving station.
 4. Unlock electric door locks in designated egress paths.
 5. Release fire and smoke doors held open by magnetic door holders.
 6. Switch heating, ventilating, and air-conditioning equipment controls to fire-alarm mode.
 7. Close smoke dampers in air ducts of designated air-conditioning duct systems.
- F. Supervisory signal initiation shall be by one or more of the following devices and actions:
1. Valve supervisory switch.
 2. High- or low-air-pressure switch of a dry-pipe or preaction sprinkler system.
 3. Independent fire-detection and -suppression systems.

- G. System trouble signal initiation shall be by one or more of the following devices and actions:
1. Open circuits, shorts, and grounds in designated circuits.
 2. Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
 3. Loss of communication with any addressable sensor, input module, relay, control module, remote annunciator, printer interface, or Ethernet module.
 4. Loss of primary power at fire-alarm control unit.
 5. Ground or a single break in internal circuits of fire-alarm control unit.
 6. Abnormal ac voltage at fire-alarm control unit.
 7. Break in standby battery circuitry.
 8. Failure of battery charging.
 9. Abnormal position of any switch at fire-alarm control unit or annunciator.
 - a. Provide battery back-up and charging system for 60 hours of standby and 5 minutes of alarm for the entire fire alarm system.
- H. Control Panel Switches:
1. Acknowledge Switch.
 - a. Activation of the control panel Acknowledge switch in response to new Alarms and/or Troubles shall silence the local panel piezo electric signal and change the Alarm and Trouble LEDs from flashing mode to steady ON mode. If multiple Alarm or Trouble conditions exist, depression of this switch shall advance the 80-character LCD display to the next Alarm or Trouble condition. Depression of the Acknowledge switch shall also silence all remote annunciator piezo sounders.
 2. Signal Silence Switch.
 - a. Activation of the Signal Silence Switch shall cause all programmed Alarm Indicating Appliances and relays to return to the normal condition after an alarm condition. The selection of indicating circuits and relays that are silenceable by this switch shall be fully field programmable within the confines of all applicable standards. The FACP software shall include silence inhibit and auto-silence timers.
 3. System Reset Switch.
 - a. Activation of the System Reset Switch shall cause all electronically latched initiating devices, appliances or software zones, as well as all associated output devices and circuits, to return to their normal condition. Holding the RESET switch shall perform a Lamp Test function.
 4. Drill (Excavate) Switch.
 - a. Press and hold of the Drill switch shall activate all Indicating Appliance circuits. The Drill function shall latch until press of Signal Silence or Reset.

- I. SLC Loop Interface:
 - 1. The SLC Interface shall provide power to, and communicate with, all of the Intelligent /Addressable Detectors and Addressable Modules over a single pair of wires.
 - 2. The Loop Interface Board shall receive analog information from all Intelligent Detectors that shall be processed to determine whether normal, alarm, or trouble conditions exist for each detector. The software shall automatically maintain the detector's desired sensitivity level by adjusting for the effects of environmental factors, including the accumulation of dust in each detector. The analog information may also be used for automatic detector testing and for the automatic determination of detector maintenance requirements.
 - 3. The detector software shall meet NFPA 72E requirements and be certified by UL as a calibrated sensitivity test instrument.
- J. System History Recording and Reporting:
 - 1. The Fire Alarm Control Panel shall contain a History Buffer that will be capable of storing up to 400 system alarms/troubles/operator actions. Each of these activation's will be stored and time and date stamped with the actual time of the activation. The contents of the History Buffer may be manually reviewed, one event at a time.
 - 2. The History Buffer shall use non-volatile memory. Systems that use volatile memory for history storage are not acceptable.
- K. Fire Alarm Control Panel:
 - 1. The Fire Alarm Control Panel shall include a full featured operator interface control and annunciation panel which shall include a backlit 80 character Liquid Crystal Display, individual, color coded system status LEDs, and an alpha-numeric keypad for the Field Programming and Control of the Fire Alarm System.
 - 2. Maintenance Functions:
 - a. Smoke Detector Sensitivity Adjust: Means shall be provided for adjusting the sensitivity of any or all analog intelligent detectors in the system from the System keypad. Sensitivity range be within the allowed UL window, and shall be a HIGH/MEDIUM/LOW selection.
 - b. Alarm Verification: Each of the Intelligent/Addressable Smoke Detectors in the system shall be alarm verified. The Alarm Verification Function shall be from 5-50 seconds and each detector shall be able to be enabled/disabled during the field programming of the system, or anytime after system turn-on.
 - c. Automatic Detector Maintenance Alert: The Fire Alarm Control Panel shall automatically interrogate each Intelligent Smoke Detector and shall analyze the detector responses over a period of time. If any Intelligent Smoke Detector in the system responds with a reading that is below or above normal limits, then the system will enter the Trouble Mode, and the particular Detector will be annunciated on the System Display. This feature shall in no way inhibit the receipt of Alarm conditions in the system, nor shall it require any special hardware, special tools or computer expertise to perform.

2.5 MANUAL FIRE-ALARM BOXES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Gamewell - FCI by Honeywell.
 2. Notifier.
 3. Siemens Industry, Inc.; Fire Safety Division.
- B. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes shall be finished in red with molded, raised-letter operating instructions in contrasting color; shall show visible indication of operation; and shall be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.
1. Double-action mechanism requiring two actions to initiate an alarm, breaking-glass or plastic-rod pull-lever type; with addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to fire-alarm control unit.
 2. Station Reset: Key- or wrench-operated switch.
 3. Indoor Protective Shield: Factory-fabricated, clear plastic enclosure hinged at the top to permit lifting for access to initiate an alarm. Lifting the cover actuates an integral battery-powered audible horn intended to discourage false-alarm operation.
 4. Weatherproof Protective Shield: Factory-fabricated, clear plastic enclosure hinged at the top to permit lifting for access to initiate an alarm.

2.6 SYSTEM SMOKE DETECTORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Gamewell - FCI by Honeywell.
 2. Notifier.
 3. Siemens Industry, Inc.; Fire Safety Division.
- B. General Requirements for System Smoke Detectors:
1. Comply with UL 268; operating at 24-V dc, nominal.
 2. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.
 3. Base Mounting: Detector and associated electronic components shall be mounted in a twist-lock module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.
 4. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
 5. Integral Visual-Indicating Light: LED type, indicating detector has operated and power-on status.
 6. Remote Control: Unless otherwise indicated, detectors shall be digital-addressable type, individually monitored at fire-alarm control unit for calibration, sensitivity, and alarm condition and individually adjustable for sensitivity by fire-alarm control unit].
 - a. Rate-of-rise temperature characteristic of combination smoke- and heat-detection units shall be selectable at fire-alarm control unit for 15 or 20 deg F per minute.

- C. Photoelectric Smoke Detectors:
 - 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
 - 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).
- D. Duct Smoke Detectors: Photoelectric type complying with UL 268A.
 - 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
 - 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).
 - 3. Weatherproof Duct Housing Enclosure: NEMA 250, Type 4X; NRTL listed for use with the supplied detector for smoke detection in HVAC system ducts.
 - 4. Each sensor shall have multiple levels of detection sensitivity.
 - 5. Sampling Tubes: Design and dimensions as recommended by manufacturer for specific duct size, air velocity, and installation conditions where applied.
 - 6. Relay Fan Shutdown: Fully programmable relay rated to interrupt fan motor-control circuit.

2.7 NOTIFICATION APPLIANCES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Gentex Corporation.
 - 2. Siemens Industry, Inc.; Fire Safety Division.
 - 3. System Sensor.
 - 4. Wheelock; a brand of Eaton.
- B. General Requirements for Notification Appliances: Individually addressed, connected to a signaling-line circuit, equipped for mounting as indicated, and with screw terminals for system connections.
- C. General Requirements for Notification Appliances: Connected to notification-appliance signal circuits, zoned as indicated, equipped for mounting as indicated, and with screw terminals for system connections.
 - 1. Combination Devices: Factory-integrated audible and visible devices in a single-mounting assembly, equipped for mounting as indicated, and with screw terminals for system connections.

- D. Horns: Electric-vibrating-polarized type, 24-V dc; with provision for housing the operating mechanism behind a grille. Comply with UL 464. Horns shall produce a sound-pressure level of 90 dBA, measured 10 feet from the horn, using the coded signal prescribed in UL 464 test protocol.
- E. Visible Notification Appliances: Xenon strobe lights complying with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch-high letters on the lens.
 - 1. Rated Light Output:
 - a. 15/30/75/110 cd, selectable in the field.
 - 2. Mounting: Wall mounted unless otherwise indicated.
 - 3. For units with guards to prevent physical damage, light output ratings shall be determined with guards in place.
 - 4. Flashing shall be in a temporal pattern, synchronized with other units.
 - 5. Strobe Leads: Factory connected to screw terminals.
 - 6. Mounting Faceplate: Factory finished, white.
- F. Signaling appliance remote power supplies shall be UL listed for fire alarm signaling and provide 6 amps of 24 VDC power. The power supply shall include 4 style Y notification appliance circuits. Provide two 7.0 amp hour batteries with each power supply. Remote power supply shall be Notifier model FCPS-24. Provide as required for horn/strobe signals.
- G.
 - a. Connect to Fire Alarm Control Panel. Provide monitor modules for connection to FACP.

2.8 Analog Addressable Heat Detectors

- A. The intelligent heat detectors shall be intelligent and addressable and shall connect with two wires to one of the fire alarm control panel signaling line circuit loops. The detectors shall use an electronic sensor to measure thermal conditions caused by a fire and shall on command from the control panel, send data to the panel representing the analog level of such thermal measurements.
- B. The detectors shall be ceiling mounted and shall include a twist-lock base. The detectors shall provide address-setting means on the detector head using rotary decimal switch shall also store an internal identifying code, which the control panel shall use to identify the type of detector. The heat detector shall be a 135 degree fixed thermal detector unless otherwise noted.

2.9 Control Module.

- A. Control modules shall be provided to supervise and control the operation of one signal circuit or as an addressable Dry Contact (Form C) relay. The control module shall provide address-setting means using rotary decimal switches and shall also store an internal identifying code the panel shall use to identify the type of device.

2.10 Monitor Module.

- A. Monitor modules shall be provided to connect any N.O. dry contact device (kitchen hood suppression system, waterflow switch, tamper switch) to the Fire Alarm Control Panel Signaling Line Circuit Loop. The Monitor module shall provide address-setting means using rotary decimal switches and shall also store an internal identifying code which the Fire Alarm Control Panel shall use to identify the model.

2.11 REMOTE ANNUNCIATOR

- A. Description: Annunciator functions shall match those of fire-alarm control unit for alarm, supervisory, and trouble indications. Manual switching functions shall match those of fire-alarm control unit, including acknowledging, silencing, resetting, and testing.
 - 1. Mounting: Flush cabinet, NEMA 250, Type 1.
- B. Display Type and Functional Performance: Alphanumeric display and LED indicating lights shall match those of fire-alarm control unit. Provide controls to acknowledge, silence, reset, and test functions for alarm, supervisory, and trouble signals.

2.12 ADDRESSABLE INTERFACE DEVICE

- A. General:
 - 1. Include address-setting means on the module.
 - 2. Store an internal identifying code for control panel use to identify the module type.
 - 3. Listed for controlling HVAC fan motor controllers.
- B. Monitor Module: Microelectronic module providing a system address for alarm-initiating devices for wired applications with normally open contacts.
- C. Integral Relay: Capable of providing a direct signal
 - 1. Allow the control panel to switch the relay contacts on command.
 - 2. Have a minimum of two normally open and two normally closed contacts available for field wiring.
- D. Control Module:
 - 1. Operate notification devices.
 - 2. Operate solenoids for use in sprinkler service.

2.13 DIGITAL ALARM COMMUNICATOR TRANSMITTER

- A. Digital alarm communicator transmitter shall be acceptable to the remote central station and shall comply with UL 632. System shall be capable of transmission to a central station despite initial installation providing local alarm only.
- B. Functional Performance: Unit shall receive an alarm, supervisory, or trouble signal from fire-alarm control unit and automatically capture two telephone line(s) and dial a preset number for a remote central station. When contact is made with central station(s),

signals shall be transmitted. If service on either line is interrupted for longer than 45 seconds, transmitter shall initiate a local trouble signal and transmit the signal indicating loss of telephone line to the remote alarm receiving station over the remaining line. Transmitter shall automatically report telephone service restoration to the central station. If service is lost on both telephone lines, transmitter shall initiate the local trouble signal.

- C. Local functions and display at the digital alarm communicator transmitter shall include the following:
 - 1. Verification that both telephone lines are available.
 - 2. Programming device.
 - 3. LED display.
 - 4. Manual test report function and manual transmission clear indication.
 - 5. Communications failure with the central station or fire-alarm control unit.
- D. Digital data transmission shall include the following:
 - 1. Address of the alarm-initiating device.
 - 2. Address of the supervisory signal.
 - 3. Address of the trouble-initiating device.
 - 4. Loss of ac supply.
 - 5. Loss of power.
 - 6. Low battery.
 - 7. Abnormal test signal.
 - 8. Communication bus failure.
- E. Secondary Power: Integral rechargeable battery and automatic charger.
- F. Self-Test: Conducted automatically every 24 hours with report transmitted to central station.
- G. Coordinate central station with owner before ordering digital communicator to insure compatibility.
- H. Digital Communicator and IPGSM
 - a. Central Monitoring Equipment shall be UL listed and include a commercial fire digital communicator complete IPGSM Communicator with the following features:
 - 1) Meet NFPA 72C requirements for Digital Alarm Communicator Transmitter.
 - 2) Capable of connection to the ethernet at the protected premises
 - 3) Contain a minimum of 3 channels.
 - 4) Connect to cellular service.
 - 5) Equipped with battery pack, charger, telephone jack, and dedicated 120 VAC receptacle.
 - 6) The contractor will provide cable, connectors and installation of data line connected to owner network system
 - 7) The digital communicator shall be connected to the fire alarm system to receive and transmit alarm signals, trouble conditions and supervisory conditions. Digital Communicator shall be Notifier model

411UDAC. Monitoring service and communicator programming shall be coordinated with owner and owner monitoring company.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions for compliance with requirements for ventilation, temperature, humidity, and other conditions affecting performance of the Work.
 - 1. Verify that manufacturer's written instructions for environmental conditions have been permanently established in spaces where equipment and wiring are installed, before installation begins.
- B. Examine roughing-in for electrical connections to verify actual locations of connections before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 EQUIPMENT INSTALLATION

- A. Comply with NFPA 72, NFPA 101, and requirements of authorities having jurisdiction for installation and testing of fire-alarm equipment. Install all electrical wiring to comply with requirements in NFPA 70 including, but not limited to, Article 760, "Fire Alarm Systems."
 - 1. Devices placed in service before all other trades have completed cleanup shall be replaced.
 - 2. Devices installed but not yet placed in service shall be protected from construction dust, debris, dirt, moisture, and damage according to manufacturer's written storage instructions.
- B. Install wall-mounted equipment, with tops of cabinets not more than 78 inches above the finished floor.
 - 1. Comply with requirements for seismic-restraint devices specified in Section 26 05 48 "Vibration and Seismic Controls for Electrical Systems."
- C. Manual Fire-Alarm Boxes:
 - 1. Install manual fire-alarm box in the normal path of egress within 60 inches of the exit doorway.
- D. Smoke- or Heat-Detector Spacing:
 - 1. HVAC: Locate detectors not closer than 36 inches from air-supply diffuser or return-air opening.
 - 2. Lighting Fixtures: Locate detectors not closer than 12 inches from any part of a lighting fixture and not directly above pendant mounted or indirect lighting.

- E. Install a cover on each smoke detector that is not placed in service during construction. Cover shall remain in place except during system testing. Remove cover prior to system turnover.
- F. Duct Smoke Detectors: Comply with NFPA 72 and NFPA 90A. Install sampling tubes so they extend the full width of duct. Tubes more than 36 inches long shall be supported at both ends.
 - 1. Do not install smoke detector in duct smoke-detector housing during construction. Install detector only during system testing and prior to system turnover.
- G. Fire Alarm Installation
 - 1. The Fire Alarm Control Panel shall be connected to a separate dedicated branch circuit, maximum 20 amperes. This circuit shall be labeled at the Main Power Distribution Panel as FIRE ALARM. Circuit breaker shall be painted red and be provided with lock. Conduit shall enter into the Fire Alarm Control Panel backbox only at those areas of the backbox which have factory conduit knockouts.
 - 2. All wiring will be as required by the Equipment Supplier. Wire color coding and the color shall remain the same throughout the system. In general, all initiating devices such as manual stations, thermal detectors, and ionization detectors will be installed across a common #18 AWG twisted shielded pair. The signal circuits shall require #14 AWG. All system wiring shall be plenum rated wire. The ground will be minimum one #6 AWG insulated copper.
 - 3. Provide sign on FACP identifying circuit number.

3.3 PATHWAYS

- A. Pathways shall be installed in EMT.

3.4 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."
- B. Install framed instructions in a location visible from fire-alarm control unit.

3.5 GROUNDING

- A. Ground fire-alarm control unit and associated circuits; comply with IEEE 1100. Install a ground wire from main service ground to fire-alarm control unit.
- B. Ground shielded cables at the control panel location only. Insulate shield at device location.

3.6 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to test and inspect components, assemblies, and equipment installations, including connections.
- B. Perform tests and inspections.
- C. Perform the following tests and inspections
 - 1. Visual Inspection: Conduct visual inspection prior to testing.
 - a. Inspection shall be based on completed record Drawings and system documentation that is required by the "Completion Documents, Preparation" table in the "Documentation" section of the "Fundamentals" chapter in NFPA 72.
 - b. Comply with the "Visual Inspection Frequencies" table in the "Inspection" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.
 - 2. System Testing: Comply with the "Test Methods" table in the "Testing" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
 - 4. Test audible appliances for the private operating mode according to manufacturer's written instructions.
 - 5. Test visible appliances for the public operating mode according to manufacturer's written instructions.
 - 6. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" section of the "Fundamentals" chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" section of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
- D. Reacceptance Testing: Perform reacceptance testing to verify the proper operation of added or replaced devices and appliances.
- E. Fire-alarm system will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.
- G. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.
- H. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.7 MAINTENANCE SERVICE

- A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by skilled employees of manufacturer's designated service organization. Include preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.
 - 1. Include visual inspections according to the "Visual Inspection Frequencies" table in the "Testing" paragraph of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 2. Perform tests in the "Test Methods" table in the "Testing" paragraph of the "Inspection, Testing and Maintenance" chapter in NFPA 72.
 - 3. Perform tests per the "Testing Frequencies" table in the "Testing" paragraph of the "Inspection, Testing and Maintenance" chapter in NFPA 72.

3.8 SOFTWARE SERVICE AGREEMENT

- A. Comply with UL 864.
- B. Technical Support: Beginning at Substantial Completion, service agreement shall include software support for 2 years.

3.9 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system.

END OF SECTION 28 31 11

SECTION 31 00 00

EARTHWORK

GENERAL

Note: the geotechnical report shall be considered part of these specifications. The contractor is responsible for obtaining a copy of the report which shall be used as the basis for construction means and methods.

1.01 DEFINITIONS IN THIS SECTION INCLUDE THE FOLLOWING

- A. Backfill: Soil materials used to fill an excavation.
- B. Base Course: Layer placed between the subbase course and asphalt paving.
- C. Bedding Course: Layer placed over the excavated subgrade in a trench before laying pipe.
- D. Borrow: Satisfactory soil imported from off-site for use as fill or backfill.
- E. Drainage Course: Layer supporting slab-on-grade used to minimize capillary flow of pore water.
- F. Excavation: Removal of material encountered above subgrade elevations.
 - 1. Additional Excavation: Excavation below subgrade elevations as directed by Construction Manager. Additional excavation and replacement material will be paid for according to Contract provisions for changes in the Work.
 - 2. Unauthorized Excavation: Excavation below subgrade elevations or beyond indicated dimensions without direction by Construction Manager. Unauthorized excavation, as well as remedial work directed by Construction Manager, shall be without additional compensation.
- G. Fill: Soil materials used to raise existing grades.
- H. Structures: Buildings, footings, foundations, retaining walls, slabs, tanks, curbs, mechanical and electrical appurtenances, or other man-made stationary features constructed above or below the ground surface.
- I. Subbase Course: Layer placed between the subgrade and base course for asphalt paving, or layer placed between the subgrade and a concrete pavement or walk.
- J. Subgrade: Surface or elevation remaining after completing excavation, or top surface of a fill or backfill immediately below subbase, drainage fill, or topsoil materials.
- K. Utilities include on-site underground pipes, conduits, ducts, and cables, as well as underground services within buildings.

Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted in writing by Construction Manager and then only after arranging to provide temporary utility services according to requirements indicated.

PRODUCTS

2.01 MATERIALS

- A. Soil Materials: Provide borrow soil materials when sufficient satisfactory soil materials are not available from excavations.
- B. Satisfactory Soils: ASTM D 2487 soil classification groups CL, ML, CL-ML, SP, SW, GP, and GW; free of rock or gravel larger than 6 inches in any dimension, debris, waste, frozen materials, vegetation, and other deleterious matter. The contractor shall refer to the geotechnical report or directly with the geotechnical engineer to confirm satisfactory soils prior to construction.
- C. Backfill and Fill: Satisfactory soil materials.
- D. Subbase Material: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and natural or crushed sand; ASTM D 2940; with at least 90 percent passing a 1-1/2-inch (38-mm) sieve and not more than 12 percent passing a No. 200 (0.075-mm) sieve.
- E. Bedding: Naturally or artificially graded mixture of natural or crushed gravel, crushed stone, and

natural or crushed sand; ASTM D 2940; except with 100 percent passing a 1-inch (25-mm) sieve and not more than 8 percent passing a No. 200 (0.075-mm) sieve.

- F. Drainage Fill: Washed, narrowly graded mixture of crushed stone, or crushed or uncrushed gravel; ASTM D 448; coarse-aggregate grading Size 57; with 100 percent passing a 1-1/2-inch (38-mm) sieve and 0 to 5 percent passing a No. 8 (2.36-mm) sieve.
- G. Detectable Warning Tape: Polyethylene film warning tape encasing a metallic core, minimum 6 inches (150 mm) wide and 4 mils (0.1 mm) thick, continuously inscribed with a description of the utility.

EXECUTION

3.01 PREPARATION

- A. Protect structures, utilities, sidewalks, pavements, and other facilities from damage caused by settlement, lateral movement, undermining, washout, and other hazards created by earthwork operations.
- B. Provide erosion and sedimentation control measures.
- C. Prevent surface water and ground water from entering excavations, from ponding on prepared subgrades, and from flooding Project Site and surrounding area.
- D. Protect subgrades from softening, undermining, washout, and damage by rain or water accumulation.
- E. Excavate to subgrade elevations regardless of the character of surface and subsurface conditions encountered including rock, soil materials, and obstructions.
 - 1. If excavated materials intended for fill and backfill include unsatisfactory soil materials and rock, replace with satisfactory soil materials.
- F. Excavate for structures, pavements, and walks to indicated elevations and dimensions. Extend excavations for placing and removing concrete form work, for installing services and other construction, and for inspections. Trim bottoms to required lines and grades to leave solid base to receive other work.
- G. Excavate utility trenches to indicated gradients, lines, depths, and invert elevations of uniform widths to provide a working clearance on each side of pipe or conduit. Excavate trench walls vertically from trench bottom to 12 inches (300 mm) higher than top of pipe or conduit.
 - 1. Excavate trenches deeper than bottom of pipe elevations, 6 inches (150 mm) deeper in rock, 4 inches (100 mm) deeper elsewhere, to allow for bedding course. Hand excavate for bell of pipe.
- H. Proof roll subgrades, before filling or placing aggregate courses, with heavy pneumatic-tired equipment to identify soft pockets and areas of excess yielding. Do not proof roll wet or saturated subgrades.
- I. Reconstruct subgrades damaged by freezing temperatures, frost, rain, accumulated water, or construction activities.
- J. Fill unauthorized excavation under foundations or wall footings by extending bottom elevation of concrete foundation or footing to excavation bottom, without altering top elevation. Lean concrete fill may be used when approved by Construction Manager.
 - 1. Fill unauthorized excavations under other construction or utility pipe as directed by Construction Manager.
- K. Stockpile borrow materials and satisfactory soil materials, without intermixing, in shaped, graded, drained, and covered stockpiles. Stockpile soil materials away from edge of excavations and outside drip line of remaining trees.
- L. Utility Trench Backfill: Place, compact, and shape bedding course to provide continuous support for pipes and conduits over rock and other unyielding bearing surfaces and to fill unauthorized excavations.

1. Place and compact initial backfill of satisfactory soil material or subbase material, free of particles larger than 1 inch (25 mm), to a height of 12 inches (300 mm) over the utility pipe or conduit. Place and compact final backfill, according to the requirements of the geotechnical report, of satisfactory soil material to final subgrade.
 2. Install warning tape directly above utilities, 12 inches (300 mm) below finished grade, except 6 inches (150 mm) below subgrade under pavements and slabs.
- M. Fill: Place and compact fill material in layers to required elevations.
- N. Uniformly moisten or aerate subgrade and each subsequent fill or backfill layer before compaction to within 2 percent of optimum moisture content.
1. Remove and replace, or scarify and air-dry, otherwise satisfactory soil material that exceeds optimum moisture content by 2 percent and is too wet to compact to specified dry unit weight.
- O. Compaction: Place backfill and fill materials in layers not more than 8 inches (200 mm) in loose depth for material compacted by heavy compaction equipment, and not more than 4 inches (100 mm) in loose depth for material compacted by hand-operated tampers.
- P. Compact soil to not less than the following percentages of maximum dry density as determined by the standard Proctor test, according to ASTM D 698:
1. Under structures, building slabs, steps, and pavements, compact and prepare subgrade and each layer of backfill or fill material at 95 percent of standard Proctor (ASTM D 698) maximum dry density or as directed by the geotechnical engineer.
 2. Under walkways, scarify and recompact top 6 inches (150 mm) below subgrade and compact each layer of backfill or fill material at 95 percent of standard Proctor (ASTM D 698) maximum dry density or as directed by the geotechnical engineer.
 3. Under lawn or unpaved areas, scarify and recompact top 6 inches (150 mm) below subgrade and compact each layer of backfill or fill material at 90 percent of standard Proctor (ASTM D 698) maximum dry density or as directed by the geotechnical engineer.
- Q. Grading: Uniformly grade areas to smooth surface, free from irregular surface changes. Comply with compaction requirements and grade to cross sections, lines, and elevations indicated. Grade lawns, walks, and unpaved subgrades to tolerances of plus or minus 1 inch (25 mm) and pavements and areas within building lines to plus or minus 1/2 inch (13 mm).
- R. Subbase and Base Courses: Under pavements and walks, place subbase course on prepared subgrade. Place base course material over subbase. Compact to required grades, lines, cross sections, and thickness to not less than 100 percent of maximum dry density as determined by the standard Proctor test, according to ASTM D 698 or as directed by the geotechnical engineer.
- S. Under slabs-on-grade, place drainage course on prepared subgrade. Compact to required cross sections and thickness to not less than 95 percent of maximum dry density as determined by the standard Proctor test, according to ASTM D 698 or as directed by the geotechnical engineer.
- T. Testing Agency: Owner will engage a qualified independent geotechnical engineering testing agency to perform field quality control testing.
1. Allow testing agency to inspect and test subgrades and each fill or backfill layer. Proceed with subsequent earthwork only after test results for previously completed work comply with requirements.
 2. When testing agency reports that subgrades, fills, or backfills have not achieved degree of compaction specified, scarify and moisten or aerate, or remove and replace soil to depth required; recompact and retest until specified compaction is obtained.
- U. Repair and reestablish grades to specified tolerances where completed or partially completed surfaces become eroded, rutted, settled or where they lose compaction.
- V. Where settling occurs before Project correction period elapses, remove finished surfacing, backfill with additional soil material, compact, and reconstruct surfacing.
- W. Disposal: Remove surplus satisfactory soil and waste material, including unsatisfactory soil, trash, and debris, and legally dispose of on-site at direction of Construction Manager.

END OF SECTION

SECTION 31 10 00
SITE CLEARING

GENERAL

1.01 SUMMARY

- A. This Section includes the following:
 - 1. Protection of existing trees to remain.
 - 2. Removal of trees and other vegetation.
 - 3. Topsoil stripping and stockpiling.
 - 4. Clearing and grubbing.
 - 5. Removing above-grade improvements.
 - 6. Removing below-grade improvements.
- B. Related Sections: The following sections contain requirements that relate to this Section:
 - 1. Section 31 22 00 - "Grading" for excavation and fill work.
 - 2. Section 015713 – "Temporary Erosion and Sediment Control"

1.02 QUALITY ASSURANCE

- A. State and local code requirements shall control the methods used to clear site and procedures for disposal of removed materials.
- B. Missouri Department of Transportation Standards shall govern unless specifically indicated otherwise.
- C. Examine Contract Documents for all work required and coordinate and cooperate with others so as not to delay or interfere with the work of others. Contractor shall be responsible for obtaining a copy of the geotechnical report prepared for this project and performing all excavations or fills according to the recommendations of the report.
- D. Employ a licensed engineer or surveyor to stake out both horizontal and vertical control for all work prior to commencing any work operations.

1.03 PROJECT CONDITIONS

- A. Traffic: Conduct site clearing operations to ensure minimum interference with roads, streets, walks, and other adjacent occupied or used facilities. Do not close or obstruct streets, walks or other occupied or used facilities without permission from authorities having jurisdiction.
- B. Protection of Existing Improvements and Utilities: Provide protection necessary to prevent damage to existing improvements and utilities indicated to remain in place.
- C. Locate existing utilities with assistance of local utility companies and public agencies.
- D. Protect improvements on adjoining properties and on Owner's property.
- E. Restore damaged improvements to their original condition and grades, as acceptable to property owners.
- F. Protection of Existing Trees and Vegetation: Protect existing trees and other vegetation indicated to remain in place, against unnecessary cutting, breaking or skinning of roots and branches, skinning or bruising of bark, smothering of trees by stockpiling construction materials or excavated materials within drip line, excess foot or vehicular traffic, or parking of vehicles within drip line. Do not run heavy equipment over tree root systems. Maintain minimum trench widths near root systems so as to avoid unnecessary injury.
- G. Provide protection for roots over 1-1/2 inch in diameter that are cut during construction operations. Coat cut faces with emulsified asphalt, or other acceptable coating, formulated for use on damaged plant tissues. Temporarily cover exposed roots with wet burlap to prevent roots from drying out; cover with earth as soon as possible.
- H. Repair or replace trees and vegetation to remain which are damaged by construction operations, in a manner acceptable to architect.

1.04 EXISTING UTILITY INFORMATION

- A. Information on the drawings relating to existing utility lines and services is from the best sources presently available. All such information is furnished only for information and is not guaranteed. Excavate test pits as required to determine exact locations of existing utilities.

PRODUCTS

Not applicable.

EXECUTION

3.01 LAYOUT

- A. Stake out both horizontal and vertical control for all work prior to commencing work operations. Accurately locate and maintain location of all buildings, roads, paved areas, features, etc. Advise architect of any Contract Document discrepancies, prior to commencing work.
- B. Maintain benchmarks, monuments and other reference points. Re-establish benchmarks if disturbed or destroyed at no cost to Owner.

3.02 SITE CLEARING

- A. General: Locate and suitably identify trees and improvements to remain. Remove trees, shrubs, grass and other vegetation, rock/boulders, improvements, or obstructions as required to permit installation of new construction. Remove similar items elsewhere on site or premises as specifically indicated. "Removal" includes transporting off-site and legally disposing of removed non-salvageable material. All work to be coordinated with the architect regarding which trees shall remain and be protected. Contractor to meet on-site with architect prior to beginning clearing work.
- B. Cut minor roots and branches of trees indicated to remain in a clean and careful manner, where such roots and branches obstruct installation of new construction.
- C. Trees to remain within cleared areas shall be trimmed of all dead branches 1-1/2 inches or more in diameter. Cut close to bole of tree and paint with acceptable tree-wound paint.
- D. Strip topsoil in all building areas and all areas to be regraded, resurfaced, or paved within Contract Limit Lines, to whatever depths encountered in a manner to prevent intermingling with underlying subsoil or other objectionable material.
- E. Stockpile topsoil shall be free of trash, brush, rock/boulders over 1 inch diameter and other extraneous matter.
- F. Remove heavy growths of grass from areas before stripping.
- G. Where existing trees are indicated to remain, leave existing topsoil in place within drip lines to prevent damage to root system.
- H. Stockpile topsoil in storage piles in areas indicated or as directed by construction manager. Construct storage piles to provide free drainage of surface water, maximum slope to be 3:1. Cover storage piles, if required, to prevent wind erosion. No topsoil shall be removed from the site, until after all topsoil requirements have been met for each phase of construction.
- J. Dispose of unsuitable or excess topsoil same as specified for disposal of waste material.
- K. Clearing and Grubbing: Clear site of trees, shrubs and other vegetation, except for those indicated to be left standing.
- L. Fell trees to be removed in a controlled safe manner. Trim branches from bole and cut bole into manageable sections.
- M. Cut off shrubs and other vegetation, to be removed, flush with original ground surface.
- N. Completely remove stumps, roots, and other debris protruding through ground surface and in area(s) of new foundations, or paved improvements.
- O. Remove organic and metallic debris to a depth of 3 feet below existing grade to remain or new

finished grade whether lower or higher than existing grade.

- P. Use only hand methods for grubbing inside drip line of trees indicated to remain. Strip grass materials under tree canopies and carefully till or scarify existing grading to a maximum depth of 1 inch.
- Q. Fill depressions caused by clearing and grubbing operations with satisfactory soil material according to the recommendations of the geotechnical report, unless further excavation or earthwork is indicated.
- R. Place fill material in horizontal layers not exceeding 8" inches loose depth, and thoroughly compact to a density as required per the geotechnical report.
- S. Removal of Improvements: Remove existing above-grade and below-grade improvements as indicated and as necessary to facilitate new construction.
- T. Remove abandoned utility poles within Contract Limit Lines. Relocate and reinstall designated utility poles. Coordinate and cooperate with local utility company.
- U. Removal of abandoned underground piping or conduit interfering with construction is included under this Section. Record existing utility termination points before disconnecting. Close abandoned piping with 8 inch thick concrete plug(s) or mortar jointed masonry bulkhead. Any existing sewer piping that will be located beneath structures shall be removed. Existing sewer piping within proposed lawn areas may be completely grout filled per the specifications of the Metropolitan St. Louis Sewer District, provided the piping does not interfere with new construction.
- V. Remove existing sidewalks, curbs, and paving, including all base material to subgrade, as required to accommodate new construction, as shown on drawings. Cut existing sidewalks, curbs, and paving in neat, straight lines to provide uniform, even transition from new to adjacent existing work. Cut back existing paving a sufficient distance to permit forming and installation of new work.
- W. Remove, temporarily relocate during construction, and reinstall in final location street signs, mail boxes, and other designated items as shown on Drawings. Coordinate the work with applicable governing authorities. Comply with all requirements concerning temporary installation and permanent reinstallation.
- X. Raise or lower existing catch basin, inlet and manhole structures and valve box covers to accommodate new grade elevations at paved and lawn areas where indicated on Drawings. Extend structures as required. Reuse existing catch basin, inlet and manhole frames, and covers, unless noted otherwise.

3.03 DISPOSAL OF WASTE MATERIALS

- A. Removal of Owner's Spoil Area: Transport non-combustible waste materials and unsuitable topsoil materials to designated spoil areas on Owner's property and dispose on-site at direction of Construction Manager or as required by governing agencies having jurisdiction of this project.

3.04 CLEANING

- A. Upon completion of site preparation work, clean areas within contract limits, remove tools, and equipment. Provide site clear, clean, and free of materials and debris and suitable for site work operations.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 31 23 16

EXCAVATION

GENERAL

Note: the geotechnical report shall be considered part of these specifications. The contractor is responsible for obtaining a copy of the report which shall be used as the basis for construction means and methods.

1.01 SECTION INCLUDES

- A. Excavating for footings, slabs-on-grade, paving, site structures, and utilities within the building.

1.02 RELATED REQUIREMENTS

- A. Section 01 7000 - Execution and Closeout Requirements: General requirements for dewatering of excavations and water control.
- B. Section 31 2200 - Grading: Soil removal from surface of site.
- C. Section 31 2200 - Grading: Grading.
- D. Section 31 2323 - Fill: Fill materials, filling, and compacting.
- E. Section 31 2316.13 - Trenching: Excavating for utility trenches outside the building to utility main connections.
- F. Section 33 4600 - Subdrainage: Filter aggregate and filter fabric for foundation drainage systems.
- G. Section 01575 - Temporary Erosion and Sedimentation Control: Slope protection and erosion control.

1.03 PRICE AND PAYMENT PROCEDURES

- A. See Section 01 2200 - Unit Prices, for general requirements applicable to unit prices for excavation.
- B. Excavating Soil Materials:
 - 1. Measurement method: By the cubic yard.
 - 2. Includes: Excavating to required elevations, loading and removing from site.
 - 3. Does Not Include Over-Excavation: Payment will not be made for over-excavated work nor for replacement materials.
- C. See Section 31 2323 - Fill, for measurement and payment provisions related to fill.

1.04 PROJECT CONDITIONS

- A. Verify that survey bench mark and intended elevations for the Work are as indicated.
- B. Protect plants, lawns, trees, and other features to remain.
- C. Protect bench marks, survey control points, existing structures, fences, sidewalks, paving, and curbs from excavating equipment and vehicular traffic.

PRODUCTS - NOT USED

EXECUTION

3.01 PREPARATION

- A. Identify required lines, levels, contours, and datum locations.
- B. See Section 312200 for additional requirements.

3.02 EXCAVATING

- A. Excavate to accommodate new structures and construction operations.
- B. Notify Architect of unexpected subsurface conditions and discontinue affected Work in area until notified to resume work.

- C. Slope banks of excavations deeper than 4 feet to angle of repose or less until shored.
- D. Do not interfere with 45 degree bearing splay of foundations.
- E. Cut utility trenches wide enough to allow inspection of installed utilities.
- F. Hand trim excavations. Remove loose matter.
- G. Correct areas that are over-excavated and load-bearing surfaces that are disturbed; see Section 31 2323.
- H. Grade top perimeter of excavation to prevent surface water from draining into excavation.
- I. Remove excavated material that is unsuitable for re-use from site.
- J. Stockpile excavated material to be re-used in area designated on site in accordance with Section 31 2200. Limited area on-site may require excavated materials to be hauled off in some instances and should be coordinated with construction manager.
- K. Remove excess excavated material from site.

3.03 FIELD QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for field inspection and testing.
- B. Provide for visual inspection of load-bearing excavated surfaces before placement of foundations.

3.04 PROTECTION

- A. Prevent displacement of banks and keep loose soil from falling into excavation; maintain soil stability.
- B. Protect bottom of excavations and soil adjacent to and beneath foundation from freezing.

END OF SECTION

SECTION 31 23 16.13

TRENCHING

GENERAL

1.01 SECTION INCLUDES

- A. Backfilling and compacting for utilities outside the building to utility main connections.

1.02 RELATED REQUIREMENTS

- A. Refer to Geotechnical Report for information regarding bore hole locations and findings of subsurface materials.
- B. Section 31 2200 - Grading: Site grading.
- C. Section 31 2316 - Excavation: Building and foundation excavating.
- D. Section 31 2323 - Fill: Backfilling at building and foundations.
- E. Section 33 4600 - Subdrainage: Filter aggregate and filter fabric for foundation drainage systems.

1.03 PRICE AND PAYMENT PROCEDURES

- A. See Section 01 2200 - Unit Prices, for general requirements applicable to unit prices for earthwork.
- B. Excavating Soil Materials:
 - 1. Measurement method: By the cubic foot
 - 2. Includes: Excavating to required elevations, loading and placing materials in stockpile.
 - 3. Does Not Include Over-Excavation: Payment will not be made for over-excavated work nor for replacement materials.
- C. General Fill:
 - 1. Measurement Method: By the cubic foot.
 - 2. Includes: Excavating existing soil, stockpiling, scarifying substrate surface, placing where required, and compacting.
- D. Structural Fill:
 - 1. Measurement Method: By the cubic foot.
 - 2. Includes: Excavating existing soil, stockpiling, scarifying substrate surface, placing where required, and compacting.
- E. Granular Fill:
 - 1. Measurement Method: By the cubic foot
 - 2. Includes: Excavating existing material, stockpiling, scarifying substrate surface, placing where required, and compacting.
- F. Aggregates:
 - 1. Measurement Method: By the cubic foot.
 - 2. Includes: Excavating existing material, stockpiling, scarifying substrate surface, placing where required, and compacting.

1.04 DEFINITIONS

- A. Finish Grade Elevations: Indicated on drawings.
- B. Subgrade Elevations: Indicated on drawings.
- C. Subgrade Elevations: 4 inches below finish grade elevations indicated on drawings, unless otherwise indicated.
- D. Finish Grade Elevations: 4 inches above subgrade elevations indicated on drawings, unless otherwise indicated.

1.05 REFERENCES

- A. AASHTO T 180 - Standard Specification for Moisture-Density Relations of Soils Using a 4.54 kg (10-lb) Rammer and a 457 mm (18 in.) Drop; American Association of State Highway and Transportation Officials; 2009.
- B. ASTM C 136 - Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates; 2006.
- C. ASTM D 698 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)); 2007.
- D. ASTM D 1556 - Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method; 2007.
- E. ASTM D 1557 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN m/m³)); 2009.
- F. ASTM D 2167 - Standard Test Method for Density and Unit Weight of Soil in Place by the Rubber Balloon Method; 2008.
- G. ASTM D 2487 - Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System); 2006.
- H. ASTM D 3017 - Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth); 2005.
- I. ASTM D 4318 - Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils; 2005.
- J. ASTM D 6938 - Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth); 2010

1.06 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Samples: 10 lb (4.5 kg) sample of each type of fill; submit in air-tight containers to testing laboratory.
- C. Materials Sources: Submit name of imported materials source.
- D. Fill Composition Test Reports: Results of laboratory tests on proposed and actual materials used.
- E. Compaction Density Test Reports.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. When necessary, store materials on site in advance of need.
- B. When fill materials need to be stored on site, locate stockpiles where indicated.
 - 1. Separate differing materials with dividers or stockpile separately to prevent intermixing.
 - 2. Prevent contamination.
 - 3. Protect stockpiles from erosion and deterioration of materials.

PRODUCTS

2.01 FILL MATERIALS

- A. Refer to Section 31 2000 Earth Moving for general fill materials.

2.02 ACCESSORIES

- A. Geotextile Fabric: Non-biodegradable, woven fabric.

2.03 SOURCE QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for testing and analysis of soil material.
- B. Where fill materials are specified by reference to a specific standard, test and analyze samples

for compliance before delivery to site.

- C. Where fill materials are specified by reference to a specific standard, testing of samples for compliance will be provided before delivery to site.
- D. If tests indicate materials do not meet specified requirements, change material and retest.
- E. Provide materials of each type from same source throughout the Work.

EXECUTION

3.01 EXAMINATION

- A. Verify that survey bench marks and intended elevations for the work are as indicated.

3.02 PREPARATION

- A. Identify required lines, levels, contours, and datum locations.
- B. See Section 31 2200 for additional requirements.
- C. Locate, identify, and protect utilities that remain and protect from damage.
- D. Notify utility company to remove and relocate utilities.
- E. Protect bench marks, survey control points, existing structures, fences, sidewalks, paving, and curbs from excavating equipment and vehicular traffic.
- F. Protect plants, lawns, rock outcroppings, and other features to remain.

3.03 TRENCHING

- A. Notify Architect of unexpected subsurface conditions and discontinue affected Work in area until notified to resume work.
- B. Slope banks of excavations deeper than 4 feet to angle of repose or less until shored.
- C. Do not interfere with 45 degree bearing splay of foundations.
- D. Cut trenches wide enough to allow inspection of installed utilities.
- E. Hand trim excavations. Remove loose matter.
- F. Remove large stones and other hard matter that could damage piping or impede consistent backfilling or compaction.
- G. Remove lumped subsoil, boulders, and rock up to 1/3 cu yd measured by volume.
- H. Remove excavated material that is unsuitable for re-use from site.
- I. Stockpile excavated material to be re-used in area designated on site in accordance with Section 31 2200.
- J. Remove excess excavated material from site.

3.04 PREPARATION FOR UTILITY PLACEMENT

- A. Cut out soft areas of subgrade not capable of compaction in place. Backfill with general fill.
- B. Compact subgrade to density equal to or greater than requirements for subsequent fill material.
- C. Until ready to backfill, maintain excavations and prevent loose soil from falling into excavation.

3.05 BACKFILLING

- A. Backfill to contours and elevations indicated using unfrozen materials.
- B. Fill up to subgrade elevations unless otherwise indicated.
- C. Employ a placement method that does not disturb or damage other work.
- D. Systematically fill to allow maximum time for natural settlement. Do not fill over porous, wet, frozen or spongy subgrade surfaces.
- E. Maintain optimum moisture content of fill materials to attain required compaction density.
- F. Granular Fill: Place and compact materials in equal continuous layers not exceeding 6 inches

compacted depth.

- G. Soil Fill: Place and compact material in equal continuous layers not exceeding 8 inches compacted depth.
- H. Slope grade away from building minimum 2 inches in 10 ft, unless noted otherwise. Make gradual grade changes. Blend slope into level areas.
- I. Correct areas that are over-excavated.
 - 1. Thrust bearing surfaces: Fill with concrete.
 - 2. Other areas: Use general fill, flush to required elevation, compacted to minimum 98 percent of maximum dry density.
- J. Compaction Density Unless Otherwise Specified or Indicated:
 - 1. Under paving, slabs-on-grade, and similar construction: 100 percent of maximum dry density.
 - 2. At other locations: 95 percent of maximum dry density unless otherwise indicated or as directed by the geotechnical engineer.
- K. Reshape and re-compact fills subjected to vehicular traffic.

3.06 BEDDING AND FILL AT SPECIFIC LOCATIONS

- A. Use general fill unless otherwise specified or indicated.
- B. Utility Piping, Conduits, Duct Bank:
 - 1. Bedding: Blended aggregate fill.
 - 2. Cover with general fill.
 - 3. Fill up to subgrade elevation.
 - 4. Compact in maximum 8 inch lifts to 95 percent of maximum dry density.
- C. At Pipe Culverts:
 - 1. Bedding: Use general fill or as specified by the Metropolitan St. Louis Sewer District for storm and sanitary sewers.
 - 2. Place filter fabric specified in Section 33 0513 over compacted bedding.
 - 3. Cover with general fill.
 - 4. Fill up to subgrade elevation.
 - 5. Compact in maximum 8 inch lifts to 95 percent of maximum dry density.
- D. Over Subdrainage Piping at Foundation Perimeter and Under Slabs:
 - 1. Drainage fill and geotextile fabric: Section 33 4600.
 - 2. Cover drainage fill with general fill.
 - 3. Compact to 95 percent of maximum dry density.
- E. At French Drains:
 - 1. Use granular fill.
 - 2. Fill up to 8 inches below finish grade.
 - 3. Compact to 95 percent of maximum dry density.

3.07 TOLERANCES

- A. Top Surface of General Backfilling: Plus or minus 1 inch from required elevations.
- B. Top Surface of Backfilling Under Paved Areas: Plus or minus 1 inch from required elevations.

3.08 FIELD QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for field inspection and testing.
- B. Perform compaction density testing on compacted fill in accordance with ASTM D1556, ASTM D2167, ASTM D3017, or ASTM D6938.
- C. Evaluate results in relation to compaction curve determined by testing uncompacted material in accordance with ASTM D 698 ("standard Proctor"), or AASHTO T 180.

- D. If tests indicate work does not meet specified requirements, remove work, replace and retest.
- E. Frequency of Tests: as directed in the geotechnical report.

3.09 CLEANING

- A. Leave unused materials in a neat, compact stockpile.
- B. Remove unused stockpiled materials, leave area in a clean and neat condition. Grade stockpile area to prevent standing surface water.
- C. Leave borrow areas in a clean and neat condition. Grade to prevent standing surface water.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 31 23 23

FILL

GENERAL

Note: the geotechnical report shall be considered part of these specifications. The contractor is responsible for obtaining a copy of the report which shall be used as the basis for construction means and methods.

1.01 SECTION INCLUDES

- A. Filling, backfilling, and compacting for footings, slabs-on-grade, paving, site structures, and utilities within the building.

1.02 RELATED REQUIREMENTS

- A. Section 31 2200 - Grading: Removal and handling of soil to be re-used.
- B. Section 31 2316 - Excavation: Removal and handling of soil to be re-used.
- C. Section 33 4600 - Subdrainage: Filter aggregate and filter fabric for foundation drainage systems.
- D. Section 01 5713 - Temporary Erosion and Sedimentation Control: Slope protection and erosion control.

1.03 PRICE AND PAYMENT PROCEDURES

- A. See Section 01 2200 - Unit Prices, for general requirements applicable to unit prices for earthwork.
- B. General Fill:
 - 1. Measurement Method: By the cubic yard.
 - 2. Includes: Supplying fill, stockpiling, scarifying substrate surface, placing where required, and compacting.
- C. Structural Fill:
 - 1. Includes: Excavating existing soil, stockpiling, scarifying substrate surface, placing where required, and compacting.

1.04 REFERENCE STANDARDS

- A. ASTM D 698 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)); 2007.
- B. ASTM D 1556 - Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method; 2007.
- C. ASTM D 2487 - Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System); 2006.

1.05 DEFINITIONS

- A. Finish Grade Elevations: Indicated on drawings.
- B. Subgrade Elevations: 6 inches below finish grade elevations indicated on drawings, unless otherwise indicated.

1.06 SUBMITTALS

- A. See Section 001 3300 - Construction Submittals, for submittal procedures.
- B. Materials Sources: Submit name of imported materials source.
- C. Fill Composition Test Reports: Results of laboratory tests on proposed and actual materials used.
- D. Compaction Density Test Reports.

1.07 DELIVERY, STORAGE, AND HANDLING

- A. Provide sufficient quantities of fill to meet project schedule and requirements.
- B. When fill materials need to be stored on site, locate stockpiles where indicated.

1. Separate differing materials with dividers or stockpile separately to prevent intermixing.
 2. Prevent contamination.
 3. Protect stockpiles from erosion and deterioration of materials.
- C. Verify that survey bench marks and intended elevations for the Work are as indicated.

PRODUCTS

2.01 FILL MATERIALS

- A. General Fill: Subsoil excavated on-site and conforming to the following unless otherwise indicated by the geotechnical engineer:
1. Low-plasticity, cohesive type.
 - a. Liquid Limit: Refer to geotechnical report or directly with geotechnical engineer.
 - b. Plasticity Index: Refer to geotechnical report or directly with geotechnical engineer.
 2. Free of lumps larger than 3 inches, rocks larger than 2 inches, and debris.
 3. Conforming to ASTM D 2487 Group Symbol CL.
- B. Blended Aggregate Fill:
- C. Granular Drainage Fill: Angular crushed washed stone; open-graded, processed aggregate; free of shale, clay, friable material and debris; and conforming to the following:
1. ASTM C33, Class Designation 2S, course aggregate for concrete.
 - a. Minimum size: No.8 sieve; 0 to 5 percent passing.
 - b. Maximum size: 3/4 inch.
- D. Sand: Natural river or bank sand; washed; free of silt, clay, loam, friable or soluble materials, and organic matter.
1. Grade in accordance with ASTM D 2487 Group Symbol SW.
- E. Topsoil: See Section 31 2200.

2.02 ACCESSORIES

- A. Filter Fabric: Polypropylene type, black non-biodegradable, non-woven, needle punched; "ADS-6600" manufactured by Advanced Drainage Systems, Inc..

2.03 SOURCE QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for testing and analysis of soil material.
- B. Where fill materials are specified by reference to a specific standard, test and analyze samples for compliance before delivery to site.
- C. If tests indicate materials do not meet specified requirements, change material and retest.
- D. Provide materials of each type from same source throughout the Work.

EXECUTION

3.01 EXAMINATION

- A. Identify required lines, levels, contours, and datum locations.
- B. See Section 31 2200 for additional requirements.
- C. Verify sub-drainage, damp-proofing, or waterproofing installation has been inspected.
- D. Verify structural ability of unsupported walls to support imposed loads by the fill.

3.02 PREPARATION

- A. Scarify and proof roll subgrade surface to a minimum depth of 8 inches prior to placement of new fill material.
- B. Cut out any soft areas of subgrade observed during the proof roll which are not capable of proper compaction in place. Backfill with general fill.
- C. Compact subgrade to density equal to or greater than requirements for subsequent fill material.
- D. Until ready to fill, maintain excavations and prevent loose soil from falling into excavation.

3.03 FILLING

- A. Fill to contours and elevations indicated using unfrozen materials.
- B. Fill up to subgrade elevations unless otherwise indicated.
- C. Employ a placement method that does not disturb or damage other work.
- D. Systematically fill to allow maximum time for natural settlement. Do not fill over porous, wet, frozen or spongy subgrade surfaces.
- E. Maintain optimum moisture content of fill materials to attain required compaction density.
- F. Granular / Aggregate Fill: Place and compact materials in equal continuous layers not exceeding 6 inches compacted depth.
- G. Soil Fill: Place and compact material in equal continuous layers not exceeding 8 inches compacted depth.
- H. Slope grade away from building minimum 2 inches in 10 ft, unless noted otherwise. Make gradual grade changes. Blend slope into level areas.
- I. Correct areas that are over-excavated.
 - 1. Load-bearing foundation surfaces: Use blended aggregate fill, flush to required bearing elevation, compacted to 100 percent of maximum dry density.
 - 2. Other areas: Use general fill, flush to required elevation, compacted to minimum 98 percent of maximum dry density unless otherwise directed by the geotechnical engineer.
- J. Compaction Density Unless Otherwise Specified or Indicated:
 - 1. Under paving, slabs-on-grade, and similar construction: 98 percent of maximum dry density unless otherwise directed by the geotechnical engineer.
 - 2. At other locations: 90 percent of maximum dry density unless otherwise directed by the geotechnical engineer.
- K. Reshape and re-compact fills subjected to vehicular traffic.

3.04 FILL AT SPECIFIC LOCATIONS

- A. Use general fill unless otherwise specified or indicated.
- B. Granular Fill Material, where specified and/or authorized:
 - 1. Relative Density (ASTM D4353 and D4254): 70%
 - 2. Minimum Percent Compaction (ASTM D698): 98%
 - 3. Moisture Content Range, from optimum: Generally -3% to +3% (specific evaluation for each material) or as otherwise directed by the geotechnical engineer
 - 4. If granular material is a coarse sand or gravel, is of a uniform size, or has a low fines content, compaction comparison to relative density may be more appropriate.
 - 5. The gradation of a granular material may affect its stability and the moisture content required for proper compaction. Samples of all proposed fill materials should be submitted to the Geotechnical Engineer for testing and approval prior to use.
- C. Below Foundations:
 - 1. Low Plasticity Cohesive soil (e.g., lean clay or sandy lean clay)
 - 2. Minimum Percent Compaction (ASTM D698): 100% or as directed by geotechnical engineer.
 - 3. Moisture Content Range, from optimum: -2% to +3% or as otherwise directed by the geotechnical engineer
 - 4. The higher degree of fill compaction below footings should extend laterally beyond the exterior edges of the perimeter footings for at least 8 inches per foot of fill thickness below the footing base elevation.
- D. Subgrade Under Interior Slabs on Grade:
 - 1. Subbase: Use low plasticity cohesive soil
 - a. Liquid limit: refer to geotechnical report or directly with geotechnical engineer
 - b. Plasticity index: refer to geotechnical report or directly with geotechnical engineer
 - c. Or use well graded crushed limestone.

- d. Depth: 12 inches.
 - e. Compact to 95 percent of maximum dry density.
- 2. Granular Base: Clean, well-graded crushed stone
 - a. Containing less than 6% passing U.S. No. 200 sieve
 - b. Granular bases serve as leveling courses, capillary moisture breaks, help provide load distribution, and expedite construction. Care will be necessary to avoid contaminating these layers with soil prior to floor slab placement
- E. Subgrade Under Interior Slabs-On-Grade:
 - 1. Scarify and recompact top 8 inches of existing subsoil to 98 percent of its maximum dry density before placing additional fill.
 - 2. Use general fill at optimum moisture as replacement for unsatisfactory subsoil materials.
 - 3. Fill up to subgrade elevations below capillary barrier.
 - 4. Compact to 98 percent of maximum dry density.
- F. Capillary Barrier Under Interior Slabs-On-Grade:
 - 1. Use granular drainage fill.
 - 2. Depth: 6 inches deep.
 - 3. Compact to 98 percent of maximum dry density.
- G. At Foundation Walls and Footings:
 - 1. Use fill as directed by geotechnical engineer
 - 2. Fill up to capillary barrier inside building line.
 - 3. Fill to within 18 inches below finish grade outside building line.
 - 4. Compact each lift as directed by geotechnical engineer and/or as indicated in geotechnical engineer's report
 - 5. Do not backfill against unsupported foundation walls.
 - 6. Backfill simultaneously on each side of unsupported foundation walls until supports are in place.
- H. Over Subdrainage Piping at Foundation Perimeter:
 - 1. Use granular drainage fill and geotextile fabric: See Section 02620 for additional requirements.
 - 2. Cover drainage fill with sand.
 - 3. Fill to within 18 inches below finish grade elevation.
 - 4. Compact to 95 percent of maximum dry density.
- I. Over Buried Utility Piping, Conduits, and Duct Bank in Trenches:
 - 1. Bedding and Haunching Layers: Use blended aggregate fill.
 - 2. Cover with general fill.
 - 3. Fill up to subgrade elevation.
 - 4. Compact in maximum 8 inch lifts to 95 percent of maximum dry density.
- J. Around and Over Underground Tanks:
 - 1. Use initial fill of sand.
 - a. Compact to 95 percent of maximum dry density.
 - 2. Complete with general fill.
 - a. Compact to 95 percent of maximum dry density.
- K. Pavement Subgrade:
 - 1. Low Plasticity Cohesive soil (e.g. lean clay or sandy lean clay)
 - 2. Minimum Percent Compaction (ASTM D698):
 - a. Upper 12 inches of pavement subgrade: 98%
 - b. Below upper 12 inches of pavement subgrade: 95%
 - 3. Moisture Content Range, from optimum -2% to +3%
- L. At Lawn Areas:
 - 1. Use general fill.
 - 2. Fill up to 6 inches below finish grade elevations.

3. Compact to 90 percent of maximum dry density.
 4. See Section 31 2200 for topsoil placement.
- M. Under Monolithic Paving:
1. Scarify and recompact top 8 inches of existing subsoil to 95 percent of its maximum dry density before placing additional fill.
 2. Use additional general fill as required to achieve final subgrade elevation.
 - a. Maximum compacted depth of each lift: 8 inches.
 - b. Compact to 95 percent of maximum dry density.
 3. See Section 32 1123 for aggregate base course placed over fill.
 4. Use sand leveling base under concrete sidewalks.
 - a. Compacted depth: 2 inches, minimum.
 - b. Compact to 95 percent of maximum dry density.

3.05 TOLERANCES

- A. Top Surface of General Filling: Plus or minus 1 inch from required elevations.
- B. Top Surface of Filling Under Paved Areas: Plus or minus 1 inch from required elevations.

3.06 FIELD QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for field inspection and testing.
- B. Perform compaction density testing on compacted fill in accordance with ASTM D1556.
- C. Evaluate results in relation to compaction curve determined by testing uncompacted material in accordance with ASTM D 698 ("standard Proctor").
- D. If tests indicate work does not meet specified requirements, remove work, replace and retest.
- E. Frequency of Tests: Comply with recommendations of geotechnical engineer.
- F. Proof roll compacted fill at surfaces that will be under slabs-on-grade.

3.07 CLEANING

- A. Remove unused materials; leave area in a clean and neat condition, properly prepared for subsequent grading operations.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 11 23
AGGREGATE BASE COURSES

GENERAL

1.01 SECTION INCLUDES

- A. Aggregate base course.

1.02 RELATED REQUIREMENTS

- A. Section 31 2200 - Grading: Preparation of site for base course.
- B. Section 31 2316.13 - Trenching: Compacted fill over utility trenches under base course.
- C. Section 31 2323 - Fill: Topsoil fill at areas adjacent to aggregate base course.
- D. Section 31 2323 - Fill: Compacted fill under base course.
- F. Section 32 1216 - Asphalt Paving: Binder and finish asphalt courses.
- G. Section 32 1313 - Concrete Paving: Finish concrete surface course.
- H. Section 33 4600 - Subdrainage: Filter aggregate and filter fabric for foundation drainage systems.

1.03 PRICE AND PAYMENT PROCEDURES

- A. See Section 01 2200 - Unit Prices, for general requirements applicable to unit prices for earthwork.
- B. Coarse Aggregate: By the cubic yard. Includes supplying aggregate material, stockpiling, scarifying substrate surface, placing, and compacting.
- C. Fine Aggregate: By the cubic yard. Includes supplying aggregate material, stockpiling, scarifying substrate surface, placing where required, and compacting.

1.04 REFERENCE STANDARDS

- A. AASHTO M 147 - Standard Specification for Materials for Aggregate and Soil-Aggregate Subbase, Base and Surface Courses; American Association of State Highway and Transportation Officials; 1965 (2004).
- B. AASHTO T 180 - Standard Specification for Moisture-Density Relations of Soils Using a 4.54 kg (10-lb) Rammer and a 457 mm (18 in.) Drop; American Association of State Highway and Transportation Officials; 2009.
- C. ASTM C 136 - Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates; 2006.
- D. ASTM D 698 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft-lbf/ft³ (600 kN-m/m³)); 2007.
- E. ASTM D 1556 - Standard Test Method for Density and Unit Weight of Soil in Place by the Sand-Cone Method; 2007.
- F. ASTM D 1557 - Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Modified Effort (56,000 ft-lbf/ft³ (2,700 kN m/m³)); 2009.
- G. ASTM D 2167 - Standard Test Method for Density and Unit Weight of Soil in Place by the Rubber Balloon Method; 2008.
- H. ASTM D 2487 - Standard Practice for Classification of Soils for Engineering Purposes (Unified Soil Classification System); 2006.
- I. ASTM D 3017 - Standard Test Method for Water Content of Soil and Rock in Place by Nuclear Methods (Shallow Depth); 2005.
- J. ASTM D 4318 - Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils; 2005.
- K. ASTM D 6938 - Standard Test Method for In-Place Density and Water Content of Soil and Soil-Aggregate by Nuclear Methods (Shallow Depth); 2010.

1.05 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Samples: 10 lb (4.5 kg) sample of each type of aggregate; submit in air-tight containers to testing laboratory.
- C. Materials Sources: Submit name of imported materials source.
- D. Aggregate Composition Test Reports: Results of laboratory tests on proposed and actual materials used.
- E. Compaction Density Test Reports.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. When necessary, store materials on site in advance of need.
- B. When aggregate materials need to be stored on site, locate stockpiles where indicated.
 - 1. Separate differing materials with dividers or stockpile separately to prevent intermixing.
 - 2. Prevent contamination.
 - 3. Protect stockpiles from erosion and deterioration of materials.

PRODUCTS

2.01 MATERIALS

- A. Type 5 Aggregate conforming to St. Louis County Department of Highways and Traffic Standards and Specifications, Section 1007, below pavement
- B. Geotextile Fabric: Geotextiles shall be in accordance with the physical and chemical requirements of AASHTO M 288 for the specified application, except as modified in this specification.

2.02 SOURCE QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for testing and analysis of aggregate materials.
- B. Where aggregate materials are specified using ASTM D 2487 classification, test and analyze samples for compliance before delivery to site.
- C. Where aggregate materials are specified using ASTM D 2487 classification, testing of samples for compliance will be provided before delivery to site.
- D. If tests indicate materials do not meet specified requirements, change material and retest.
- E. Provide materials of each type from same source throughout the Work.

EXECUTION

3.01 EXAMINATION

- A. Verify that survey bench marks and intended elevations for the work are as indicated.
- B. Verify substrate has been inspected, gradients and elevations are correct, and is dry.

3.02 PREPARATION

- A. Correct irregularities in substrate gradient and elevation by scarifying, reshaping, and re-compacting.
- B. Do not place aggregate on soft, muddy, or frozen surfaces.

3.03 INSTALLATION

- A. Under Bituminous Concrete Paving:
 - 1. Place aggregate base to a total compacted thickness as indicated on the plan details.
 - 2. Compact to 100 percent of maximum dry density.
- B. Under Portland Cement Concrete Paving:
 - 1. Place coarse aggregate to a total compacted thickness as indicated on the plan details.
 - 2. Compact to 100 percent of maximum dry density.

- C. Place aggregate in maximum 4 inch layers and roller compact to specified density.
- D. Level and contour surfaces to elevations and gradients indicated.
- E. Add small quantities of fine aggregate to coarse aggregate as appropriate to assist compaction.
- F. Add water to assist compaction. If excess water is apparent, remove aggregate and aerate to reduce moisture content.
- G. Use mechanical tamping equipment in areas inaccessible to compaction equipment.
- H. Apply herbicide to finished surface.

3.04 TOLERANCES

- A. Flatness: Maximum variation of 1/4 inch measured with 10 foot straight edge.
- B. Scheduled Compacted Thickness: Within 1/4 inch.
- C. Variation From Design Elevation: Within 1/2 inch.

3.05 FIELD QUALITY CONTROL

- A. See Section 01 4000 - Quality Requirements, for general requirements for field inspection and testing.
- B. Compaction density testing will be performed on compacted aggregate base course in accordance with ASTM D1556.
- C. Results will be evaluated in relation to compaction curve determined by testing uncompacted material in accordance with ASTM D 698 ("standard Proctor").
- D. If tests indicate work does not meet specified requirements, remove work, replace and retest.
- E. Frequency of Tests: Refer to Geotechnical Report.
- F. Proof roll compacted aggregate at surfaces that will be under slabs-on-grade.

3.06 CLEANING

- A. Leave unused materials in a neat, compact stockpile.
- B. Remove unused stockpiled materials, leave area in a clean and neat condition. Grade stockpile area to prevent standing surface water.
- C. Leave borrow areas in a clean and neat condition. Grade to prevent standing surface water.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 32 12 16
ASPHALT PAVING

GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification sections, apply to work of this section.
- B. Related Work Specified Elsewhere
 - 1. Grading - See Section 31 2200
 - 2. Concrete Paving - See Section 32 1313

1.02 DESCRIPTION OF WORK

- A. Extent of asphalt concrete paving work is shown on Drawings.
- B. Prepared aggregate sub-base is specified in earthwork sections.
- C. Saw-cutting of edge of existing pavement is specified in site preparation section.
- D. Furnish all labor, material and equipment necessary to complete all paving and related work as shown and/or specified herein.

1.03 SUBMITTALS

- A. Material Certificates: Provide copies of material certificates signed by material producer and Contractor, certifying that each material item complies with, or exceeds, specified requirements.
- B. Shop Drawings: Layout of pavement markings.
- C. Product Data
 - 1. Submit complete materials list of items proposed for the work; identify material source.
 - 2. Submit manufacturer's literature for sealer, striping paint, and soil sterilizer, and soil separator.
- D. Test Reports
 - 1. Submit reports to Architect for all tests as herein specified, to include subgrade surfaces, foundation course, surface material and compaction operations.

1.04 QUALITY ASSURANCE

- A. Codes and Standards: Comply with County highway or transportation department standard specifications, latest edition, and with local governing regulations if more stringent than herein specified.
- B. Provide material furnished by a bulk asphaltic concrete producer regularly engaged in the production of hot-mix, hot-laid asphaltic concrete paving materials.
- C. Construct street paving in accordance with local requirements.

1.05 DELIVERY, STORAGE AND HANDLING

- A. Deliver manufactured products in manufacturer's original unopened, and undamaged containers with labels intact and legible.
- B. Store and handle manufactured products to prevent damage and deterioration.

1.06 SITE CONDITIONS

- A. Weather Limitations: Apply prime and tack coats when ambient temperature is above 50 degrees F (10 degrees C) and when temperature has not been below 35 degrees F (1 degree C) for 12 hours immediately prior to application. Do not apply when base is wet or contains an excess of moisture.
- B. Construct asphalt concrete surface course when atmospheric temperature is above 40 degrees F (4 degrees C) and when base is dry. Base course may be placed when air temperature is above 30 degrees F (-1 degree C) and rising.

- C. Grade Control: Establish and maintain required lines and elevations, including crown, inverted crown, and cross-slopes, for each course during paving operations.
- D. Provide temporary barricades and warning lights as required for protection of project work and public safety.
- E. Protect adjacent work from damage, soiling and staining during paving operations.

1.07 EQUIPMENT

- A. Paving Equipment: Spreading, self-propelled asphalt paving machines capable of maintaining line, grade and thickness shown.
- B. Compacting equipment: Self-propelled rollers, minimum 10 ton weight.
- C. Hand tools: Rakes, shovels, tampers, and other miscellaneous equipment required to complete the work.
- D. Pavement marking equipment: Provide spray machines specifically designed for pavement marking.

1.08 COOPERATION

- A. Examine Drawings and Specifications for all Contracts, to determine nature of proposed construction. Perform work to conform with construction called for in such a manner as not to interfere or delay work of other Contractors.

PRODUCTS

2.01 MATERIALS

- A. General: Use locally available, State Department of Transportation or County approved materials and gradations which exhibit a satisfactory record of previous installations.

2.02 BITUMINOUS CONCRETE (ASPHALT) PAVEMENT

- A. Foundation Course
 - 1. Type "5" crushed limestone with gradation as described in Section 1007 of the "St. Louis County Department of Highways and Traffic Standard Specifications for Highway Construction".
- B. Asphalt Top Course
 - 1. Type "C" material produced and placed in accordance with Section 405 of the "St. Louis County Standard Specifications for Highway Construction."
- C. Asphalt Base Course
 - 1. Type "X" material produced and placed in accordance with Section 405 of the "St. Louis County Standard Specifications for Highway Construction."
- D. Pavement Sealer
 - 1. Sealer: Jennite J-16 asphalt surface treatment by Maintenance, Inc., Koppers Pavement Sealer by Koppers Inc., or Playtime Pavement Sealer by Playtime U.S.A., Spec-Seal by Northeast Sealcoat Co., or approved equal.
 - 2. Sand: Clean, hard, and durable, free from clay, salt and organic matter, well graded within the following limits: 100 percent passing #16 sieve, 80 to 100 percent passing #20 sieve, 50 to 90 percent passing #30 sieve, 20 to 60 percent passing #50 sieve, 0 to 5 percent passing #100 sieve.
- E. Asphalt Cement: AASHTO M 226 (ASTM D 3381) for viscosity-graded material and AASHTO M 20 (ASTM D 946) for penetration-graded material.
- F. Prime Coat: Cut-back asphalt type; AASHTO M 82 (ASTM D-2027) MC-30, MC-70 or MC-250.
- G. Tack Coat: Emulsified asphalt; AASHTO M 140 (ASTM D 977) or M 208 (D 2397); SS-1, SS-1h, CSS-1 or CSS-1h, diluted with one part water to one part emulsified asphalt.

2.03 CONSTRUCTION ROAD(S)

- A. Where indicated, construction road(s) and/or parking lot(s) are to become permanent road(s) and/or parking lot(s).
- B. Foundation Course
 - 1. Type "5" crushed limestone with gradation as described in Section 1007 of the "St. Louis County Department of Highways and Traffic Standard Specifications for Highway Construction".

EXECUTION

3.01 SUBGRADE PREPARATION

- A. Remove loose material from compacted sub-base surface immediately before applying herbicide treatment or prime coat.
- B. Proof roll prepared sub-base surface to check for unstable areas and areas requiring additional compaction.
- C. Proof Rolling in Cut Sections - Immediately prior to final trimming of the subgrade surface and placement of sub-base materials in cut sections, all areas of the subgrade surface within roadway and parking lot limits shall be proof rolled. This work, and any delays due to this work, shall be considered incidental to the excavation item.
 - 1. Purpose: In cut sections, the purpose of proof rolling is to determine the location and extent of areas below the subgrade surface that require corrective undercutting and are not so specified in the contract plans.
 - 2. Equipment: The proof roller shall be loaded to achieve a single stress level in operation, using a gross ballasted weight of 30 tons and all tires inflated to 40 psi.
 - 3. Procedure: Two complete passes shall be applied over all elements of the area to be proof rolled. Where any portion of the cut subgrade surface fails to provide a satisfactory support for the proof rolling operation, the Architect may order corrective undercut and backfill work performed. Backfill of undercuts as ordered by the Architect shall meet the requirements of the foundation course as specified in this section, placed and compacted to 95 percent of standard Proctor (ASTM D 698) maximum dry density. Where natural soil below this course will not support the weight of the construction equipment, and when ordered by the Architect, the course shall be placed in one lift.
 - 4. Exceptions: Proof rolling of the subgrade surface in cut sections will not be required in any area where the subgrade surface is in a rock cut, or where undercut and backfill has been previously performed unless required by the geotechnical engineer. The Architect may order undercutting and backfill without proof rolling of any cut where the need for corrective work is obvious without actual proof rolling.
- D. Notify Contractor of unsatisfactory conditions. Do not begin paving work until deficient sub-base areas have been corrected and are ready to receive paving.
- E. Prime Coat. Apply at rate of 0.20 to 0.50 gal. per sq. yd., over compacted subgrade. Apply material to penetrate and seal, but not flood, surface. Cure and dry as long as necessary to attain penetration and evaporation of volatile.
- F. Tack Coat. Apply to contact surfaces of previously constructed asphalt or Portland cement concrete and surfaces abutting or projecting into asphalt concrete pavement. Distribute at rate of 0.05 to 0.15 gal. per sq. yd. of surface.
- G. All to dry until at proper condition to receive paving.
- H. Exercise care in applying bituminous materials to avoid smearing of adjoining concrete surfaces. Remove and clean damaged surfaces.

3.02 PLACING FOUNDATION

- A. Bituminous Concrete (Asphalt) Paving
 - 1. Foundation Course
 - a. Place on dry subgrade in lifts from minimum 6" to maximum 12". Remove all subgrade

material churned or mixed with foundation course and replace as necessary at Contractor's expense.

- b. Grades for foundation course shall be $\pm .25"$ of required grades.
- c. Remove loose and foreign material from compacted foundation course immediately before application of surface materials.

3.03 PLACING MIX

- A. General. Place asphalt concrete mixture on prepared surface, spread and strike-off. Spread mixture at minimum temperature of 225 deg. F (107 deg. C). Place inaccessible and small areas by hand. Place each course to required grade, cross-section, and compacted thickness.
 - 1. Comply with Asphalt Institute (AI) MS-3 Asphalt Plant Manual for material storage, control and mixing, and for plant equipment and operation.
 - 2. Transport asphaltic concrete mixtures from the mixing plant to the project site in trucks with tight, clean compartments.
- B. Paver Placing. Place in strips not less than 10' wide, unless otherwise acceptable to Architect. After first strip has been placed and rolled, place succeeding strips and extend rolling to overlap previous strips. Complete base course for a section before placing surface course.
- C. Joints. Make joints between old and new pavements, or between successive days' work, to ensure continuous bond between adjoining work. Construct joints to have same texture, density and smoothness as other sections of asphalt concrete course. Clean contact surfaces and apply tack coat.

3.04 ROLLING

- A. General. Begin rolling when mixture will bear roller weight without excessive displacement.
 - 1. Compact mixture with hot hand tampers or vibrating plate compactors in areas inaccessible to rollers.
- B. Breakdown Rolling. Accomplish breakdown or initial rolling immediately following rolling of joints and outside edge. Check surface after breakdown rolling, and repair displaced areas by loosening and filling, if required, with hot material.
- C. Second Rolling. Follow breakdown rolling as soon as possible, while mixture is hot. Continue second rolling until mixture has been thoroughly compacted.
- D. Finish Rolling. Perform finish rolling while mixture is still warm enough for removal of roller marks. Continue rolling until roller marks are eliminated and course has attained maximum density.
 - 1. After placement and compaction of binder course, binder shall be proof-rolled in presence of testing agent to determine that no displacement or deflection occurs.
 - 2. Top course compaction shall be minimum 95 percent of laboratory specimen density.
 - 3. Form or cut all pavement edges to clean, sharp lines of dimensions, alignment, or radius indicated.
- E. Patching. Remove and replace paving areas mixed with foreign materials and defective areas. Cut-out such areas and fill with fresh, hot asphalt concrete. Compact by rolling to maximum surface density and smoothness.
- F. Protection. After final rolling, do not permit vehicular traffic on pavement until it has cooled and hardened.
- G. Erect barricades to protect paving from traffic until mixture has cooled enough not to become marked.
- H. Pavement Sealer
 - 1. Preparation work - Asphalt surface must be cured as per pavement sealer manufacturer's instructions, and must be free from dirt, oil and other foreign matter. Just prior to application of sealer, fog spray the pavement surface with clean, fresh water.
 - 2. Pavement sealer shall not be applied when weather is rainy or foggy, or when ambient

temperature is below 45 deg. F.

3. Application - Apply two coats of sealer uniformly at .09 gal./sq. yd. per coat. Apply in accordance with manufacturer's Specifications.

3.05 TRAFFIC AND LANE MARKINGS

- A. Cleaning. Sweep and clean surface to eliminate loose material and dust.
- B. Over clean, dry bituminous pavement, following application and curing of sealer, apply parking line stripes and other pavement markings as indicated, per manufacturer's recommendations. Provide uniform lines with straight edges, 4" minimum width.
- C. Provide lines, lettering, and markings shown to define parking spaces and traffic flow.
 1. Stencil all parking spaces noted as handicapped parking with the international symbol of access.
- D. Striping. Use traffic lane-marking paint, factory-mixed, quick-drying, and non-bleeding.
 1. Color: White/Yellow
 2. Do not apply traffic and lane marking paint until layout and placement has been verified with Architect.
 3. Apply paint with mechanical equipment to produce uniform straight edges. Apply in 2 coats at manufacturer's recommended rates.

3.06 CONSTRUCTION ROAD(S)

- A. Install where indicated, construction road(s) and/or parking lot(s) that are to become permanent road(s) and/or parking lot(s).
- B. Prepare subgrade as specified above.
- C. Foundation Course
 1. Place and roll in accordance with the "St. Louis County Department of Highways and Traffic Standard Specifications for Highway Construction", Section 304.
 2. Compaction for foundation course shall be 98 percent of standard proctor maximum density - tests to be taken before installation of bituminous courses.
 3. Grades for foundation course shall be $\pm .25"$ of required grades.
 4. Maintain to required grades during construction period, by the addition (when required) of specified foundation course material, well compacted.
- D. Bituminous Course
 1. When directed by the architect, repair foundation course, with specified material, to obtain proper grade and required compaction.
 2. Install bituminous pavement as detailed and specified, over repaired foundation course.

3.07 FIELD QUALITY CONTROL

- A. General. Test in-place asphalt concrete courses for compliance with requirements for thickness and surface smoothness. Repair or remove and replace unacceptable paving as directed by Architect.
- B. Thickness. In-place compacted thickness will not be acceptable if exceeding following allowable variation from required thickness.
 1. Base course: 1/4"
 2. Surface Course: 1/4"
- C. Surface Smoothness. Test finished surface of each asphalt concrete course for smoothness, using 10' straightedge applied parallel with, and at right angles to centerline of paved areas. Surfaces will not be acceptable if exceeding the following tolerances for smoothness.
 1. Base Course Surface: 1/4"
 2. Wearing Course Surface: 3/16"
 3. Crowned Surfaces: Test with crowned template centered and at right angle to crown. Maximum allowable variance from template, 1/4".

D. Check surface areas at intervals as directed by Architect.

3.08 CLEANING

- A. Perform cleaning during installation of the work and upon completion of the work. Remove from site all excess materials, debris, and equipment. Repair damage resulting from paving operations.
- B. Sweep pavement and wash free of stains, discolorations, dirt, and other foreign material immediately prior to final acceptance.

END OF SECTION

SECTION 32 13 13
CONCRETE PAVING

GENERAL

1.01 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to work of this section.

1.02 SUMMARY

- A. Extent of portland cement concrete paving is shown on Drawings, including curbs, gutters, walkways, and pavement.
 - 1. Related Sections: The following sections contain requirements that relate to this Section.
 - 2. Section 31 22 00 - "Grading" for subbase preparation.
 - 3. Section 33 41 11 - "Storm Utility Drainage Piping" for drainage structures and underdrains.

1.03 SUBMITTALS

- A. Shop Drawings: Layout of concrete pavement score lines and expansion joints.
- B. Test Reports: All test reports required by this section and referenced related sections.
- C. Certification: Written "Certificate of Compliance", signed by Contractor, that all concrete paving and curb materials and products, to be used on this project will comply with Standards referenced in the Specifications.

1.04 QUALITY ASSURANCE

- A. Codes and Standards: Comply with local codes if more stringent than herein specified. Comply with State Department of Transportation's standard specifications, except as otherwise specified herein.
- B. Do not change source of brands of cement and aggregate materials during course of the work.
- C. Maintain accurate field records of time, date of placing, curing and removal of forms for concrete work in each portion of the work.

1.05 DELIVERY, STORAGE AND HANDLING

- A. Store decorative exposed aggregate in segregated area to prevent mixing with foreign materials.
- B. Deliver curing materials, admixtures, and retarders in manufacturer's standard, unopened containers with labels legible and intact. Store and protect from freezing and damage.

1.06 PROJECT CONDITIONS

- A. Establish and maintain required lines and grade elevations.
- B. Do not install concrete work over wet, saturated, muddy or frozen subgrade.
- C. Protect adjacent work.
- D. Provide temporary barricades, warning lights and signs as required for protection of work and public safety.

1.07 COOPERATION

- A. Examine Drawings and Specifications for all Contracts, to determine nature of proposed construction. Perform work to conform with construction called for in such a manner as not to interfere or delay work of other Contractors.

PRODUCTS

2.01 MATERIALS

- A. Forms: Steel, wood, or other suitable material of sufficient size and strength to resist movement during concrete placement and to retain horizontal and vertical alignment until removal. Use straight forms, free of distortion, defects and of height equal to full depth of concrete work.
 - 1. Use flexible spring steel forms or laminated boards to form radius bends as required.

- B. Coat forms with a nonstaining form release agent that will not discolor or deface surface of concrete.
- C. Welded Wire Mesh: Welded plain cold-drawn steel wire fabric, ASTM A 185. Refer to Division 3 Section "Concrete Reinforcing".
 - 1. Furnish in flat sheets, not rolls, unless otherwise acceptable to Architect.
- D. Joint Dowel Bars: Plain steel bars, ASTM A 615, Grade 60. Cut bars true to length with ends square and free of burrs.
- E. Hook Bolts: ASTM A 307, Grade A bolts, internally and externally threaded. Design hook bolt joint assembly to hold coupling against pavement form and in position during concreting operations, and to permit removal without damage to concrete or hook bolt.
- F. Concrete Materials: Comply with requirements of applicable Division 3 sections for concrete materials, admixtures, bonding materials, curing materials, and others as required.
 - 1. Minimum compressive strength of 4000 psi at 28 days, 6 percent (plus or minus 1 percent) air entrained unless otherwise indicated.
- G. Expansion Joint Materials; Comply with requirements of the following for preformed expansion joint fillers and sealers:
 - 1. Fillers: Preformed expansion joint fillers conforming to ASTM D-1752, 1/2" thickness. Filler material(s) selected must be compatible with sealant(s) to be used when applicable, and suitable for intended use.
 - 2. Sealants: Meeting requirements of ASTM C920, Type M, Grade P or NS as required by application, Class 25, Use T, Color: gray, unless otherwise indicated.
- H. Antispalling Compound: Combination of boiled linseed oil and mineral spirits, complying with AASHTO M-223.
- I. Liquid-Membrane Forming and Sealing Curing Compound: Comply with ASTM C 309, Type I, Class A unless other type acceptable to Architect. Mixture loss no more than 0.055 gr./sq. cm. when applied at 200 sq. ft./gal.
 - 1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work include, but are not limited to, the following:
 - a. "Masterseal"; Master Builders.
 - b. "A-H 3 Way Sealer"; Anti-Hydro Waterproofing Co.
 - c. "Ecocure"; Euclid Chemical Co.
 - d. "Clear Seal"; A.C. Horn.
 - e. "J-20 Acrylic Cure"; Dayton Superior.
 - f. "Sure Cure"; Kaufman Products Inc.
 - g. "AR-30"; W.R. Meadows.
 - h. "Spartan-Cote"; The Burke Co.
 - i. "Sealkure"; Toch Div. - Carboline.
 - j. "Kure-N-Seal"; Sonneborn-Contech.
 - k. "Polyclear"; Upco Chemical/USM Corp.
 - l. "L&M Cure"; L & M Construction Chemicals.
 - m. "Klearseal"; Setcon Industries.
 - n. "LR-152; Protex Industries.
 - o. "Hardtop"; Gifford - Hill.
- J. Bonding Compound: Polyvinyl acetate or acrylic base, rewettable type.
 - 1. Products: Subject to compliance with requirements, provide one of the following:
 - a. "J-40 Bonding Agent"; Dayton Superior Corp.
 - b. "Weldcrete"; Larsen Products.
 - c. "Intralok"; W.R. Meadows.
 - d. "Everbond"; L & M Construction Chemicals.
 - e. "Euroweld"; Euclid Chemical Co.
 - f. "Hornweld"; A. C. Horn.

- g. "Sonocrete"; Sonneborn-Contech.
- h. "Acrylic Bondcrete"; The Burke Co.
- K. Epoxy Adhesive: ASTM C 881, 2-component material suitable for use on dry or damp surfaces. Provide material "Type", "Grade", and "Class" to suit project requirements.
 - 1. Available Products: Subject to compliance with requirements, products which may be incorporated in the work, include, but are not limited to the following:
 - a. "Epoxite", A. C. Horn.
 - b. "Edoco 2118 Epoxy Adhesive"; Edoco Technical Prod.
 - c. "Sikadur Hi-Mod"; Sika Chemical Co.
 - d. "Euco Epoxy 463 or 615"; Euclid Chemical Co.
 - e. "Patch and bond Epoxy"; The burke Co.
 - f. "Sure-Poxy"; Kaufman Products Inc.

EXECUTION

3.01 SUBGRADE PREPARATION: REFER TO SECTION "EARTHWORK".

3.02 FOUNDATION COURSE PLACEMENT: PAVEMENT AND WALKS/PADS

- A. Place and roll in accordance with the "St. Louis County Department of Highways and Traffic Standard Specifications for Highway Construction", Section 304.
- B. Place on dry subgrade in lifts from minimum 6" to maximum 12" for pavement, maximum 6" lifts for walks. Remove all subgrade material churned or mixed with foundation course and replace as necessary at Contractor's expense.
- C. Compaction for foundation course shall be 100 percent of standard proctor maximum density.
- D. Grades for foundation course shall be $\pm .25"$ of required grades.

3.03 FORM CONSTRUCTION

- A. Set forms to required grades and lines, braced and secured. Install forms to allow continuous progress of work and so that forms can remain in place at least 24 hours after concrete placement.
 - 1. Check completed form work for grade and alignment to following tolerances:
 - a. Top of forms not more than 1/8 inch in 10 feet.
 - b. Vertical face on longitudinal axis, not more than 1/4 inch in 10 feet.
 - 2. Clean forms after each use and coat with form release agent as required to ensure separation from concrete without damage.

3.04 REINFORCEMENT

- A. Locate, place, and support reinforcement as specified in Division 3 sections, unless otherwise indicated.
 - 1. Install slip bars at all expansion joints.

3.05 CONCRETE PLACEMENT

- A. General: Comply with requirements of Division 3 sections for mixing and placing concrete, and as herein specified.
- B. Do not place concrete until subbase and forms have been checked for line and grade. Moisten subbase if required to provide a uniform dampened condition at time concrete is placed. Do not place concrete around manholes or other structures until they are at required finish elevation and alignment.
- C. Place concrete by methods that prevent segregation of mix. Consolidate concrete along face of forms and adjacent to transverse joints with internal vibrator. Keep vibrator away from joint assemblies, reinforcement, or side forms. Use only square-faced shovels for hand-spreading and consolidation. Consolidate with care to prevent dislocation of reinforcing, dowels, and joint devices.
- D. Use bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.

- E. Deposit and spread concrete in a continuous operation between transverse joints as far as possible. If interrupted for more than 1/2 hour, place a construction joint.

3.06 JOINTS

- A. General: Construct expansion, weakened-plane (contraction), and construction joints true to line with face perpendicular to surface of concrete. Construct transverse joints at right angles to the center line, unless otherwise indicated.
 - 1. When joining existing structures, place transverse joints to align with previously placed joints, unless otherwise indicated.
- B. Weakened-Plane (Contraction) Joints: Provide weakened-plane (contraction) joints, sectioning concrete into areas as shown on drawings. Construct weakened-plane joints for a depth equal to at least 1/4 concrete thickness, as follows:
 - 1. Tooled Joints: Form weakened-plane joints in fresh concrete by grooving top portion with a recommended cutting tool and finishing edges with a jointer.
 - 2. Sawed Joints: Form weakened-plane joints with powered saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut joints into hardened concrete as soon as surface will not be torn, abraded, or otherwise damaged by cutting action.
 - 3. Inserts: Use embedded strips of metal or sealed wood to form weakened-plane joints. Set strips into plastic concrete and carefully remove strips after concrete has hardened.
- C. Walks/Pads: Score joints at approximately 5 ft. on center or matching width of walk, unless otherwise noted on Plans. Use tool that produces "V" joint not over 1/4" wide.
- D. Concrete Curbs: Score joints at approximately 5 ft. on center matching, as closely as possible, abutting walk joints. Use tool that produces "V" joint not over 1/4" wide.
- E. Construction Joints: Place construction joints at end of placements and at locations where placement operations are stopped for more than 1/2 hour, except where such placements terminate at expansion joints.
 - 1. Construct joints as shown or, if not shown, use standard metal keyway-section forms.
 - 2. Where load transfer-slip dowel devices are used, install so that one end of each dowel bar is free to move.
- F. Expansion Joints: Provide pre-molded joint filler for expansion joints abutting concrete curbs, catch basins, manholes, inlets, structures, walks, and other fixed objects, unless otherwise indicated.
 - 1. Locate expansion joints in step construction where indicated on Drawings.
 - 2. Locate expansion joints at maximum intervals of 15 ft. on center and at all beginnings and ends of radius at curbs. Match abutting walk expansion joints as much as possible.
 - 3. Locate expansion joints at a maximum of every 225 sq. ft. of drive/pads with a minimum dimension one way between joints of 10 lin. ft.
 - 4. Locate expansion joints at a maximum of 150 sq. ft. of walks/pads, except that maximum dimensions between joints in a linear walk to be no more than 15 ft.
- G. Extend joint fillers full width and depth of joint, not less than 1/2 inch or more than 1 inch below finished surface where joint sealer is indicated. If no joint sealer, place top of joint filler flush with finished concrete surface.
- H. Furnish joint fillers in one-piece lengths for full width being placed wherever possible. Where more than one length is required, lace or clip joint filler sections together.
- I. Protect top edge of joint filler during concrete placement with a metal cap or other temporary material. Remove protection after concrete has been placed on both sides of joint.
- J. Fill joint, with sealant, flush with top surfaces and tool concave, unless otherwise indicated.
- K. Fillers and Sealants: Comply with requirements of applicable Division 7 sections for preparation of joints, materials, installation, and performance.

3.07 FIELD QUALITY CONTROL

- A. Provide field quality control testing and inspection during concrete operations.
- B. Contractor shall provide adequate notice, cooperate with, provide access to the work, obtain samples, and assist test agency and their representatives in execution of their function.
- C. Testing
 - 1. Provide slump test on first load of concrete delivered each day and whenever requested due to changes in consistency or appearance of concrete.
 - 2. Provide air indicator tests and air meter tests for all air-entrained concrete.
 - a. Perform air indicator test with a "Chase" AE 35 or equal air indicator, and air meter test in accordance with ASTM C231 or C173. Test first load of concrete delivered each day.
 - b. Furnish copies of field records and test reports as listed for strength tests.
 - 3. Strength testing:
 - a. Provide 1 set of 3 test specimens for each 50 cu. yd. placed in any one day. Secure samples in accordance with ASTM C172 and mold specimens in accordance with ASTM C31.
 - b. Test 1 specimen at 7 days and 2 specimens at 28 days in accordance with ASTM C39.
 - c. Furnish copies of field records and test reports as follows:
 - (1) 2 copies to Architect
 - (2) 1 copy to Contractor
 - (3) 1 copy to Ready Mix Supplier
 - (4) 1 copy to Engineer
 - d. Record the exact location of the concrete in the work represented by each set of cylinders and show on test reports.
 - e. Provide an insulated moist box for protection of the test cylinders until shipped to the laboratory.
- D. Finishing and Sealing - See Division 3. Screed to grade and wood float, edge all sides, fine broom finish (except where otherwise indicated) and seal.

3.08 CONCRETE FINISHING

- A. After striking-off and consolidating concrete, smooth surface by screeding and floating. Use hand methods only where mechanical floating is not possible. adjust floating to compact surface and produce uniform texture.
- B. After floating, test surface for trueness with a 10-ft. straightedge. Distribute concrete as required to remove surface irregularities, and refloat repaired areas to provide a continuous smooth finish.
- C. Work edges of slabs, gutters, back top edge of curb, and formed joints with an edging tool, and round to 1/2-inch radius, unless otherwise indicated. Eliminate tool marks on concrete surface.
- D. After completion of floating and when excess moisture or surface sheen has disappeared, complete troweling and finish surface as follows:
 - 1. All flat work to receive a fine broom finish by drawing a fine-hair broom across concrete surface perpendicular to line of traffic. Repeat operation if required to provide a fine line texture acceptable to Architect.
 - a. On inclined slab surfaces, provide a coarse, non-slip finish by scoring surface with a stiff-bristled broom perpendicular to line of traffic.
 - 2. Burlap finish by dragging a seamless strip of damp burlap across concrete, perpendicular to line of traffic. Repeat operation to provide a gritty texture acceptable to Architect.

3.09 CURING

- A. Protect and cure finished concrete paving in compliance with applicable requirements of Division 3 sections. Use membrane-forming curing and sealing compound or approved moist-curing methods.
- B. Antispalling Treatment: Apply treatment where required to concrete surfaces no sooner than 28 days after placement, to clean, dry concrete free of oil, dirt, and other foreign material. Apply curing and sealing compound at a maximum coverage rate of 300 s.f. per gallon. Apply antispalling

compound in 2 sprayed applications. First application at rate of 40 sq. yds. per gal.; second application, 60 sq. yds. per gallon. Allow complete drying between applications.

3.10 PAINTING OF PAVEMENT MARKINGS

- A. Over clean, dry bituminous pavement, following application and curing of sealer, apply parking line stripes and other pavement markings as indicated, per manufacturer's recommendations.
- B. Apply by brush or zone marking equipment, one coat.

3.11 REPAIRS AND PROTECTIONS

- A. Repair or replace broken or defective concrete, as directed by Architect.
- B. Drill test cores where directed by Architect when necessary to determine magnitude of cracks or defective areas. Fill drilled core holes in satisfactory pavement areas with portland cement concrete bonded to pavement with epoxy adhesive.
- C. Protect concrete from damage until acceptance of work. Exclude traffic from pavement for at least 14 days after placement. When construction traffic is permitted, maintain pavement as clean as possible by removing surface stains and spillage of material as they occur.
- D. Sweep concrete pavement and wash free of stains, discolorations, dirt, and other foreign material just before final inspection.

END OF SECTION

SECTION 32 17 23.13
PAINTED PAVEMENT MARKINGS

GENERAL

1.01 SECTION INCLUDES

- A. Parking lot markings, including parking bays, crosswalks, arrows, handicapped symbols, and curb markings.
- B. Roadway lane markings and crosswalk markings.
- C. "No Parking" curb painting.

1.02 RELATED REQUIREMENTS

- A. Section 32 1216 - Asphalt Paving.
- B. Section 32 1313 - Concrete Paving.

1.03 REFERENCE STANDARDS

- A. FS TT-B-1325 - Beads (Glass Spheres); Retro-Reflective; Rev. D, 2007.
- B. FS TT-P-1952 - Paint, Traffic Black, and Airfield Marking, Waterborne; Rev. E, 2007.
- C. MPI (APL) - Master Painters Institute Approved Products List; Master Painters and Decorators Association; current edition, www.paintinfo.com.
- D. FHWA MUTCD - Manual on Uniform Traffic Control Devices for Streets and Highways; U.S. Department of Transportation, Federal Highway Administration; <http://mutcd.fhwa.dot.gov>; current edition.

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Product Data: Manufacturer's data sheets on each product to be used, including:
 - 1. Preparation instructions and recommendations.
 - 2. Storage and handling requirements and recommendations.
 - 3. Installation methods.
- C. Certificates: Submit for each batch of paint and glass beads stating compliance with specified requirements.
- D. Maintenance Materials: Furnish the following for owner's use in maintenance of project.
 - 1. See Section 01 6000 - Product Requirements, for additional provisions.
 - 2. Extra Paint: 2 containers, 1 gallon (4 liter) size, of each type and color.

1.05 DELIVERY, STORAGE, AND HANDLING

- A. Deliver paint in containers of at least 5 gallons (18 L) accompanied by batch certificate.
- B. Deliver glass beads in containers suitable for handling and strong enough to prevent loss during shipment accompanied by batch certificate.
- C. Store products in manufacturer's unopened packaging until ready for installation.
- D. Store and dispose of solvent-based materials, and materials used with solvent-based materials, in accordance with requirements of local authorities having jurisdiction.

1.06 FIELD CONDITIONS

- A. Do not install products under environmental conditions outside manufacturer's absolute limits.

PRODUCTS

2.01 MATERIALS

- A. Line and Zone Marking Paint: MPI No. 97 Latex Traffic Marking Paint; color(s) as indicated.
 - 1. Roadway Markings: As required by authorities having jurisdiction.

2. Parking Lots: Yellow.
 3. Handicapped Symbols: Blue.
 4. Traffic marking paint by Sherwin Williams; Traffic Paint by Pratt and Lambert, Inc.; Hi-Hide Plexi-color line paint by California Products Corporation, or approved equal.
 5. Substitutions: See Section 01 6000 - Product Requirements.
- B. Line and Zone Marking Paint: Refer to Section 09 9000.
- C. Paint For Obliterating Existing Markings: FS TT-P-1952; black for bituminous pavements, gray for portland cement pavements.
1. Contractor to provide product in compliance with municipal or county Public Works Department
- D. Reflective Glass Beads: FS TT-B-1325, Type I (low index of refraction), Gradation A (coarse, drop-on); with silicone or other suitable waterproofing coating to ensure free flow.
1. Contractor to provide product in compliance with municipal or county Public Works Department
- E. Temporary Marking Tape: Preformed, reflective, pressure sensitive adhesive tape in color(s) required; Contractor is responsible for selection of material of sufficient durability as to perform satisfactorily during period for which its use is required.

EXECUTION

3.01 EXAMINATION

- A. Do not begin installation until substrates have been properly prepared.
- B. If substrate preparation is the responsibility of another installer, notify Architect of unsatisfactory preparation before proceeding.

3.02 PREPARATION

- A. Allow new pavement surfaces to cure for a period of not less than 14 days before application of marking materials.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Obliteration of existing markings using paint is acceptable in lieu of removal; apply the black paint in as many coats as necessary to completely obliterate the existing markings.
- D. Clean surfaces thoroughly prior to installation.
 1. Remove dust, dirt, and other granular surface deposits by sweeping, blowing with compressed air, rinsing with water, or a combination of these methods.
 2. Completely remove rubber deposits, existing paint markings, and other coatings adhering to the pavement, by scraping, wire brushing, sandblasting, mechanical abrasion, or approved chemicals.
 3. Sandblasting: Use equipment of size and capacity necessary, providing not less than 150 cfm (0.08 cu m per second) of air at pressure not less than 90 psi (625 kPa) at each nozzle used.
- E. Where oil or grease are present, scrub affected areas with several applications of trisodium phosphate solution or other approved detergent or degreaser, and rinse thoroughly after each application; after cleaning, seal oil-soaked areas with cut shellac to prevent bleeding through the new paint.
- F. Establish survey control points to determine locations and dimensions of markings; provide templates to control paint application by type and color at necessary intervals.
- G. Temporary Pavement Markings: When required or directed by Architect, apply temporary markings of the color(s), width(s) and length(s) as indicated or directed.
 1. After temporary marking has served its purpose, remove temporary marking by carefully controlled sandblasting, approved grinding equipment, or other approved method so that

- surface to which the marking was applied will not be damaged.
2. At Contractor's option, temporary marking tape may be used in lieu of temporary painted marking; remove unsatisfactory tape and replace with painted markings at no additional cost to owner.

3.03 INSTALLATION

- A. Begin pavement marking as soon as practicable after surface has been cleaned and dried.
- B. Do not apply paint if temperature of surface to be painted or the atmosphere is less than 50 degrees F (10 degrees C) or more than 95 degrees F (35 degrees C).
- C. Apply in accordance with manufacturer's instructions using an experienced technician that is thoroughly familiar with equipment, materials, and marking layouts.
- D. Comply with FHWA MUTCD manual (<http://mutcd.fhwa.dot.gov>) for details not shown.
- E. Apply markings in locations determined by measurement from survey control points; preserve control points until after markings have been accepted.
- F. Apply uniformly painted markings of color(s), lengths, and widths as indicated on the drawings true, sharp edges and ends.
 1. Apply paint in one coat only.
 2. Wet Film Thickness: 0.015 inch (0.4 mm), minimum.
 3. Length Tolerance: Plus or minus 3 inches (75 mm).
 4. Width Tolerance: Plus or minus 1/8 inch (3 mm).
- G. Roadway Traffic Lanes: Use suitable mobile mechanical equipment that provides constant agitation of paint and travels at controlled speeds.
 1. Conduct operations in such a manner that necessary traffic can move without hindrance.
 2. Place warning signs at the beginning of the wet line, and at points well in advance of the marking equipment for alerting approaching traffic from both directions. Place small flags or other similarly effective small objects near freshly applied markings at frequent intervals to reduce crossing by traffic.
 3. If paint does not dry within expected time, discontinue paint operations until cause of slow drying is determined and corrected.
 4. Skip Markings: Synchronize one or more paint "guns" to automatically begin and cut off paint flow; make length of intervals as indicated.
 5. Use hand application by pneumatic spray for application of paint in areas where a mobile paint applicator cannot be used.
 6. Distribute glass beads uniformly on the paint lines within ten seconds without any waste, applied at rate of 6 pounds per gallon (720 g per L) of paint; if the marking equipment does not have a glass bead dispenser, use a separate piece of equipment adjusted and synchronized with the paint applicator; remove and replace markings having faulty distribution of beads.
- H. Parking Lots: Apply parking space lines, entrance and exit arrows, painted curbs, and other markings indicated on drawings.
 1. Mark the International Handicapped Symbol at indicated parking spaces.
 2. Hand application by pneumatic spray is acceptable.
- I. Symbols: Use a suitable template that will provide a pavement marking with true, sharp edges and ends, of the design and size indicated.

3.04 DRYING, PROTECTION, AND REPLACEMENT

- A. Protect newly painted markings so that paint is not picked up by tires, smeared, or tracked.
- B. Provide barricades, warning signs, and flags as necessary to prevent traffic crossing newly painted markings.
- C. Allow paint to dry at least the minimum time specified by the applicable paint standard and not less than that recommended by the manufacturer.

- D. Remove and replace markings that are applied at less than minimum material rates; deviate from true alignment; exceed length and width tolerances; or show light spots, smears, or other deficiencies or irregularities.
- E. Remove markings in manner to avoid damage to the surface to which the marking was applied, using carefully controlled sand blasting, approved grinding equipment, or other approved method.
- F. Replace removed markings at no additional cost to the owner.

END OF SECTION

SECTION 32 31 13
CHAIN LINK FENCES AND GATES

GENERAL

1.01 SECTION INCLUDES

- A. Fence framework, fabric, and accessories.
- B. Excavation for post bases; concrete foundation for posts.
- C. Manual gates and related hardware.

1.02 RELATED REQUIREMENTS

- A. Section 03 30 00 - Cast-in-Place Concrete: Concrete anchorage for posts.
- B. Section 08 71 00 - Door Hardware: Gate locking device.
- C. Section 33 79 00 - Site Grounding.

1.03 PRICE AND PAYMENT PROCEDURES

- A. Fences will be provided by the unit price method.
- B. See Section 01 22 00 - Unit Prices, for additional unit price requirements.
- C. Fencing: Measurement and payment by the linear foot, to the fence height specified, based on the specified post spacing. Includes posts, rails, tension wire, fabric, accessories, attachments.
- D. Post Footings: Measurement and payment by each unit of footing, to the depth specified. Includes excavation, concrete placed, finishing.
- E. Gates: Measurement and payment by the square foot. Includes frame posts, fabric, accessories, hardware.

1.04 REFERENCE STANDARDS

- A. ASTM A121 - Standard Specification for Metallic-Coated Carbon Steel Barbed Wire; 2013.
- B. ASTM A123/A123M - Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products; 2013.
- C. ASTM A153/A153M - Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware; 2009.
- D. ASTM A392 - Standard Specification for Zinc-Coated Steel Chain-Link Fence Fabric; 2011a.
- E. ASTM A428/A428M - Standard Test Method for Weight (Mass) of Coating on Aluminum-Coated Iron or Steel Articles; 2010.
- F. ASTM A491 - Standard Specification for Aluminum-Coated Steel Chain-Link Fence Fabric; 2011.
- G. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2013.
- H. ASTM A1011/A1011M - Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, and Ultra-High Strength; 2013.
- I. ASTM C94/C94M - Standard Specification for Ready-Mixed Concrete; 2013.
- J. ASTM F567 - Standard Practice for Installation of Chain-Link Fence; 2011.
- K. ASTM F668 - Standard Specification for Polyvinyl Chloride (PVC) and Other Organic Polymer-Coated Steel Chain-Link Fence Fabric; 2011.
- L. ASTM F1043 - Standard Specification for Strength and Protective Coatings on Steel Industrial Chain Link Fence Framework; 2012.
- M. ASTM F1083 - Standard Specification for Pipe, Steel, Hot-Dipped Zinc-Coated (Galvanized) Welded, for Fence Structures; 2010.

- N. ASTM F1665 - Standard Specification for Poly(Vinyl Chloride)(PVC) and Other Conforming Organic Polymer-Coated Steel Barbed Wire Used with Chain-Link Fence; 2008 (Reapproved 2013).
- O. CLFMI CLF 2445 - Product Manual; Chain Link Fence Manufacturers Institute; 1997.

1.05 SUBMITTALS

- A. See Section 01 30 00 - Administrative Requirements, for submittal procedures.
- B. Product Data: Provide data on fabric, posts, accessories, fittings and hardware.
- C. Shop Drawings: Indicate plan layout, spacing of components, post foundation dimensions, hardware anchorage, and schedule of components.
- D. Samples: Submit two samples of fence fabric, slat infill, 12 inch by 12 inch in size illustrating construction and colored finish.
- E. Manufacturer's Installation Instructions: Indicate installation requirements, post foundation anchor bolt templates
- F. Project Record Documents: Accurately record actual locations of property perimeter posts relative to property lines and easements.

1.06 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing products specified in this section, with not less than three years of documented experience.

PRODUCTS

2.01 MANUFACTURERS

- A. Chain Link Fences and Gates:
 - 1. Master-Halco, Inc.; www.fenceonline.com.
 - 2. Merchants Metals; www.merchantsmetals.com.
 - 3. Substitutions: See Section 01 60 00 - Product Requirements.

2.02 MATERIALS AND COMPONENTS

- A. Materials and Components: Conform to CLFMI Product Manual.
- B. Fabric Size: CLFMI Heavy Industrial service.
- C. Intermediate Posts: Type I round.
- D. Terminal, Corner, Rail, Brace, and Gate Posts: Type I round.

2.03 MATERIALS

- A. Posts, Rails, and Frames: ASTM F1083 Schedule 40 hot-dipped galvanized steel pipe, welded construction, minimum yield strength of 30 ksi.
- B. Posts, Rails, and Frames: ASTM A1011/A1011M, Designation SS; hot-rolled steel strip, cold formed to pipe configuration, longitudinally welded construction, minimum yield strength of 50 ksi; zinc coating conforming to ASTM F1043 Type B on pipe exterior and interior.
- C. Posts, Rails, and Frames: Formed from hot-dipped galvanized steel sheet, ASTM A653/A653M, HSLAS, Grade 50, with G90 (Z275) zinc coating.
- D. Wire Fabric: ASTM A392 zinc coated steel chain link fabric.
- E. Barbed Wire: Zinc-coated steel, complying with ASTM A121 Type Z Coating Class 1; 2 strands of 0.099 inch diameter wire, with 2-pointed barbs at 4 inches on center.
- F. Barbed Wire: Aluminum-coated steel, complying with ASTM A121; 2 strands of 0.099 inch diameter wire, with 4-pointed barbs at 3 inches on centers.
- G. Barbed Wire: PVC-coated steel, complying with ASTM F1665; 2 strands of 0.099 inch diameter wire, with 2-pointed barbs at 4 inches on center.
- H. Barbed Tape: Stainless steel, 0.025 inch thick x 1 inch wide, coil diameter of 24 inch, die stamped to produce 4 barbed points at 4 inch on center; cold clench over stainless steel core.

- I. Concrete: Type specified in Section 03 30 00.
- J. Concrete: Ready-mixed, complying with ASTM C94/C94M; normal Portland cement; 2,500 psi strength at 28 days, 3 inch slump; 1/4 inch nominal size aggregate.

2.04 COMPONENTS

- A. Line Posts: 1.9 inch diameter.
- B. Corner and Terminal Posts: 2.38 inch.
- C. Gate Posts: 3.5 inch diameter.
- D. Top and Brace Rail: 1.66 inch diameter, plain end, sleeve coupled.
- E. Gate Frame: 1.66 inch diameter for welded fabrication.
- F. Fabric: 2 inch diamond mesh interwoven wire, 6 gage thick, top selvage knuckle end closed, bottom selvage twisted tight.
- G. Tension Wire: 6 gage thick steel, single strand.
- H. Tension Band:
- I. Tension Strap:
- J. Tie Wire: Aluminum alloy steel wire.

2.05 ACCESSORIES

- A. Caps: Cast steel galvanized; sized to post diameter, set screw retainer.
- B. Fittings: Sleeves, bands, clips, rail ends, tension bars, fasteners and fittings; steel.
- C. Extension Arms: Cast steel galvanized, to accommodate 3 strands of barbed wire, single arm, vertical.
- D. Hardware for Single Swinging Gates: 180 degree hinges, 2 for gates up to 60 inches high, 3 for taller gates; fork latch with gravity drop and padlock hasp; keeper to hold gate in fully open position.
- E. Hardware for Double Swinging Gates: 180 degree hinges, 2 for gates up to 60 inches high, 3 for taller gates; drop bolt on inactive leaf engaging socket stop set in concrete, active leaf latched to inactive leaf preventing raising of drop bolt, padlock hasp; keepers to hold gate in fully open position.
- F. Privacy Slats: Vinyl strips, sized to fit fabric weave.

2.06 FINISHES

- A. Components (Other than Fabric): Galvanized in accordance with ASTM A123/A123M, at 1.7 oz/sq ft.
- B. Components (Other than Fabric): Aluminum coated at 0.40 oz/sq ft, when measured in accordance with ASTM A428/A428M.
- C. Components and Fabric: Vinyl coated over coating of 1.8 oz/sq ft galvanizing.
- D. Hardware: Hot-dip galvanized to weight required by ASTM A153/A153M.
- E. Accessories: Same finish as framing.
- F. Color(s): To be selected by Architect from manufacturer's standard range.
- G. Color(s): Medium green.

EXECUTION

3.01 INSTALLATION

- A. Install framework, fabric, accessories and gates in accordance with ASTM F567.
- B. Place fabric on outside of posts and rails.
- C. Set intermediate posts plumb, in concrete footings with top of footing 2 inches above finish grade. Slope top of concrete for water runoff.

- D. Line Post Footing Depth Below Finish Grade: ASTM F567.
- E. Corner, Gate and Terminal Post Footing Depth Below Finish Grade: ASTM F567.
- F. Brace each gate and corner post to adjacent line post with horizontal center brace rail and diagonal truss rods. Install brace rail one bay from end and gate posts.
- G. Provide top rail through line post tops and splice with 6 inch long rail sleeves.
- H. Install center brace rail on corner gate leaves.
- I. Do not stretch fabric until concrete foundation has cured 28 days.
- J. Stretch fabric between terminal posts or at intervals of 100 feet maximum, whichever is less.
- K. Position bottom of fabric 2 inches above finished grade.
- L. Fasten fabric to top rail, line posts, braces, and bottom tension wire with tie wire at maximum 15 inches on centers.
- M. Attach fabric to end, corner, and gate posts with tension bars and tension bar clips.
- N. Install bottom tension wire stretched taut between terminal posts.
- O. Install support arms sloped inward and attach barbed wire; tension and secure.
- P. Do not attach the hinged side of gate to building wall; provide gate posts.
- Q. Install gate with fabric and barbed wire overhang to match fence. Install hardware.
- R. Provide concrete center drop to footing depth and drop rod retainers at center of double gate openings.
- S. Ground fence in accordance with Section 33 79 00.
- T. Install gate locking device specified in Section 08 71 00 - Door Hardware.

3.02 TOLERANCES

- A. Maximum Variation From Plumb: 1/4 inch.
- B. Maximum Offset From True Position: 1 inch.
- C. Components shall not infringe adjacent property lines.

3.03 SCHEDULES

END OF SECTION

SECTION 32 32 23
SEGMENTAL RETAINING WALL SYSTEMS

GENERAL

1.01 DESCRIPTION

- A. Work includes furnishing and installing segmental retaining wall (SRW) units to the lines and grades designated on the project's final construction drawings or as directed by the Architect/Engineer. Also included are furnishing and installing appurtenant materials required for construction of the retaining wall as shown on the construction drawings.

1.02 REFERENCE STANDARDS

- A. Segmental Retaining Wall Units
 - 1. ASTM C 1372 – Standard Specification for Segmental Retaining Wall Units.
 - 2. ASTM C 140 - Standard Test Methods of Sampling and Testing Concrete Masonry Units
- B. Geosynthetic Reinforcement
 - 1. ASTM D 4595 - Tensile Properties of Geotextiles by the Wide-Width Strip Method
 - 2. ASTM D 5262 - Test Method for Evaluating the Unconfined Creep Behavior of Geosynthetics
 - 3. GRI:GG1 – Single-Rib Geogrid Tensile Strength
 - 4. GRI:GG5 - Geogrid Pullout
- C. Soils
 - 1. ASTM D 698 - Moisture Density Relationship for Soils, Standard Method
 - 2. ASTM D 422 - Gradation of Soils
 - 3. ASTM D 424 - Atterberg Limits of Soil
- D. Drainage Pipe
 - 1. ASTM D 3034 - Specification for Polyvinyl Chloride (PVC) Plastic Pipe
 - 2. ASTM D 1248 - Specification for Corrugated Plastic Pipe
- E. Engineering Design
 - 1. "NCMA Design Manual for Segmental Retaining Walls," Second Edition
- F. Where specifications and reference documents conflict, the Architect/Engineer shall make the final determination of applicable document.

1.03 SUBMITTALS

- A. Materials Submittals: The Contractor shall submit manufacturers' certifications four weeks prior to start of work stating that the SRW units and geosynthetic reinforcement meet the requirements of Section 2 of this specification. The contractor is also required to obtain written approval from the architect on the type, style and color of block to be used.
- B. Design Submittal: The Contractor shall submit two sets of detailed design calculations and final retaining wall plans for approval at least four weeks prior to the beginning of wall construction. All calculations and drawings shall be prepared and sealed by a professional Civil Engineer (P.E.) – (Wall Design Engineer) experienced in SRW design and licensed in the state where the wall is to be built.

1.04 DELIVERY, STORAGE AND HANDLING

- A. Contractor shall check materials upon delivery to assure that specified type and grade of materials have been received and proper color and texture of SRW units have been received.
- B. Contractor shall prevent excessive mud, wet concrete, epoxies and like materials that may affix themselves from coming in contact with materials.
- C. Contractor shall store and handle materials in accordance with manufacturer's recommendations.

- D. Contractor shall protect materials from damage. Damaged materials shall not be incorporated into the retaining wall.

MATERIALS

2.01 SEGMENTAL RETAINING WALL UNITS

- A. SRW units shall be machine formed, Portland cement concrete blocks specifically designed for retaining wall applications. SRW units shall be VERSA-LOK or pre-approved equal. Contractor is required to obtain written approval from the architect on the type, style, and color of block to be used.
- B. Color of SRW units shall be approved by architect.
- C. Finish of SRW units shall be split-face or as directed by architect.
- D. SRW unit faces shall be of straight geometry or as directed by architect.
- E. SRW unit height shall be 6 inches minimum. Final block type, style and color to be pre-approved by architect. Contractor required to obtain approval in writing.
- F. SRW units (not including aggregate fill in unit voids) shall provide a minimum weight of 105 psf wall face area.
- G. SRW units shall be solid through the full depth of the unit.
- H. SRW units shall have a depth (front face to rear) to height ratio of 2:1, minimum.
- I. SRW units shall be interlocked with connection pins, designed with proper setback to provide 8:1 vertical-to-horizontal batter (a 7-degree cant from vertical).
- J. SRW units shall be capable of being erected with the horizontal gap between adjacent units not exceeding 1/8 inch.
- K. SRW units shall be capable of providing overlap of units on each successive course so that walls meeting at corner are interlocked and continuous. SRW units that require corners to be mitered shall not be allowed.
- L. SRW units shall be capable of providing a split-face, textured surface for all vertical surfaces that will be exposed after completion of wall, including any exposed sides and backs of units.
- M. SRW units shall be sound and free of cracks or other defects that would interfere with the proper placing of the unit or significantly impair the strength or permanence of the structure. Cracking or excessive chipping may be grounds for rejection. Units showing cracks longer than 1/2 inch shall not be used within the wall. Units showing chips visible at a distance of 30 feet from the wall shall not be used within the wall.
- N. Concrete used to manufacture SRW units shall have a minimum 28 days compressive strength of 3,000 psi and a maximum moisture absorption rate, by weight, of 8% as determined in accordance with ASTM C1372. Compressive strength test specimens shall conform to the saw-cut coupon provisions of ASTM C140.
- O. SRW units' molded dimensions shall not differ more than + 1/8 inch from that specified, in accordance with ASTM C1372.

2.02 SEGMENTAL RETAINING WALL UNIT CONNECTION PINS

- A. SRW units shall be interlocked with VERSA-Tuff connection pins. The pins shall consist of glass-reinforced nylon made for the expressed use with the SRW units supplied.

2.03 GEOSYNTHETIC REINFORCEMENT

- A. Geosynthetic reinforcement shall consist of geogrids or geotextiles manufactured as a soil reinforcement element. The manufacturers/suppliers of the geosynthetic reinforcement shall have demonstrated construction of similar size and types of segmental retaining walls on previous projects.

The geosynthetic type must be approved one week prior to bid opening.

- B. The type, strength and placement location of the reinforcing geosynthetic shall be as

determined by the Wall Design Engineer, as shown on the final, P.E.-sealed retaining wall plans.

2.04 LEVELING PAD

- A. Material for leveling pad shall consist of compacted sand, gravel, or combination thereof (USCS soil types GP, GW, SP, & SW) and shall be a minimum of 6 inches in depth. Lean concrete with a strength of 200-300 psi and 3 inches thick maximum may also be used as a leveling pad material. The leveling pad should extend laterally at least a distance of 6 inches from the toe and heel of the lowermost SRW unit.

2.05 DRAINAGE AGGREGATE

- A. Drainage aggregate shall be angular, clean stone or granular fill meeting the following gradation as determined in accordance with ASTM D422

<u>Sieve Size</u>	<u>Percent Passing</u>
1 inch	100
3/4 inch	75-100
No. 4	0-60
No. 40	0-50
No. 200	0-5

2.06 DRAINAGE PIPE

- A. The drainage collection pipe shall be a perforated or slotted PVC, or corrugated HDPE pipe. The drainage pipe may be wrapped with a geotextile to function as a filter.
- B. Drainage pipe shall be manufactured in accordance with ASTM D 3034 and/or ASTM D 1248.

2.07 REINFORCED (INFILL) SOIL

- A. The reinforced soil material shall be free of debris. Unless otherwise noted on the final, P.E.-sealed, retaining wall plans prepared by the Wall Design Engineer, the reinforced material shall consist of the inorganic USCS soil types GP, GW, SW, SP, SM, meeting the following gradation, as determined in accordance with ASTM D422:

<u>Sieve Size</u>	<u>Percent Passing</u>
4 inch	100
No. 4	20-100
No. 40	0-60
No. 200	0-35

- B. The maximum particle size of poorly-graded gravels (GP) (no fines) should not exceed 3/4 inch unless expressly approved by the Wall Design Engineer and the long-term design strength (LTDS) of the geosynthetic is reduced to account for additional installation damage from particles larger than this maximum.
- C. The plasticity of the fine fraction shall be less than 20.

DESIGN PARAMETERS

3.01 SOIL

- A. The soil parameters shall be as determined by the Owner's Geotechnical Engineer.
- B. Should the actual soil conditions observed during construction differ from those assumed for the design, design shall be reviewed by the Wall Design Engineer at the Owner's Geotechnical Engineer's direction.

3.02 DESIGN

- A. The design analysis for the final, P.E.-sealed retaining wall plans prepared by the Wall Design Engineer shall consider the external stability against sliding and overturning,

internal stability and facial stability of the reinforced soil mass and shall be in accordance with acceptable engineering practice and these specifications. The internal and external stability analysis shall be performed in accordance with the "NCMA Design Manual for Segmental Retaining Walls," using the recommended minimum factors of safety in this manual.

- B. External stability analysis for bearing capacity, global stability, and total and differential settlement shall be the responsibility of the Owner and the Owner's Geotechnical Engineer. Geotechnical Engineer shall perform bearing capacity, settlement estimates, and global stability analysis based on the final wall design provided by the Wall Design Engineer and coordinate any required changes with Wall Design Engineer.
- C. While vertical spacing between geogrid layers may vary, it shall not exceed 2.0 feet maximum in the wall design.
- D. The geosynthetic placement in the wall design shall have 100% continuous coverage parallel to the wall face. Gapping between horizontally adjacent layers of geosynthetic (partial coverage) will not be allowed.

CONSTRUCTION

4.01 INSPECTION

- A. The Owner or Owner's Representative is responsible for verifying that the Contractor meets all the requirements of the specification. This includes all submittals for materials and design, qualifications, and proper installation of wall system.
- B. Contractor's field construction supervisor shall have demonstrated experience and be qualified to direct all work at the site.

4.02 EXCAVATION

- A. Contractor shall excavate to the lines and grades shown on the project grading plans. Contractor shall take precautions to minimize over-excavation. Over-excavation shall be filled with compacted infill material, or as directed by the Engineer/Architect, at the Contractor's expense.
- B. Contractor shall verify location of existing structures and utilities prior to excavation. Contractor shall ensure all surrounding structures are protected from the effects of wall excavation. Excavation support, if required, is the responsibility of the Contractor.

4.03 FOUNDATION PREPARATION

- A. Following the excavation, the foundation soil shall be examined by the Owner's Engineer to assure actual foundation soil strength meets or exceeds the assumed design bearing strength. Soils not meeting the required strength shall be removed and replaced with infill soils, as directed by the Owner's Engineer.
- B. Foundation soil shall be proof-rolled and compacted to 95% standard Proctor density and inspected by the Owner's Engineer prior to placement of leveling pad materials.

4.04 LEVELING PAD CONSTRUCTION

- A. Leveling pad shall be placed as shown on the final, P.E.-sealed retaining wall plans with a minimum thickness of 6 inches. The leveling pad should extend laterally at least a distance of 6 inches from the toe and heel of the lowermost SRW unit.
- B. Granular leveling pad material shall be compacted to provide a firm, level bearing surface on which to place the first course of units. Well-graded sand can be used to smooth the top 1/4 inch to 1/2 inch of the leveling pad. Compaction will be with mechanical plate compactors to achieve 95% of maximum standard Proctor density (ASTM D 698).

4.05 SRW UNIT INSTALLATION

- A. All SRW units shall be installed at the proper elevation and orientation as shown on the final, P.E.-sealed wall plans and details or as directed by the Wall Design Engineer. The SRW units shall be installed in general accordance with the manufacturer's recommendations. The specifications and drawings shall govern in any conflict between

the two requirements.

- B. First course of SRW units shall be placed on the leveling pad. The units shall be leveled side-to-side, front-to-rear and with adjacent units, and aligned to ensure intimate contact with the leveling pad. The first course is the most important to ensure accurate and acceptable results. No gaps shall be left between the front of adjacent units. Alignment may be done by means of a string line or offset from base line to the back of the units.
- C. All excess debris shall be cleaned from top of units and the next course of units installed on top of the units below.
- D. Two VERSA-Tuff connection pins shall be inserted through the pin holes of each upper-course unit into receiving slots in lower-course units. Pins shall be fully seated in the pin slot below. Units shall be pushed forward to remove any looseness in the unit-to-unit connection.
- E. Prior to placement of next course, the level and alignment of the units shall be checked and corrected where needed.
- F. Layout of curves and corners shall be installed in accordance with the wall plan details or in general accordance with SRW manufacturer's installation guidelines. Walls meeting at corners shall be interlocked by overlapping successive courses.
- G. Procedures C. through F. shall be repeated until reaching top of wall units, just below the height of the cap units. Geosynthetic reinforcement, drainage materials, and reinforced backfill shall be placed in sequence with unit installation as described in Section 4.06, 4.07 and 4.08.

4.06 GEOSYNTHETIC REINFORCEMENT PLACEMENT

- A. All geosynthetic reinforcement shall be installed at the proper elevation and orientation as shown on the final P.E.-sealed retaining wall plan profiles and details, or as directed by the Wall Design Engineer.
- B. At the elevations shown on the final plans, (after the units, drainage material and backfill have been placed to this elevation) the geosynthetic reinforcement shall be laid horizontally on compacted infill and on top of the concrete SRW units, to within 1 inch of the front face of the unit below. Embedment of the geosynthetic in the SRW units shall be consistent with SRW manufacturer's recommendations. Correct orientation of the geosynthetic reinforcement shall be verified by the Contractor to be in accordance with the geosynthetic manufacturer's recommendations. The highest-strength direction of the geosynthetic must be perpendicular to the wall face.
- C. Geosynthetic reinforcement layers shall be one continuous piece for their entire embedment length. Splicing of the geosynthetic in the design-strength direction (perpendicular to the wall face) shall not be permitted. Along the length of the wall, horizontally adjacent sections of geosynthetic reinforcement shall be butted in a manner to assure 100% coverage parallel to the wall face.
- D. Tracked construction equipment shall not be operated directly on the geosynthetic reinforcement. A minimum of 6 inches of backfill is required prior to operation of tracked vehicles over the geosynthetic. Turning should be kept to a minimum. Rubber-tired equipment may pass over the geosynthetic reinforcement at slow speeds (less than 5 mph).
- E. The geosynthetic reinforcement shall be free of wrinkles prior to placement of soil fill. The nominal tension shall be applied to the reinforcement and secured in place with staples, stakes or by hand tensioning until reinforcement is covered by 6 inches of fill.

4.07 DRAINAGE MATERIALS

- A. Drainage aggregate shall be installed to the line, grades and sections shown on the final P.E.-sealed retaining wall plans. Drainage aggregate shall be placed to the minimum thickness shown on the construction plans between and behind units (a minimum of 1 cubic foot for each exposed square foot of wall face unless otherwise noted on the final wall

plans).

- B. Drainage collection pipes shall be installed to maintain gravity flow of water outside the reinforced-soil zone. The drainage collection pipe shall daylight into a storm sewer or along a slope, at an elevation lower than the lowest point of the pipe within the aggregate drain.

4.08 BACKFILL PLACEMENT

- A. The reinforced backfill shall be placed as shown in the final wall plans in the maximum compacted lift thickness of 10 inches and shall be compacted to a minimum of 95% modified Proctor (ASTM D 1557) maximum dry density at a moisture content within 2% of optimum or as indicated on the wall design drawings. The backfill shall be placed and spread in such a manner as to eliminate wrinkles or movement of the geosynthetic reinforcement and the SRW units.
- B. Only hand-operated compaction equipment shall be allowed within 3 feet of the back of the wall units. Compaction within the 3 feet behind the wall units shall be achieved by at least three passes of a lightweight mechanical tamper, plate, or roller.
- C. At the end of each day's operation, the Contractor shall slope the last level of backfill away from the wall facing and reinforced backfill to direct water runoff away from the wall face.
- D. At completion of wall construction, backfill shall be placed level with final top of wall elevation. If final grading, paving, landscaping and/or storm drainage installation adjacent to the wall is not placed immediately after wall completion, temporary grading and drainage shall be provided to ensure water runoff is not directed at the wall nor allowed to collect or pond behind the wall until final construction adjacent to the wall is completed.

4.09 SRW CAPS

- A. SRW caps shall be properly aligned and glued to underlying units with VERSA-LOK adhesive, a flexible, high-strength concrete adhesive. Rigid adhesive or mortar are not acceptable.
- B. Caps shall overhang the top course of units by 3/4 inch to 1 inch. Slight variation in overhang is allowed to correct alignment at the top of the wall.

4.10 CONSTRUCTION ADJACENT TO COMPLETED WALL

- A. The Owner or Owner's Representative is responsible for ensuring that construction by others adjacent to the wall does not disturb the wall or place temporary construction loads on the wall that exceed design loads, including loads such as water pressure, temporary grades, or equipment loading. Heavy paving or grading equipment shall be kept a minimum of 3 feet behind the back of the wall face. Equipment with wheel loads in excess of 150 psf live load shall not be operated within 10 feet of the face of the retaining wall during construction adjacent to the wall. Care should be taken by the General Contractor to ensure water runoff is directed away from the wall structure until final grading and surface drainage collection systems are completed.

END OF SECTION

SECTION 33 11 16
SITE WATER UTILITY DISTRIBUTION PIPING

This Section uses the term "Architect." Change this term to match that used to identify the design professional as defined in the General and Supplementary Conditions.

GENERAL

1.01 SUMMARY

- A. This Section includes water-distribution piping and specialties outside the building for the following:
 - 1. Water services.
 - 2. Fire-service mains.

1.02 SUBMITTALS

- A. Product Data: For the following:
 - 1. Valves, piping and accessories.
 - 2. Delete water meters below if provided by utility company.
 - 3. Fire hydrants.
 - 4. Fire department connections.
 - 5. Contractor shall submit a letter with product data certifying that all materials are in compliance with governing authority.
- B. Wiring Diagrams: Power, signal, and control wiring.
- C. Field quality-control test reports.
- D. Operation and Maintenance Data: For the following:
 - 1. Valves.
 - 2. Backflow preventers.
 - 3. Protective enclosures.
 - 4. Hydrants.

1.03 QUALITY ASSURANCE

- A. Regulatory Requirements:
 - 1. Comply with requirements of City of Festus Water Department.
 - 2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
 - 3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
 - 4. Comply with requirements of local fire district
- B. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- D. Comply with requirements of governing jurisdiction for fire-service-main products, materials, installations, tests, flushing and all other activities and materials associated with installation.

1.04 PROJECT CONDITIONS

- A. Existing Utilities: Do not interrupt utilities serving facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary utility services according to requirements indicated:
 - 1. Notify Architect not less than five days in advance of proposed utility interruptions.
 - 2. Do not proceed with utility interruptions without Construction Manager's written permission.

1.05 COORDINATION

- A. Coordinate connection to water main with City of Festus Water Department.

PRODUCTS

2.01 MANUFACTURERS

F. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:

1. Available Products: Subject to compliance with requirements of the governing authority(s).
2. Products: Subject to compliance with requirements of the governing authority(s).
3. Manufacturers: Subject to compliance with requirements of the governing authority(s).

2.02 PIPING MATERIALS

A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.

2.03 PIPE AND FITTINGS

A. Regulatory Requirements (subject to requirements of governing jurisdiction):

1. Comply with requirements of City of Festus Water Department
2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
4. Comply with requirements of local fire district where applicable

2.04 JOINING MATERIALS

A. Regulatory Requirements (subject to requirements of governing jurisdiction):

1. Comply with requirements of City of Festus Water Department.
2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
4. Comply with requirements of local fire district where applicable.

2.05 VALVES

A. Regulatory Requirements (subject to requirements of governing jurisdiction):

1. Comply with requirements of City of Festus Water Department.
2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
4. Comply with requirements of local fire district where applicable.

2.06 GATE VALVE ACCESSORIES AND SPECIALTIES

A. Regulatory Requirements (subject to requirements of governing jurisdiction):

1. Comply with requirements of City of Festus Water Department.
2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
4. Comply with requirements of local fire district where applicable.

2.07 BACKFLOW-PREVENTION DEVICES

A. Regulatory Requirements (subject to requirements of governing jurisdiction):

1. Comply with requirements of City of Festus Water Department.
2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
4. Comply with requirements of local fire district where applicable.

2.08 FREESTANDING FIRE HYDRANTS

- A. Regulatory Requirements (subject to requirements of governing jurisdiction)
 - 1. Comply with requirements of City of Festus Water Department.
 - 2. Comply with standards of authorities having jurisdiction for potable-water-service piping, including materials, installation, testing, and disinfection.
 - 3. Comply with standards of authorities having jurisdiction for fire-suppression water-service piping, including materials, hose threads, installation, and testing.
 - 4. Comply with requirements of local fire district where applicable.

EXECUTION

3.01 PIPING INSTALLATION

- B. Water-Main Connection: Tap water main according to requirements of City of Festus Water Department and of size and in location indicated.
- C. Comply with requirements of governing jurisdiction for fire-service-main piping materials and installation.
- D. Bury piping with depth of cover over top at least 42 inches (or as dictated by the governing jurisdiction if more stringent requirement), with top at least 12 inches below level of maximum frost penetration.
- E. Extend water-service piping and connect to water-supply source and building water piping systems at outside face of building wall in locations and pipe sizes indicated.
 - 1. Terminate water-service piping at building wall until building water piping systems are installed. Terminate piping with caps, plugs, or flanges as required for piping material. Make connections to building water piping systems when those systems are installed.

3.02 ANCHORAGE INSTALLATION

- A. Install anchorages for tees, plugs and caps, bends, crosses, valves, and hydrant branches according to the requirement of the governing jurisdiction.

3.03 VALVE INSTALLATION

- A. Comply with the requirements of the governing jurisdiction for means and methods of installation for valves.

3.04 BACKFLOW-PREVENTER INSTALLATION

- A. Install backflow preventers of type, size, and capacity indicated. Include valves and test cocks. Install according to requirements of plumbing and health department and authorities having jurisdiction.
- B. Do not install backflow preventers with relief drain in vault or other space subject to flooding.

3.05 FIRE HYDRANT INSTALLATION

- A. General: Install each fire hydrant with separate gate valve in supply pipe, anchor with restrained joints or thrust blocks, and support in upright position. Contractor shall comply with requirements of governing jurisdiction(s).

3.06 CONNECTION

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping and specialties.
- B. Connect water-distribution piping to existing water main. Contractor to coordinate the tap with City of Festus Water Department.
- C. Connect water-distribution piping to interior domestic-water or fire-suppression piping; see drawings.
- D. Connect waste piping from drinking fountains to sanitary sewerage system. See Section 22 13 13 - "Facility Sanitary Sewers" for connection to sanitary-sewer piping.

3.07 FIELD QUALITY CONTROL

- A. Piping Tests: Conduct piping tests before joints are covered and after thrust blocks have hardened sufficiently. Fill pipeline 24 hours before testing and apply test pressure to stabilize system. Use only potable water.
- B. Hydrostatic Tests: Tests shall be conducted in accordance with the requirements of the governing authority(s).
- C. Prepare reports of testing activities.

END OF SECTION

SECTION 33 13 00
DISINFECTING OF WATER UTILITY DISTRIBUTION

GENERAL

1.01 SECTION INCLUDES

- A. Disinfection of site domestic water lines and site fire water lines specified in Section 33 1116.
- B. Disinfection of building domestic water piping specified in Section 22 1005.
- C. Testing and reporting results.

1.02 RELATED REQUIREMENTS

- A. Section 33 1116 - Site Water Utility Distribution Piping.

1.03 REFERENCE STANDARDS

- A. AWWA B300 - Hypochlorites; American Water Works Association; 2004 (ANSI/AWWA B300).
- B. AWWA B301 - Liquid Chlorine; American Water Works Association; 2004 (ANSI/AWWA B301).
- C. AWWA B302 - Ammonium Sulfate; American Water Works Association; 2005 (ANSI/AWWA B302).
- D. AWWA B303 - Sodium Chlorite; American Water Works Association; 2005.
- E. AWWA C651 - Disinfecting Water Mains; American Water Works Association; 2005 (ANSI/AWWA C651).

1.04 SUBMITTALS

- A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
- B. Test Reports: Indicate results comparative to specified requirements.
- C. Certificate: From authority having jurisdiction indicating approval of water system.
- D. Certificate: Certify that cleanliness of water distribution system meets or exceeds specified requirements.
- E. Disinfection report:
 - 1. Type and form of disinfectant used.
 - 2. Date and time of disinfectant injection start and time of completion.
 - 3. Test locations.
 - 4. Initial and 24 hour disinfectant residuals (quantity in treated water) in ppm for each outlet tested.
 - 5. Date and time of flushing start and completion.
 - 6. Disinfectant residual after flushing in ppm for each outlet tested.
- F. Bacteriological report:
 - 1. Date issued, project name, and testing laboratory name, address, and telephone number.
 - 2. Time and date of water sample collection.
 - 3. Name of person collecting samples.
 - 4. Test locations.
 - 5. Initial and 24 hour disinfectant residuals in ppm for each outlet tested.
 - 6. Coliform bacteria test results for each outlet tested.
 - 7. Certification that water conforms, or fails to conform, to bacterial standards of City of Festus Water Department.

1.05 QUALITY ASSURANCE

- A. Water Treatment Firm: Company specializing in disinfecting potable water systems specified in this Section with minimum three years documented experience.
- B. Testing Firm: Company specializing in testing potable water systems, certified by governing authorities of the State in which the Project is located.

- C. Submit bacteriologist's signature and authority associated with testing.

PRODUCTS

2.01 DISINFECTION CHEMICALS

- A. Chemicals: AWWA B300, Hypochlorite, AWWA B301, Liquid Chlorine, AWWA B302, Ammonium Sulfate, and AWWA B303, Sodium Chlorite.

EXECUTION

3.01 EXAMINATION

- A. Verify that piping system and water well has been cleaned, inspected, and pressure tested.
- B. Schedule disinfecting activity to coordinate with start-up, testing, adjusting and balancing, demonstration procedures, including related systems.

3.02 DISINFECTION

- A. Use method prescribed by the applicable state or local codes, or health authority or water purveyor having jurisdiction, or in the absence of any of these follow AWWA C651.
- B. Provide and attach equipment required to perform the work.
- C. Inject treatment disinfectant into piping system.
- D. Maintain disinfectant in system for 24 hours.
- E. Flush, circulate, and clean until required cleanliness is achieved; use municipal domestic water.
- F. Replace permanent system devices removed for disinfection.
- G. Pressure test system to requirements of City of Festus Water Department specifications. Repair leaks and re-test.

3.03 FIELD QUALITY CONTROL

- A. Perform field inspection and testing in accordance with Section 01 4000.
- B. Test samples in accordance with AWWA C651.

END OF SECTION

SECTION 33 31 00
SITE SANITARY UTILITY SEWERAGE PIPING

GENERAL

1.01 SUMMARY

- A. This Section includes gravity-flow, non-pressure sanitary sewerage outside the building, with the following components:
 - 1. Cleanouts.
 - 2. Pre-cast concrete manholes.
- B. Related Sections: The following sections contain requirements that relate to this Section.
 - 1. Section 31 22 00 - "Grading" for excavating, backfilling and compacting operations required for sanitary sewer work.

1.02 SUBMITTALS

- A. Product Data: Submit complete materials list of items proposed for the work. Submit piping and sewer structures product data.
- B. Shop Drawings: For manholes. Include plans, elevations, sections, details, and frames and covers.
- C. Sanitary Sewer Record Drawings: Legibly mark drawings to record actual construction. Indicate horizontal and vertical locations, referenced to permanent surface improvements. Identify field changes of dimension and detail and changes made by change order.
- D. Certification: For all materials specified to comply with reference standards, submit Certificate of Compliance.

1.03 QUALITY ASSURANCE

- A. Manufacturer's Qualifications: Firms regularly engaged in manufacture of sanitary sewage system's products of types, materials, and sizes required, whose products have been in satisfactory use in similar service for not less than 5 years.
- B. Materials and methods of construction shall comply with the following standards.
 - 1. American Water Works Association, (AWWA).
 - 2. American Society for Testing and Materials, (ASTM).
 - 3. American Association of State Highway and Transportation Officials, (AASHTO).
 - 4. American Concrete Pipe Association, (ACPA).
 - 5. Metropolitan St. Louis Sewer District Standard Construction Specifications for Sewers and Drainage Facilities, 2009 (or latest revision)
 - 6. Comply with all rules, regulations, or ordinances having jurisdiction over this work. In the absence of local codes, comply with the Uniform Plumbing Code.

1.04 DELIVERY, STORAGE AND HANDLING

- A. Deliver, store, and handle piping and accessories to prevent damage and deterioration. Materials shall not be stored directly on the ground. The inside of pipes and fittings shall be kept free of dirt and debris. Gasket materials and plastic materials shall be protected from exposure to the direct sunlight. Storage facilities for plastic pipe, fittings, joint materials and solvents shall be classified and marked in accordance with NFPA No. 704 with classification as indicated in NFPA No. 49 and NFPA No. 325M.

1.05 COORDINATION

- A. Coordinate locations and inverts of sanitary sewer lines at 5' outside building as noted on the plans.

1.06 PROJECT CONDITIONS

- A. Known underground and surface utility lines are indicated on the drawings. Contractor is

responsible for verifying all utility locations shown or not shown.

- B. Protect existing trees, plant, lawns, and other features designated to remain as part of the landscape work.
- C. Barricade open excavations and post warning lights at work adjacent to public streets and walks.
- D. Promptly repair damage to adjacent facilities caused by sanitary sewer earthwork operations. Cost of repair at Contractor's expense.
- E. Promptly notify the owner's representative of unexpected sub-surface conditions.

1.07 COOPERATION

- A. Examine Drawings and Specifications for all Contracts to determine the nature of proposed construction. Perform work to conform with construction called for in such a manner as not to interfere or delay work of other Contractors.

PRODUCTS

2.01 PIPES AND PIPE FITTINGS

- A. General: Provide pipes of one of the following materials, of weight/class indicated. Provide pipe fittings and accessories of same material and weight/class as pipes, with joining method as indicated.
- B. Gravity Sewer Piping:
 - 1. Polyvinyl Chloride (PVC) Pipe: ASTM D3034, Type PSM, SDR 35 (unless otherwise indicated)
- C. Joints for Gravity Sewer Pipings:
 - 1. PVC Pipe: Elastomeric joints complying with ASTM D3212 using elastomeric seals complying with ASTM F477.
- D. Manholes and Cleanouts
- E. Frames and Covers: ASTM A48 gray cast-iron, asphalt coated, with lettering cast into top reading "SANITARY SEWER".
 - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated into the work include, but are not limited to, the following:
 - a. Neenah Foundry Co., Neenah, WI
 - b. McKinley Iron Works, Fort Worth, TX
 - c. Flockhart Foundry Co., Newark, NJ
 - 2. Concrete Masonry Units: ASTM C139.
 - 3. Manhole Brick: ASTM C32, Grade MS.
 - 4. Precast Concrete Manhole Barrels and Cones: ASTM C478, 5" wall thickness with ASTM C443 "O" - ring gasket joints.
 - a. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products which may be incorporated into the work include, but are not limited to the following:
 - (1) Kienstra, Inc., Woodriver, IL
 - (2) Kistner Septic Tank Co., Inc. Cheektowaga, NY
 - (3) Warren Concrete Products, Inc., Warren, PA
 - (4) United States Concrete Pipe Company, Cleveland, Ohio.
 - 5. Mortar
 - a. Mortar for laying and parging concrete masonry: 1 part portland cement and 2 parts sand.
 - b. Mortar for brickwork: 1 part portland cement, 1/2 part hydrated lime, and 4-1/2 parts sand.
 - 6. Manhole Rungs: cast-iron steps.

7. Manhole Drop Assembly: The vertical drop pipe and sweep shall be made from polyvinyl chloride (PVC) sewer pipe and fittings as specified herein. The fitting required for this work shall be molded PVC tees, plugs, and adapters. To the inside end of the tee, a threaded adapter shall be solvent welded, utilizing fresh solvent cement, made by the fittings manufacturer, containing at least 15 percent by weight of the same PVC compound used in making the fittings. Outside drop assemblies shall be encased in concrete as indicated on drawings.
8. Bedding Material: Clean, natural sand conforming to requirements in Section 31 20 00 or minus-fraction crushed stone can be used.
9. Backfill Material: Backfill material shall adhere to the requirements of the local governing agency(s).
10. Pipe Connections: The precast reinforced concrete manhole sections shall be provided with circular openings at the locations and elevations for the proper connection of all pipes. Unless otherwise indicated, all PVC pipe connections shall be sealed with a flexible manhole seal assembly, per ASTM C-923. Flexible manhole seal assemblies shall permit at least an eight (8) degrees deflection from the centerline of the opening in any direction while maintaining a watertight connection.

EXECUTION

3.01 PREPARATION

- A. Permits and Inspections: File all drawings and obtain all necessary permits, licenses, and inspections required by authorities having jurisdiction over the work.
- B. Layout sanitary sewer work and establish extent of excavation by area and elevation. Designate and identify datum elevation and project engineering reference points. Set required lines, levels and elevations.
- C. Do not cover or enclose work of this Section before obtaining required inspections, test approvals and location recording.

3.02 EXISTING UTILITIES

- A. Before starting excavation, establish the location and extent of underground utilities in the work area. Exercise care to protect existing utilities during earthwork operations. Perform excavation work near utilities by hand and provide necessary shoring, sheeting, and supports as work progresses.
- B. Protect active utility services uncovered by excavation.

3.03 HANDLING PIPE

- A. Pipe and accessories shall be handled so as to insure delivery to the trench in sound, undamaged condition. Particular care shall be taken not to injure the pipe coating or lining. If the coating or lining of any pipe or fitting is damaged, the repair shall be made by the Contractor at his expense in a satisfactory manner. No other pipe or material of any kind shall be placed inside a pipe or fitting after the coating has been applied. Pipe shall be carried into position and not dragged. Use of pinch bars and tongs for aligning or turning pipe will be permitted only on the bare ends of the pipe. The interior of pipe and accessories shall be thoroughly cleaned of foreign matter before being lowered into the trench and shall be kept clean during laying operations by plugging or other approved method. Before installation, the pipe shall be inspected for defects. Material found to be defective before or after laying shall be replaced with sound material without additional expense to the Owner. Rubber gaskets that are not to be installed immediately shall be stored in a cool and dark place.

3.04 CUTTING OF PIPE

- A. Cutting of pipe shall be done in a neat and workmanlike manner without damage to the pipe. Cutting shall be done with an approved type mechanical cutter. Wheel cutter shall be used when practicable. Copper tubing shall be cut square and all burrs shall be removed. Squeeze type

mechanical cutters shall not be used for ductile iron.

3.05 LOCATING SEWER LINES NEAR WATER LINES

- A. Where the location of the sewer is not clearly defined by dimensions on the drawings, the sewer shall not be laid closer horizontally than 10 feet from the water pipe except where the bottom of the water pipe will be at least 18" above the top of the sewer pipe, in which case the sewer shall not be laid closer horizontally than 6 feet from the water pipe. Where gravity-flow sewers cross above water lines, the sewer pipe for a distance of at least 10 feet on each side of the crossing shall be fully encased in concrete or shall be made of pressure pipe. The minimum cover of the concrete encasement, including that at the pipe joints, shall not be less than 6" unless otherwise indicated on the drawings. Water and sanitary line crossings shall be at the mid points of full lengths of both pipes.

3.06 SEWER LINES AT STRUCTURES

- A. Where shown on the drawings, the sewer pipe shall be sleeved as required. Care shall be exercised and proper precautions taken during installation of the sewer pipe and sleeve to assure that there will be no damage to such structures and no settlement or movement of foundations or footings. Any damage occurring as a result of the Contractor's operation shall be corrected and all costs connected therewith shall be borne by the Contractor. When the sewer pipe location is within 3 feet of a proposed building, retaining wall, or structural foundation as stated above, the pipe shall be sleeved as required for an existing structure.

3.07 TRENCHING

- A. Perform excavating and backfilling as required to install sanitary sewer work. Excavation and backfill operations shall comply with the requirements of the local governing agency(s).
- B. Provide trench wall support and pumping of surface and ground water as required to provide suitable conditions for performing the work.
- C. Excavate trenches to accommodate indicated bedding conditions and material. Trim and shape trench bottoms to proper line and grade, free of irregularities. Remove unstable material and replace with compacted fill.

3.08 PLACING AND LAYING OF PIPE

- A. Pipe shall be protected during handling against impact shocks and free fall and the pipe interior shall be free of extraneous material.
- B. Gravity Sewer Piping
 - 1. Pipe laying shall proceed upgrade with the spigot ends of bell-and-spigot pipe pointing in the direction of the flow. Each pipe shall be laid accurately to the line and grade shown on the drawing by use of a laser projector in the downstream manhole. Lay and fit pipe with sealed joints and full bearing in bedding material. Pipe shall be laid and centered so that the sewer has a uniform invert. As the work progresses, the interior of the sewer shall be cleared of all superfluous materials.
 - 2. Before making pipe joints, all surfaces of the portions of the pipe to be joined shall be clean and dry. Lubricants, and primers, shall be used as recommended by the pipe manufacturer. The joints shall then be placed, fitted, joined, and adjusted so as to obtain the degree of water tightness required.
 - 3. Installation of PVC pipe shall be installed in accordance with ASTM D2321 and ASTM F402, and all required precautions shall be taken to assure adequate trench ventilation and protection for workers installing the pipe.
- C. Trenches shall be kept free of water and as dry as possible during bedding, laying, and jointing and for as long a period as required. When work is not in progress, open ends of pipe and fittings shall be satisfactorily closed so that no trench water or other material will enter the pipe or fittings.
- D. Install pipe joint gaskets in accordance with manufacturer's recommendations.
- E. Cut pipe ends entering structures flush with inner face of structures.

- F. Extend sanitary sewer system as shown on drawings and make required connection.
- G. Backfill trenches to subgrade with suitable materials and per the compaction requirements as specified per the geotechnical report.
 - 1. Backfill evenly on both sides of piping for its full depth. Provide thorough compaction of fill under pipe haunches.
 - 2. Provide granular backfill of $\frac{3}{4}$ " minus crushed limestone and compacted to a minimum 95% of standard density (ASTM D-698 or AASHTO T-99-57). Use of clean rock will not be permitted.
- H. Mechanically compact backfill in accordance with the requirements of the geotechnical report. Water settling, puddling, and jetting as a compaction method are not acceptable.
- I. Fill, compact, and restore to subgrade level and condition all settlement.

3.09 TESTING

- A. General:
 - 1. The Contractor shall maintain his work site in a manner that will be fully accessible by the Owner's Representative for observation of the work.
 - 2. The Contractor shall conduct the leakage test promptly following installation of waste water pipe. This test shall include services that have been constructed.
 - 3. The Contractor shall notify the Owner's Representative 48 hours before conducting the leakage test so that the Owner's Representative can schedule inspection and observation of the test.
 - 4. The Contractor shall provide all equipment and conduct the test.
- B. Plastic Pipe Deformation: In addition to leakage tests, a deformation test will be done as follows:
 - 1. The test shall be conducted not less than one month (30 days) after backfill has been properly installed.
 - 2. The maximum allowable deflection shall not exceed 5% of the pipe's internal diameter.
 - 3. Mandrel testing shall be performed on 100% of the pipeline.
 - 4. Mandrels shall be "Wortco 9-Arm Mandrel" (5% deflection) for flexible or semi-rigid pipe or approved equal.
 - 5. Gauge shall be pulled through the pipe by hand. Mechanical pulling assistance is not permitted.
 - 6. If any section of pipe does not conform to this requirement, it shall be replaced by the Contractor at no cost to the Owner. Leakage re-testing and mandrel re-testing shall take place 30 days after backfilling.
- C. Leakage:
 - 1. General:
 - a. Contractor shall clean pipe of excess mortar, joint sealant, and other dirt and debris prior to inspection.
 - b. Sewer will be inspected by flashing a light (lamping) between manholes and/or by physical passage where space permits.
 - c. The Owner's Representative will determine from illumination and/or physical inspection the presence of visible infiltration or other defects.
 - d. Defects shall be corrected prior to conducting leakage tests.
 - 2. Leakage test shall be done either by a water exfiltration test or air exfiltration test.
 - a. For water tests, the allowable exfiltration shall be less than 0.15 gallons per inch of internal diameter per hour per 100' of pipe length (200 gallons per inch of ID per day per mile) per 24 hours.
 - b. For air exfiltration tests, the holding time shall not be less than that listed below:

TABLE 1
MINIMUM TIME REQUIRED FOR A 1.0 psig PRESSURE DROP FOR SIZE AND LENGTH
OF PIPE INDICATED FOR Q=0.0015 (CFM/SF INTERNAL SURFACE AREA)

Pipe Diameter (in.)	Minimum Time, (min:sec)	Length for Minimum Time, (ft)	Time for Longer Length, (sec)	Specification Time for Length (L) Shown, (min:sec)							
				100 ft.	150 ft.	200 ft.	250 ft.	300 ft.	350 ft.	400 ft.	450 ft.
6	5:40	398	0.854L	5:40	5:40	5:40	5:40	5:40	5:40	5:42	6:24
8	7:34	298	1.520L	7:34	7:34	7:34	7:34	7:36	8:52	10:08	11:24
10	9:26	239	2.374L	9:26	9:26	9:26	9:53	11:52	13:51	15:49	17:48

- c. The Contractor may use air exfiltration testing for pipes of all sizes.
- d. The Contractor shall perform water exfiltration tests on manholes and may perform water exfiltration tests on sewer pipe larger than 18" ID.
3. Any sections of pipe not meeting the test requirements shall be repaired and the test shall be repeated until work is acceptable.
 - a. The Contractor is encouraged to pretest the pipes prior to notifying the Owner's Representative and formal testing.
 - b. For any section of pipe not passing the test when requested by the Contractor, the Contractor shall be responsible for the total cost of re-inspection. The Owner reserves the right to deduct the cost of re-inspection from the Contractor's payment for the work.
- D. Exfiltration Test (Water)
 1. The Contractor shall furnish all labor, equipment, tools, and materials required including bulkheads, water, and all miscellaneous items required to perform the test.
 2. Perform all tests for lines at a minimum water depth 2' above the high point of the system or 2' above ground water elevation, whichever is higher. Perform tests at a minimum water depth of 2' above casting elevation for manholes.
 3. Tests shall be maintained to locate all leaks, but not less than two hours. Measurement of exfiltration amounts shall be confirmed by the Owner's Representative.
 4. Tests shall be repeated after repair of leaks and defects, until leakage meets the requirements of this specification.
 5. Manholes and other structures shall be protected by means of bulkheads to prevent bursting pressure from being applied inside the structure.
 6. Pipe shall be de-watered upon completion of the successful test.
- E. Exfiltration Test (Air)
 1. In the areas where ground water is known to exist, the Contractor shall install a 1/2" diameter capped pipe nipple approximately 10" long through the manhole wall on top of one of the sewer lines entering the manhole.
 - a. Install at the time the sewer line is installed.
 - b. Immediately prior to performance of the line acceptance test, the ground water level shall be determined by removing the pipe cap, blowing air through the pipe nipple into the ground to clear it, and then connecting a clear plastic tube to pipe nipple.
 - c. The hose shall be held vertically and measurement of height of water, in feet, shall be taken after the water stops rising in this plastic tube.

- d. The height shall be divided by 2.3 to establish the pounds of pressure that will be added to all readings.
- 2. Contractor shall furnish all facilities required including necessary piping connections, test pumping equipment, pressure gauges, bulkheads, regulators to avoid over-pressurization, and all miscellaneous items required.
 - a. The pipe plug for introducing air to the sewer pipe shall be equipped with two taps. One tap will be used to introduce air into the line being tested, through suitable valves and fittings, so that the input air may be regulated. The second tap will be fitted with valves and fittings to accept a pressure test gauge indicating internal pressure in the sewer pipe. An additional valve and fitting will be incorporated on the tap used to check internal pressures so that a second test gauge may be attached to the internal pressure tap. Pressure test gauge will also be used to indicate loss of air pressure due to leaks in the sewer line.
 - b. The pressure test gauge shall meet the following minimum specifications: Size (diameter)--4-1/2"; Pressure Range -- 0 to 15 psi; Figure Intervals 1 psi increments; Minor Subdivisions -- 0.05 psi; pressure Tube Bourdon 2 or diaphragm; Accuracy -- +/- 0.25% of maximum scale reading; Dial white coated aluminum with black lettering, 2700 arc and mirror edge; Pipe Connection - low male, 1/2" NPT.
 - c. Calibration data will be supplied with all pressure test gauges. Certification of pressure test gauge will be required from the gauge manufacturer. This certification and calibration data will be available to the Owner's Representative whenever air tests are performed.
- 3. Test each reach of sewer pipe between manholes at the completion of the installation of pipe and appurtenances and the backfill of the sewer trench.
- 4. Plug ends of line, cap or plug all connections to withstand internal pressure. One of the plugs provided must have two taps for connecting equipment.
 - a. After connecting air control equipment to air hose, monitor air pressure so that the internal pressure does not exceed 5 psig.
 - b. After reaching 4 psig, throttle the air supply to maintain between 4 and 3.5 psig for at least two minutes in order to allow equilibrium between air temperature and pipe walls. During this time, check all plugs to detect any leakage.
 - c. If plugs are found to leak, bleed off air, tighten plugs, and repressurize. After the temperature has stabilized, the pressure is allowed to decrease to 3.5 psig.
 - d. At 3.5 psig, begin timing to determine the time required for the air pressure to drop to 2.5 psig. If the time in seconds for the air pressure to decrease from 3.5 psig to 2.5 psig is greater than the time shown in Table 1 in this section, the pipe shall be presumed free of defects.
- F. If the air test fails to meet the above requirements, repeat test as necessary after all leaks and defects have been repaired. Prior to acceptance, all constructed sewer lines shall satisfactorily pass the low pressure air test or the exfiltration test.

3.10 REPAIRS TO BROKEN PIPE

- A. Where cracks or ruptures develop in the pipe after installation, the entire length of pipe to a distance of at least 3 feet beyond the pipe joint on each side of the damage area shall be re-excavated. The pipe shall be replaced, or if approved by the Architect, shall be repaired in a suitable manner. Details of repairs shall be submitted for record. If the Contractor utilizes concrete cradle or encasement in his repair, he shall take precautions to guard against shear breaks at the limits of the concrete. Repaired sections shall be re-inspected approximately 6 months after completion of the repair. Should additional failures be noted, they shall be promptly repaired and later reinspected as approved and at no additional cost to the Owner.

3.11 MANHOLE STRUCTURES

- A. Precast Concrete Manholes

1. Place precast concrete manhole sections as indicated. Where manholes occur in pavements, set tops of frames and covers flush with finish surface. Elsewhere, set tops 3" above finish surface, unless otherwise indicated.
 - a. Install in accordance with ASTM C891.
 - b. Provide rubber joint gasket complying with ASTM C443 at joints of sections.
 - c. Apply bituminous mastic coating at joints of sections.
- B. Construct flow channels with concrete or brick, conforming to the inside diameter of connecting lines. Make changes in grade gradually and make changes in line with true curves.
- C. Set frames and covers to required grade and bed in place with mortar.
- D. Cold weather protection: Provide all necessary means for heating concrete, masonry materials, and mortar to protect concrete and masonry work during and after installation from damage by frost and freezing.
- E. Perform no work when the temperature is below 25 degrees F. (ambient)

3.12 CLEANOUTS

- A. Furnish and install where shown on Drawings all exterior cleanouts extended to finished grade, with solid cover, of size indicated on Drawings. Where cleanouts occur in lawn area, provide concrete collar per detail.

3.13 CONNECTIONS TO EXISTING MANHOLES

- A. Pipe connections to existing manholes shall be made in such manner that the finished work will conform as nearly as practicable to the essential applicable requirements specified for new manholes, including all necessary concrete work, cutting, and shaping.

3.14 BUILDING CONNECTIONS

- A. Shall include the lines to and connection with the building waste drainage piping at a point approximately 5 feet outside the building, unless otherwise indicated. Where building drain piping is not installed, the contractor shall terminate the building connections approximately 5 feet from the site of the building at a point as shown on the plans.

3.15 TAP CONNECTIONS

- A. Make connections to existing piping and underground structures, so that finished work will conform as nearly as practicable to requirements specified for new work.
- B. For branch connections from side into existing 24" or larger pipe or to underground structures, cut opening into unit sufficiently large to allow 3" of concrete to be placed around entering connection. Cut ends of connection passing through pipe or structure wall to conform to shape of, and be flush with, inside wall, unless otherwise indicated. On outside of pipe or structure wall, encase entering connection in 6" of concrete for a minimum length of 12 to provide additional support or collar from connection to undisturbed ground.
 1. Provide concrete which will attain minimum 28-day compressive strength of 3,000 psi unless otherwise indicated.
 2. Use epoxy bonding compound as interface between new and existing concrete and piping materials.
- C. Take care while making tap connections to prevent concrete or debris from entering existing piping or structure. Remove debris, concrete, or other extraneous material which may accumulate.

3.16 CLOSING ABANDONED UTILITIES

- A. Close open ends of abandoned underground utilities which are indicated to remain in place. Provide sufficiently strong closures to withstand hydro-static or earth pressure which may result after ends of abandoned utilities have been closed.
 1. Close open ends of concrete or masonry utilities with not less than 8" thick brick masonry bulkheads.

2. Close open ends of piping with threaded metal caps, plastic plugs, or other acceptable methods for size and type material being closed. Wood plugs are not acceptable.

3.17 DISPOSAL OF WASTE MATERIALS

- A. Stockpile, haul from site and legally dispose of waste materials, including excess excavated materials, rock, trash, and debris.
- B. Maintain disposal route clear, clean, and free of debris.

3.18 CLEANING

- A. Maintain sanitary sewer piping and structures in a clean workable condition during construction operations.
- B. Flush sanitary sewer system with water in sufficient volume to obtain free flow through each line. Remove all silt, trash, and debris just prior to acceptance of work by Owner.
- C. Upon completion of sanitary sewer work, remove tools and equipment. Provide site clear, clean, free of debris, and suitable for sitework operations.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

SECTION 33 41 00
SITE STORM UTILITY DRAINAGE PIPING

GENERAL

1.01 SUMMARY

- A. Extent of storm sewage systems work is indicated on drawings and schedules, and by requirements of this section.
- B. Related Sections: The following sections contain requirements that relate to this Section:
- C. Section 31 22 00 - "Grading" for excavation and backfill work as required for storm sewage systems.

1.02 SUBMITTALS

- A. Product Data: Submit manufacturer's technical product data and installation instructions for storm sewage system materials and products.
- B. Shop Drawings: Submit shop drawings for storm sewage systems, showing piping materials, size, locations, inverts, and reinforcement. Include details of underground structures, connections, and manholes. Show interface and spatial relationship between piping and proximate structures.
- C. Record Drawings: At project close-out, submit record drawings of installed storm sewage piping and products.
- D. Maintenance Data: Submit maintenance data and parts lists for storm sewage system materials and products. Include this data, product data, shop drawings, and record drawings in maintenance manual.

1.03 QUALITY ASSURANCE

- A. Manufacturer's Qualifications: Firms regularly engaged in manufacture of storm sewage system's products of types, materials, and sizes required, whose products have been in satisfactory use in similar service for not less than 5 years.
- B. Installer's Qualifications: Firm with at least 5 years of successful installation experience on projects with storm sewage work similar to that required for project.
- C. Codes and Standards:
- D. Plumbing Code Compliance: Comply with applicable portions of National Standard Plumbing Code pertaining to selection and installation of storm sewage system's materials and products.
- E. Comply with the latest edition of the Metropolitan St. Louis Sewer District (MSD) "Standard Construction Specifications for Sewers and Drainage Facilities".
- F. Environmental Compliance: Comply with applicable portions of local Environmental Agency regulations pertaining to storm sewage systems.

PRODUCTS

2.01 PIPES AND PIPE FITTINGS

- A. General: Provide pipes of one of the following materials, of weight/class indicated. Provide pipe fittings and accessories of same material and weight/class as pipes, with joining method as indicated. Sewers to be dedicated as public must be a pipe material approved by the Metropolitan St. Louis Sewer District.
- B. Storm Lines 10 inch diameter or less, except where specifically indicated otherwise:
Polyvinyl Chloride (PVC) Pipe: ASTM D 3034, Type PSM, SDR 35
- C. Storm Lines 12 inch diameter or larger, except where specifically indicated otherwise.
 - 1. Concrete Pipe: ASTM C 76, Class III, reinforced concrete pipe unless otherwise indicated.
 - 2. Corrugated Metal: Materials shall conform with AASHTO M218 (ASTM A 444) with 2.0 oz.

of zinc per sq. ft. Fabrication shall comply with AASHTO M36, Type 1 round and/or Type 2 other shapes as indicated. Provide flared end sections on all exposed ends, unless skewed or beveled ends are indicated or unless pipe terminates at a concrete headwall.

- a. Minimum metal thickness for round pipe.
 - (1) Up to and including 24" dia. 14 gauge.
 - (2) 27" to 36" dia. 12 gauge.
 - (3) 42" to 72" dia. 10 gauge.
3. Polyvinyl Chloride(PVC) Pipe: ASTM D-3034, Type PSM, SDR 35.
4. High Density Polyethylene: ADS-N12 WT IB
- D. Pipe Fittings
 1. Concrete Pipe: Reinforced or non-reinforced concrete fittings to match type and strength of concrete pipe being joined. Tongue-and-groove gasketed joints complying with ASTM C 443.
 2. PVC Pipe: Bell and spigot elastomeric joints shall conform to ASTM D3212 and shall be assembled with gaskets conforming to ASTM F477. Assembly shall be per manufacturer's specifications.
 3. Corrugated Metal Pipe: Comply with the requirements of AASHTO M36 and in addition include neoprene gaskets as indicated in the technical manual of the National Corrugated Steel Pipe Association. Design to provide strength to preserve pipe alignment, to prevent separation of pipe to prevent filtration of fill material and penetration of roots into pipe, and to prevent seepage of storm water out of pipe.
- E. Precast Concrete Manholes and Catch Basins
 1. Units shall be manufactured in accordance with ASTM C478, Specifications for Precast Reinforced Concrete Manhole Risers and Tops.
 2. Concrete to be minimum 3000 psi at 28 days.
 3. Joints between units shall be made using flexible watertight rubber gaskets, Portland Cement mortar or approved jointing compound, at Contractor's option and to meet local regulations.
 4. Include cast iron steps and traps where indicated, at all required openings.
 5. Available Manufacturers: Subject to compliance with requirements, products which may be incorporated include but are not limited to the following:
 - a. Kienstra, Inc. - Woodriver, IL
 - b. Kistner Septic Tank Co., Inc., Cheektowaga N.Y.
 - c. Warren Concrete Products, Inc., Warren, Pennsylvania
 - d. United States Concrete Pipe Company, Cleveland, Ohio

2.02 DRAINAGE STRUCTURE CASTINGS

1. Material: Gray iron castings, ASTM A-48-76 Class 30B.
2. Finish: One coat of high grade bituminous asphalt paint, Federal Spec. MIL-C-4508, on all castings except where field painting is indicated. Surface preparation for shop priming and field painting shall be SSPC-SP10 near-white blast cleaning and prime paint shall be equivalent to TNEMEC 66-1211 Epoxoline Primer applied in accordance with manufacturers written recommendations.
3. Manufacturer: The products of the Neenah Foundry Company, Neenah, Wisconsin, have been indicated on the Drawings by catalog number to establish the types and quality of products expected. Submit other equivalent product manufacturer for review and approval by the architect.

2.03 CLEANOUT

1. Cleanout pipe and fittings shall be cast-iron soil pipe conforming to ASTM A74-69, extra heavy, table 1. Each cleanout shall have a brass ferrule and a cast-brass screw jointed plug with socket for wrench.

EXECUTION

3.01 INSTALLATION OF PIPE AND PIPE FITTINGS

- A. General: Install pipeline in accordance with governing authorities having jurisdiction, except

where more stringent requirements are indicated.

- B. Bedding: Round trench bottom so that pipe has firm bearing on well compacted soil or on undisturbed soil. Provide minimum of 4" of minus crushed stone where bed rock or broken rock exists on trench bottom. Excavate bell hole by hand. Do not lay pipe in wet trench. Do not permit water in trench until joints are set.
- C. Inspect piping before installation to detect apparent defects. Mark defective materials with white paint and promptly remove from site.
- D. Lay pipe true to line and grades. Set grade boards maximum of 30 ft. on center. Begin at low end. Place spigot ends facing downstream. Center spigot in bells with inverts smooth and uniform. Protect exposed ends against impact, dirt, cement, and debris. A perfect circle shall be evident when "lamped". Install rubber gasket or caulked joints per manufacturer's recommendations. Install oakum or jute in place. Ram mortar into joint with wooden caulking tool. Over-fill joint and finish to smooth 45 degrees bevel.
- E. Install gaskets in accordance with manufacturer's recommendations for use of lubricants, cements, and other special installation requirements.
- F. Concrete Pipe: Install in accordance with applicable provisions of ACPA "Concrete Pipe Installation Manual".
- G. Plastic Pipe: Install in accordance with manufacturer's installation recommendations, and in accordance with ASTM D 2321.
- H. Cleaning Piping: Clear interior of piping of dirt and other superfluous material as work progresses. Maintain swab or drag in line and pull past each joint as it is completed.
 - 1. In large, accessible piping, brushes and brooms may be used for cleaning.
 - 2. Place plugs in ends of uncompleted conduit at end of day or whenever work stops.
 - 3. Flush lines between manholes if required to remove collected debris.
- I. Joint Adaptors: Make joints between different types of pipe with standard manufactured adapters and fittings intended for that purpose.
- J. Closing Abandoned Utilities: Close open ends of abandoned underground utilities which are indicated to remain in place. Provide sufficiently strong closures to withstand hydrostatic or earth pressure which may result after ends of abandoned utilities have been closed.
 - 1. Close open ends of concrete or masonry utilities with not less than 8" thick brick masonry bulkheads.
 - 2. Close open ends of piping with threaded metal caps, plastic plugs, or other acceptable methods suitable for size and type of material being closed. Wood plugs are not acceptable.
- K. Interior Inspection: Inspect piping to determine whether line displacement or other damage has occurred.
 - 1. Make inspections after lines between manholes, or manhole locations, have been installed and approximately 2' of backfill is in place, and again at completion of project.
 - 2. If inspection indicates poor alignment, debris, displaced pipe, infiltration or other defects, correct such defects, and reinspect.

3.02 DRAINAGE STRUCTURES

- A. Manholes, Catch Basins & Trench Drains
 - 1. Precast structure: Place on prepared subgrade per detail and manufacturer's recommendations and specifications.
- B. Headwall: Construct as detailed. Finish as specified for Formed Surfaces in Division 3.

3.03 CLEANOUTS

- A. Cleanouts shall be provided and installed in location indicated. Rim of cleanout flush with finished grade.

3.04 TAP CONNECTIONS

- A. Make connections to existing piping and underground structures, so that finished work will conform as nearly as practicable to requirements specified for new work.
- B. For branch connections from side into existing 24" or larger piping, or to underground structures, cut opening into unit sufficiently large to allow 3" of concrete to be packed around entering connection. Cut ends of connection passing through pipe or structure wall to conform to shape of and be flush with inside wall, unless otherwise indicated. On outside of pipe or structure all, encase entering connection in 6" of concrete for minimum length of 12" to provide additional support or collar from connection to undisturbed ground.
 - 1. Provide concrete which will attain minimum 28-day compressive strength of 3000 psi, unless otherwise indicated.
 - 2. Use epoxy bonding compound as interface between new and existing concrete and piping materials.
- C. Take care while making tap connections to prevent concrete or debris from entering existing piping or structure. Remove debris, concrete, or other extraneous material which may accumulate.

3.05 BACKFILLING

- A. General: Conduct backfill operations of open-cut trenches closely following laying, jointing, and bedding of pipe, and after initial inspection and testing are completed. Backfill material and requirements shall adhere to the requirements of the local governing agency(s).
 - 1. To minimize local area traffic interruptions, allow no more than 100' between pipe laying and point of complete backfilling.

3.06 FIELD QUALITY CONTROL

- A. Testing: Perform testing of completed piping in accordance with local authorities having jurisdiction.

END OF SECTION

SECTION 33 46 00

SUBDRAINAGE

Note: the geotechnical report shall be considered part of these specifications. The contractor is responsible for obtaining a copy of the report which shall be used as the basis for construction means and methods.

GENERAL

1.01 SECTION INCLUDES

- A. Building Perimeter and Retaining Wall Drainage Systems.
- B. Filter aggregate and fabric and bedding.

1.02 RELATED REQUIREMENTS

- A. Section 31 2316 - Excavation: Excavating for subdrainage system piping and surrounding filter aggregate.
- B. Section 31 2323 - Fill: Backfilling over filter aggregate, up to subgrade elevation.
- C. Section 31 2316.13 - Trenching: Excavating and backfilling for site subdrainage systems.

1.03 SUBMITTALS

- A. See Section 01 3300 - Construction Submittals, for submittal procedures.
- B. Shop Drawings: Indicate dimensions, layout of piping, high and low points of pipe inverts, gradient of slope between corners and intersections, and cleanouts.
- C. Product Data: Provide data on pipe drainage products and pipe accessories.
- D. Manufacturer's Certificate: Certify that products meet or exceed specified requirements.
- E. Project Record Documents: Record location of pipe runs, connections, cleanouts and principal invert elevations.

PRODUCTS

2.01 PIPE MATERIALS

- A. Manufacturers:
 - 1. Advanced Drainage Systems, Inc.; Product - "N-12 Smooth Interior Pipe": www.ads-pipe.com.
 - 2. Substitutions: See Section 01 6000 - Product Requirements.
- B. Flexible Corrugated Plastic Tubing: AASHTO M 294, Type S flexible pipe; 6 inch diameter, annular corrugated exterior combined with smooth inner wall, with required fittings.
- C. Use perforated pipe at subdrainage system; unperforated through sleeved walls.

2.02 AGGREGATE AND BEDDING

- A. Drainage Aggregate Material: Granular fill as specified in design drawings or as directed by geotechnical engineer

2.03 ACCESSORIES

- A. Pipe Couplings: ASTM F477, solid elastomeric gaskets.
- B. Filter Fabric: Polypropylene, water pervious type, black non-biodegradable, non-woven, needle-punched. Provide "ADS-6600" manufactured by Advanced Drainage Systems, Inc.
- C. Sleeve: Manufacturer recommended type for foundation wall.
- D. Drainage Composite Panels:
 - 1. "CCW MiraDRAIN 2000" manufactured by Carlisle Coatings & Waterproofing: www.carlisle-ccw.com.
 - 2. "J-DRain - 1000 Series" manufactured by JDR Enterprises, Inc.: www.j-drain.com
 - 3. "SealTight Mel-Drain" manufactured by W.R.Meadows, Inc.: www.wrmeadows.com.

4. Substitutions: See Section 01600 - Product Requirements.

EXECUTION

3.01 EXAMINATION

- A. Verify that excavated base is ready to receive work and excavations, dimensions, and elevations are as indicated on Drawings.

3.02 PREPARATION

- A. Hand trim excavations to required elevations. Correct over-excavation with compacted General Fill installed in accordance with requirements of Section 31 2323.
- B. Remove large stones or other hard matter that could damage drainage piping or impede consistent backfilling or compaction.
- C. Install filter fabric trench lining.

3.03 INSTALLATION

- A. Install and join pipe and pipe fittings in accordance with pipe manufacturer's instructions.
- B. Place drainage pipe on filter fabric laid over clean cut subsoil.
- C. Lay pipe to slope gradients noted on Drawings; with maximum variation from true slope of 1/8 inch in 10 feet.
- D. Place pipe with perforations facing down. Mechanically join pipe ends.
- E. Install pipe couplings.
- F. Install filter aggregate at sides, over joint and top of pipe. Provide top cover compacted thickness of 12 inches.
- G. Place filter fabric over levelled top surface of aggregate cover prior to subsequent backfilling operations.
- H. Place aggregate in maximum 4 inch lifts, consolidating each lift.
- I. Refer to Section 31 2323 for compaction requirements. Do not displace or damage pipe when compacting.
- J. Place general fill over drainage pipe aggregate cover and compact.
- K. Connect to storm sewer system with unperforated pipe, through installed sleeves.

3.04 FIELD QUALITY CONTROL

- A. Section 01 4000 - Quality Requirements: Field inspection and testing.
- B. Request inspection prior to and immediately after placing aggregate cover over pipe.

3.05 PROTECTION

- A. Protect pipe and aggregate cover from damage or displacement until backfilling operation begins.

END OF SECTION

THIS PAGE INTENTIONALLY LEFT BLANK

Archimages

143 West Clinton Place
St. Louis, MO 63122
314.965.7445
www.archimages-stl.com